

OCTOBER 4, 2024

Town of Arlington Conservation Commission
c/o Mr. David Morgan, Environmental Planner + Conservation Agent
Robbins Memorial Town Hall
730 Massachusetts Avenue
Arlington, Massachusetts 02476

RE: Response to GZA Peer Review Comments
Thorndike Place Residential Development

Dear Members of the Arlington Conservation Commission,

On behalf of the Applicant, Arlington Land Realty, LLC, BSC Group, Inc. (BSC) is pleased to submit this response to peer review comments provided by GZA GeoEnvironmental, Inc. (GZA) relative to the Thorndike Place residential development (the Project) to be located off of Dorothy Road in the Town of Arlington. GZA's peer review on behalf of the Arlington Conservation Commission was issued in a letter dated August 1, 2024. For clarity, our responses are organized in accordance with GZA's letter. Each of GZA's conclusions is followed by a response or acknowledgement by BSC as appropriate.

Design Seasonal High-Water Table

In their August 1, 2024, letter, GZA wrote:

Therefore, we conclude that the seasonal high water table elevation of 4.0 feet used by BSC is for "above normal" groundwater conditions and is suitable to be used for stormwater design for this project. As noted above, GZA's opinion on design groundwater elevation findings are consistent with the opinion expressed by Hatch and BSC.

Note that we did not use USGS well Lexington MA-LTW-104 (which was used by MMA and Horsley) in our analysis because that well is in a sand and gravel aquifer with a very shallow water table. Those conditions are not present at the Site. In addition, that USGS well is more effected by individual rainfall events than by seasonal variations of the groundwater table, which is not typical of other USGS wells in the area.

BSC agrees with GZA's conclusions, and no response is required.

Groundwater Mound Evaluation

In their August 1, 2024, letter, GZA wrote:

As noted above, the Required Recharge Volume is 1,638 cubic feet, but the main stormwater infiltration system has a storage volume of 10,497 cubic feet. It is GZA's opinion that the large main stormwater infiltration system would need to be redesigned to allow drainage of the system within 72-hours to meet the requirements of the MassDEP Stormwater Handbook, and to account for the impacts of groundwater mounding during storm events which result in greater than 1638 cubic feet of stormwater runoff. The redesign should also address peak flow rates that discharge to the stormwater outfall control system.

The five smaller (driveway) stormwater infiltration areas are planned to be 21 feet long and 14 feet wide. Per BSC's Stormwater Report the recharge volume during the 100-year storm event for these systems is up to 883 cubic feet. Dividing that recharge volume by the bottom area of 294 feet results

in a water height of 3.0 feet (or 36-inches). Using the Kv design rate of 0.27-inches per hour, it would take 133.3 hours (i.e., 5.55 days) to drain the recharge basin. This exceeds the MassDEP Stormwater Handbook requirement of draining within 72 hours. These smaller infiltration systems would need to be redesigned and then a groundwater mound analysis should be performed to redesign these stormwater management systems.

After discussing this portion of the review with GZA, we have performed revisions to address their concerns regarding groundwater mounding for storm events that result in greater than 1,638 cubic feet of stormwater runoff. The result of these revisions is that a smaller volume of runoff is forced to infiltrate, and the entire infiltration volume can be drained in 72 hours. Specifically, the following revisions have been made:

- The R-Tank underground chamber systems from the townhouse driveways have been removed from the design. The trench drains that capture runoff from these driveways have been redirected to the large infiltration system (Infiltration System 1).
- The roof top detention system has been adjusted so that a somewhat larger area of the roof is detained and discharged at a controlled rate to Infiltration System 1 and a smaller portion of the roof runoff is being discharged via the rip rap apron at the southeast portion of the building.
- Infiltration System 1 has been revised to a 2.5-foot StormTrap system from the previous system height of 3-feet. The elevation of the bottom of the system has been raised 0.5 feet higher to elevation 6.5, and the outlet control for this system has been revised. These revisions allow for infiltration of the required recharge and water quality volumes but minimizes the amount of recharged stormwater during larger storm events.
- Various pipe sizes and slope have been revised to accommodate the changes detailed above.

Calculations for outlet protection sizing, post-development peak runoff rates, groundwater recharge, groundwater mounding, and total suspended solids (TSS) removal have been performed and are attached along with the revised Grading and Drainage Plan for the Project.

Conclusions

In their August 1, 2024, letter, GZA wrote:

GZA agrees with BSC and Hatch that the design seasonal high groundwater elevation for the stormwater infiltrations systems should be 4.0 feet.

BSC agrees with GZA's conclusions, and no response is required.

In their August 1, 2024, letter, GZA wrote:

Although GZA believes the Required Recharge Volume of 1,638 cubic feet can be infiltrated into the ground without causing excessive groundwater mounding, larger volumes of storm water runoff will not drain within the required 72-hour period. It is GZA's opinion that for stormwater volumes larger than the Required Recharge Volume, the rate of groundwater infiltration will decrease significantly, and the groundwater mound will extend into the bottom of the large main infiltration system. In GZA's opinion both the large main stormwater infiltration system and the smaller driveway stormwater infiltrations systems would need to be redesigned to account for the impacts of groundwater mounding during large storm events and to meet the MassDEP Stormwater Manual's maximum allowable drainage standard of 72-hours.

As described above, we have revised the stormwater management system to respond to GZA's concern. Applicable plans and calculations are attached.


We believe that these responses fully respond to all comments from the GZA peer review. We look forward to discussing this project with you further at the upcoming public hearing on the project. Please feel free to contact me at (617) 896-4386 or drinaldi@bscgroup.com should you have any questions on the information in this letter.

Sincerely,
BSC Group, Inc.



Dominic Rinaldi, PE
Senior Associate

ATTACHMENT A
THORNDIKE PLACE NOTICE OF INTENT
GRADING & DRAINAGE PLAN, SHEET C-104
REVISION 1 DATED 9/12/24



PROFESSIONAL ENGINEER

**THORNDIKE PLACE
NOTICE OF INTENT**

DOROTHY ROAD
IN
ARLINGTON
MASSACHUSETTS
(MIDDLESEX COUNTY)

GRADING &
DRAINAGE PLAN

SEPTEMBER 6, 2023

REVISIONS:

NO.	DATE	DESC.
1	9/12/24	INFILTRATION SYSTEM

PREPARED FOR:

ARLINGTON LAND REALTY, LLC
84 SHERMAN STREET, 2ND FLOOR
CAMBRIDGE, MA

BSC GROUP

803 Summer Street
Boston, Massachusetts
02127

617 896 4300

© 2023 BSC Group, Inc.

SCALE: 1" = 30'

0 15 30 60 FEET

FILE: 2340702\CD\2340702-GR

DWG.: SHEET C-104

JOB. NO: 23407.02

ISSUED FOR PERMITTING
NOT FOR CONSTRUCTION

ATTACHMENT B
OUTLET PROTECTION SIZING CALCULATIONS

OUTLET PROTECTION SIZING



Project No. 23407.02
Subject Outlet Protection Sizing Calcs
Location Arlington, MA

Calc By EAD
Date 9/5/2024
Checked by DRR
Date 9/5/2024

FES-1

Q=Design Discharge, (ft³/s) = 7.1 cfs
D=Culvert Diameter, (ft) = 1.50 ft
TW=Tailwater Depth, (ft) = 0.6 ft, (0.4xD for unknow tailwater, or enter known tailwater)
(Tailwater depth is to be limited to between 0.4D and 1.0D)

Riprap Rock Sizing

$$D_{50} = 0.2D \left[\frac{Q}{\sqrt{gD^{2.5}}} \right]^{4/3} \left[\frac{D}{TW} \right]$$
$$D_{50} = 0.28 \left| \frac{7.10}{15.64} \right|^{(4/3)} \left| \frac{1.50}{0.60} \right| = 0.24 \text{ ft}$$
$$= 2.93 \text{ inches}$$

g=32.2 fps
D₅₀ = median rock size, ft

Table 1 : Riprap Classes and Apron Dimensions

Class	D ₅₀ (in)	Apron Length	Apron Depth
1	5	4D	3.5D ₅₀
2	6	4D	3.5D₅₀
3	10	5D	3.3D ₅₀
4	14	6D	2.2D ₅₀
5	20	7D	2.0D ₅₀
6	22	8D	2.0D ₅₀

Use Class 2

Apron Dimensions

Length, L=5D = 8 ft
Depth=3.3D₅₀ = 19.80 Inches
Width=3D+(2/3)L = 9.50 ft (at apron end)

Riprap Rock Sizing Gradation

Given Size	Size of Stone, inches
100	9 to 12
85	8 to 11
50	6 to 9
15	3 to 8

OUTLET PROTECTION SIZING



Project No. 23407.02
Subject Outlet Protection Sizing Calcs
Location Arlington, MA

Calc By EAD
Date 9/5/2024
Checked by DRR
Date 9/5/2024

Roof Drain

Q=Design Discharge, (ft³/s) = 2 cfs
D=Culvert Diameter, (ft) = 1.00 ft
TW=Tailwater Depth, (ft) = 0.4 ft, (0.4xD for unknow tailwater, or enter known tailwater)
(Tailwater depth is to be limited to between 0.4D and 1.0D)

Riprap Rock Sizing

$$D_{50} = 0.2D \left[\frac{Q}{\sqrt{gD^{2.5}}} \right]^{4/3} \left[\frac{D}{TW} \right]$$
$$D_{50} = 0.28 \left| \frac{2.00}{5.67} \right|^{(4/3)} \left| \frac{1.00}{0.40} \right| = 0.17 \text{ ft}$$
$$= 2.09 \text{ inches}$$

g=32.2 fps
D₅₀ = median rock size, ft

Table 1 : Riprap Classes and Apron Dimensions

Class	D ₅₀ (in)	Apron Length	Apron Depth
1	5	4D	3.5D ₅₀
2	6	4D	3.5D₅₀
3	10	5D	3.3D ₅₀
4	14	6D	2.2D ₅₀
5	20	7D	2.0D ₅₀
6	22	8D	2.0D ₅₀

Use Class 2

Apron Dimensions

Length, L=5D = 5 ft
Depth=3.3D₅₀ = 19.80 Inches
Width=3D+(2/3)L = 6.33 ft (at apron end)

Riprap Rock Sizing Gradation

Given Size	Size of Stone, inches
100	9 to 12
85	8 to 11
50	6 to 9
15	3 to 8

ATTACHMENT C
POST-DEVELOPMENT HYDROCAD CALCULATIONS

Post-development watershed modeling was updated based upon the revisions to the stormwater management system detailed in our October 4, 2024, letter. The following tables demonstrate that there will be no increase to peak runoff rates from the Project site for the 2, 10, 25, 50, and 100-year, 24-hour storm events:

Node 1L – Flow to Wetlands

Storm Event	Pre-Development Peak Discharge Rate (cfs) ¹	Post-Development Peak Discharge Rate (cfs)	Change in Peak Discharge Rate (cfs)
2-Year	3.7	3.5	-0.2
10-Year	9.0	8.2	-0.8
25-Year	13.7	11.4	-2.3
50-Year	17.2	13.7	-3.5
100-Year	22.0	18.5	-3.5


Node 2L – Flow Towards Street

Storm Event	Pre-Development Peak Discharge Rate (cfs) ¹	Post-Development Peak Discharge Rate (cfs)	Change in Peak Discharge Rate (cfs)
2-Year	0.3	0.3	0.0
10-Year	0.7	0.6	-0.1
25-Year	1.0	0.9	-0.1
50-Year	1.2	1.1	-0.1
100-Year	1.5	1.3	-0.2

Node 100L – Total Flows

Storm Event	Pre-Development Peak Discharge Rate (cfs) ¹	Post-Development Peak Discharge Rate (cfs)	Change in Peak Discharge Rate (cfs)
2-Year	3.8	3.7	-0.1
10-Year	9.4	8.7	-0.7
25-Year	14.2	12.1	-2.1
50-Year	17.9	14.4	-3.5
100-Year	22.7	19.3	-3.4

¹ Pre-development peak discharge rates taken from Stormwater Report, Thorndike Place, Dorothy Road, Arlington, MA, prepared by BSC Group, dated November 2020, last revised September 2023. These rates have not changed.



THORNDIKE PLACE

DOROTHY ROAD

ARLINGTON
MASSACHUSETTS
(MIDDLESEX COUNTY)

PROPOSED WATERSHED
PLAN

NOVEMBER 3, 2020

PREPARED
FOR:
ARLINGTON LAND REALTY
84 SHERMAN STREET
CAMBRIDGE, MA



803 Summer Street
Boston, Massachusetts
02127

617 896 4300

Job No.: 23407.02 Date: 11/3/2020
Scale: 1" = 60' Revised: 9/13/2024
Dwg No: PRW
File: C:\DRAINAGE DESIGN\2340700-PRW


LEGEND



SUBCATCHMENT





SUBCATCHMENT BOUNDARY



TIME OF CONCENTRATION FLOW
PATH

SCALE: 1" = 60'





2340702-PR-2024-09

Prepared by BSC Group
HydroCAD® 10.20-5b s/n 00904 © 2023 HydroCAD Software Solutions LLC

Printed 9/12/2024
Page 2

Rainfall Events Listing

Event#	Event Name	Storm Type	Curve	Mode	Duration (hours)	B/B	Depth (inches)	AMC
1	2-Year	Type III 24-hr		Default	24.00	1	4.02	2
2	10-Year	Type III 24-hr		Default	24.00	1	6.40	2
3	25-Year	Type III 24-hr		Default	24.00	1	8.30	2
4	50-Year	Type III 24-hr		Default	24.00	1	9.67	2
5	100-Year	Type III 24-hr		Default	24.00	1	11.50	2

Area Listing (all nodes)

Area (sq-ft)	CN	Description (subcatchment-numbers)
74,444	74	>75% Grass cover, Good, HSG C (1S, 3.1S, 4.2S, 4.3S, 4.4S, 4.5S, 4.6S, 5S, 6.1S, 6S, 7S)
220	89	Gravel roads, HSG C (6.1S)
411	89	Gravel sidewalk, HSG C (3.1S)
25,811	98	Paved parking, HSG C (1S, 4.2S, 4.3S, 4.4S, 4.5S, 4.6S, 5S, 7S)
6,444	98	Paved roads w/curbs & sewers, HSG C (6.1S)
46,099	98	Roofs, HSG C (2.1S, 2S, 3S, 6S)
272	98	Unconnected pavement, HSG C (3.1S)
4,985	70	Woods, Good, HSG C (6S)
158,686	86	TOTAL AREA

Soil Listing (all nodes)

Area (sq-ft)	Soil Group	Subcatchment Numbers
0	HSG A	
0	HSG B	
158,686	HSG C	1S, 2.1S, 2S, 3.1S, 3S, 4.2S, 4.3S, 4.4S, 4.5S, 4.6S, 5S, 6.1S, 6S, 7S
0	HSG D	
0	Other	
158,686		TOTAL AREA

Ground Covers (all nodes)						
HSG-A (sq-ft)	HSG-B (sq-ft)	HSG-C (sq-ft)	HSG-D (sq-ft)	Other (sq-ft)	Total (sq-ft)	Ground Cover
0	0	74,444	0	0	74,444	>75% Grass cover, Good
0	0	220	0	0	220	Gravel roads
0	0	411	0	0	411	Gravel sidewalk
0	0	25,811	0	0	25,811	Paved parking
0	0	6,444	0	0	6,444	Paved roads w/curbs & sewers
0	0	46,099	0	0	46,099	Roofs
0	0	272	0	0	272	Unconnected pavement
0	0	4,985	0	0	4,985	Woods, Good
0	0	158,686	0	0	158,686	TOTAL AREA


Time span=0.00-72.00 hrs, dt=0.01 hrs, 7201 points	
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN	
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method	
Subcatchment1S: CB-1	Runoff Area=22,742 sf 72.16% Impervious Runoff Depth=3.04" Tc=6.0 min CN=91 Runoff=1.8 cfs 5,755 cf
Subcatchment2.1S: Building	Runoff Area=7,811 sf 100.00% Impervious Runoff Depth=3.79" Tc=6.0 min CN=98 Runoff=0.7 cfs 2,464 cf
Subcatchment2S: Building Roof	Runoff Area=25,114 sf 100.00% Impervious Runoff Depth=3.79" Tc=6.0 min CN=98 Runoff=2.3 cfs 7,921 cf
Subcatchment3.1S: BackyardADs	Runoff Area=8,985 sf 3.03% Impervious Runoff Depth=1.68" Flow Length=147' Tc=10.3 min CN=75 Runoff=0.3 cfs 1,259 cf
Subcatchment3S: Townhouse Roofs	Runoff Area=13,067 sf 100.00% Impervious Runoff Depth=3.79" Tc=6.0 min CN=98 Runoff=1.2 cfs 4,122 cf
Subcatchment4.2S: Townhouse TDs	Runoff Area=1,112 sf 95.68% Impervious Runoff Depth=3.67" Tc=6.0 min CN=97 Runoff=0.1 cfs 340 cf
Subcatchment4.3S: Townhouse TDs	Runoff Area=1,105 sf 97.29% Impervious Runoff Depth=3.67" Tc=6.0 min CN=97 Runoff=0.1 cfs 338 cf
Subcatchment4.4S: Townhouse TDs	Runoff Area=1,104 sf 97.46% Impervious Runoff Depth=3.67" Tc=6.0 min CN=97 Runoff=0.1 cfs 338 cf
Subcatchment4.5S: Townhouse TDs	Runoff Area=1,082 sf 98.06% Impervious Runoff Depth=3.79" Tc=6.0 min CN=98 Runoff=0.1 cfs 341 cf
Subcatchment4.6S: Townhouse TDs	Runoff Area=1,056 sf 99.24% Impervious Runoff Depth=3.79" Tc=6.0 min CN=98 Runoff=0.1 cfs 333 cf
Subcatchment5S: TD-1	Runoff Area=5,851 sf 51.63% Impervious Runoff Depth=2.56" Tc=6.0 min CN=86 Runoff=0.4 cfs 1,250 cf
Subcatchment6.1S: East driveway	Runoff Area=12,275 sf 52.50% Impervious Runoff Depth=2.66" Tc=6.0 min CN=87 Runoff=0.9 cfs 2,716 cf
Subcatchment6S: Bypass Towards	Runoff Area=51,539 sf 0.21% Impervious Runoff Depth=1.61" Flow Length=125' Tc=14.0 min CN=74 Runoff=1.7 cfs 6,919 cf
Subcatchment7S: To Street	Runoff Area=5,843 sf 18.07% Impervious Runoff Depth=1.90" Tc=6.0 min CN=78 Runoff=0.3 cfs 927 cf
Pond 1P: Underground Infiltration System	Peak Elev=7.38' Storage=6,133 cf Inflow=4.3 cfs 21,954 cf Discarded=0.1 cfs 9,980 cf Primary=1.2 cfs 11,973 cf Outflow=1.3 cfs 21,953 cf
Pond 2P: Rooftop Detention	Peak Elev=57.22' Storage=4,423 cf Inflow=2.3 cfs 7,921 cf Outflow=0.2 cfs 7,878 cf

Pond 3P: Rain garden	Peak Elev=6.37'	Storage=196 cf	Inflow=0.9 cfs	2,716 cf
	Discarded=0.0 cfs	411 cf	Primary=0.9 cfs	2,305 cf
Link 1L: Towards Wetlands			Inflow=3.5 cfs	23,660 cf
			Primary=3.5 cfs	23,660 cf
Link 2L: Towards Street			Inflow=0.3 cfs	927 cf
			Primary=0.3 cfs	927 cf
Link 100L: Total Flows			Inflow=3.7 cfs	24,587 cf
			Primary=3.7 cfs	24,587 cf
Total Runoff Area = 158,686 sf Runoff Volume = 35,023 cf Average Runoff Depth = 2.65"				
50.45% Pervious = 80,060 sf 49.55% Impervious = 78,626 sf				

Summary for Subcatchment 1S: CB-1

Runoff	=	1.8 cfs @ 12.09 hrs,	Volume=	5,755 cf,	Depth=	3.04"
Routed to Pond 1P : Underground Infiltration System						
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs						
Type III 24-hr 2-Year Rainfall=4.02"						
Area (sf)	CN	Description				
16,410	98	Paved parking, HSG C				
6,332	74	>75% Grass cover, Good, HSG C				
22,742	91	Weighted Average				
6,332		27.84% Pervious Area				
16,410		72.16% Impervious Area				
Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description	
6.0					Direct Entry, Min. Tc	

Subcatchment 1S: CB-1



Summary for Subcatchment 2.1S: Building Roof-Southeast


Runoff = 0.7 cfs @ 12.08 hrs, Volume= 2,464 cf, Depth= 3.79"
Routed to Link 1L : Towards Wetlands

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 2-Year Rainfall=4.02"

Area (sf)	CN	Description
7,811	98	Roofs, HSG C
7,811		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 2.1S: Building Roof-Southeast



Summary for Subcatchment 2S: Building Roof


Runoff = 2.3 cfs @ 12.08 hrs, Volume= 7,921 cf, Depth= 3.79"
Routed to Pond 2P : Rooftop Detention

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 2-Year Rainfall=4.02"

Area (sf)	CN	Description
25,114	98	Roofs, HSG C
25,114		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 2S: Building Roof



Summary for Subcatchment 3.1S: Backyard ADs


Runoff = 0.3 cfs @ 12.15 hrs, Volume= 1,259 cf, Depth= 1.68"
Routed to Pond 1P : Underground Infiltration System

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 2-Year Rainfall=4.02"

Area (sf)	CN	Description
272	98	Unconnected pavement, HSG C
8,302	74	>75% Grass cover, Good, HSG C
411	89	Gravel sidewalk, HSG C
8,985	75	Weighted Average
8,713		96.97% Pervious Area
272		3.03% Impervious Area
272		100.00% Unconnected

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
9.4	50	0.0142	0.09		Sheet Flow, Grass: Dense n= 0.240 P2= 3.23"
0.9	97	0.0154	1.86		Shallow Concentrated Flow, Grassed Waterway Kv= 15.0 fps
10.3	147	Total			

Subcatchment 3.1S: Backyard ADs



Summary for Subcatchment 3S: Townhouse Roofs


Runoff = 1.2 cfs @ 12.08 hrs, Volume= 4,122 cf, Depth= 3.79"
Routed to Pond 1P : Underground Infiltration System

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 2-Year Rainfall=4.02"

Area (sf)	CN	Description
13,067	98	Roofs, HSG C
13,067		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 3S: Townhouse Roofs



Summary for Subcatchment 4.2S: Townhouse TDs


Runoff = 0.1 cfs @ 12.08 hrs, Volume= 340 cf, Depth= 3.67"
Routed to Pond 1P : Underground Infiltration System

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 2-Year Rainfall=4.02"

Area (sf)	CN	Description
1,064	98	Paved parking, HSG C
48	74	>75% Grass cover, Good, HSG C
1,112	97	Weighted Average
48		4.32% Pervious Area
1,064		95.68% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.2S: Townhouse TDs



Summary for Subcatchment 4.3S: Townhouse TDs


Runoff = 0.1 cfs @ 12.08 hrs, Volume= 338 cf, Depth= 3.67"
Routed to Pond 1P : Underground Infiltration System

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 2-Year Rainfall=4.02"

Area (sf)	CN	Description
1,075	98	Paved parking, HSG C
30	74	>75% Grass cover, Good, HSG C
1,105	97	Weighted Average
30		2.71% Pervious Area
1,075		97.29% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.3S: Townhouse TDs



Summary for Subcatchment 4.4S: Townhouse TDs


Runoff = 0.1 cfs @ 12.08 hrs, Volume= 338 cf, Depth= 3.67"
Routed to Pond 1P : Underground Infiltration System

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 2-Year Rainfall=4.02"

Area (sf)	CN	Description
1,076	98	Paved parking, HSG C
28	74	>75% Grass cover, Good, HSG C
1,104	97	Weighted Average
28		2.54% Pervious Area
1,076		97.46% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.4S: Townhouse TDs



Summary for Subcatchment 4.5S: Townhouse TDs


Runoff = 0.1 cfs @ 12.08 hrs, Volume= 341 cf, Depth= 3.79"
Routed to Pond 1P : Underground Infiltration System

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 2-Year Rainfall=4.02"

Area (sf)	CN	Description
1,061	98	Paved parking, HSG C
21	74	>75% Grass cover, Good, HSG C
1,082	98	Weighted Average
21		1.94% Pervious Area
1,061		98.06% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.5S: Townhouse TDs



Summary for Subcatchment 4.6S: Townhouse TDs


Runoff = 0.1 cfs @ 12.08 hrs, Volume= 333 cf, Depth= 3.79"
Routed to Pond 1P : Underground Infiltration System

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 2-Year Rainfall=4.02"

Area (sf)	CN	Description
1,048	98	Paved parking, HSG C
8	74	>75% Grass cover, Good, HSG C
1,056	98	Weighted Average
8		0.76% Pervious Area
1,048		99.24% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.6S: Townhouse TDs



Summary for Subcatchment 5S: TD-1


Runoff = 0.4 cfs @ 12.09 hrs, Volume= 1,250 cf, Depth= 2.56"
Routed to Pond 1P : Underground Infiltration System

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 2-Year Rainfall=4.02"

Area (sf)	CN	Description
3,021	98	Paved parking, HSG C
2,830	74	>75% Grass cover, Good, HSG C
5,851	86	Weighted Average
2,830		48.37% Pervious Area
3,021		51.63% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 5S: TD-1



Summary for Subcatchment 6.1S: East driveway


Runoff = 0.9 cfs @ 12.09 hrs, Volume= 2,716 cf, Depth= 2.66"
Routed to Pond 3P : Rain garden

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 2-Year Rainfall=4.02"

Area (sf)	CN	Description
5,611	74	>75% Grass cover, Good, HSG C
6,444	98	Paved roads w/curbs & sewers, HSG C
220	89	Gravel roads, HSG C
12,275	87	Weighted Average
5,831		47.50% Pervious Area
6,444		52.50% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

Subcatchment 6.1S: East driveway



Summary for Subcatchment 6S: Bypass Towards Wetlands


Runoff = 1.7 cfs @ 12.20 hrs, Volume= 6,919 cf, Depth= 1.61"
Routed to Link 1L : Towards Wetlands

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 2-Year Rainfall=4.02"

Area (sf)	CN	Description
4,985	70	Woods, Good, HSG C
46,447	74	>75% Grass cover, Good, HSG C
107	98	Roofs, HSG C
51,539	74	Weighted Average
51,432		99.79% Pervious Area
107		0.21% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.8	50	0.0220	0.07		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.23"
2.2	75	0.0133	0.58		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
14.0	125	Total			

Subcatchment 6S: Bypass Towards Wetlands



Summary for Subcatchment 7S: To Street


Runoff = 0.3 cfs @ 12.09 hrs, Volume= 927 cf, Depth= 1.90"
Routed to Link 2L : Towards Street

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 2-Year Rainfall=4.02"

Area (sf)	CN	Description
1,056	98	Paved parking, HSG C
4,787	74	>75% Grass cover, Good, HSG C
5,843	78	Weighted Average
4,787		81.93% Pervious Area
1,056		18.07% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 7S: To Street



Summary for Pond 1P: Underground Infiltration System

Inflow Area = 81,218 sf, 77.83% Impervious, Inflow Depth > 3.24" for 2-Year event
Inflow = 4.3 cfs @ 12.09 hrs, Volume= 21,954 cf
Outflow = 1.3 cfs @ 12.46 hrs, Volume= 21,953 cf, Atten= 70%, Lag= 22.6 min
Discarded = 0.1 cfs @ 9.04 hrs, Volume= 9,980 cf
Primary = 1.2 cfs @ 12.46 hrs, Volume= 11,973 cf
Routed to Link 1L : Towards Wetlands

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Peak Elev= 7.38' @ 12.46 hrs Surf.Area= 8,137 sf Storage= 6,133 cf

Plug-Flow detention time= 175.6 min calculated for 21,953 cf (100% of inflow)
Center-of-Mass det. time= 175.4 min (1,080.9 - 905.5)


Volume	Invert	Avail.Storage	Storage Description
#1	6.50'	17,495 cf	6.89'W x 14.06'L x 2.50'H StormTrap ST-1 Units (Irregular Shape) 84 20,343 cf Overall x 86.0% Voids

Device	Routing	Invert	Outlet Devices
#1	Discarded	6.50'	0.520 in/hr Exfiltration over Surface area
#2	Primary	6.80'	18.0" Round Culvert L= 190.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 6.80' / 6.00' S= 0.0042 ' /' Cc= 0.900 n= 0.013, Flow Area= 1.77 sf
#3	Device 2	6.80'	12.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 2	8.25'	4.0' long Sharp-Crested Rectangular Weir 2 End Contraction(s)

Discarded OutFlow Max=0.1 cfs @ 9.04 hrs HW=6.53' (Free Discharge)
1=Exfiltration (Exfiltration Controls 0.1 cfs)

Primary OutFlow Max=1.2 cfs @ 12.46 hrs HW=7.38' (Free Discharge)
2=Culvert (Barrel Controls 1.2 cfs @ 2.84 fps)
3=Orifice/Grate (Passes 1.2 cfs of 1.2 cfs potential flow)
4=Sharp-Crested Rectangular Weir (Controls 0.0 cfs)

Pond 1P: Underground Infiltration System



Summary for Pond 2P: Rooftop Detention

Inflow Area = 25,114 sf, 100.00% Impervious, Inflow Depth = 3.79" for 2-Year event
Inflow = 2.3 cfs @ 12.08 hrs, Volume= 7,921 cf
Outflow = 0.2 cfs @ 12.96 hrs, Volume= 7,878 cf, Atten= 91%, Lag= 52.8 min
Primary = 0.2 cfs @ 12.96 hrs, Volume= 7,878 cf
Routed to Pond 1P : Underground Infiltration System

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs / 3
Peak Elev= 57.22' @ 12.96 hrs Surf.Area= 20,000 sf Storage= 4,423 cf

Plug-Flow detention time= 374.6 min calculated for 7,878 cf (99% of inflow)
Center-of-Mass det. time= 370.8 min (1,122.7 - 751.9)


Volume	Invert	Avail.Storage	Storage Description
#1	57.00'	14,000 cf	Rooftop Detention (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
57.00	20,000	0	0
57.70	20,000	14,000	14,000

Device	Routing	Invert	Outlet Devices
#1	Primary	8.02'	12.0" Round Roof Drain L= 16.0' CPP, mitered to conform to fill, Ke= 0.700 Inlet / Outlet Invert= 8.02' / 7.70' S= 0.0200 '/' Cc= 0.900 n= 0.013, Flow Area= 0.79 sf
#2	Device 1	57.00'	4.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads

Primary OutFlow Max=0.2 cfs @ 12.96 hrs HW=57.22' (Free Discharge)
1=Roof Drain (Passes 0.2 cfs of 23.3 cfs potential flow)
2=Orifice/Grate (Orifice Controls 0.2 cfs @ 2.26 fps)

Pond 2P: Rooftop Detention



Summary for Pond 3P: Rain garden

Inflow Area = 12,275 sf, 52.50% Impervious, Inflow Depth = 2.66" for 2-Year event
Inflow = 0.9 cfs @ 12.09 hrs, Volume= 2,716 cf
Outflow = 0.9 cfs @ 12.09 hrs, Volume= 2,716 cf, Atten= 0%, Lag= 0.3 min
Discarded = 0.0 cfs @ 12.09 hrs, Volume= 411 cf
Primary = 0.9 cfs @ 12.09 hrs, Volume= 2,305 cf
Routed to Link 1L : Towards Wetlands

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Peak Elev= 6.37' @ 12.09 hrs Surf.Area= 384 sf Storage= 196 cf


Plug-Flow detention time= 80.6 min calculated for 2,715 cf (100% of inflow)
Center-of-Mass det. time= 80.8 min (809.3 - 809.6)

Volume	Invert	Avail.Storage	Storage Description			
#1	5.60'	253 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)	
5.60	125	46.0	0	0	125	
6.00	276	66.0	78	78	305	
6.30	350	73.0	94	172	385	
6.50	460	87.0	81	253	564	

Device	Routing	Invert	Outlet Devices											
#1	Discarded	5.60'	0.520 in/hr Exfiltration over Surface area											
#2	Primary	6.30'	22.0' long x 5.0' breadth Broad-Crested Rectangular Weir											
			Head (feet)	0.20	0.40	0.60	0.80	1.00	1.20	1.40	1.60	1.80	2.00	
			Coef. (English)	2.34	2.50	2.70	2.68	2.68	2.66	2.65	2.65	2.65		
				2.65	2.67	2.66	2.68	2.70	2.74	2.79	2.88			

Discarded OutFlow Max=0.0 cfs @ 12.09 hrs HW=6.37' (Free Discharge)
1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.9 cfs @ 12.09 hrs HW=6.37' (Free Discharge)
2=Broad-Crested Rectangular Weir (Weir Controls 0.9 cfs @ 0.60 fps)



Summary for Link 1L: Towards Wetlands


Inflow Area = 152,843 sf, 50.75% Impervious, Inflow Depth = 1.86" for 2-Year event

Inflow = 3.5 cfs @ 12.17 hrs, Volume= 23,660 cf

Primary = 3.5 cfs @ 12.17 hrs, Volume= 23,660 cf, Atten= 0%, Lag= 0.0 min

Routed to Link 100L : Total Flows

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs




Summary for Link 2L: Towards Street

Inflow Area = 5,843 sf, 18.07% Impervious, Inflow Depth = 1.90" for 2-Year event
Inflow = 0.3 cfs @ 12.09 hrs, Volume= 927 cf
Primary = 0.3 cfs @ 12.09 hrs, Volume= 927 cf, Atten= 0%, Lag= 0.0 min
Routed to Link 100L : Total Flows

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link 2L: Towards Street




Summary for Link 100L: Total Flows

Inflow Area = 158,686 sf, 49.55% Impervious, Inflow Depth = 1.86" for 2-Year event
Inflow = 3.7 cfs @ 12.15 hrs, Volume= 24,587 cf
Primary = 3.7 cfs @ 12.15 hrs, Volume= 24,587 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link 100L: Total Flows



Time span=0.00-72.00 hrs, dt=0.01 hrs, 7201 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment1S: CB-1	Runoff Area=22,742 sf 72.16% Impervious Runoff Depth=5.35" Tc=6.0 min CN=91 Runoff=3.1 cfs 10,138 cf
Subcatchment2.1S: Building	Runoff Area=7,811 sf 100.00% Impervious Runoff Depth=6.16" Tc=6.0 min CN=98 Runoff=1.1 cfs 4,011 cf
Subcatchment2S: Building Roof	Runoff Area=25,114 sf 100.00% Impervious Runoff Depth=6.16" Tc=6.0 min CN=98 Runoff=3.6 cfs 12,895 cf
Subcatchment3.1S: BackyardADs	Runoff Area=8,985 sf 3.03% Impervious Runoff Depth=3.63" Flow Length=147' Tc=10.3 min CN=75 Runoff=0.8 cfs 2,715 cf
Subcatchment3S: Townhouse Roofs	Runoff Area=13,067 sf 100.00% Impervious Runoff Depth=6.16" Tc=6.0 min CN=98 Runoff=1.9 cfs 6,709 cf
Subcatchment4.2S: Townhouse TDs	Runoff Area=1,112 sf 95.68% Impervious Runoff Depth=6.04" Tc=6.0 min CN=97 Runoff=0.2 cfs 560 cf
Subcatchment4.3S: Townhouse TDs	Runoff Area=1,105 sf 97.29% Impervious Runoff Depth=6.04" Tc=6.0 min CN=97 Runoff=0.2 cfs 556 cf
Subcatchment4.4S: Townhouse TDs	Runoff Area=1,104 sf 97.46% Impervious Runoff Depth=6.04" Tc=6.0 min CN=97 Runoff=0.2 cfs 556 cf
Subcatchment4.5S: Townhouse TDs	Runoff Area=1,082 sf 98.06% Impervious Runoff Depth=6.16" Tc=6.0 min CN=98 Runoff=0.2 cfs 556 cf
Subcatchment4.6S: Townhouse TDs	Runoff Area=1,056 sf 99.24% Impervious Runoff Depth=6.16" Tc=6.0 min CN=98 Runoff=0.2 cfs 542 cf
Subcatchment5S: TD-1	Runoff Area=5,851 sf 51.63% Impervious Runoff Depth=4.79" Tc=6.0 min CN=86 Runoff=0.7 cfs 2,336 cf
Subcatchment6.1S: East driveway	Runoff Area=12,275 sf 52.50% Impervious Runoff Depth=4.90" Tc=6.0 min CN=87 Runoff=1.6 cfs 5,013 cf
Subcatchment6S: Bypass Towards	Runoff Area=51,539 sf 0.21% Impervious Runoff Depth=3.52" Flow Length=125' Tc=14.0 min CN=74 Runoff=3.8 cfs 15,135 cf
Subcatchment7S: To Street	Runoff Area=5,843 sf 18.07% Impervious Runoff Depth=3.93" Tc=6.0 min CN=78 Runoff=0.6 cfs 1,916 cf
Pond 1P: Underground Infiltration System	Peak Elev=7.85' Storage=9,468 cf Inflow=7.3 cfs 37,510 cf Discarded=0.1 cfs 11,761 cf Primary=2.8 cfs 25,748 cf Outflow=2.9 cfs 37,508 cf
Pond 2P: Rooftop Detention	Peak Elev=57.36' Storage=7,258 cf Inflow=3.6 cfs 12,895 cf Outflow=0.3 cfs 12,842 cf

Pond 3P: Rain garden Peak Elev=6.40' Storage=208 cf Inflow=1.6 cfs 5,013 cf
Discarded=0.0 cfs 442 cf Primary=1.6 cfs 4,571 cf Outflow=1.6 cfs 5,013 cf

Link 1L: Towards Wetlands Inflow=8.2 cfs 49,465 cf
Primary=8.2 cfs 49,465 cf

Link 2L: Towards Street Inflow=0.6 cfs 1,916 cf
Primary=0.6 cfs 1,916 cf

Link 100L: Total Flows Inflow=8.7 cfs 51,381 cf
Primary=8.7 cfs 51,381 cf

Total Runoff Area = 158,686 sf Runoff Volume = 63,637 cf Average Runoff Depth = 4.81"
50.45% Pervious = 80,060 sf 49.55% Impervious = 78,626 sf

Summary for Subcatchment 1S: CB-1


Runoff = 3.1 cfs @ 12.08 hrs, Volume= 10,138 cf, Depth= 5.35"
Routed to Pond 1P : Underground Infiltration System

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 10-Year Rainfall=6.40"

Area (sf)	CN	Description
16,410	98	Paved parking, HSG C
6,332	74	>75% Grass cover, Good, HSG C
22,742	91	Weighted Average
6,332		27.84% Pervious Area
16,410		72.16% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 1S: CB-1



Summary for Subcatchment 2.1S: Building Roof-Southeast


Runoff = 1.1 cfs @ 12.08 hrs, Volume= 4,011 cf, Depth= 6.16"
Routed to Link 1L : Towards Wetlands

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 10-Year Rainfall=6.40"

Area (sf)	CN	Description
7,811	98	Roofs, HSG C
7,811		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 2.1S: Building Roof-Southeast



Summary for Subcatchment 2S: Building Roof


Runoff = 3.6 cfs @ 12.08 hrs, Volume= 12,895 cf, Depth= 6.16"
Routed to Pond 2P : Rooftop Detention

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 10-Year Rainfall=6.40"

Area (sf)	CN	Description
25,114	98	Roofs, HSG C
25,114		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 2S: Building Roof



Summary for Subcatchment 3.1S: Backyard ADs

Runoff = 0.8 cfs @ 12.14 hrs, Volume= 2,715 cf, Depth= 3.63"
Routed to Pond 1P : Underground Infiltration System

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 10-Year Rainfall=6.40"


Area (sf)	CN	Description
272	98	Unconnected pavement, HSG C
8,302	74	>75% Grass cover, Good, HSG C
411	89	Gravel sidewalk, HSG C

8,985	75	Weighted Average
8,713		96.97% Pervious Area
272		3.03% Impervious Area
272		100.00% Unconnected

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
9.4	50	0.0142	0.09		Sheet Flow, Grass: Dense n= 0.240 P2= 3.23"
0.9	97	0.0154	1.86		Shallow Concentrated Flow, Grassed Waterway Kv= 15.0 fps

10.3 147 Total

Subcatchment 3.1S: Backyard ADs



Summary for Subcatchment 3S: Townhouse Roofs


Runoff = 1.9 cfs @ 12.08 hrs, Volume= 6,709 cf, Depth= 6.16"
Routed to Pond 1P : Underground Infiltration System

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 10-Year Rainfall=6.40"

Area (sf)	CN	Description
13,067	98	Roofs, HSG C
13,067		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 3S: Townhouse Roofs



Summary for Subcatchment 4.2S: Townhouse TDs


Runoff = 0.2 cfs @ 12.08 hrs, Volume= 560 cf, Depth= 6.04"
Routed to Pond 1P : Underground Infiltration System

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 10-Year Rainfall=6.40"

Area (sf)	CN	Description
1,064	98	Paved parking, HSG C
48	74	>75% Grass cover, Good, HSG C
1,112	97	Weighted Average
48		4.32% Pervious Area
1,064		95.68% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.2S: Townhouse TDs



Summary for Subcatchment 4.3S: Townhouse TDs


Runoff = 0.2 cfs @ 12.08 hrs, Volume= 556 cf, Depth= 6.04"
Routed to Pond 1P : Underground Infiltration System

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 10-Year Rainfall=6.40"

Area (sf)	CN	Description
1,075	98	Paved parking, HSG C
30	74	>75% Grass cover, Good, HSG C
1,105	97	Weighted Average
30		2.71% Pervious Area
1,075		97.29% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.3S: Townhouse TDs



Summary for Subcatchment 4.4S: Townhouse TDs


Runoff = 0.2 cfs @ 12.08 hrs, Volume= 556 cf, Depth= 6.04"
Routed to Pond 1P : Underground Infiltration System

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 10-Year Rainfall=6.40"

Area (sf)	CN	Description
1,076	98	Paved parking, HSG C
28	74	>75% Grass cover, Good, HSG C
1,104	97	Weighted Average
28		2.54% Pervious Area
1,076		97.46% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.4S: Townhouse TDs



Summary for Subcatchment 4.5S: Townhouse TDs


Runoff = 0.2 cfs @ 12.08 hrs, Volume= 556 cf, Depth= 6.16"
Routed to Pond 1P : Underground Infiltration System

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 10-Year Rainfall=6.40"

Area (sf)	CN	Description
1,061	98	Paved parking, HSG C
21	74	>75% Grass cover, Good, HSG C
1,082	98	Weighted Average
21		1.94% Pervious Area
1,061		98.06% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.5S: Townhouse TDs



Summary for Subcatchment 4.6S: Townhouse TDs


Runoff = 0.2 cfs @ 12.08 hrs, Volume= 542 cf, Depth= 6.16"
Routed to Pond 1P : Underground Infiltration System

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 10-Year Rainfall=6.40"

Area (sf)	CN	Description
1,048	98	Paved parking, HSG C
8	74	>75% Grass cover, Good, HSG C
1,056	98	Weighted Average
8		0.76% Pervious Area
1,048		99.24% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.6S: Townhouse TDs



Summary for Subcatchment 5S: TD-1


Runoff = 0.7 cfs @ 12.09 hrs, Volume= 2,336 cf, Depth= 4.79"
Routed to Pond 1P : Underground Infiltration System

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 10-Year Rainfall=6.40"

Area (sf)	CN	Description
3,021	98	Paved parking, HSG C
2,830	74	>75% Grass cover, Good, HSG C
5,851	86	Weighted Average
2,830		48.37% Pervious Area
3,021		51.63% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 5S: TD-1



Summary for Subcatchment 6.1S: East driveway


Runoff = 1.6 cfs @ 12.09 hrs, Volume= 5,013 cf, Depth= 4.90"
Routed to Pond 3P : Rain garden

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 10-Year Rainfall=6.40"

Area (sf)	CN	Description
5,611	74	>75% Grass cover, Good, HSG C
6,444	98	Paved roads w/curbs & sewers, HSG C
220	89	Gravel roads, HSG C
12,275	87	Weighted Average
5,831		47.50% Pervious Area
6,444		52.50% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

Subcatchment 6.1S: East driveway




Summary for Subcatchment 6S: Bypass Towards Wetlands

Runoff = 3.8 cfs @ 12.19 hrs, Volume= 15,135 cf, Depth= 3.52"
Routed to Link 1L : Towards Wetlands

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 10-Year Rainfall=6.40"

Area (sf)	CN	Description
4,985	70	Woods, Good, HSG C
46,447	74	>75% Grass cover, Good, HSG C
107	98	Roofs, HSG C
51,539	74	Weighted Average
51,432		99.79% Pervious Area
107		0.21% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.8	50	0.0220	0.07		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.23"
2.2	75	0.0133	0.58		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
14.0	125	Total			




Summary for Subcatchment 7S: To Street

Runoff = 0.6 cfs @ 12.09 hrs, Volume= 1,916 cf, Depth= 3.93"
Routed to Link 2L : Towards Street

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 10-Year Rainfall=6.40"

Area (sf)	CN	Description
1,056	98	Paved parking, HSG C
4,787	74	>75% Grass cover, Good, HSG C
5,843	78	Weighted Average
4,787		81.93% Pervious Area
1,056		18.07% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc



Summary for Pond 1P: Underground Infiltration System

Inflow Area = 81,218 sf, 77.83% Impervious, Inflow Depth > 5.54" for 10-Year event
Inflow = 7.3 cfs @ 12.09 hrs, Volume= 37,510 cf
Outflow = 2.9 cfs @ 12.35 hrs, Volume= 37,508 cf, Atten= 60%, Lag= 15.7 min
Discarded = 0.1 cfs @ 7.20 hrs, Volume= 11,761 cf
Primary = 2.8 cfs @ 12.35 hrs, Volume= 25,748 cf
Routed to Link 1L : Towards Wetlands

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Peak Elev= 7.85' @ 12.35 hrs Surf.Area= 8,137 sf Storage= 9,468 cf

Plug-Flow detention time= 140.1 min calculated for 37,508 cf (100% of inflow)
Center-of-Mass det. time= 139.9 min (1,041.4 - 901.5)


Volume	Invert	Avail.Storage	Storage Description
#1	6.50'	17,495 cf	6.89'W x 14.06'L x 2.50'H StormTrap ST-1 Units (Irregular Shape) 84 20,343 cf Overall x 86.0% Voids

Device	Routing	Invert	Outlet Devices
#1	Discarded	6.50'	0.520 in/hr Exfiltration over Surface area
#2	Primary	6.80'	18.0" Round Culvert L= 190.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 6.80' / 6.00' S= 0.0042 ' S= 0.0042 ' Cc= 0.900 n= 0.013, Flow Area= 1.77 sf
#3	Device 2	6.80'	12.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 2	8.25'	4.0' long Sharp-Crested Rectangular Weir 2 End Contraction(s)

Discarded OutFlow Max=0.1 cfs @ 7.20 hrs HW=6.53' (Free Discharge)
1=Exfiltration (Exfiltration Controls 0.1 cfs)

Primary OutFlow Max=2.8 cfs @ 12.35 hrs HW=7.85' (Free Discharge)
2=Culvert (Passes 2.8 cfs of 3.6 cfs potential flow)
3=Orifice/Grate (Orifice Controls 2.8 cfs @ 3.58 fps)
4=Sharp-Crested Rectangular Weir(Controls 0.0 cfs)

Pond 1P: Underground Infiltration System



Summary for Pond 2P: Rooftop Detention

Inflow Area = 25,114 sf,100.00% Impervious, Inflow Depth = 6.16" for 10-Year event
Inflow = 3.6 cfs @ 12.08 hrs, Volume= 12,895 cf
Outflow = 0.3 cfs @ 13.30 hrs, Volume= 12,842 cf, Atten= 93%, Lag= 72.7 min
Primary = 0.3 cfs @ 13.30 hrs, Volume= 12,842 cf
Routed to Pond 1P : Underground Infiltration System

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs / 3
Peak Elev= 57.36' @ 13.30 hrs Surf.Area= 20,000 sf Storage= 7,258 cf

Plug-Flow detention time= 406.8 min calculated for 12,842 cf (100% of inflow)
Center-of-Mass det. time= 404.0 min (1,148.2 - 744.2)


Volume	Invert	Avail.Storage	Storage Description
#1	57.00'	14,000 cf	Rooftop Detention (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
57.00	20,000	0	0
57.70	20,000	14,000	14,000

Device	Routing	Invert	Outlet Devices
#1	Primary	8.02'	12.0" Round Roof Drain L= 16.0' CPP, mitered to conform to fill, Ke= 0.700 Inlet / Outlet Invert= 8.02' / 7.70' S= 0.0200 '/' Cc= 0.900 n= 0.013, Flow Area= 0.79 sf
#2	Device 1	57.00'	4.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads

Primary OutFlow Max=0.3 cfs @ 13.30 hrs HW=57.36' (Free Discharge)
1=Roof Drain (Passes 0.3 cfs of 23.3 cfs potential flow)
2=Orifice/Grate (Orifice Controls 0.3 cfs @ 2.90 fps)

Pond 2P: Rooftop Detention



Summary for Pond 3P: Rain garden

Inflow Area = 12,275 sf, 52.50% Impervious, Inflow Depth = 4.90" for 10-Year event
Inflow = 1.6 cfs @ 12.09 hrs, Volume= 5,013 cf
Outflow = 1.6 cfs @ 12.09 hrs, Volume= 5,013 cf, Atten= 0%, Lag= 0.3 min
Discarded = 0.0 cfs @ 12.09 hrs, Volume= 442 cf
Primary = 1.6 cfs @ 12.09 hrs, Volume= 4,571 cf
Routed to Link 1L : Towards Wetlands

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Peak Elev= 6.40' @ 12.09 hrs Surf.Area= 402 sf Storage= 208 cf

Plug-Flow detention time= 47.7 min calculated for 5,012 cf (100% of inflow)
Center-of-Mass det. time= 47.9 min (840.3 - 792.4)


Volume	Invert	Avail.Storage	Storage Description			
#1	5.60'	253 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)	
5.60	125	46.0	0	0	125	
6.00	276	66.0	78	78	305	
6.30	350	73.0	94	172	385	
6.50	460	87.0	81	253	564	

Device	Routing	Invert	Outlet Devices													
#1	Discarded	5.60'	0.520 in/hr Exfiltration over Surface area													
#2	Primary	6.30'	22.0' long x 5.0' breadth Broad-Crested Rectangular Weir													
			Head (feet)	0.20	0.40	0.60	0.80	1.00	1.20	1.40	1.60	1.80	2.00	2.50	3.00	3.50
			Coef. (English)	2.34	2.50	2.70	2.68	2.68	2.66	2.65	2.65	2.65	2.65	2.65	2.67	2.66
				2.65	2.67	2.66	2.68	2.70	2.74	2.79	2.88					

Discarded OutFlow Max=0.0 cfs @ 12.09 hrs HW=6.40' (Free Discharge)
1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=1.6 cfs @ 12.09 hrs HW=6.40' (Free Discharge)
2=Broad-Crested Rectangular Weir (Weir Controls 1.6 cfs @ 0.73 fps)

Pond 3P: Rain garden




Summary for Link 1L: Towards Wetlands

Inflow Area = 152,843 sf, 50.75% Impervious, Inflow Depth = 3.88" for 10-Year event
Inflow = 8.2 cfs @ 12.15 hrs, Volume= 49,465 cf
Primary = 8.2 cfs @ 12.15 hrs, Volume= 49,465 cf, Atten= 0%, Lag= 0.0 min
Routed to Link 100L : Total Flows

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link 1L: Towards Wetlands




Summary for Link 2L: Towards Street

Inflow Area = 5,843 sf, 18.07% Impervious, Inflow Depth = 3.93" for 10-Year event
Inflow = 0.6 cfs @ 12.09 hrs, Volume= 1,916 cf
Primary = 0.6 cfs @ 12.09 hrs, Volume= 1,916 cf, Atten= 0%, Lag= 0.0 min
Routed to Link 100L : Total Flows

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs


Link 2L: Towards Street



Summary for Link 100L: Total Flows

Inflow Area = 158,686 sf, 49.55% Impervious, Inflow Depth = 3.89" for 10-Year event
Inflow = 8.7 cfs @ 12.14 hrs, Volume= 51,381 cf
Primary = 8.7 cfs @ 12.14 hrs, Volume= 51,381 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs



Time span=0.00-72.00 hrs, dt=0.01 hrs, 7201 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment1S: CB-1	Runoff Area=22,742 sf 72.16% Impervious Runoff Depth=7.22" Tc=6.0 min CN=91 Runoff=4.1 cfs 13,685 cf
Subcatchment2.1S: Building	Runoff Area=7,811 sf 100.00% Impervious Runoff Depth=8.06" Tc=6.0 min CN=98 Runoff=1.5 cfs 5,246 cf
Subcatchment2S: Building Roof	Runoff Area=25,114 sf 100.00% Impervious Runoff Depth=8.06" Tc=6.0 min CN=98 Runoff=4.7 cfs 16,868 cf
Subcatchment3.1S: Backyard ADs	Runoff Area=8,985 sf 3.03% Impervious Runoff Depth=5.31" Flow Length=147' Tc=10.3 min CN=75 Runoff=1.1 cfs 3,978 cf
Subcatchment3S: Townhouse Roofs	Runoff Area=13,067 sf 100.00% Impervious Runoff Depth=8.06" Tc=6.0 min CN=98 Runoff=2.4 cfs 8,777 cf
Subcatchment4.2S: Townhouse TDs	Runoff Area=1,112 sf 95.68% Impervious Runoff Depth=7.94" Tc=6.0 min CN=97 Runoff=0.2 cfs 736 cf
Subcatchment4.3S: Townhouse TDs	Runoff Area=1,105 sf 97.29% Impervious Runoff Depth=7.94" Tc=6.0 min CN=97 Runoff=0.2 cfs 731 cf
Subcatchment4.4S: Townhouse TDs	Runoff Area=1,104 sf 97.46% Impervious Runoff Depth=7.94" Tc=6.0 min CN=97 Runoff=0.2 cfs 730 cf
Subcatchment4.5S: Townhouse TDs	Runoff Area=1,082 sf 98.06% Impervious Runoff Depth=8.06" Tc=6.0 min CN=98 Runoff=0.2 cfs 727 cf
Subcatchment4.6S: Townhouse TDs	Runoff Area=1,056 sf 99.24% Impervious Runoff Depth=8.06" Tc=6.0 min CN=98 Runoff=0.2 cfs 709 cf
Subcatchment5S: TD-1	Runoff Area=5,851 sf 51.63% Impervious Runoff Depth=6.62" Tc=6.0 min CN=86 Runoff=1.0 cfs 3,229 cf
Subcatchment6.1S: East driveway	Runoff Area=12,275 sf 52.50% Impervious Runoff Depth=6.74" Tc=6.0 min CN=87 Runoff=2.1 cfs 6,897 cf
Subcatchment6S: Bypass Towards	Runoff Area=51,539 sf 0.21% Impervious Runoff Depth=5.19" Flow Length=125' Tc=14.0 min CN=74 Runoff=5.6 cfs 22,311 cf
Subcatchment7S: To Street	Runoff Area=5,843 sf 18.07% Impervious Runoff Depth=5.67" Tc=6.0 min CN=78 Runoff=0.9 cfs 2,760 cf
Pond 1P: Underground Infiltration System	Peak Elev=8.22' Storage=12,020 cf Inflow=9.7 cfs 50,110 cf Discarded=0.1 cfs 13,046 cf Primary=3.6 cfs 37,062 cf Outflow=3.7 cfs 50,108 cf
Pond 2P: Rooftop Detention	Peak Elev=57.48' Storage=9,608 cf Inflow=4.7 cfs 16,868 cf Outflow=0.3 cfs 16,808 cf

Pond 3P: Rain garden

Peak Elev=6.42' Storage=217 cf Inflow=2.1 cfs 6,897 cf
Discarded=0.0 cfs 459 cf Primary=2.1 cfs 6,438 cf Outflow=2.1 cfs 6,897 cf

Link 1L: Towards Wetlands

Inflow=11.4 cfs 71,057 cf
Primary=11.4 cfs 71,057 cf

Link 2L: Towards Street

Inflow=0.9 cfs 2,760 cf
Primary=0.9 cfs 2,760 cf

Link 100L: Total Flows

Inflow=12.1 cfs 73,817 cf
Primary=12.1 cfs 73,817 cf

Total Runoff Area = 158,686 sf Runoff Volume = 87,385 cf Average Runoff Depth = 6.61"
50.45% Pervious = 80,060 sf 49.55% Impervious = 78,626 sf

Summary for Subcatchment 1S: CB-1


Runoff = 4.1 cfs @ 12.08 hrs, Volume= 13,685 cf, Depth= 7.22"
Routed to Pond 1P : Underground Infiltration System

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 25-Year Rainfall=8.30"

Area (sf)	CN	Description
16,410	98	Paved parking, HSG C
6,332	74	>75% Grass cover, Good, HSG C
22,742	91	Weighted Average
6,332		27.84% Pervious Area
16,410		72.16% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 1S: CB-1



Summary for Subcatchment 2.1S: Building Roof-Southeast


Runoff = 1.5 cfs @ 12.08 hrs, Volume= 5,246 cf, Depth= 8.06"
Routed to Link 1L : Towards Wetlands

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 25-Year Rainfall=8.30"

Area (sf)	CN	Description
7,811	98	Roofs, HSG C
7,811		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 2.1S: Building Roof-Southeast



Summary for Subcatchment 2S: Building Roof


Runoff = 4.7 cfs @ 12.08 hrs, Volume= 16,868 cf, Depth= 8.06"
Routed to Pond 2P : Rooftop Detention

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 25-Year Rainfall=8.30"

Area (sf)	CN	Description
25,114	98	Roofs, HSG C
25,114		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 2S: Building Roof



Summary for Subcatchment 3.1S: Backyard ADs


Runoff = 1.1 cfs @ 12.14 hrs, Volume= 3,978 cf, Depth= 5.31"
Routed to Pond 1P : Underground Infiltration System

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 25-Year Rainfall=8.30"

Area (sf)	CN	Description
272	98	Unconnected pavement, HSG C
8,302	74	>75% Grass cover, Good, HSG C
411	89	Gravel sidewalk, HSG C
8,985	75	Weighted Average
8,713		96.97% Pervious Area
272		3.03% Impervious Area
272		100.00% Unconnected

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
9.4	50	0.0142	0.09		Sheet Flow, Grass: Dense n= 0.240 P2= 3.23"
0.9	97	0.0154	1.86		Shallow Concentrated Flow, Grassed Waterway Kv= 15.0 fps
10.3	147	Total			

Subcatchment 3.1S: Backyard ADs



Summary for Subcatchment 3S: Townhouse Roofs


Runoff = 2.4 cfs @ 12.08 hrs, Volume= 8,777 cf, Depth= 8.06"
Routed to Pond 1P : Underground Infiltration System

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 25-Year Rainfall=8.30"

Area (sf)	CN	Description
13,067	98	Roofs, HSG C
13,067		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 3S: Townhouse Roofs



Summary for Subcatchment 4.2S: Townhouse TDs


Runoff = 0.2 cfs @ 12.08 hrs, Volume= 736 cf, Depth= 7.94"
Routed to Pond 1P : Underground Infiltration System

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 25-Year Rainfall=8.30"

Area (sf)	CN	Description
1,064	98	Paved parking, HSG C
48	74	>75% Grass cover, Good, HSG C
1,112	97	Weighted Average
48		4.32% Pervious Area
1,064		95.68% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.2S: Townhouse TDs



Summary for Subcatchment 4.3S: Townhouse TDs


Runoff = 0.2 cfs @ 12.08 hrs, Volume= 731 cf, Depth= 7.94"
Routed to Pond 1P : Underground Infiltration System

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 25-Year Rainfall=8.30"

Area (sf)	CN	Description
1,075	98	Paved parking, HSG C
30	74	>75% Grass cover, Good, HSG C
1,105	97	Weighted Average
30		2.71% Pervious Area
1,075		97.29% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.3S: Townhouse TDs



Summary for Subcatchment 4.4S: Townhouse TDs


Runoff = 0.2 cfs @ 12.08 hrs, Volume= 730 cf, Depth= 7.94"
Routed to Pond 1P : Underground Infiltration System

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 25-Year Rainfall=8.30"

Area (sf)	CN	Description
1,076	98	Paved parking, HSG C
28	74	>75% Grass cover, Good, HSG C
1,104	97	Weighted Average
28		2.54% Pervious Area
1,076		97.46% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.4S: Townhouse TDs



Summary for Subcatchment 4.5S: Townhouse TDs


Runoff = 0.2 cfs @ 12.08 hrs, Volume= 727 cf, Depth= 8.06"
Routed to Pond 1P : Underground Infiltration System

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 25-Year Rainfall=8.30"

Area (sf)	CN	Description
1,061	98	Paved parking, HSG C
21	74	>75% Grass cover, Good, HSG C
1,082	98	Weighted Average
21		1.94% Pervious Area
1,061		98.06% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.5S: Townhouse TDs



Summary for Subcatchment 4.6S: Townhouse TDs


Runoff = 0.2 cfs @ 12.08 hrs, Volume= 709 cf, Depth= 8.06"
Routed to Pond 1P : Underground Infiltration System

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 25-Year Rainfall=8.30"

Area (sf)	CN	Description
1,048	98	Paved parking, HSG C
8	74	>75% Grass cover, Good, HSG C
1,056	98	Weighted Average
8		0.76% Pervious Area
1,048		99.24% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.6S: Townhouse TDs



Summary for Subcatchment 5S: TD-1


Runoff = 1.0 cfs @ 12.08 hrs, Volume= 3,229 cf, Depth= 6.62"
Routed to Pond 1P : Underground Infiltration System

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 25-Year Rainfall=8.30"

Area (sf)	CN	Description
3,021	98	Paved parking, HSG C
2,830	74	>75% Grass cover, Good, HSG C
5,851	86	Weighted Average
2,830		48.37% Pervious Area
3,021		51.63% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 5S: TD-1



Summary for Subcatchment 6.1S: East driveway


Runoff = 2.1 cfs @ 12.08 hrs, Volume= 6,897 cf, Depth= 6.74"
Routed to Pond 3P : Rain garden

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 25-Year Rainfall=8.30"

Area (sf)	CN	Description
5,611	74	>75% Grass cover, Good, HSG C
6,444	98	Paved roads w/curbs & sewers, HSG C
220	89	Gravel roads, HSG C
12,275	87	Weighted Average
5,831		47.50% Pervious Area
6,444		52.50% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

Subcatchment 6.1S: East driveway



Summary for Subcatchment 6S: Bypass Towards Wetlands


Runoff = 5.6 cfs @ 12.19 hrs, Volume= 22,311 cf, Depth= 5.19"
Routed to Link 1L : Towards Wetlands

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 25-Year Rainfall=8.30"

Area (sf)	CN	Description
4,985	70	Woods, Good, HSG C
46,447	74	>75% Grass cover, Good, HSG C
107	98	Roofs, HSG C
51,539	74	Weighted Average
51,432		99.79% Pervious Area
107		0.21% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.8	50	0.0220	0.07		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.23"
2.2	75	0.0133	0.58		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
14.0	125	Total			

Subcatchment 6S: Bypass Towards Wetlands



Summary for Subcatchment 7S: To Street


Runoff = 0.9 cfs @ 12.09 hrs, Volume= 2,760 cf, Depth= 5.67"
Routed to Link 2L : Towards Street

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 25-Year Rainfall=8.30"

Area (sf)	CN	Description
1,056	98	Paved parking, HSG C
4,787	74	>75% Grass cover, Good, HSG C
5,843	78	Weighted Average
4,787		81.93% Pervious Area
1,056		18.07% Impervious Area

Tc	Length	Slope	Velocity	Capacity	Description
(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)	
6.0					Direct Entry, Min. Tc

Subcatchment 7S: To Street



Summary for Pond 1P: Underground Infiltration System

Inflow Area = 81,218 sf, 77.83% Impervious, Inflow Depth = 7.40" for 25-Year event
Inflow = 9.7 cfs @ 12.09 hrs, Volume= 50,110 cf
Outflow = 3.7 cfs @ 12.36 hrs, Volume= 50,108 cf, Atten= 62%, Lag= 16.4 min
Discarded = 0.1 cfs @ 5.98 hrs, Volume= 13,046 cf
Primary = 3.6 cfs @ 12.36 hrs, Volume= 37,062 cf
Routed to Link 1L : Towards Wetlands

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Peak Elev= 8.22' @ 12.36 hrs Surf.Area= 8,137 sf Storage= 12,020 cf

Plug-Flow detention time= 127.6 min calculated for 50,101 cf (100% of inflow)
Center-of-Mass det. time= 127.5 min (1,033.4 - 905.9)


Volume	Invert	Avail.Storage	Storage Description
#1	6.50'	17,495 cf	6.89'W x 14.06'L x 2.50'H StormTrap ST-1 Units (Irregular Shape) 84 20,343 cf Overall x 86.0% Voids

Device	Routing	Invert	Outlet Devices
#1	Discarded	6.50'	0.520 in/hr Exfiltration over Surface area
#2	Primary	6.80'	18.0" Round Culvert L= 190.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 6.80' / 6.00' S= 0.0042 ' /' Cc= 0.900 n= 0.013, Flow Area= 1.77 sf
#3	Device 2	6.80'	12.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 2	8.25'	4.0' long Sharp-Crested Rectangular Weir 2 End Contraction(s)

Discarded OutFlow Max=0.1 cfs @ 5.98 hrs HW=6.53' (Free Discharge)
1=Exfiltration (Exfiltration Controls 0.1 cfs)

Primary OutFlow Max=3.6 cfs @ 12.36 hrs HW=8.22' (Free Discharge)
2=Culvert (Passes 3.6 cfs of 5.6 cfs potential flow)
3=Orifice/Grate (Orifice Controls 3.6 cfs @ 4.61 fps)
4=Sharp-Crested Rectangular Weir (Controls 0.0 cfs)

Pond 1P: Underground Infiltration System



Summary for Pond 2P: Rooftop Detention

Inflow Area = 25,114 sf, 100.00% Impervious, Inflow Depth = 8.06" for 25-Year event
Inflow = 4.7 cfs @ 12.08 hrs, Volume= 16,868 cf
Outflow = 0.3 cfs @ 13.62 hrs, Volume= 16,808 cf, Atten= 94%, Lag= 92.1 min
Primary = 0.3 cfs @ 13.62 hrs, Volume= 16,808 cf
Routed to Pond 1P : Underground Infiltration System

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs / 3
Peak Elev= 57.48' @ 13.62 hrs Surf.Area= 20,000 sf Storage= 9,608 cf

Plug-Flow detention time= 442.0 min calculated for 16,805 cf (100% of inflow)
Center-of-Mass det. time= 439.8 min (1,180.6 - 740.8)


Volume	Invert	Avail.Storage	Storage Description
#1	57.00'	14,000 cf	Rooftop Detention (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
57.00	20,000	0	0
57.70	20,000	14,000	14,000

Device	Routing	Invert	Outlet Devices
#1	Primary	8.02'	12.0" Round Roof Drain L= 16.0' CPP, mitered to conform to fill, Ke= 0.700 Inlet / Outlet Invert= 8.02' / 7.70' S= 0.0200 '/' Cc= 0.900 n= 0.013, Flow Area= 0.79 sf
#2	Device 1	57.00'	4.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads

Primary OutFlow Max=0.3 cfs @ 13.62 hrs HW=57.48' (Free Discharge)
1=Roof Drain (Passes 0.3 cfs of 23.3 cfs potential flow)
2=Orifice/Grate (Orifice Controls 0.3 cfs @ 3.34 fps)

Pond 2P: Rooftop Detention



Summary for Pond 3P: Rain garden

Inflow Area = 12,275 sf, 52.50% Impervious, Inflow Depth = 6.74" for 25-Year event
Inflow = 2.1 cfs @ 12.08 hrs, Volume= 6,897 cf
Outflow = 2.1 cfs @ 12.09 hrs, Volume= 6,897 cf, Atten= 0%, Lag= 0.3 min
Discarded = 0.0 cfs @ 12.09 hrs, Volume= 459 cf
Primary = 2.1 cfs @ 12.09 hrs, Volume= 6,438 cf
Routed to Link 1L : Towards Wetlands

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Peak Elev= 6.42' @ 12.09 hrs Surf.Area= 414 sf Storage= 217 cf

Plug-Flow detention time= 36.5 min calculated for 6,896 cf (100% of inflow)
Center-of-Mass det. time= 36.7 min (820.5 - 783.8)


Volume	Invert	Avail.Storage	Storage Description		
#1	5.60'	253 cf	Custom Stage Data (Irregular) Listed below (Recalc)		
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
5.60	125	46.0	0	0	125
6.00	276	66.0	78	78	305
6.30	350	73.0	94	172	385
6.50	460	87.0	81	253	564

Device	Routing	Invert	Outlet Devices
#1	Discarded	5.60'	0.520 in/hr Exfiltration over Surface area
#2	Primary	6.30'	22.0' long x 5.0' breadth Broad-Crested Rectangular Weir
Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00			
2.50 3.00 3.50 4.00 4.50 5.00 5.50			
Coef. (English) 2.34 2.50 2.70 2.68 2.68 2.66 2.65 2.65 2.65			
2.65 2.67 2.66 2.68 2.70 2.74 2.79 2.88			

Discarded OutFlow Max=0.0 cfs @ 12.09 hrs HW=6.42' (Free Discharge)
1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=2.1 cfs @ 12.09 hrs HW=6.42' (Free Discharge)
2=Broad-Crested Rectangular Weir (Weir Controls 2.1 cfs @ 0.81 fps)

Pond 3P: Rain garden




Summary for Link 1L: Towards Wetlands

Inflow Area = 152,843 sf, 50.75% Impervious, Inflow Depth = 5.58" for 25-Year event
Inflow = 11.4 cfs @ 12.15 hrs, Volume= 71,057 cf
Primary = 11.4 cfs @ 12.15 hrs, Volume= 71,057 cf, Atten= 0%, Lag= 0.0 min
Routed to Link 100L : Total Flows

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link 1L: Towards Wetlands




Summary for Link 2L: Towards Street

Inflow Area = 5,843 sf, 18.07% Impervious, Inflow Depth = 5.67" for 25-Year event
Inflow = 0.9 cfs @ 12.09 hrs, Volume= 2,760 cf
Primary = 0.9 cfs @ 12.09 hrs, Volume= 2,760 cf, Atten= 0%, Lag= 0.0 min
Routed to Link 100L : Total Flows

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link 2L: Towards Street

Hydrograph




Summary for Link 100L: Total Flows

Inflow Area = 158,686 sf, 49.55% Impervious, Inflow Depth = 5.58" for 25-Year event
Inflow = 12.1 cfs @ 12.14 hrs, Volume= 73,817 cf
Primary = 12.1 cfs @ 12.14 hrs, Volume= 73,817 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link 100L: Total Flows

Hydrograph



Time span=0.00-72.00 hrs, dt=0.01 hrs, 7201 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment1S: CB-1	Runoff Area=22,742 sf 72.16% Impervious Runoff Depth=8.58" Tc=6.0 min CN=91 Runoff=4.8 cfs 16,254 cf
Subcatchment2.1S: Building	Runoff Area=7,811 sf 100.00% Impervious Runoff Depth=9.43" Tc=6.0 min CN=98 Runoff=1.7 cfs 6,138 cf
Subcatchment2S: Building Roof	Runoff Area=25,114 sf 100.00% Impervious Runoff Depth=9.43" Tc=6.0 min CN=98 Runoff=5.5 cfs 19,734 cf
Subcatchment3.1S: BackyardADs	Runoff Area=8,985 sf 3.03% Impervious Runoff Depth=6.57" Flow Length=147' Tc=10.3 min CN=75 Runoff=1.4 cfs 4,920 cf
Subcatchment3S: Townhouse Roofs	Runoff Area=13,067 sf 100.00% Impervious Runoff Depth=9.43" Tc=6.0 min CN=98 Runoff=2.9 cfs 10,268 cf
Subcatchment4.2S: Townhouse TDs	Runoff Area=1,112 sf 95.68% Impervious Runoff Depth=9.31" Tc=6.0 min CN=97 Runoff=0.2 cfs 863 cf
Subcatchment4.3S: Townhouse TDs	Runoff Area=1,105 sf 97.29% Impervious Runoff Depth=9.31" Tc=6.0 min CN=97 Runoff=0.2 cfs 857 cf
Subcatchment4.4S: Townhouse TDs	Runoff Area=1,104 sf 97.46% Impervious Runoff Depth=9.31" Tc=6.0 min CN=97 Runoff=0.2 cfs 856 cf
Subcatchment4.5S: Townhouse TDs	Runoff Area=1,082 sf 98.06% Impervious Runoff Depth=9.43" Tc=6.0 min CN=98 Runoff=0.2 cfs 850 cf
Subcatchment4.6S: Townhouse TDs	Runoff Area=1,056 sf 99.24% Impervious Runoff Depth=9.43" Tc=6.0 min CN=98 Runoff=0.2 cfs 830 cf
Subcatchment5S: TD-1	Runoff Area=5,851 sf 51.63% Impervious Runoff Depth=7.96" Tc=6.0 min CN=86 Runoff=1.2 cfs 3,880 cf
Subcatchment6.1S: East driveway	Runoff Area=12,275 sf 52.50% Impervious Runoff Depth=8.08" Tc=6.0 min CN=87 Runoff=2.5 cfs 8,268 cf
Subcatchment6S: Bypass Towards	Runoff Area=51,539 sf 0.21% Impervious Runoff Depth=6.44" Flow Length=125' Tc=14.0 min CN=74 Runoff=6.9 cfs 27,672 cf
Subcatchment7S: To Street	Runoff Area=5,843 sf 18.07% Impervious Runoff Depth=6.95" Tc=6.0 min CN=78 Runoff=1.1 cfs 3,385 cf
Pond 1P: Underground Infiltration System	Peak Elev=8.42' Storage=13,421 cf Inflow=11.5 cfs 59,246 cf Discarded=0.1 cfs 13,870 cf Primary=4.9 cfs 45,374 cf Outflow=5.0 cfs 59,244 cf
Pond 2P: Rooftop Detention	Peak Elev=57.57' Storage=11,360 cf Inflow=5.5 cfs 19,734 cf Outflow=0.3 cfs 19,668 cf

Pond 3P: Rain garden Peak Elev=6.43' Storage=223 cf Inflow=2.5 cfs 8,268 cf
Discarded=0.0 cfs 469 cf Primary=2.5 cfs 7,799 cf Outflow=2.5 cfs 8,268 cf

Link 1L: Towards Wetlands Inflow=13.7 cfs 86,982 cf
Primary=13.7 cfs 86,982 cf

Link 2L: Towards Street Inflow=1.1 cfs 3,385 cf
Primary=1.1 cfs 3,385 cf

Link 100L: Total Flows Inflow=14.4 cfs 90,367 cf
Primary=14.4 cfs 90,367 cf

Total Runoff Area = 158,686 sf Runoff Volume = 104,774 cf Average Runoff Depth = 7.92"
50.45% Pervious = 80,060 sf 49.55% Impervious = 78,626 sf

Summary for Subcatchment 1S: CB-1


Runoff = 4.8 cfs @ 12.08 hrs, Volume= 16,254 cf, Depth= 8.58"
Routed to Pond 1P : Underground Infiltration System

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 50-Year Rainfall=9.67"

Area (sf)	CN	Description
16,410	98	Paved parking, HSG C
6,332	74	>75% Grass cover, Good, HSG C
22,742	91	Weighted Average
6,332		27.84% Pervious Area
16,410		72.16% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 1S: CB-1



Summary for Subcatchment 2.1S: Building Roof-Southeast


Runoff = 1.7 cfs @ 12.08 hrs, Volume= 6,138 cf, Depth= 9.43"
Routed to Link 1L : Towards Wetlands

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 50-Year Rainfall=9.67"

Area (sf)	CN	Description
7,811	98	Roofs, HSG C
7,811		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 2.1S: Building Roof-Southeast



Summary for Subcatchment 2S: Building Roof


Runoff = 5.5 cfs @ 12.08 hrs, Volume= 19,734 cf, Depth= 9.43"
Routed to Pond 2P : Rooftop Detention

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 50-Year Rainfall=9.67"

Area (sf)	CN	Description
25,114	98	Roofs, HSG C
25,114		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 2S: Building Roof



Summary for Subcatchment 3.1S: Backyard ADs

Runoff = 1.4 cfs @ 12.14 hrs, Volume= 4,920 cf, Depth= 6.57"
Routed to Pond 1P : Underground Infiltration System

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 50-Year Rainfall=9.67"


Area (sf)	CN	Description
272	98	Unconnected pavement, HSG C
8,302	74	>75% Grass cover, Good, HSG C
411	89	Gravel sidewalk, HSG C

8,985	75	Weighted Average
8,713		96.97% Pervious Area
272		3.03% Impervious Area
272		100.00% Unconnected

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
9.4	50	0.0142	0.09		Sheet Flow, Grass: Dense n= 0.240 P2= 3.23"
0.9	97	0.0154	1.86		Shallow Concentrated Flow, Grassed Waterway Kv= 15.0 fps

10.3 147 Total

Subcatchment 3.1S: Backyard ADs



Summary for Subcatchment 3S: Townhouse Roofs


Runoff = 2.9 cfs @ 12.08 hrs, Volume= 10,268 cf, Depth= 9.43"
Routed to Pond 1P : Underground Infiltration System

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 50-Year Rainfall=9.67"

Area (sf)	CN	Description
13,067	98	Roofs, HSG C
13,067		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 3S: Townhouse Roofs



Summary for Subcatchment 4.2S: Townhouse TDs


Runoff = 0.2 cfs @ 12.08 hrs, Volume= 863 cf, Depth= 9.31"
Routed to Pond 1P : Underground Infiltration System

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 50-Year Rainfall=9.67"

Area (sf)	CN	Description
1,064	98	Paved parking, HSG C
48	74	>75% Grass cover, Good, HSG C
1,112	97	Weighted Average
48		4.32% Pervious Area
1,064		95.68% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.2S: Townhouse TDs



Summary for Subcatchment 4.3S: Townhouse TDs


Runoff = 0.2 cfs @ 12.08 hrs, Volume= 857 cf, Depth= 9.31"
Routed to Pond 1P : Underground Infiltration System

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 50-Year Rainfall=9.67"

Area (sf)	CN	Description
1,075	98	Paved parking, HSG C
30	74	>75% Grass cover, Good, HSG C
1,105	97	Weighted Average
30		2.71% Pervious Area
1,075		97.29% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.3S: Townhouse TDs



Summary for Subcatchment 4.4S: Townhouse TDs


Runoff = 0.2 cfs @ 12.08 hrs, Volume= 856 cf, Depth= 9.31"
Routed to Pond 1P : Underground Infiltration System

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 50-Year Rainfall=9.67"

Area (sf)	CN	Description
1,076	98	Paved parking, HSG C
28	74	>75% Grass cover, Good, HSG C
1,104	97	Weighted Average
28		2.54% Pervious Area
1,076		97.46% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.4S: Townhouse TDs



Summary for Subcatchment 4.5S: Townhouse TDs


Runoff = 0.2 cfs @ 12.08 hrs, Volume= 850 cf, Depth= 9.43"
Routed to Pond 1P : Underground Infiltration System

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 50-Year Rainfall=9.67"

Area (sf)	CN	Description
1,061	98	Paved parking, HSG C
21	74	>75% Grass cover, Good, HSG C
1,082	98	Weighted Average
21		1.94% Pervious Area
1,061		98.06% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.5S: Townhouse TDs



Summary for Subcatchment 4.6S: Townhouse TDs


Runoff = 0.2 cfs @ 12.08 hrs, Volume= 830 cf, Depth= 9.43"
Routed to Pond 1P : Underground Infiltration System

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 50-Year Rainfall=9.67"

Area (sf)	CN	Description
1,048	98	Paved parking, HSG C
8	74	>75% Grass cover, Good, HSG C
1,056	98	Weighted Average
8		0.76% Pervious Area
1,048		99.24% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.6S: Townhouse TDs



Summary for Subcatchment 5S: TD-1


Runoff = 1.2 cfs @ 12.08 hrs, Volume= 3,880 cf, Depth= 7.96"
Routed to Pond 1P : Underground Infiltration System

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 50-Year Rainfall=9.67"

Area (sf)	CN	Description
3,021	98	Paved parking, HSG C
2,830	74	>75% Grass cover, Good, HSG C
5,851	86	Weighted Average
2,830		48.37% Pervious Area
3,021		51.63% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 5S: TD-1



Summary for Subcatchment 6.1S: East driveway


Runoff = 2.5 cfs @ 12.08 hrs, Volume= 8,268 cf, Depth= 8.08"
Routed to Pond 3P : Rain garden

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 50-Year Rainfall=9.67"

Area (sf)	CN	Description
5,611	74	>75% Grass cover, Good, HSG C
6,444	98	Paved roads w/curbs & sewers, HSG C
220	89	Gravel roads, HSG C
12,275	87	Weighted Average
5,831		47.50% Pervious Area
6,444		52.50% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

Subcatchment 6.1S: East driveway




Summary for Subcatchment 6S: Bypass Towards Wetlands

Runoff = 6.9 cfs @ 12.19 hrs, Volume= 27,672 cf, Depth= 6.44"
Routed to Link 1L : Towards Wetlands

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 50-Year Rainfall=9.67"

Area (sf)	CN	Description
4,985	70	Woods, Good, HSG C
46,447	74	>75% Grass cover, Good, HSG C
107	98	Roofs, HSG C
51,539	74	Weighted Average
51,432		99.79% Pervious Area
107		0.21% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.8	50	0.0220	0.07		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.23"
2.2	75	0.0133	0.58		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
14.0	125	Total			




Summary for Subcatchment 7S: To Street

Runoff = 1.1 cfs @ 12.09 hrs, Volume= 3,385 cf, Depth= 6.95"
Routed to Link 2L : Towards Street

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 50-Year Rainfall=9.67"

Area (sf)	CN	Description
1,056	98	Paved parking, HSG C
4,787	74	>75% Grass cover, Good, HSG C
5,843	78	Weighted Average
4,787		81.93% Pervious Area
1,056		18.07% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc



Summary for Pond 1P: Underground Infiltration System

Inflow Area = 81,218 sf, 77.83% Impervious, Inflow Depth = 8.75" for 50-Year event
Inflow = 11.5 cfs @ 12.09 hrs, Volume= 59,246 cf
Outflow = 5.0 cfs @ 12.31 hrs, Volume= 59,244 cf, Atten= 56%, Lag= 13.2 min
Discarded = 0.1 cfs @ 5.12 hrs, Volume= 13,870 cf
Primary = 4.9 cfs @ 12.31 hrs, Volume= 45,374 cf
Routed to Link 1L : Towards Wetlands

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Peak Elev= 8.42' @ 12.31 hrs Surf.Area= 8,137 sf Storage= 13,421 cf

Plug-Flow detention time= 121.1 min calculated for 59,236 cf (100% of inflow)
Center-of-Mass det. time= 121.0 min (1,031.5 - 910.5)


Volume	Invert	Avail.Storage	Storage Description
#1	6.50'	17,495 cf	6.89'W x 14.06'L x 2.50'H StormTrap ST-1 Units (Irregular Shape) 84 20,343 cf Overall x 86.0% Voids

Device	Routing	Invert	Outlet Devices
#1	Discarded	6.50'	0.520 in/hr Exfiltration over Surface area
#2	Primary	6.80'	18.0" Round Culvert L= 190.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 6.80' / 6.00' S= 0.0042 ' S= 0.0042 ' Cc= 0.900 n= 0.013, Flow Area= 1.77 sf
#3	Device 2	6.80'	12.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 2	8.25'	4.0' long Sharp-Crested Rectangular Weir 2 End Contraction(s)

Discarded OutFlow Max=0.1 cfs @ 5.12 hrs HW=6.53' (Free Discharge)
1=Exfiltration (Exfiltration Controls 0.1 cfs)

Primary OutFlow Max=4.9 cfs @ 12.31 hrs HW=8.42' (Free Discharge)
2=Culvert (Passes 4.9 cfs of 6.6 cfs potential flow)
3=Orifice/Grate (Orifice Controls 4.0 cfs @ 5.09 fps)
4=Sharp-Crested Rectangular Weir(Weir Controls 0.9 cfs @ 1.34 fps)

Pond 1P: Underground Infiltration System



Summary for Pond 2P: Rooftop Detention

Inflow Area = 25,114 sf,100.00% Impervious, Inflow Depth = 9.43" for 50-Year event
Inflow = 5.5 cfs @ 12.08 hrs, Volume= 19,734 cf
Outflow = 0.3 cfs @ 13.79 hrs, Volume= 19,668 cf, Atten= 94%, Lag= 102.2 min
Primary = 0.3 cfs @ 13.79 hrs, Volume= 19,668 cf
Routed to Pond 1P : Underground Infiltration System

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs / 3
Peak Elev= 57.57' @ 13.79 hrs Surf.Area= 20,000 sf Storage= 11,360 cf

Plug-Flow detention time= 468.2 min calculated for 19,665 cf (100% of inflow)
Center-of-Mass det. time= 466.2 min (1,205.2 - 739.0)


Volume	Invert	Avail.Storage	Storage Description
#1	57.00'	14,000 cf	Rooftop Detention (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
57.00	20,000	0	0
57.70	20,000	14,000	14,000

Device	Routing	Invert	Outlet Devices
#1	Primary	8.02'	12.0" Round Roof Drain L= 16.0' CPP, mitered to conform to fill, Ke= 0.700 Inlet / Outlet Invert= 8.02' / 7.70' S= 0.0200 '/' Cc= 0.900 n= 0.013, Flow Area= 0.79 sf
#2	Device 1	57.00'	4.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads

Primary OutFlow Max=0.3 cfs @ 13.79 hrs HW=57.57' (Free Discharge)
1=Roof Drain (Passes 0.3 cfs of 23.4 cfs potential flow)
2=Orifice/Grate (Orifice Controls 0.3 cfs @ 3.63 fps)

Pond 2P: Rooftop Detention



Summary for Pond 3P: Rain garden

Inflow Area = 12,275 sf, 52.50% Impervious, Inflow Depth = 8.08" for 50-Year event
Inflow = 2.5 cfs @ 12.08 hrs, Volume= 8,268 cf
Outflow = 2.5 cfs @ 12.09 hrs, Volume= 8,268 cf, Atten= 0%, Lag= 0.2 min
Discarded = 0.0 cfs @ 12.09 hrs, Volume= 469 cf
Primary = 2.5 cfs @ 12.09 hrs, Volume= 7,799 cf
Routed to Link 1L : Towards Wetlands

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Peak Elev= 6.43' @ 12.09 hrs Surf.Area= 422 sf Storage= 223 cf

Plug-Flow detention time= 31.4 min calculated for 8,266 cf (100% of inflow)
Center-of-Mass det. time= 31.5 min (810.6 - 779.1)


Volume	Invert	Avail.Storage	Storage Description			
#1	5.60'	253 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)	
5.60	125	46.0	0	0	125	
6.00	276	66.0	78	78	305	
6.30	350	73.0	94	172	385	
6.50	460	87.0	81	253	564	

Device	Routing	Invert	Outlet Devices													
#1	Discarded	5.60'	0.520 in/hr Exfiltration over Surface area													
#2	Primary	6.30'	22.0' long x 5.0' breadth Broad-Crested Rectangular Weir													
			Head (feet)	0.20	0.40	0.60	0.80	1.00	1.20	1.40	1.60	1.80	2.00			
				2.50	3.00	3.50	4.00	4.50	5.00	5.50						
			Coef. (English)	2.34	2.50	2.70	2.68	2.68	2.66	2.65	2.65	2.65				
				2.65	2.67	2.66	2.68	2.70	2.74	2.79	2.88					

Discarded OutFlow Max=0.0 cfs @ 12.09 hrs HW=6.43' (Free Discharge)
1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=2.5 cfs @ 12.09 hrs HW=6.43' (Free Discharge)
2=Broad-Crested Rectangular Weir (Weir Controls 2.5 cfs @ 0.85 fps)

Pond 3P: Rain garden




Summary for Link 1L: Towards Wetlands

Inflow Area = 152,843 sf, 50.75% Impervious, Inflow Depth = 6.83" for 50-Year event
Inflow = 13.7 cfs @ 12.18 hrs, Volume= 86,982 cf
Primary = 13.7 cfs @ 12.18 hrs, Volume= 86,982 cf, Atten= 0%, Lag= 0.0 min
Routed to Link 100L : Total Flows

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link 1L: Towards Wetlands




Summary for Link 2L: Towards Street

Inflow Area = 5,843 sf, 18.07% Impervious, Inflow Depth = 6.95" for 50-Year event
Inflow = 1.1 cfs @ 12.09 hrs, Volume= 3,385 cf
Primary = 1.1 cfs @ 12.09 hrs, Volume= 3,385 cf, Atten= 0%, Lag= 0.0 min
Routed to Link 100L : Total Flows

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link 2L: Towards Street




Summary for Link 100L: Total Flows

Inflow Area = 158,686 sf, 49.55% Impervious, Inflow Depth = 6.83" for 50-Year event
Inflow = 14.4 cfs @ 12.14 hrs, Volume= 90,367 cf
Primary = 14.4 cfs @ 12.14 hrs, Volume= 90,367 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link 100L: Total Flows



Time span=0.00-72.00 hrs, dt=0.01 hrs, 7201 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method


Subcatchment1S: CB-1	Runoff Area=22,742 sf 72.16% Impervious Runoff Depth=10.39" Tc=6.0 min CN=91 Runoff=5.8 cfs 19,696 cf
Subcatchment2.1S: Building	Runoff Area=7,811 sf 100.00% Impervious Runoff Depth=11.26" Tc=6.0 min CN=98 Runoff=2.0 cfs 7,328 cf
Subcatchment2S: Building Roof	Runoff Area=25,114 sf 100.00% Impervious Runoff Depth=11.26" Tc=6.0 min CN=98 Runoff=6.5 cfs 23,563 cf
Subcatchment3.1S: Backyard ADs	Runoff Area=8,985 sf 3.03% Impervious Runoff Depth=8.28" Flow Length=147' Tc=10.3 min CN=75 Runoff=1.7 cfs 6,203 cf
Subcatchment3S: Townhouse Roofs	Runoff Area=13,067 sf 100.00% Impervious Runoff Depth=11.26" Tc=6.0 min CN=98 Runoff=3.4 cfs 12,260 cf
Subcatchment4.2S: Townhouse TDs	Runoff Area=1,112 sf 95.68% Impervious Runoff Depth=11.14" Tc=6.0 min CN=97 Runoff=0.3 cfs 1,032 cf
Subcatchment4.3S: Townhouse TDs	Runoff Area=1,105 sf 97.29% Impervious Runoff Depth=11.14" Tc=6.0 min CN=97 Runoff=0.3 cfs 1,026 cf
Subcatchment4.4S: Townhouse TDs	Runoff Area=1,104 sf 97.46% Impervious Runoff Depth=11.14" Tc=6.0 min CN=97 Runoff=0.3 cfs 1,025 cf
Subcatchment4.5S: Townhouse TDs	Runoff Area=1,082 sf 98.06% Impervious Runoff Depth=11.26" Tc=6.0 min CN=98 Runoff=0.3 cfs 1,015 cf
Subcatchment4.6S: Townhouse TDs	Runoff Area=1,056 sf 99.24% Impervious Runoff Depth=11.26" Tc=6.0 min CN=98 Runoff=0.3 cfs 991 cf
Subcatchment5S: TD-1	Runoff Area=5,851 sf 51.63% Impervious Runoff Depth=9.75" Tc=6.0 min CN=86 Runoff=1.4 cfs 4,756 cf
Subcatchment6.1S: East driveway	Runoff Area=12,275 sf 52.50% Impervious Runoff Depth=9.88" Tc=6.0 min CN=87 Runoff=3.0 cfs 10,109 cf
Subcatchment6S: Bypass Towards	Runoff Area=51,539 sf 0.21% Impervious Runoff Depth=8.15" Flow Length=125' Tc=14.0 min CN=74 Runoff=8.7 cfs 34,988 cf
Subcatchment7S: To Street	Runoff Area=5,843 sf 18.07% Impervious Runoff Depth=8.69" Tc=6.0 min CN=78 Runoff=1.3 cfs 4,233 cf
Pond 1P: Underground Infiltration System	Peak Elev=8.61' Storage=14,744 cf Inflow=13.8 cfs 71,490 cf Discarded=0.1 cfs 14,852 cf Primary=7.1 cfs 56,636 cf Outflow=7.2 cfs 71,488 cf
Pond 2P: Rooftop Detention	Peak Elev=57.69' Storage=13,762 cf Inflow=6.5 cfs 23,563 cf Outflow=0.3 cfs 23,488 cf

Pond 3P: Rain garden	Peak Elev=6.45' Storage=231 cf Inflow=3.0 cfs 10,109 cf Discarded=0.0 cfs 480 cf Primary=3.0 cfs 9,630 cf Outflow=3.0 cfs 10,109 cf
Link 1L: Towards Wetlands	Inflow=18.5 cfs 108,582 cf Primary=18.5 cfs 108,582 cf
Link 2L: Towards Street	Inflow=1.3 cfs 4,233 cf Primary=1.3 cfs 4,233 cf
Link 100L: Total Flows	Inflow=19.3 cfs 112,815 cf Primary=19.3 cfs 112,815 cf
Total Runoff Area = 158,686 sf Runoff Volume = 128,224 cf Average Runoff Depth = 9.70" 50.45% Pervious = 80,060 sf 49.55% Impervious = 78,626 sf	

Summary for Subcatchment 1S: CB-1

Runoff	=	5.8 cfs @ 12.08 hrs, Volume=	19,696 cf, Depth=10.39"
Routed to Pond 1P : Underground Infiltration System			
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 100-Year Rainfall=11.50"			
Area (sf)	CN	Description	
16,410	98	Paved parking, HSG C	
6,332	74	>75% Grass cover, Good, HSG C	
22,742	91	Weighted Average	
6,332		27.84% Pervious Area	
16,410		72.16% Impervious Area	
Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)
6.0			
Capacity (cfs)	Description		
	Direct Entry, Min. Tc		

Subcatchment 1S: CB-1



Summary for Subcatchment 2.1S: Building Roof-Southeast


Runoff = 2.0 cfs @ 12.08 hrs, Volume= 7,328 cf, Depth=11.26"
Routed to Link 1L : Towards Wetlands

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 100-Year Rainfall=11.50"

Area (sf)	CN	Description
7,811	98	Roofs, HSG C
7,811		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 2.1S: Building Roof-Southeast



Summary for Subcatchment 2S: Building Roof


Runoff = 6.5 cfs @ 12.08 hrs, Volume= 23,563 cf, Depth=11.26"
Routed to Pond 2P : Rooftop Detention

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 100-Year Rainfall=11.50"

Area (sf)	CN	Description
25,114	98	Roofs, HSG C
25,114		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 2S: Building Roof



Summary for Subcatchment 3.1S: Backyard ADs


Runoff = 1.7 cfs @ 12.14 hrs, Volume= 6,203 cf, Depth= 8.28"
Routed to Pond 1P : Underground Infiltration System

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 100-Year Rainfall=11.50"

Area (sf)	CN	Description
272	98	Unconnected pavement, HSG C
8,302	74	>75% Grass cover, Good, HSG C
411	89	Gravel sidewalk, HSG C
8,985	75	Weighted Average
8,713		96.97% Pervious Area
272		3.03% Impervious Area
272		100.00% Unconnected

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
9.4	50	0.0142	0.09		Sheet Flow, Grass: Dense n= 0.240 P2= 3.23"
0.9	97	0.0154	1.86		Shallow Concentrated Flow, Grassed Waterway Kv= 15.0 fps
10.3	147	Total			

Subcatchment 3.1S: Backyard ADs



Summary for Subcatchment 3S: Townhouse Roofs


Runoff = 3.4 cfs @ 12.08 hrs, Volume= 12,260 cf, Depth=11.26"
Routed to Pond 1P : Underground Infiltration System

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 100-Year Rainfall=11.50"

Area (sf)	CN	Description
13,067	98	Roofs, HSG C
13,067		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 3S: Townhouse Roofs



Summary for Subcatchment 4.2S: Townhouse TDs


Runoff = 0.3 cfs @ 12.08 hrs, Volume= 1,032 cf, Depth=11.14"
Routed to Pond 1P : Underground Infiltration System

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 100-Year Rainfall=11.50"

Area (sf)	CN	Description
1,064	98	Paved parking, HSG C
48	74	>75% Grass cover, Good, HSG C
1,112	97	Weighted Average
48		4.32% Pervious Area
1,064		95.68% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.2S: Townhouse TDs



Summary for Subcatchment 4.3S: Townhouse TDs


Runoff = 0.3 cfs @ 12.08 hrs, Volume= 1,026 cf, Depth=11.14"
Routed to Pond 1P : Underground Infiltration System

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 100-Year Rainfall=11.50"

Area (sf)	CN	Description
1,075	98	Paved parking, HSG C
30	74	>75% Grass cover, Good, HSG C
1,105	97	Weighted Average
30		2.71% Pervious Area
1,075		97.29% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.3S: Townhouse TDs



Summary for Subcatchment 4.4S: Townhouse TDs


Runoff = 0.3 cfs @ 12.08 hrs, Volume= 1,025 cf, Depth=11.14"
Routed to Pond 1P : Underground Infiltration System

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 100-Year Rainfall=11.50"

Area (sf)	CN	Description
1,076	98	Paved parking, HSG C
28	74	>75% Grass cover, Good, HSG C
1,104	97	Weighted Average
28		2.54% Pervious Area
1,076		97.46% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.4S: Townhouse TDs



Summary for Subcatchment 4.5S: Townhouse TDs


Runoff = 0.3 cfs @ 12.08 hrs, Volume= 1,015 cf, Depth=11.26"
Routed to Pond 1P : Underground Infiltration System

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 100-Year Rainfall=11.50"

Area (sf)	CN	Description
1,061	98	Paved parking, HSG C
21	74	>75% Grass cover, Good, HSG C
1,082	98	Weighted Average
21		1.94% Pervious Area
1,061		98.06% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.5S: Townhouse TDs



Summary for Subcatchment 4.6S: Townhouse TDs


Runoff = 0.3 cfs @ 12.08 hrs, Volume= 991 cf, Depth=11.26"
Routed to Pond 1P : Underground Infiltration System

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 100-Year Rainfall=11.50"

Area (sf)	CN	Description
1,048	98	Paved parking, HSG C
8	74	>75% Grass cover, Good, HSG C
1,056	98	Weighted Average
8		0.76% Pervious Area
1,048		99.24% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.6S: Townhouse TDs



Summary for Subcatchment 5S: TD-1


Runoff = 1.4 cfs @ 12.08 hrs, Volume= 4,756 cf, Depth= 9.75"
Routed to Pond 1P : Underground Infiltration System

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 100-Year Rainfall=11.50"

Area (sf)	CN	Description
3,021	98	Paved parking, HSG C
2,830	74	>75% Grass cover, Good, HSG C
5,851	86	Weighted Average
2,830		48.37% Pervious Area
3,021		51.63% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 5S: TD-1



Summary for Subcatchment 6.1S: East driveway


Runoff = 3.0 cfs @ 12.08 hrs, Volume= 10,109 cf, Depth= 9.88"
Routed to Pond 3P : Rain garden

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 100-Year Rainfall=11.50"

Area (sf)	CN	Description
5,611	74	>75% Grass cover, Good, HSG C
6,444	98	Paved roads w/curbs & sewers, HSG C
220	89	Gravel roads, HSG C
12,275	87	Weighted Average
5,831		47.50% Pervious Area
6,444		52.50% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

Subcatchment 6.1S: East driveway



Summary for Subcatchment 6S: Bypass Towards Wetlands


Runoff = 8.7 cfs @ 12.18 hrs, Volume= 34,988 cf, Depth= 8.15"
Routed to Link 1L : Towards Wetlands

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 100-Year Rainfall=11.50"

Area (sf)	CN	Description
4,985	70	Woods, Good, HSG C
46,447	74	>75% Grass cover, Good, HSG C
107	98	Roofs, HSG C
51,539	74	Weighted Average
51,432		99.79% Pervious Area
107		0.21% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.8	50	0.0220	0.07		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.23"
2.2	75	0.0133	0.58		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
14.0	125	Total			

Subcatchment 6S: Bypass Towards Wetlands



Summary for Subcatchment 7S: To Street


Runoff = 1.3 cfs @ 12.09 hrs, Volume= 4,233 cf, Depth= 8.69"
Routed to Link 2L : Towards Street

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 100-Year Rainfall=11.50"

Area (sf)	CN	Description
1,056	98	Paved parking, HSG C
4,787	74	>75% Grass cover, Good, HSG C
5,843	78	Weighted Average
4,787		81.93% Pervious Area
1,056		18.07% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 7S: To Street



Summary for Pond 1P: Underground Infiltration System

Inflow Area = 81,218 sf, 77.83% Impervious, Inflow Depth = 10.56" for 100-Year event
Inflow = 13.8 cfs @ 12.09 hrs, Volume= 71,490 cf
Outflow = 7.2 cfs @ 12.24 hrs, Volume= 71,488 cf, Atten= 48%, Lag= 9.4 min
Discarded = 0.1 cfs @ 4.26 hrs, Volume= 14,852 cf
Primary = 7.1 cfs @ 12.24 hrs, Volume= 56,636 cf
Routed to Link 1L : Towards Wetlands

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Peak Elev= 8.61' @ 12.24 hrs Surf.Area= 8,137 sf Storage= 14,744 cf

Plug-Flow detention time= 113.7 min calculated for 71,478 cf (100% of inflow)
Center-of-Mass det. time= 113.6 min (1,031.2 - 917.6)


Volume	Invert	Avail.Storage	Storage Description
#1	6.50'	17,495 cf	6.89'W x 14.06'L x 2.50'H StormTrap ST-1 Units (Irregular Shape) 84 20,343 cf Overall x 86.0% Voids

Device	Routing	Invert	Outlet Devices
#1	Discarded	6.50'	0.520 in/hr Exfiltration over Surface area
#2	Primary	6.80'	18.0" Round Culvert L= 190.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 6.80' / 6.00' S= 0.0042 ' /' Cc= 0.900 n= 0.013, Flow Area= 1.77 sf
#3	Device 2	6.80'	12.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 2	8.25'	4.0" long Sharp-Crested Rectangular Weir 2 End Contraction(s)

Discarded OutFlow Max=0.1 cfs @ 4.26 hrs HW=6.53' (Free Discharge)
1=Exfiltration (Exfiltration Controls 0.1 cfs)

Primary OutFlow Max=7.1 cfs @ 12.24 hrs HW=8.61' (Free Discharge)
2=Culvert (Passes 7.1 cfs of 7.3 cfs potential flow)
3=Orifice/Grate (Orifice Controls 4.3 cfs @ 5.50 fps)
4=Sharp-Crested Rectangular Weir (Weir Controls 2.7 cfs @ 1.95 fps)

Pond 1P: Underground Infiltration System



Summary for Pond 2P: Rooftop Detention

Inflow Area = 25,114 sf, 100.00% Impervious, Inflow Depth = 11.26" for 100-Year event
Inflow = 6.5 cfs @ 12.08 hrs, Volume= 23,563 cf
Outflow = 0.3 cfs @ 13.96 hrs, Volume= 23,488 cf, Atten= 95%, Lag= 112.7 min
Primary = 0.3 cfs @ 13.96 hrs, Volume= 23,488 cf
Routed to Pond 1P : Underground Infiltration System

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs / 3
Peak Elev= 57.69' @ 13.96 hrs Surf.Area= 20,000 sf Storage= 13,762 cf

Plug-Flow detention time= 503.0 min calculated for 23,485 cf (100% of inflow)
Center-of-Mass det. time= 501.1 min (1,238.3 - 737.2)


Volume	Invert	Avail.Storage	Storage Description
#1	57.00'	14,000 cf	Rooftop Detention (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
57.00	20,000	0	0
57.70	20,000	14,000	14,000

Device	Routing	Invert	Outlet Devices
#1	Primary	8.02'	12.0" Round Roof Drain L= 16.0' CPP, mitered to conform to fill, Ke= 0.700 Inlet / Outlet Invert= 8.02' / 7.70' S= 0.0200 '/' Cc= 0.900 n= 0.013, Flow Area= 0.79 sf
#2	Device 1	57.00'	4.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads

Primary OutFlow Max=0.3 cfs @ 13.96 hrs HW=57.69' (Free Discharge)
1=Roof Drain (Passes 0.3 cfs of 23.4 cfs potential flow)
2=Orifice/Grate (Orifice Controls 0.3 cfs @ 3.99 fps)

Pond 2P: Rooftop Detention



Summary for Pond 3P: Rain garden

Inflow Area = 12,275 sf, 52.50% Impervious, Inflow Depth = 9.88" for 100-Year event
Inflow = 3.0 cfs @ 12.08 hrs, Volume= 10,109 cf
Outflow = 3.0 cfs @ 12.09 hrs, Volume= 10,109 cf, Atten= 0%, Lag= 0.2 min
Discarded = 0.0 cfs @ 12.09 hrs, Volume= 480 cf
Primary = 3.0 cfs @ 12.09 hrs, Volume= 9,630 cf
Routed to Link 1L : Towards Wetlands

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Peak Elev= 6.45' @ 12.09 hrs Surf.Area= 432 sf Storage= 231 cf

Plug-Flow detention time= 26.5 min calculated for 10,108 cf (100% of inflow)
Center-of-Mass det. time= 26.6 min (800.6 - 774.0)


Volume	Invert	Avail.Storage	Storage Description							
#1	5.60'	253 cf	Custom Stage Data (Irregular) Listed below (Recalc)							
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)				Wet.Area (sq-ft)		
5.60	125	46.0	0	0				125		
6.00	276	66.0	78	78				305		
6.30	350	73.0	94	172				385		
6.50	460	87.0	81	253				564		

Device	Routing	Invert	Outlet Devices													
#1	Discarded	5.60'	0.520 in/hr Exfiltration over Surface area													
#2	Primary	6.30'	22.0' long x 5.0' breadth Broad-Crested Rectangular Weir													
			Head (feet)	0.20	0.40	0.60	0.80	1.00	1.20	1.40	1.60	1.80	2.00			
			2.50	3.00	3.50	4.00	4.50	5.00	5.50							
			Coef. (English)	2.34	2.50	2.70	2.68	2.68	2.66	2.66	2.65	2.65	2.65			
			2.65	2.67	2.66	2.68	2.70	2.74	2.79	2.88						

Discarded OutFlow Max=0.0 cfs @ 12.09 hrs HW=6.45' (Free Discharge)
1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=3.0 cfs @ 12.09 hrs HW=6.45' (Free Discharge)
2=Broad-Crested Rectangular Weir (Weir Controls 3.0 cfs @ 0.91 fps)

Pond 3P: Rain garden




Summary for Link 1L: Towards Wetlands

Inflow Area = 152,843 sf, 50.75% Impervious, Inflow Depth = 8.53" for 100-Year event
Inflow = 18.5 cfs @ 12.18 hrs, Volume= 108,582 cf
Primary = 18.5 cfs @ 12.18 hrs, Volume= 108,582 cf, Atten= 0%, Lag= 0.0 min
Routed to Link 100L : Total Flows

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link 1L: Towards Wetlands




Summary for Link 2L: Towards Street

Inflow Area = 5,843 sf, 18.07% Impervious, Inflow Depth = 8.69" for 100-Year event
Inflow = 1.3 cfs @ 12.09 hrs, Volume= 4,233 cf
Primary = 1.3 cfs @ 12.09 hrs, Volume= 4,233 cf, Atten= 0%, Lag= 0.0 min
Routed to Link 100L : Total Flows

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link 2L: Towards Street

Hydrograph




Summary for Link 100L: Total Flows

Inflow Area = 158,686 sf, 49.55% Impervious, Inflow Depth = 8.53" for 100-Year event
Inflow = 19.3 cfs @ 12.18 hrs, Volume= 112,815 cf
Primary = 19.3 cfs @ 12.18 hrs, Volume= 112,815 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link 100L: Total Flows

Hydrograph



ATTACHMENT D
GROUNDWATER RECHARGE CALCULATIONS

Required Recharge Volume

$$Rv = F \times \text{Impervious Area}$$

Where:

Rv = Recharge Volume

F=Target Depth Factor associated with each Hydrologic Soil Group

(F=0.25-inch for Soil Type C)

Impervious Area = Proposed Pavement and Rooftop area on-site

$$Rv = \left(\frac{0.25in}{12} \right) (78,626sft) =$$

$$Rv = 1,638 \text{ cf (required recharge volume)}$$

As not all impervious surfaces are directed to an infiltration BMP, an adjusted Required Volume must be provided. The adjusted Required Volume (Rva) is calculated as:

$$Rva = \frac{\text{Total Imp.Area}}{\text{Imp.Area to BMP}} (Rv) =$$

$$Rva = \left(\frac{78,626sft}{69,652sft} \right) (1,638cf) =$$

$$Rva = 1,849 \text{ cf}$$

Storage Provided

- Underground Infiltration System = 2,099 cubic feet provided.
Rain garden not required to meet volume, but provides additional infiltration above and beyond that required.
Refer to the HydroCAD storage table provided for more information.

Drawdown Within 72-Hours

Pond 1P

Rv = Recharge Volume, cu.ft. (see above)

K = Saturated Hydraulic Conductivity, in/hr (from Rawls Table)

Bottom Area = Area of Infiltration System Bottom, sq.ft.

$$Time = \frac{Rv}{(K)(Bottom\ Area)}$$

$$Time = \left(\frac{2,099\ cu.\ ft.}{(0.043\ ft/hr)(8,137\ sq.\ ft.)} \right) =$$

$$Time = 6.0\ hours$$

- 6 hours < 72 hours

Pond 3P (Rain Garden)

Rv = Recharge Volume, 172 cu.ft. (see HydroCAD)

K = Saturated Hydraulic Conductivity, in/hr (from Rawls Table)

Bottom Area = Area of Infiltration System Bottom, sq.ft.

$$Time = \frac{Rv}{(K)(Bottom\ Area)}$$

$$Time = \left(\frac{172\ cu.\ ft.}{(0.043\ ft/hr)(125\ sq.\ ft.)} \right) =$$

$$Time = 32\ hours$$

- 32 hours < 72 hours

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
6.5	8,137	0
6.55	8,137	350
6.6	8,137	700
6.65	8,137	1,050
6.7	8,137	1,400
6.75	8,137	1,750
6.8	8,137	2,099
6.85	8,137	2,449
6.9	8,137	2,799
6.95	8,137	3,149
7	8,137	3,499
7.05	8,137	3,849
7.1	8,137	4,199
7.15	8,137	4,549
7.2	8,137	4,899
7.25	8,137	5,249
7.3	8,137	5,599
7.35	8,137	5,948
7.4	8,137	6,298
7.45	8,137	6,648
7.5	8,137	6,998
7.55	8,137	7,348
7.6	8,137	7,698
7.65	8,137	8,048
7.7	8,137	8,398
7.75	8,137	8,748
7.8	8,137	9,098
7.85	8,137	9,447
7.9	8,137	9,797
7.95	8,137	10,147
8	8,137	10,497
8.05	8,137	10,847
8.1	8,137	11,197
8.15	8,137	11,547
8.2	8,137	11,897
8.25	8,137	12,247
8.3	8,137	12,597
8.35	8,137	12,947
8.4	8,137	13,296
8.45	8,137	13,646
8.5	8,137	13,996
8.55	8,137	14,346
8.6	8,137	14,696
8.65	8,137	15,046
8.7	8,137	15,396
8.75	8,137	15,746
8.8	8,137	16,096
8.85	8,137	16,446
8.9	8,137	16,796
8.95	8,137	17,145
9	8,137	17,495

ATTACHMENT E
GROUNDWATER MOUNDING CALCULATION

Input Values

0.2580
0.080
5.40
98.420
20.670
1.000
5.000

R
Sy
K
x
y
t
hi(0)

Recharge (infiltration) rate (feet/day)
Specific yield, *Sy* (dimensionless, between 0 and 1)
Horizontal hydraulic conductivity, *Kh* (feet/day)*
1/2 length of basin (*x* direction, in feet)
1/2 width of basin (*y* direction, in feet)
duration of infiltration period (days)
initial thickness of saturated zone (feet)

inch/hour feet/day
0.67 1.33

2.00 4.00

hours days
36 1.50

In the repor
(USGS SIR 20
(ft/d) is assu
hydraulic co

7.339
2.339

h(max)
Δh(max)

maximum thickness of saturated zone (beneath center of basin at end of infiltration period)
maximum groundwater mounding (beneath center of basin at end of infiltration period)


Ground-
water
Mounding, in
feet

Distance from
center of basin
in *x* direction, in
feet

2.339	0
2.338	20
2.329	40
2.313	50
2.275	60
2.192	70
2.022	80
1.695	90
1.086	100
0.243	120



Re-Calculate Now



Disclaimer

This spreadsheet solving the Hantush (1967) equation for ground-water mounding beneath an infiltration basin is made available to the general public as a convenience for those wishing to replicate values documented in the USGS Scientific Investigations Report 2010-5102 "Groundwater mounding beneath hypothetical stormwater infiltration basins" or to calculate values based on user-specified site conditions. Any changes made to the spreadsheet (other than values identified as user-specified) after transmission from the USGS could have unintended, undesirable consequences. These consequences could include, but may not be limited to: erroneous output, numerical instabilities, and violations of underlying assumptions that are inherent in results presented in the accompanying USGS published report. The USGS assumes no responsibility for the consequences of any changes made to the spreadsheet. If changes are made to the spreadsheet, the user is responsible for documenting the changes and justifying the results and conclusions.

Recharge/Infiltration Rate (ft/day) = [Required Recharge Volume (cft)/Bottom Recharge System (sft)]/Duration (day)

Required Recharge Volume 2,099 cft

Bottom Recharge System 8,137 sft

Duration 1 day

Recharge/Infiltration Rate 0.2580 ft/day

Horizontal Hydraulic Conductivity (ft/day) = [Rawls Rate (in/hr) * (1ft/12in) * (24hr/1day)] * 10

Rawls Rate (silt loam) 0.27 in/hr

Horizontal Hydraulic Conductivity 5.40 ft/day

ATTACHMENT F
WATER QUALITY CALCULATIONS

Water Quality Volume Calculation

$$V_{WQ} = (D_{WQ}/12 \text{ inches/foot}) * (A_{IMP} \text{ square feet})$$

V_{WQ} = Required Water Quality Volume (in cubic feet)

D_{WQ} = Water Quality Depth: **0.5-inch**

A_{IMP} = Total Impervious Area (in acres) used for driveways, parking, etc.

Underground Infiltration Systems and Bio-Retention Areas

$$A_{IMP} = 32,527 \text{ sq.ft.}$$

$$V_{WQ} = (0.5 \text{ inches}/12 \text{ inches/foot}) * (32,527 \text{ sq.ft.})$$

$V_{WQ} = 1,355$ cubic feet (required volume), provided volume = 2,099 cubic feet in Underground Infiltration System (refer to the HydroCAD storage tables provided in groundwater recharge section). Additional water quality volume provided in rain garden above and beyond the water quality volume required.

TSS Removal Calculation Worksheet

Location: Thorndike Place, Arlington, MA

Project: 23407.02



Prepared By: E. Derrig

Date: 9/12/2024

AREA 1 - CB-1

Total Impervious Area, Acres= 0.377

A	B	C	D	E
BMP	TSS Removal Rate	Starting TSS Load*	Amount Removed (BxC)	Remaining Load (C-D)
Deep Sump and Hooded Catchbasins	0.25	1.00	0.25	0.75
Hydrodynamic Separator	0.7	0.75	0.53	0.23
Infiltration Basin	0.8	0.23	0.18	0.05

TSS Removal = 0.96

AREA 2 - TD-1

Total Impervious Area, Acres= 0.069

A	B	C	D	E
BMP	TSS Removal Rate	Starting TSS Load*	Amount Removed (BxC)	Remaining Load (C-D)
Hydrodynamic Separator	0.7	1.00	0.70	0.30
Infiltration Basin	0.8	0.30	0.24	0.06

TSS Removal = 0.94

AREA 3 - TD-2-6

Total Impervious Area, Acres= 0.122

A	B	C	D	E
BMP	TSS Removal Rate	Starting TSS Load*	Amount Removed (BxC)	Remaining Load (C-D)
Infiltration Basin	0.8	1.00	0.80	0.20

TSS Removal = 0.80

AREA 4 - Bypass to Street**Total Impervious Area, Acres= 0.024**

A	B	C	D	E
BMP	TSS Removal Rate	Starting TSS Load*	Amount Removed (BxC)	Remaining Load (C-D)
		1.00		

TSS Removal =

AREA 5 - East Driveway**Total Impervious Area, Acres= 0.148**

A	B	C	D	E
BMP	TSS Removal Rate	Starting TSS Load*	Amount Removed (BxC)	Remaining Load (C-D)
Rain Garden	0.8	1.00	0.80	0.20

TSS Removal = 0.80

Weighted Annual Average TSS Removal Rate

[TSS Removal-1 (Area-1) + TSS Removal-2 (Area-2)+] / [Area-1 + Area-2 + ...] = 0.87

Project Site TSS Removal = 0.87