

EXISTING SITE PHOTOGRAPH



Site Recommendation Book

Arlington ID #: 1021 880 Massachusetts Avenue Arlington, MA

Preliminary Recommendations July 22, 2019

Revisions

November 13, 2019 November 20, 2019 December 17, 2019









Project Policies and Procedures

You are a valued asset to this project's success - please take a moment to review the guidelines listed, below because your safety and reputation matter.

Standard Onsite Code of Conduct Expectations

- IRG Project Manager must be aware of your presence while on site.
 Crew Lead must present letter of authorization to the store management prior to the start of work.
- Vehicles and equipment are to be staged as far from customer entrances & parking as possible.
- Crew members' attire should clearly identify the company with which they are working. Please do not interact with customers unless life safety concerns apply.
- Standard Protocol for working overhead is to properly block the walk space beneath the work area with cones when working on sign faces and to have a full flag crew when cabinets and heavy items are being lifted. Be mindful of potential debris dropping onto pedestrians & customers walking below, especially when removing old sign faces that may break during removal.
- No Project related trash (bulbs, faces, signs, screws, crating, etc.) shall be left on site in any trash bin or containers NOT owned by the respective vendor. All waste to be recycled/disposed offsite.
- All signs installed must be level and in pristine condition upon completion. Touch up paint will be provided to address scratched cabinets.
- Photographs: All signs installations and punch-related revisit work
 must be photographed to include exterior, and interior to confirm that
 signs light properly prior to leaving the site. Please note that by
 photographing the interior and exterior of the sign, you will capture the
 installation, and relieve yourself of potential liability for damages that
 may occur after leaving a site.

Sign Type- Specific Instructions

- Refacing Monuments & Pylons: If new damage is discovered on site, immediately notify IRG to include landscaping issues found or created by sign removal/installation. Ensure sign is properly lighting.
- Refacing Channel Letters: Confirm lettersets lights properly. Wipe down all letter cabinets and "BANK" letter faces
- Replacing Wall Signs: All holes from previous sign should be sealed
 and water tight, without excess of sealants left behind. Every attempt
 to cover as many existing holes with the new sign as possible should
 be made, especially where new signs are smaller. The IRG Project
 Manager must be notified of any holes, ghosting, or damage still
 visible following the installation of a new sign.
- <u>Directional Signs:</u> All directional signs are to coordinate with any
 marking on the pavement, If new directional signage counteracts the
 current flow of traffic, remain on site until you have reviewed next
 steps with your IRG Project Manager. Any existing electrical must be
 powered down and made safe, then hidden below ground level
 consistent with regulations. Immediately notify IRG of damaged
 landscaping found or created by sign removal/installation
- <u>Acrylic/Plate Lettersets:</u> Retained letters are to be wiped down, and completion photos should include the entire letterset.
- Awnings: Completion photos are to include all recovered awnings, applied graphics, and enough surrounding area to confirm the location of each.
- Restoration & Painting: Completion photos are to include close up photos and enough surrounding area to confirm the location of the impacted area.








Site Plan
















COMPOSITE PHOTOGRAPH with PROPOSED SIGNAGE



FRONT VIEW Scale- 1/2"=1'-0"

TDB-RP-FS.0002

Qty 2

24.05 sq.ft.

.177" thk Makrolon sl #7328 (B54) polycarbonate. Background to be 3M 3630-6513 Translucent Dark Green Vinyl applied to first surface. Logo to be 3M 3630-5741 TD Light Green Translucent Vinyl laminated with 3M 3660M applied to the first surface. Copy to be dropped out to illuminate white.



E01

Existing Signage:

D/F Non-Illuminated Pylon Overall: 4'-2" tall 5'-10" wide 1'-2" deep Square Footage: 24 sq.ft.

SPECIAL CONDITIONS

Power to be run to sign. Retrofit installation of LED sticks required. (Qty - 12) Sloan Bracket 402297-10 Required to complete retrofit

Lighting

Lamp Size: 48" Lamp Qty: 6 Power Supply Qty: 2















COMPOSITE PHOTOGRAPH with PROPOSED SIGNAGE

E02

Existing Signage:


Illuminated Wall Sign Overall: 2'-1/2" tall 7'-1" wide 8" deep Square Footage: 14.5 sq.ft.

SPECIAL CONDITIONS

No special conditions.

Lighting

Lamp Size: 84" Lamp Qty: 2 Power Supply Qty: 1



FRONT VIEW Scale- 3/8"=1'-0"

TDB-CRP-24X85

14.17 sq.ft.

.177" thk Makrolon sl #7328 (B54) polycarbonate. Vinyl to be 3M 3630-5741 TD Light Green Translucent Vinyl laminated with 3M 3660M applied to the first surface. Copy to be dropped out to illuminate white.















COMPOSITE PHOTOGRAPH with PROPOSED SIGNAGE

E03

Existing Signage:


Illuminated Wall Sign Overall: 2'-1/2" tall 7'-1" wide 8" deep Square Footage: 14.5 sq.ft.

SPECIAL CONDITIONS

No special conditions.

Lighting

Lamp Size: 84" Lamp Qty: 2 Power Supply Qty: 1



FRONT VIEW Scale- 3/8"=1'-0"

TDB-CRP-24X85

14.17 sq.ft.

.177" thk Makrolon sl #7328 (B54) polycarbonate. Vinyl to be 3M 3630-5741 TD Light Green Translucent Vinyl laminated with 3M 3660M applied to the first surface. Copy to be dropped out to illuminate white.





Overall: 2'-1/2" tall 7'-1" wide 8" deep Square Footage: 14.5 sq.ft.

E04



Existing Signage: Illuminated Wall Sign










COMPOSITE PHOTOGRAPH with PROPOSED SIGNAGE

SPECIAL CONDITIONS

No special conditions.

Lighting

Lamp Size: 84" Lamp Qty: 2 Power Supply Qty: 1



FRONT VIEW Scale- 3/8"=1'-0"

TDB-CRP-24X85

14.17 sq.ft.

.177" thk Makrolon sl #7328 (B54) polycarbonate. Vinyl to be 3M 3630-5741 TD Light Green Translucent Vinyl laminated with 3M 3660M applied to the first surface. Copy to be dropped out to illuminate white.



E05

Illuminated/Non-Illuminated Directional

Existing Signage:

Overall: 3'-6" tall 2'-1" wide

Square Footage: 7.3 sq.ft.










COMPOSITE PHOTOGRAPH with PROPOSED SIGNAGE

SPECIAL CONDITIONS

Turn off power at breaker, cap off existing power, and replace with new directional



Non-illuminated painted directional sign with film decorated sign face. Aluminum tube frame and aluminum sheet construction. Sign to be painted to match: PMS 5535 #MP62874V1.0 (Satin Finish). Sign face first surface film 3M 5000 Scotchlite Reflective White Vinyl and 3M IJ680-10 Scotchlite Reflective Film (InkJet Digital) to match Matthews Pantone 361 with 3M MCS approved inkjet inks.



ORIGINAL PHOTOGRAPH - SIDE B









ORIGINAL PHOTOGRAPH

RETAIN EXISTING SIGNAGE

E19-E22

Existing Signage:
Blade Sign
Overall: 1'-3 1/2" tall 1'-0" wide
Square Footage: 1.29 sq.ft.

SPECIAL CONDITIONS

No special conditions.



Overall: TBD tall TBD wide TBD deep

F01

Existing Signage:

Illuminated ATM Header

Square Footage: TBD sq.ft.










COMPOSITE PHOTOGRAPH with PROPOSED SIGNAGE

SPECIAL CONDITIONS

Technical Survey Required prior to manufacture.



FRONT VIEW Scale- 3/8"=1'-0"

Lighting Please photograph inside of sign during technical survey Lamp Size: Lamp Qty: _ Power Supply Qty: X

TDB-CRP-TBDXTBD

TBD sq.ft.

.177" thk Makrolon sl #7328 (B54) polycarbonate. Background to be 3M 3632-6513 Translucent Dark Green Vinyl applied to first surface. Logo to be 3M 3630-5741 TD Light Green Translucent Vinyl laminated with 3M 3660M applied to the first surface. Copy to be dropped out to illuminate white.











E01 / Side B / East



E02 / Side A / West



E03 / Side A / North



E04 / Side A / East



E05 / Side A / North



E05 / Side B / South




E12 / Side A / East



F01 / Side A / South



/ /



1



/ /

