

EXISTING TREES, PERENNIALS, AND INVASIVE PLANTS WITHIN THE EXISTING FENCE AREA WILL BE ADDRESSED IN COORDINATION WITH THE DPW PROJECT CURRENTLY IN DESIGN AND THE TOWN OF ARLINGTON CONSERVATION COMMISSION, AND IN ACCORDANCE WITH THEIR STANDARDS. THE INVASIVE REMOVAL SPECIFICATION DEVELOPED FOR THE EAST SIDE MILL BROOK CULVERT AREA WILL BE REFERENCED FOR THIS WORK AS WELL.

TOP OF BANK/BVW

25' WETLAND BUFFER

8 Aa

696 pv

1 HVA

6 Vd

936 rl

EXISTING CONCRETE CULVERT TO REMAIN AND BE PROTECTED

EXISTING FENCE TO REMAIN AND BE PROTECTED.

624 av

4 Vd

6 Lb

564 pv

PROPOSED PLANT LIST

TREES, SHRUBS, PERENNIALS

SYMBOL	BOTANICAL NAME	COMMON NAME	QUANTITY	SIZE	REMARKS
HVA	Hamamelis virginiana	Common Witch hazel	1	5-6 FT HT	B&B
Aa	Aronia arbutifolia	Red Chokeberry	8	3 GAL	CONTAINER
Lb	Lindera benzoin	Spicebush	6	5 GAL	CONTAINER
Vd	Viburnum dentatum	Arrow-wood Viburnum	10	5 GAL	CONTAINER
av	Andropogon virginicus	Broom Sedge	624	landscape plugs	4 PER S.F.
pv	Panicum virgatum	Switch Grass	1260	landscape plugs	4 PER S.F.
rl	Rudbeckia laciniata	Green Coneflower	936	landscape plugs	4 PER S.F.

HMFH ARCHITECTS

130 Bishop Allen Drive
Cambridge, MA 02139
617 492 2200
@HMFHarch hmfh.com

H M
F H

Arlington High School
CONSERVATION COMMISSION PLANTING IMPROVEMENTS
LANDSCAPE PLAN
WEST SIDE CULVERT PLANTING CHANGES

CROSBY SCHLESSINGER SMALLRIDGE T 617 399-7000 F 617 399-7008
C S S
www.cssboston.com 67 Batterymarch St Boston, MA 02110

SCALE: NTS DATE: 7.14.2020 DRAWN: CSS CHECKED: CSS

DRAWING NUMBER

1

JOB NUMBER 408417