



Arlington Conservation Commission

Date: Thursday, January 16, 2025

Time: 7:00 PM

Location: In person at the Town Hall Annex 2nd floor conference room and conducted by remote participation.

Please register in advance for this meeting. Reference materials, instructions, and access information for this specific meeting will be available 48 hours prior to the meeting on the Commission's agenda and minutes page. This meeting will be conducted in a remote format consistent with Chapter 2 of the Acts of 2023, which further extends certain COVID-19 measures regarding remote participation in public meetings until March 31, 2025. Please note: Not all items listed may in fact be discussed and other items not listed may be brought up for discussion to the extent permitted by law. This agenda includes those matters which can be reasonably anticipated to be discussed at the meeting.

Agenda

1. Administrative
 - a. 2025 Meeting Schedule Changes.
 - b. Correspondence Received.
2. Discussion
 - a. Certificate of Compliance Request: 1165R Massachusetts Avenue.
 - b. Enforcement Order: 335 Mystic Street.
 - c. Enforcement Order: 40 Park Avenue.
 - d. Water Bodies Working Group.
 - Budget Update.
 - e. CPA Committee Liaison.
 - f. Tree Committee Update.
 - g. Vice Chair Term.

3. Hearings

DEP #091-0356: Notice of Intent: Thorndike Place (Continued from 01/02/2025).

DEP #091-0356: Notice of Intent: Thorndike Place (Continued from 01/02/2025).

The Conservation Commission will hold a public hearing under the Wetlands Protection Act to consider a Notice of Intent for the construction of Thorndike Place, a multifamily development on Dorothy Road in Arlington. Areas proposed to be altered include Buffer Zone to Bordering Vegetated Wetland and Bordering Land Subject to Flooding associated with Alewife Brook.



Town of Arlington, Massachusetts

2025 Meeting Schedule Changes.

Summary:

2025 Meeting Schedule Changes.

ATTACHMENTS:

	Type	File Name	Description
▢	Reference Material	2025_Filing_Deadlines.pdf	2025 Filing Deadlines.pdf



TOWN OF ARLINGTON
 MASSACHUSETTS
CONSERVATION COMMISSION

FILING DEADLINES FOR 2025

Meeting Date	Application Deadline	Supplemental Information Deadline¹	Legal Notices Published	Agenda Published
<i>Thursdays, 7:00pm</i>	<i>Wednesdays, 12pm</i>		<i>Thursdays</i>	<i>Tuesdays</i>
January 2, 2025	12/18/2024	12/26/2024	12/26/2024	12/31/2024
January 16, 2025	1/2/2025	1/8/2025	1/9/2025	1/14/2025
February 6, 2025	1/22/2025	1/29/2025	1/30/2025	2/4/2025
February 20, 2025	2/5/2025	2/12/2025	2/13/2025	2/18/2025
March 6, 2025	2/19/2025	2/26/2025	2/27/2025	3/4/2025
March 20, 2025	3/5/2025	3/12/2025	3/13/2025	3/18/2025
April 3, 2025	3/19/2025	3/26/2025	3/27/2025	4/1/2025
April 17, 2025	4/2/2025	4/9/2025	4/10/2025	4/15/2025
May 1, 2025	4/16/2025	4/23/2025	4/24/2025	4/29/2025
May 15, 2025	4/30/2025	5/7/2025	5/8/2025	5/13/2025
June 5, 2025	5/21/2025	5/28/2025	5/29/2025	6/3/2025
June 26, 2025	6/11/2025	6/18/2025	6/19/2025	6/24/2025
July 10, 2025	6/25/2025	7/2/2025	7/3/2025	7/8/2025
July 24, 2025	7/9/2025	7/16/2025	7/17/2025	7/22/2025
August 7, 2025	7/23/2025	7/30/2025	7/31/2025	8/5/2025
August 21, 2025	8/6/2025	8/13/2025	8/14/2025	8/19/2025
September 4, 2025	8/20/2025	8/27/2025	8/28/2025	9/2/2025
September 18, 2025	9/3/2025	9/10/2025	9/11/2025	9/16/2025
October 9, 2025	9/25/2025	10/1/2025	10/2/2025	10/7/2025
October 23, 2025	10/8/2025	10/15/2025	10/16/2025	10/21/2025
November 6, 2025	10/22/2025	10/29/2025	10/30/2025	11/4/2025
November 20, 2025	11/5/2025	11/12/2025	11/13/2025	11/18/2025
December 4, 2025	11/19/2025	11/26/2025	11/27/2025	12/2/2025
December 18, 2025	12/3/2025	12/10/2025	12/11/2025	12/16/2025

¹ Supplemental information deadlines are for hearings continued from the previous meeting.



Town of Arlington, Massachusetts

Correspondence Received.

Summary:

Correspondence Received.

ATTACHMENTS:

	Type	File Name	Description
▢	Reference Material	FINAL_MMA_Review_Letter_1-15-25.pdf	Correspondence Received - Thorndike Place - MMA

January 15, 2025

Town of Arlington Conservation Commission
Attn: Mr. Charles Tirone, Chairperson
730 Massachusetts Avenue
Arlington, MA 02476

RE: Thorndike Place, Dorothy Road, Arlington, Massachusetts – Preliminary Review of New Applicant Information

Dear Mr. Tirone and Commission Members,

McDonald Morrissey Associates, LLC (MMA) is providing this letter in response to The Arlington Land Trust’s request for a preliminary technical review of new materials presented by BSC Group (BSC) on behalf of Arlington Land Realty, LLC (Applicant). In conducting our review, MMA primarily focused on the following documents:

- *Stormwater Report, Thorndike Place, Dorothy Road, Arlington, MA.* Prepared by BSC Group, Inc., revised December 2024. Note: this reference extends to the associated “calculations only” version of the stormwater report presented as an electronic file named “2024-12_Revised_Stormwater-Calcs_Only.pdf”
- Letter to the Town of Arlington Conservation Commission from Dominic Rinaldi of BSC Group, Inc. *RE: Revisions to Stormwater Management/Response to Peer Review, Thorndike Place Residential Development.* Dated January 3, 2025.

MMA’s preliminary review of the new materials has resulted in a set of initial observations, which are summarized as follows:

- The new design does away with the concept of temporarily storing significant quantities of stormwater on the roof of the main building, but the smaller infiltration systems located between the proposed townhomes along the northern boundary of the property have returned.
- System 1, which was created by dividing the primary stormwater infiltration system included in prior design iterations into two subareas, has been elevated such that BSC is now claiming 4-feet of vertical separation between the bottom of the system and estimated seasonal high groundwater (ESHGW) is provided. Based on this change, BSC claims they are absolved of the responsibility of performing a groundwater mounding analysis for System 1 according to Volume 3, Chapter 1 of the Massachusetts Stormwater Handbook (MSH). It is worth noting that, according to BSC’s HydroCAD modeling, System 1 would be

responsible for approximately 84% of cumulative infiltration across the seven proposed subsurface structures and the rain garden during storm events under post-development conditions.

- Groundwater mounding analyses are performed by BSC for the other, smaller proposed stormwater infiltration structures (i.e., Systems 2 through 7 and the rain garden). BSC presents the analyses as being reliable predictions of mounding generated during the 100-year, 24-hour storm event; however, they are fundamentally flawed for a variety of reasons, including the following: 1. any additive effects from simultaneous infiltration by other systems, including System 1, are ignored; and 2. the inputs used by BSC are inconsistent with the infiltration rates and durations used/predicted by their own HydroCAD model.
- Correcting only the two issues described above causes predicted groundwater mounding to rise well above the bottoms of Systems 1 and 7 during all considered design storm events, ranging from the 2-year, 24-hour storm event to the 100-year, 24-hour storm event (refer to **Attachment A**).

The following section provides additional technical detail and discussion related to the initial observations presented above:

- In describing the HydroCAD modeling, BSC’s Stormwater Report claims the following: “...*the infiltration rate for silt loam (0.27-inches per hour [in/hr]) has been used in the infiltration system design to account for the materials found being primarily fill*”. This statement is inaccurate, as certain features (e.g., System 1) selectively utilize a 0.52 in/hr infiltration rate, while other, smaller infiltration systems rely on the 0.27 in/hr infiltration rate. Though the same issue was previously highlighted in a prior review letter authored by MMA¹, it appears to remain unaddressed by BSC.
- BSC’s revised design includes raising the bottom of System 1 to elevation (El.) +8-feet, thus creating a claimed vertical separation (i.e., that BSC measures from the chamber bottoms, not the bottom of the proposed stone layer) of exactly 4-feet relative to the proposed ESHGW condition at El. +4-feet. Rather than providing an obvious functional benefit, this modification appears to intentionally target a detail contained in the MSH. Specifically, as noted in Volume 3, Chapter 1 of the MSH, a groundwater mounding analysis requirement is triggered when a proposed system is intended to attenuate peak discharges for certain storm events (i.e., equal to or greater in magnitude than the 10-year, 24-hour event) and less than 4-feet of vertical separation from ESHGW is provided. While BSC is now claiming a groundwater mounding analysis for System 1 can be avoided under the letter of the MSH, the following considerations should be noted:

¹ Letter to the Town of Arlington Conservation Commission from McDonald Morrissey Associates, LLC. RE: Thorndike Place, Dorothy Road, Arlington, Massachusetts – Preliminary Review of New Applicant and Reviewer Information. Dated November 4, 2024.

- BSC inappropriately treats their proposed ESHGW elevation as a highly certain condition, disregarding evidence illustrating significant degrees of spatial and temporal variability in water table conditions at the site. Under prior proposed design iterations, a groundwater mounding analysis—albeit flawed in a variety of ways—was being performed by BSC for each significant infiltration structure. In MMA’s opinion, this approach allowed for a minor amount of leeway relative to the specific ESHGW elevation, particularly given the severity (i.e., significant heights) of groundwater mounding predicted for design storm events using BSC’s selected method. BSC’s new approach now unreasonably relies on the uncertain ESHGW condition as a means of avoiding conducting an important analysis for a controlling (i.e., in terms of infiltration volume) structure, particularly since previously presented information suggests 4-feet of vertical separation is unlikely to be adequate in terms of preventing groundwater mounding from adversely impacting System 1².
- Though the MSH clearly identifies the criteria defining the mounding analysis requirement, it does not say groundwater mounding should be completely ignored in cases where larger (i.e., 4-feet or greater) vertical separations are provided. Hydraulic responses to infiltration, such as groundwater mounding heights, are governed by site-specific characteristics including aquifer properties (e.g., hydraulic conductivity, storativity, etc.). A single/common threshold (e.g., 4-foot vertical separation distance) may be conservative and therefore applicable in most cases, but it would be technically invalid to assume it would be universally applicable. The pre-existing evidence highlighting concerns over adverse effects associated with groundwater mounding³ should be a cause for more careful analysis to verify the viability of the proposed design, as opposed to being treated as motivation to sidestep such efforts.
- By completely ignoring groundwater mounding caused by System 1 infiltration, BSC has compromised the results of groundwater mounding analyses performed for other proposed infiltration systems, particularly System 7. Effects from infiltration sources that are simultaneously active and located in close proximity to one another are generally additive and must be handled accordingly. The very U.S. Geological Survey (USGS) study that produced the spreadsheet used by BSC to perform their groundwater mounding analyses⁴ states the following: “...*groundwater mounding associated with two or more nearby infiltration basins can be*

² Letter to The Arlington Land Trust from McDonald Morrissey Associates, LLC. *RE: Thorndike Place, Dorothy Road, Arlington, Massachusetts – Preliminary Review of Applicant’s Groundwater Mounding Analysis*. Dated April 26, 2024

³ Letter to The Arlington Land Trust from McDonald Morrissey Associates, LLC. *RE: Thorndike Place, Dorothy Road, Arlington, Massachusetts – Preliminary Review of Applicant’s Groundwater Mounding Analysis*. Dated April 26, 2024.

⁴ Carleton, G.B., 2010, *Simulation of groundwater mounding beneath hypothetical stormwater infiltration basins*: U.S. Geological Survey Scientific Investigations Report 2010-5102, 64 p.

conservatively estimated by simulating the basins separately then adding together the mounding at any given location associated with each individual basin". MMA will be prepared to elaborate on this point during the next public hearing, which is currently scheduled for January 16, 2025.

- Regarding BSC's application of the Hantush analytical model for conducting mounding analyses for infiltration systems other than System 1, MMA currently believes the most notable deficiency is the failure to account for additive mounding effects caused by simultaneous infiltration from multiple systems, as discussed above. However, additional deficiencies are also evident. For example, the applied infiltration (i.e., "recharge") rates and durations used by BSC are inexplicably inconsistent with their own HydroCAD predictions. The inconsistency is best evidenced by the fact that, in many cases, the assigned rates of recharge significantly exceed the claimed assumed infiltration capacity of site soils (i.e., 0.27 in/hr). Furthermore, site-specific and project-specific complexities, such as building foundations acting as barriers to lateral groundwater flow, continue to limit the applicability and representativeness of the idealized Hantush analytical model that is used by BSC. In consideration of these limitations, MMA reiterates our previously stated perspective that a more robust and flexible numerical modeling approach (e.g., MODFLOW) should be pursued to provide more reliable predictions of post-development groundwater mounding during storm events.

The review described herein is preliminary and based on information made available to MMA as of the indicated transmittal date. MMA therefore reserves the right to amend and/or extend this commentary based on expanded review and/or review of new information provided by the Applicant or other interested parties.

Sincerely,



Michael Mobile, Ph.D., CGWP
President, McDonald Morrissey Associates, LLC

Attachment: (A) MOUNDSOLV Summary Reports

MAM/

\\mma-server\Data\1_Projects\Arlington\Thorndike_Place\7_Reports_and_Memos\Comment_Letter_1-14-25\FINAL_MMA_Review_Letter_1-15-25.docx

Attachment A:
MOUNDSOLV Summary Reports

2-Year, 24-Hour Storm Event

System 7 Infiltration Volume = 1,379 cu. ft. (HydroCAD)

System 7 Infiltration Duration = 25.3 hrs @ 0.27 in/hr

System 1 Infiltration Volume = 13,377 cu. ft. (HydroCAD)

System 1 Infiltration Duration = 41.4 hrs @ 0.52 in/hr

MOUNDSOLV

GROUNDWATER MOUNDING ANALYSIS FOR A SLOPING WATER-TABLE AQUIFER

ZLOTNIK ET AL. (2017) SOLUTION

Solution Method

Zlotnik et al. (2017) transient solution for a rectangular source (linearization method 2)


Site Description

Aquifer Data

Property	Value
Horizontal hydraulic conductivity, K (ft/d)	5.4
Specific yield, S_y	0.08
Initial saturated thickness, h_0 (ft)	16
Maximum allowable water-table rise, σ (ft)	4
Dip, i (ft/ft)	0
Slope rotation from x axis, γ ($^\circ$)	0

Recharge Sources

Property	Source 1	Source 2
X coordinate at center, X (ft)	0	120
Y coordinate at center, Y (ft)	0	0
Dimension along x^* axis, L (ft)	34.45	160
Dimension along y^* axis, W (ft)	70.3	46.62
Rotation from slope direction, ϕ ($^\circ$)	0	0
Recharge rate, Q (ft ³ /d)	1307.7909	7757.568
Infiltration rate, q (ft/d)	0.54	1.04




Map of recharge source.


Monitoring Points

Elapsed Time, $t = 1.05 d$

Name	x (ft)	y (ft)	s (ft)	h (ft)	z (ft)
Source 1	0	0	3.152	19.15	0
System 1	120	0	7.065	23.06	0



Contour plot of water-table rise.




Contour plot of water-table elevation.


Time Series Data

Time (d)	Source 1		System 1	
	s (ft)	h (ft)	s (ft)	h (ft)
0	0	16	0	16
0.003062	0.02067	16.02	0.0398	16.04
0.006889	0.0465	16.05	0.08956	16.09
0.01167	0.07879	16.08	0.1517	16.15
0.01765	0.119	16.12	0.2295	16.23
0.02513	0.1689	16.17	0.3266	16.33
0.03447	0.2299	16.23	0.4476	16.45
0.04615	0.3035	16.3	0.5973	16.6
0.06075	0.391	16.39	0.7809	16.78

0.079	0.4935	16.49	1.003	17
0.1018	0.6122	16.61	1.269	17.27
0.1303	0.748	16.75	1.583	17.58
0.166	0.9021	16.9	1.949	17.95
0.2105	1.076	17.08	2.372	18.37
0.2662	1.272	17.27	2.854	18.85
0.3358	1.494	17.49	3.401	19.4
0.4228	1.745	17.75	4.012	20.01
0.5316	2.03	18.03	4.688	20.69
0.6676	2.356	18.36	5.427	21.43
0.8376	2.727	18.73	6.221	22.22
1.05	3.152	19.15	7.065	23.06



Time-series plot of water-table rise.



Time-series plot of water-table elevation.

Profile Data


Profile Along X* Axis for Source 1 at Elapsed Time, $t = 1.05 d$

x^* (ft)	s (ft)	h (ft)	z (ft)
-71	0.2256	16.23	0
-68.16	0.2593	16.26	0


-65.32	0.2975	16.3	0
-62.48	0.3405	16.34	0
-59.64	0.3888	16.39	0
-56.8	0.4431	16.44	0
-53.96	0.5039	16.5	0
-51.12	0.5718	16.57	0
-48.28	0.6476	16.65	0
-45.44	0.7319	16.73	0
-42.6	0.8256	16.83	0
-39.76	0.9294	16.93	0
-36.92	1.044	17.04	0
-34.08	1.171	17.17	0
-31.24	1.31	17.31	0
-28.4	1.463	17.46	0
-25.56	1.631	17.63	0
-22.72	1.815	17.82	0
-19.88	2.015	18.02	0
-17.04	2.233	18.23	0
-14.2	2.444	18.44	0
-11.36	2.629	18.63	0
-8.52	2.791	18.79	0
-5.68	2.931	18.93	0
-2.84	3.051	19.05	0
0	3.152	19.15	0
2.84	3.235	19.24	0
5.68	3.302	19.3	0
8.52	3.353	19.35	0
11.36	3.389	19.39	0
14.2	3.411	19.41	0
17.04	3.419	19.42	0
19.88	3.433	19.43	0
22.72	3.481	19.48	0
25.56	3.565	19.56	0
28.4	3.685	19.69	0
31.24	3.845	19.84	0

34.08	4.044	20.04	0
36.92	4.285	20.28	0
39.76	4.569	20.57	0
42.6	4.862	20.86	0
45.44	5.121	21.12	0
48.28	5.349	21.35	0
51.12	5.552	21.55	0
53.96	5.732	21.73	0
56.8	5.892	21.89	0
59.64	6.035	22.03	0
62.48	6.163	22.16	0
65.32	6.277	22.28	0
68.16	6.379	22.38	0
71	6.471	22.47	0

The axes of Source 1 (x^* , y^*) are rotated 0° from the axes of mapping coordinate system (x , y)



Profile of water-table rise along x^* axis of Source 1.



Profile of water-table elevation along x^* axis of Source 1.


Profile Along Y^* Axis for Source 1 at Elapsed Time, $t = 1.05 d$

y^* (ft) s (ft) h (ft) z (ft)


-71	0.4641	16.46	0
-68.16	0.5262	16.53	0
-65.32	0.5954	16.6	0
-62.48	0.6724	16.67	0
-59.64	0.7578	16.76	0
-56.8	0.8524	16.85	0
-53.96	0.9571	16.96	0
-51.12	1.073	17.07	0
-48.28	1.201	17.2	0
-45.44	1.342	17.34	0
-42.6	1.498	17.5	0
-39.76	1.671	17.67	0
-36.92	1.861	17.86	0
-34.08	2.067	18.07	0
-31.24	2.257	18.26	0
-28.4	2.424	18.42	0
-25.56	2.57	18.57	0
-22.72	2.698	18.7	0
-19.88	2.807	18.81	0
-17.04	2.9	18.9	0
-14.2	2.978	18.98	0
-11.36	3.041	19.04	0
-8.52	3.09	19.09	0
-5.68	3.124	19.12	0
-2.84	3.145	19.14	0
0	3.152	19.15	0
2.84	3.145	19.14	0
5.68	3.124	19.12	0
8.52	3.09	19.09	0
11.36	3.041	19.04	0
14.2	2.978	18.98	0
17.04	2.9	18.9	0
19.88	2.807	18.81	0
22.72	2.698	18.7	0
25.56	2.57	18.57	0

28.4	2.424	18.42	0
31.24	2.257	18.26	0
34.08	2.067	18.07	0
36.92	1.861	17.86	0
39.76	1.671	17.67	0
42.6	1.498	17.5	0
45.44	1.342	17.34	0
48.28	1.201	17.2	0
51.12	1.073	17.07	0
53.96	0.9571	16.96	0
56.8	0.8524	16.85	0
59.64	0.7578	16.76	0
62.48	0.6724	16.67	0
65.32	0.5954	16.6	0
68.16	0.5262	16.53	0
71	0.4641	16.46	0

The axes of Source 1 (x^ , y^*) are rotated 0° from the axes of mapping coordinate system (x , y)*



Profile of water-table rise along y^ axis of Source 1.*




Profile of water-table elevation along y^ axis of Source 1.*

Sensitivity Data

Source 1, $x=0$ ft, $y=0$ ft

Parameter Water-Table Rise (ft)

Multiplier	K	Sy	h_o
0.5	3.943	4.876	3.797
0.575	3.772	4.47	3.672
0.65	3.628	4.14	3.559
0.725	3.502	3.865	3.457
0.8	3.392	3.632	3.364
0.875	3.294	3.431	3.279
0.95	3.206	3.256	3.201
1.025	3.126	3.102	3.128
1.1	3.053	2.965	3.061
1.175	2.986	2.843	2.998
1.25	2.924	2.732	2.939
1.325	2.866	2.632	2.884
1.4	2.813	2.54	2.832
1.475	2.762	2.456	2.783
1.55	2.715	2.378	2.737
1.625	2.671	2.306	2.694
1.7	2.629	2.24	2.652
1.775	2.589	2.177	2.613
1.85	2.551	2.119	2.575
1.925	2.515	2.065	2.539
2	2.481	2.014	2.505



Sensitivity plot for water-table rise.

Notation

h is water-table elevation above datum¹

h_o is aquifer saturated thickness prior to mounding

i is dip of aquifer

K is horizontal hydraulic conductivity

L is dimension of recharge source parallel to x^* axis

q is infiltration rate ($= Q / L \cdot W$)

Q is recharge rate

s is water-table rise above static water table

S_y is specific yield

t is time since start of recharge

t_0 is time when recharge stops

W is dimension of recharge source parallel to y^* axis

x, y are mapping Cartesian coordinate axes

x^*, y^* are recharge source Cartesian coordinate axes

z is elevation above datum¹

γ is angle between x axis and dip direction

ϕ is angle between dip direction and x^* axis of recharge source

σ is maximum acceptable water-table rise

¹*Elevation datum is the base of aquifer beneath the center of primary recharge source*

Report generated by MOUNDSOLV v4.0 on 14 Jan 2025 at 23:00:23

MOUNDSOLV (www.aqtesolv.com)

Copyright © 2019-2021 HydroSOLVE, Inc. All rights reserved.

100-Year, 24-Hour Storm Event

System 7 Infiltration Volume = 1,621 cu. ft. (HydroCAD)

System 7 Infiltration Duration = 29.7 hrs @ 0.27 in/hr

System 1 Infiltration Volume = 15,354 cu. ft. (HydroCAD)

System 1 Infiltration Duration = 47.5 hrs @ 0.52 in/hr

MOUNDSOLV

GROUNDWATER MOUNDING ANALYSIS FOR A SLOPING WATER-TABLE AQUIFER

ZLOTNIK ET AL. (2017) SOLUTION

Solution Method

Zlotnik et al. (2017) transient solution for a rectangular source (linearization method 2)


Site Description

Aquifer Data

Property	Value
Horizontal hydraulic conductivity, K (ft/d)	5.4
Specific yield, S_y	0.08
Initial saturated thickness, h_0 (ft)	16
Maximum allowable water-table rise, σ (ft)	4
Dip, i (ft/ft)	0
Slope rotation from x axis, γ ($^\circ$)	0

Recharge Sources

Property	Source 1	Source 2
X coordinate at center, X (ft)	0	120
Y coordinate at center, Y (ft)	0	0
Dimension along x^* axis, L (ft)	34.45	160
Dimension along y^* axis, W (ft)	70.3	46.62
Rotation from slope direction, ϕ ($^\circ$)	0	0
Recharge rate, Q (ft ³ /d)	1307.7909	7757.568
Infiltration rate, q (ft/d)	0.54	1.04




Map of recharge source.


Monitoring Points

Elapsed Time, $t = 1.24 d$

Name	x (ft)	y (ft)	s (ft)	h (ft)	z (ft)
Source 1	0	0	3.503	19.5	0
System 1	120	0	7.714	23.71	0



Contour plot of water-table rise.




Contour plot of water-table elevation.


Time Series Data

Time (d)	Source 1		System 1	
	s (ft)	h (ft)	s (ft)	h (ft)
0	0	16	0	16
0.003616	0.02441	16.02	0.047	16.05
0.008135	0.05491	16.05	0.1058	16.11
0.01379	0.09303	16.09	0.1792	16.18
0.02085	0.1404	16.14	0.271	16.27
0.02967	0.1988	16.2	0.3855	16.39
0.04071	0.2696	16.27	0.5278	16.53
0.0545	0.3541	16.35	0.7029	16.7
0.07174	0.4536	16.45	0.9159	16.92

0.09329	0.569	16.57	1.172	17.17
0.1202	0.7013	16.7	1.474	17.47
0.1539	0.8516	16.85	1.828	17.83
0.196	1.021	17.02	2.238	18.24
0.2486	1.213	17.21	2.707	18.71
0.3144	1.428	17.43	3.238	19.24
0.3966	1.672	17.67	3.835	19.83
0.4994	1.949	17.95	4.497	20.5
0.6278	2.263	18.26	5.221	21.22
0.7884	2.623	18.62	6.004	22
0.9891	3.034	19.03	6.837	22.84
1.24	3.503	19.5	7.714	23.71



Time-series plot of water-table rise.



Time-series plot of water-table elevation.

Profile Data


Profile Along X* Axis for Source 1 at Elapsed Time, $t = 1.24 d$

x^* (ft)	s (ft)	h (ft)	z (ft)
-71	0.3052	16.31	0
-68.16	0.3462	16.35	0


-65.32	0.3919	16.39	0
-62.48	0.4429	16.44	0
-59.64	0.4997	16.5	0
-56.8	0.5627	16.56	0
-53.96	0.6326	16.63	0
-51.12	0.7101	16.71	0
-48.28	0.7956	16.8	0
-45.44	0.8901	16.89	0
-42.6	0.9941	16.99	0
-39.76	1.109	17.11	0
-36.92	1.234	17.23	0
-34.08	1.372	17.37	0
-31.24	1.523	17.52	0
-28.4	1.687	17.69	0
-25.56	1.867	17.87	0
-22.72	2.062	18.06	0
-19.88	2.275	18.27	0
-17.04	2.505	18.5	0
-14.2	2.727	18.73	0
-11.36	2.926	18.93	0
-8.52	3.1	19.1	0
-5.68	3.254	19.25	0
-2.84	3.388	19.39	0
0	3.503	19.5	0
2.84	3.601	19.6	0
5.68	3.683	19.68	0
8.52	3.75	19.75	0
11.36	3.801	19.8	0
14.2	3.838	19.84	0
17.04	3.861	19.86	0
19.88	3.89	19.89	0
22.72	3.952	19.95	0
25.56	4.049	20.05	0
28.4	4.182	20.18	0
31.24	4.352	20.35	0

34.08	4.562	20.56	0
36.92	4.812	20.81	0
39.76	5.103	21.1	0
42.6	5.403	21.4	0
45.44	5.669	21.67	0
48.28	5.904	21.9	0
51.12	6.113	22.11	0
53.96	6.299	22.3	0
56.8	6.466	22.47	0
59.64	6.615	22.61	0
62.48	6.748	22.75	0
65.32	6.869	22.87	0
68.16	6.977	22.98	0
71	7.074	23.07	0

The axes of Source 1 (x^* , y^*) are rotated 0° from the axes of mapping coordinate system (x , y)



Profile of water-table rise along x^* axis of Source 1.



Profile of water-table elevation along x^* axis of Source 1.


Profile Along Y^* Axis for Source 1 at Elapsed Time, $t = 1.24 d$

y^* (ft) s (ft) h (ft) z (ft)


-71	0.6139	16.61	0
-68.16	0.687	16.69	0
-65.32	0.7675	16.77	0
-62.48	0.8559	16.86	0
-59.64	0.9529	16.95	0
-56.8	1.059	17.06	0
-53.96	1.176	17.18	0
-51.12	1.303	17.3	0
-48.28	1.442	17.44	0
-45.44	1.595	17.6	0
-42.6	1.762	17.76	0
-39.76	1.945	17.94	0
-36.92	2.145	18.14	0
-34.08	2.36	18.36	0
-31.24	2.559	18.56	0
-28.4	2.734	18.73	0
-25.56	2.887	18.89	0
-22.72	3.022	19.02	0
-19.88	3.137	19.14	0
-17.04	3.236	19.24	0
-14.2	3.319	19.32	0
-11.36	3.386	19.39	0
-8.52	3.437	19.44	0
-5.68	3.474	19.47	0
-2.84	3.496	19.5	0
0	3.503	19.5	0
2.84	3.496	19.5	0
5.68	3.474	19.47	0
8.52	3.437	19.44	0
11.36	3.386	19.39	0
14.2	3.319	19.32	0
17.04	3.236	19.24	0
19.88	3.137	19.14	0
22.72	3.022	19.02	0
25.56	2.887	18.89	0

28.4	2.734	18.73	0
31.24	2.559	18.56	0
34.08	2.36	18.36	0
36.92	2.145	18.14	0
39.76	1.945	17.94	0
42.6	1.762	17.76	0
45.44	1.595	17.6	0
48.28	1.442	17.44	0
51.12	1.303	17.3	0
53.96	1.176	17.18	0
56.8	1.059	17.06	0
59.64	0.9529	16.95	0
62.48	0.8559	16.86	0
65.32	0.7675	16.77	0
68.16	0.687	16.69	0
71	0.6139	16.61	0

The axes of Source 1 (x^ , y^*) are rotated 0° from the axes of mapping coordinate system (x , y)*



Profile of water-table rise along y^ axis of Source 1.*




Profile of water-table elevation along y^ axis of Source 1.*

Sensitivity Data

Source 1, $x=0$ ft, $y=0$ ft

Parameter Water-Table Rise (ft)

Multiplier	K	Sy	h_o
0.5	4.387	5.4	4.214
0.575	4.197	4.956	4.078
0.65	4.035	4.593	3.955
0.725	3.895	4.291	3.843
0.8	3.772	4.034	3.74
0.875	3.663	3.812	3.646
0.95	3.564	3.619	3.558
1.025	3.474	3.449	3.477
1.1	3.393	3.298	3.402
1.175	3.318	3.162	3.331
1.25	3.248	3.039	3.265
1.325	3.183	2.928	3.204
1.4	3.123	2.827	3.146
1.475	3.067	2.733	3.091
1.55	3.014	2.648	3.039
1.625	2.964	2.568	2.99
1.7	2.916	2.495	2.943
1.775	2.872	2.426	2.899
1.85	2.829	2.362	2.856
1.925	2.789	2.302	2.816
2	2.75	2.245	2.778



Sensitivity plot for water-table rise.

Notation

h is water-table elevation above datum¹

h_o is aquifer saturated thickness prior to mounding

i is dip of aquifer

K is horizontal hydraulic conductivity

L is dimension of recharge source parallel to x^* axis

q is infiltration rate ($= Q / L \cdot W$)

Q is recharge rate

s is water-table rise above static water table

S_y is specific yield

t is time since start of recharge

t_0 is time when recharge stops

W is dimension of recharge source parallel to y^* axis

x, y are mapping Cartesian coordinate axes

x^*, y^* are recharge source Cartesian coordinate axes

z is elevation above datum¹

γ is angle between x axis and dip direction

ϕ is angle between dip direction and x^* axis of recharge source

σ is maximum acceptable water-table rise

¹*Elevation datum is the base of aquifer beneath the center of primary recharge source*

Report generated by MOUNDSOLV v4.0 on 14 Jan 2025 at 22:34:47

MOUNDSOLV (www.aqtesolv.com)

Copyright © 2019-2021 HydroSOLVE, Inc. All rights reserved.



Town of Arlington, Massachusetts

Certificate of Compliance Request: 1165R Massachusetts Avenue.

Summary:

Certificate of Compliance Request: 1165R Massachusetts Avenue.

ATTACHMENTS:

Type	File Name	Description
▢ Reference Material	Exhibit_A_Ryder_Brook_Deed_Restrictions_REV_10.10.24.pdf	Exhibit A Ryder Brook Deed Restrictions REV 10.10.24.pdf Access and Conservation Easement re Land Under Water and Stream Bank - Ryder Brook - 1.14.25.docx Access and Conservation Easement re Land Under Water and Stream Bank - Ryder Brook REDLINE- 1.14.25.docx
▢ Reference Material	Access_and_Conservation_Easement_re_Land_Under_Water_and_Stream_Bank_-_Ryder_Brook_-_1.14.25.docx	Access and Conservation Easement re Land Under Water and Stream Bank - Ryder Brook - 1.14.25.docx Access and Conservation Easement re Land Under Water and Stream Bank - Ryder Brook REDLINE- 1.14.25.docx
▢ Reference Material	Access_and_Conservation_Easement_re_Land_Under_Water_and_Stream_Bank_-_Ryder_Brook_REDLINE-_1.14.25.docx	Access and Conservation Easement re Land Under Water and Stream Bank - Ryder Brook REDLINE- 1.14.25.docx



DEED RESTRICTION AREA FOR BANK
AND LAND UNDER WATER FOR
RELOCATED RYDER BROOK


BANK EASEMENT AREA

STREAM EASEMENT AREA

ACCESS AREA TO
RELOCATED RYDER BROOK

PARKING ONLY

VEHICULAR ACCESS
ONLY (NO PARKING)



P:\161618\161830\DRAWING\PLAN SET\REV\AWP\161830-CVL-24-1-LAYOUT_DEED_EXHIBIT.dwg




Know what's below.
Call before you dig.

ALWAYS CALL 811

It's fast. It's free. It's the law.

THIS DRAWING IS INTENDED FOR MUNICIPAL AND/OR AGENCY
REVIEW AND APPROVAL. IT IS NOT INTENDED AS A CONSTRUCTION
DOCUMENT UNLESS INDICATED OTHERWISE.



BOHLER //

SITE CIVIL AND CONSULTING ENGINEERING
LAND SURVEYING
PROGRAM MANAGEMENT
LANDSCAPE ARCHITECTURE
SUSTAINABLE DESIGN
PERMITTING SERVICES
TRANSPORTATION SERVICES

REVISIONS

REV	DATE	COMMENT	DRAWN BY	CHECKED BY

PROJECT No.: W191330
DRAWN BY: SBB
CHECKED BY: AWP
DATE: 10/10/2024
CAD I.D.: W191330-CVL-24

PROJECT:
**DEED RESTRICTION
AREAS EXHIBIT PLAN**
FOR
**1165R MASS MA
PROPERTY LLC**
MAP #57, BLOCK #2, LOT #10B
1163 MASSACHUSETTS AVE.
TOWN OF ARLINGTON
MIDDLESEX COUNTY,
MASSACHUSETTS

BOHLER //

352 TURNPIKE ROAD
SOUTHBOROUGH, MA 01772
Phone: (508) 480-9900

www.BohlerEngineering.com

**EXHIBIT A
STREAM AND
BANK
EASEMENT
PLAN**

SHEET TITLE:
**RYDER BROOK
DEED
RESTRICTIONS**

SHEET NUMBER:
EX-A

Recording requested by and when recorded return to:

Robinson & Cole LLP
One Boston Place
Boston, MA 02108
Attention: Matthew J. Lawlor, Esq.

**ACCESS AND CONSERVATION EASEMENT REGARDING
LAND UNDER WATER AND STREAM BANK**

[Property Address: 1165R Massachusetts Avenue, Arlington, MA.]

THIS ACCESS AND CONSERVATION EASEMENT REGARDING LAND UNDER WATER AND STREAM BANK (this “**Easement**”), is made this ___ day of September, 2024, by **1165R MASS MA PROPERTY LLC**, a Delaware limited liability company with an address of c/o Spaulding & Slye Investments, 71 Commercial Street, #266, Boston, Massachusetts 02109 (the “**Grantor**”), in favor of the **TOWN OF ARLINGTON CONSERVATION COMMISSION**, a Massachusetts municipality with an address of 112 Mystic Street, Arlington, Massachusetts 02474 (the “**Grantee**”).

Grantor hereby grants to Grantee the perpetual right and easement to access, maintain, inspect, repair, replace, and protect the land under water of the relocated Ryder Brook (respectively, the “**Stream Easement**” and the “**Stream Easement Area**”) and further Grantor hereby grants to Grantee the perpetual right and easement to access, maintain, inspect, repair, replace, and protect the stream bank of the relocated Ryder Brook (respectively, the “**Bank Easement**,” and collectively with the Stream Easement, the “**Stream and Bank Easement**,” and the “**Bank Easement Area**,” and collectively with the Stream Easement Area, the “**Stream and Bank Easement Area**”) located on that certain property of Grantor located at 1165R Massachusetts Avenue in Arlington, MA, more specifically described and shown on the plan entitled “**Deed Restriction Area Exhibit Plan for 1165R Mass MA Property**,” dated May 16, 2022, prepared by Bohler Engineering, and attached hereto at Exhibit A and hereby made a part hereof (the “**Stream and Bank Easement Plan**”), as required to protect stormwater and flood control systems by that certain “**Decision on Application for Comprehensive Permit, G.L. c.40B, §§20-23**,” issued by the Arlington Zoning Board of Appeals, filed with the Arlington Town Clerk on September 17, 2021,

and recorded with the Middlesex South Registry of Deeds (the “**Registry**”) in Book 79029, Page 164, and that certain Order of Conditions issued by the Arlington Conservation Commission on October 28, 2021, and recorded with the Registry in Book 79496, Page 78 (together, the “**Project Approvals**”). As shown on the Stream and Bank Easement Plan, the Stream and Bank Easement Area is labeled with cross-hatching and defined as “Prop. Deed Restriction Area for Bank and Land Under Water for Relocated Ryder Brook.” A metes and bounds description of the Stream Easement Area is attached hereto as Exhibit B and a metes and bounds description of the Bank Easement Area is attached hereto as Exhibit C.

1. Purpose

The purpose of this Easement is to provide Grantee with access to the Stream and Bank Easement Area in order to maintain and protect the critical stormwater handling and storage capacity thereof. Any and all jurisdictional activities outside of the scope of maintenance performed in the Stream and Bank Easement Area shall require the approval of Grantor and consultation with, and, where required by applicable law, permitting by, the Town of Arlington Conservation Commission. Accordingly, Grantee shall have the right to conduct the following activities in the Stream and Bank Easement Area:

- a. Access the Stream and Bank Easement Area as shown on the Stream and Bank Easement Plan, labeled with hatching and defined as “Prop. Access Area to Relocated Ryder Brook,” with vehicular access and parking only areas related thereto as shown on the Stream and Bank Easement Plan;
- b. Post stream and bank protection signs;
- c. Conduct routine inspections; and
- d. Place stream and bank protection measures, including but not limited to stabilizing structures, fences, measures deemed by Grantee, in its reasonable judgment, to be necessary or beneficial for the operation, maintenance and protection of the Steam and Bank Easement Area.

2. Conditions

- a. Prohibited Uses

Grantor and Grantee agree that, with the exception of the Reserved Rights set forth in Subsection (b), below, uses or activities inconsistent with the preservation of the land under water and stream bank located within the Stream and Bank Easement Area may not occur or be made therein. Without limitation, Grantee and Grantor agree that the following uses and activities are not allowed in the Stream and Bank Easement Area:

1. Motorized vehicles of any kind;
2. Disposal or discharges of hazardous materials or wastes;
3. Storage of hazardous materials;
4. Storage or use of fertilizers or pesticides;
5. Access by the general public; and

6. Installation or construction of structures not related to the operation, maintenance, or protection of land under water and stream bank.

b. **Reserved Rights**

Grantor agrees that neither they, nor their successors or assigns, will impair or interfere with the purpose of this Easement for stormwater and flood control, maintenance, and protection. Notwithstanding the provisions of Subsection (a), above, the following rights are reserved by Grantor:

1. Installation, maintenance, repair, replacement, and/or removal of existing stormwater infrastructure in the Stream and Bank Easement Area;
2. Selective cutting or pruning of trees, brush, and other vegetation to prevent, control or remove hazards, disease, insect damage, fire damage, storm damage or invasive species; and
3. Other activities, uses, and structures not inconsistent with the Stream and Bank Easement's purposes of protecting stormwater and flood control facilities within the Stream and Bank Easement Area.

3. Access and Enforcement

Grantee is granted an easement to permit personnel of Grantee to enter the Stream and Bank Easement Area with reasonable advance written notice to Grantor, for the purpose of inspecting the same to determine compliance with or to enforce the conditions of this Easement or take any and all actions as may be necessary or appropriate with or without order of court, to remedy or abate any material violation hereof, provided that Grantee has provided prior written notice to Grantor of such material violation and given Grantor a reasonable amount of time from the date of receipt of notice in which to cure such material violation. The provisions of this Easement, which is executed under seal, shall be in effect in perpetuity, and shall be binding upon and may be enforced against Grantor and Grantee and its successors and/or assigns.

4. Amendment

Modifications and amendments may be made by a written instrument executed by Grantor and Grantee, or their respective successors and/or assigns.

5. Duration; Release

Grantor intends this Easement to be in effect in perpetuity. This Easement may only be released, in whole or in part, by Grantee in writing.

6. Notice

Any notice or communication hereunder shall be effective only if given in writing and shall be deemed duly delivered if (i) hand delivered; (ii) mailed by prepaid certified or registered mail, return receipt requested; or (iii) delivered by a national overnight delivery service, delivery

confirmed. Any notice so addressed shall be deemed duly delivered on the third business day following the day of mailing if so mailed by registered or certified mail, return receipt requested, whether or not accepted, or on the date of delivery if hand delivered or sent by overnight delivery service, to the following addresses:

To Grantor:

1165R MASS MA PROPERTY LLC
c/o Spaulding & Slye Investments
71 Commercial Street, #266
Boston, Massachusetts 02109
Attention: Portfolio Manager

and

1165R MASS MA PROPERTY LLC
c/o Spaulding & Slye Investments
1410 19th Street, NW, Suite 610
Washington, DC 20036
Attention: General Counsel

To Grantee:

TOWN OF ARLINGTON
51 Grove Street
Arlington, Massachusetts 02476
Attention: Zoning Board of Appeals

and

TOWN OF ARLINGTON
730 Massachusetts Avenue Annex
Arlington, Massachusetts 02476
Attention: Conservation Commission

Either party may from time to time designate other addresses within the continental United States by notice to the other.

7. Governing Law

This Easement shall be deemed to constitute a contract made under seal and governed by the laws of the Commonwealth of Massachusetts.

[This page ends here. Signature appears on following page.]

IN WITNESS WHEREOF, Grantor has caused this Easement to be executed as of the Effective Date.

GRANTOR:

1165R MASS MA PROPERTY LLC,
a Delaware limited liability company

By: _____

Name: _____

Title: Authorized Signatory

Commonwealth of Massachusetts

County of _____

On this ___ day of _____, 2024, before me, the undersigned notary public, personally appeared _____, as Authorized Signatory of 1165R MASS MA PROPERTY LLC, proved to me through satisfactory evidence of identification, which was _____, to be the person whose name is signed on the preceding document, and acknowledged to me that he/she/they signed it voluntarily for its stated purpose on behalf of said entity and as the voluntary act of said entity.

Notary Public

Print Name of Notary: _____

My commission expires: _____

EXHIBIT A

Stream and Bank Easement Plan

[See attached.]

EXHIBIT B

Stream Easement Area

COMMENCING AT THE SOUTHWESTERLY CORNER OF RYDER STREET (PRIVATE - 40' WIDE), SAID POINT BEING THE NORTHWESTERLY CORNER OF MAP 57, BLOCK 2, LOT 10B (N/F 1165R MASS MA PROPERTY, LLC), THENCE;

- A. ALONG THE SOUTHERLY LINE OF RYDER STREET, ALONG THE DIVIDING LINE BETWEEN SAID LOT 10B AND MAP 57, BLOCK 2, LOT 11 (N/F ABCJ LAND, LLC), SOUTH 40 DEGREES - 22 MINUTES - 10 SECONDS EAST, A DISTANCE OF 203.42 FEET, THENCE;
- B. DEPARTING SAID DIVIDING LINE, RUNNING THROUGH THE INTERIOR OF SAID LOT 10B, NORTH 57 DEGREES - 43 MINUTES - 30 SECONDS EAST, A DISTANCE OF 52.40 FEET TO THE POINT OF BEGINNING, THENCE CONTINUING THROUGH SAID INTERIOR OF LOT 10B THE FOLLOWING EIGHT (8) COURSES
 - 1. NORTH 36 DEGREES - 07 MINUTES - 02 SECONDS WEST, A DISTANCE OF 10.01 FEET TO A POINT, THENCE;
 - 2. NORTH 55 DEGREES - 54 MINUTES - 20 SECONDS EAST, A DISTANCE OF 100.43 FEET TO A POINT, THENCE;
 - 3. SOUTH 41 DEGREES - 12 MINUTES - 55 SECONDS EAST, A DISTANCE OF 92.14 FEET TO A POINT, THENCE;
 - 4. SOUTH 76 DEGREES - 37 MINUTES - 32 SECONDS EAST, A DISTANCE OF 10.35 FEET TO A POINT, THENCE;
 - 5. SOUTH 41 DEGREES - 13 MINUTES - 52 SECONDS EAST, A DISTANCE OF 10.06 FEET TO A POINT, THENCE;
 - 6. SOUTH 48 DEGREES - 47 MINUTES - 06 SECONDS WEST, A DISTANCE OF 15.53 FEET TO A POINT, THENCE;
 - 7. NORTH 41 DEGREES - 14 MINUTES - 46 SECONDS WEST, A DISTANCE FO 101.76 FEET TO A POINT, THENCE;
 - 8. SOUTH 55 DEGREES - 54 MINUTES - 20 SECONDS WEST, A DISTANCE OF 91.67 FEET TO THE POINT AND PLACE OF BEGINNING.

CONTAINING 2,062 SQUARE FEET 0.047 ACRES

EXHIBIT C

Bank Easement Area

COMMENCING AT THE SOUTHWESTERLY CORNER OF RYDER STREET (PRIVATE - 40' WIDE), SAID POINT BEING THE NORTHWESTERLY CORNER OF MAP 57, BLOCK 2, LOT 10B (N/F 1165R MASS MA PROPERTY, LLC), THENCE;

C. ALONG THE SOUTHERLY LINE OF RYDER STREET, ALONG THE DIVIDING LINE BETWEEN SAID LOT 10B AND MAP 57, BLOCK 2, LOT 11 (N/F ABCJ LAND, LLC), SOUTH 40 DEGREES - 22 MINUTES - 10 SECONDS EAST, A DISTANCE OF 203.42 FEET, THENCE;

D. DEPARTING SAID DIVIDING LINE, RUNNING THROUGH THE INTERIOR OF SAID LOT 10B, NORTH 57 DEGREES - 43 MINUTES - 30 SECONDS EAST, A DISTANCE OF 52.40 FEET TO THE POINT OF BEGINNING, THENCE CONTINUING THROUGH SAID INTERIOR OF LOT 10B THE FOLLOWING FOUR (4) COURSES

9. NORTH 55 DEGREES - 54 MINUTES - 20 SECONDS EAST, A DISTANCE OF 91.67 FEET TO A POINT, THENCE;

10. SOUTH 41 DEGREES - 14 MINUTES - 46 SECONDS EAST, A DISTANCE OF 3.02 FEET TO A POINT, THENCE;

11. SOUTH 55 DEGREES - 54 MINUTES - 20 SECONDS WEST, A DISTANCE OF 91.93 FEET TO A POINT, THENCE;

4. NORTH 36 DEGREES - 20 MINUTES - 30 SECONDS WEST, A DISTANCE OF 3.00 FEET TO THE POINT AND PLACE OF BEGINNING.

CONTAINING 276 SQUARE FEET 0.006 ACRES

and

COMMENCING AT THE SOUTHWESTERLY CORNER OF RYDER STREET (PRIVATE - 40' WIDE), SAID POINT BEING THE NORTHWESTERLY CORNER OF MAP 57, BLOCK 2, LOT 10B (N/F 1165R MASS MA PROPERTY, LLC), THENCE;

E. ALONG THE SOUTHERLY LINE OF RYDER STREET, ALONG THE DIVIDING LINE BETWEEN SAID LOT 10B AND MAP 57, BLOCK 2, LOT 11 (N/F ABCJ LAND, LLC), SOUTH 40 DEGREES - 22 MINUTES - 10 SECONDS EAST, A DISTANCE OF 203.42 FEET, THENCE;

F. DEPARTING SAID DIVIDING LINE, RUNNING THROUGH THE INTERIOR OF SAID LOT 10B, NORTH 64 DEGREES - 55 MINUTES - 18 SECONDS EAST, A DISTANCE OF 49.55 FEET TO THE POINT OF BEGINNING, THENCE CONTINUING THROUGH SAID INTERIOR OF LOT 10B THE FOLLOWING SIX (6) COURSES

12. NORTH 37 DEGREES - 12 MINUTES - 24 SECONDS WEST, A DISTANCE OF 2.60 FEET TO A POINT, THENCE;

13. NORTH 53 DEGREES - 37 MINUTES - 00 SECONDS EAST, A DISTANCE OF 105.82 FEET TO A POINT, THENCE;

14. SOUTH 41 DEGREES - 13 MINUTES - 52 SECONDS EAST, A DISTANCE OF 106.71 FEET TO A POINT, THENCE;

15. NORTH 76 DEGREES - 37 MINUTES - 32 SECONDS WEST, A DISTANCE OF 10.35 FEET TO A POINT, THENCE;

16. NORTH 41 DEGREES - 12 MINUTES - 55 SECONDS WEST, A DISTANCE OF 92.14 FEET TO A POINT, THENCE;

17. SOUTH 55 DEGREES - 54 MINUTES - 20 SECONDS WEST, A DISTANCE OF 100.43 FEET TO THE POINT AND PLACE OF BEGINNING.

CONTAINING 1,075 SQUARE FEET 0.025 ACRES

Recording requested by and when recorded return to:

Robinson & Cole LLP
One Boston Place
Boston, MA 02108
Attention: Matthew J. Lawlor, Esq.

**ACCESS AND CONSERVATION EASEMENT REGARDING
LAND UNDER WATER AND STREAM BANK**

[Property Address: 1165R Massachusetts Avenue, Arlington, MA.]

THIS ACCESS AND CONSERVATION EASEMENT REGARDING LAND UNDER WATER AND STREAM BANK (this “**Easement**”), is made this ___ day of September, 2024, by **1165R MASS MA PROPERTY LLC**, a Delaware limited liability company with an address of c/o Spaulding & Slye Investments, 71 Commercial Street, #266, Boston, Massachusetts 02109 (the “**Grantor**”), in favor of the **TOWN OF ARLINGTON CONSERVATION COMMISSION**, a Massachusetts municipality with an address of 112 Mystic Street, Arlington, Massachusetts 02474 (the “**Grantee**”).

Grantor hereby grants to Grantee the perpetual right and easement to access, maintain, inspect, repair, replace, and protect the land under water of the relocated Ryder Brook (respectively, the “**Stream Easement**” and the “**Stream Easement Area**”) and further Grantor hereby grants to Grantee the perpetual right and easement to access, maintain, inspect, repair, replace, and protect the stream bank of the relocated Ryder Brook (respectively, the “**Bank Easement**,” and collectively with the Stream Easement, the “**Stream and Bank Easement**,” and the “**Bank Easement Area**,” and collectively with the Stream Easement Area, the “**Stream and Bank Easement Area**”) located on that certain property of Grantor located at 1165R Massachusetts Avenue in Arlington, MA, more specifically described and shown on the plan entitled “**Deed Restriction Area Exhibit Plan for 1165R Mass MA Property**,” dated May 16, 2022, prepared by Bohler Engineering, and attached hereto at Exhibit A and hereby made a part hereof (the “**Stream and Bank Easement Plan**”), as required to protect stormwater and flood control systems by that certain “**Decision on Application for Comprehensive Permit, G.L. c.40B, §§20-23**,” issued by the Arlington Zoning Board of Appeals, filed with the Arlington Town Clerk on September 17, 2021,

and recorded with the Middlesex South Registry of Deeds (the “**Registry**”) in Book 79029, Page 164, and that certain Order of Conditions issued by the Arlington Conservation Commission on October 28, 2021, and recorded with the Registry in Book 79496, Page 78 (together, the “**Project Approvals**”). As shown on the Stream and Bank Easement Plan, the Stream and Bank Easement Area is labeled with cross-hatching and defined as “Prop. Deed Restriction Area for Bank and Land Under Water for Relocated Ryder Brook.” A metes and bounds description of the Stream Easement Area is attached hereto as Exhibit B and a metes and bounds description of the Bank Easement Area is attached hereto as Exhibit C.

1. Purpose

The purpose of this Easement is to provide Grantee with access to the Stream and Bank Easement Area in order to maintain and protect the critical stormwater handling and storage capacity thereof. Any and all jurisdictional activities outside of the scope of maintenance performed in the Stream and Bank Easement Area shall require the approval of Grantor and consultation with, and, where required by applicable law, permitting by, the Town of Arlington Conservation Commission. Accordingly, Grantee shall have the right to conduct the following activities in the Stream and Bank Easement Area:

- a. Access the Stream and Bank Easement Area as shown on the Stream and Bank Easement Plan, labeled with hatching and defined as “Prop. Access Area to Relocated Ryder Brook,” with vehicular access and parking only areas related thereto as shown on the Stream and Bank Easement Plan;
- b. Post stream and bank protection signs;
- c. Conduct routine inspections; and
- d. Place stream and bank protection measures, including but not limited to stabilizing structures, fences, measures deemed by Grantee, in its reasonable judgment, to be necessary or beneficial for the operation, maintenance and protection of the Steam and Bank Easement Area.

2. Conditions

- a. Prohibited Uses

Grantor and Grantee agree that, with the exception of the Reserved Rights set forth in Subsection (b), below, uses or activities inconsistent with the preservation of the land under water and stream bank located within the Stream and Bank Easement Area may not occur or be made therein. Without limitation, Grantee and Grantor agree that the following uses and activities are not allowed in the Stream and Bank Easement Area:

1. Motorized vehicles of any kind;
2. Disposal or discharges of hazardous materials or wastes;
3. Storage of hazardous materials;
4. Storage or use of fertilizers or pesticides;
5. Access by the general public; and

6. Installation or construction of structures not related to the operation, maintenance, or protection of land under water and stream bank.

b. **Reserved Rights**

Grantor agrees that neither they, nor their successors or assigns, will impair or interfere with the purpose of this Easement for stormwater and flood control, maintenance, and protection. Notwithstanding the provisions of Subsection (a), above, the following rights are reserved by Grantor:

1. Installation, maintenance, repair, replacement, and/or removal of existing stormwater infrastructure in the Stream and Bank Easement Area;
2. Selective cutting or pruning of trees, brush, and other vegetation to prevent, control or remove hazards, disease, insect damage, fire damage, storm damage or invasive species; and
3. Other activities, uses, and structures not inconsistent with the Stream and Bank Easement's purposes of protecting stormwater and flood control facilities within the Stream and Bank Easement Area.

3. Access and Enforcement

Grantee is granted an easement to permit personnel of Grantee to enter the Stream and Bank Easement Area with reasonable advance written notice to Grantor, for the purpose of inspecting the same to determine compliance with or to enforce the conditions of this Easement or take any and all actions as may be necessary or appropriate with or without order of court, to remedy or abate any material violation hereof, provided that Grantee has provided prior written notice to Grantor of such material violation and given Grantor a reasonable amount of time from the date of receipt of notice in which to cure such material violation. The provisions of this Easement, which is executed under seal, shall be in effect in perpetuity, and shall be binding upon and may be enforced against Grantor and Grantee and its successors and/or assigns.

4. Amendment

Modifications and amendments may be made by a written instrument executed by Grantor and Grantee, or their respective successors and/or assigns.

5. Duration; Release

Grantor intends this Easement to be in effect in perpetuity. This Easement may only be released, in whole or in part, by Grantee in writing.

6. Notice

Any notice or communication hereunder shall be effective only if given in writing and shall be deemed duly delivered if (i) hand delivered; (ii) mailed by prepaid certified or registered mail, return receipt requested; or (iii) delivered by a national overnight delivery service, delivery

confirmed. Any notice so addressed shall be deemed duly delivered on the third business day following the day of mailing if so mailed by registered or certified mail, return receipt requested, whether or not accepted, or on the date of delivery if hand delivered or sent by overnight delivery service, to the following addresses:

To Grantor:

1165R MASS MA PROPERTY LLC
c/o Spaulding & Slye Investments
71 Commercial Street, #266
Boston, Massachusetts 02109
Attention: Portfolio Manager

and

1165R MASS MA PROPERTY LLC
c/o Spaulding & Slye Investments
1410 19th Street, NW, Suite 610
Washington, DC 20036
Attention: General Counsel

To Grantee:

TOWN OF ARLINGTON
51 Grove Street
Arlington, Massachusetts 02476
Attention: Zoning Board of Appeals

and

TOWN OF ARLINGTON
730 Massachusetts Avenue Annex
Arlington, Massachusetts 02476
Attention: Conservation Commission

Either party may from time to time designate other addresses within the continental United States by notice to the other.

7. Governing Law

This Easement shall be deemed to constitute a contract made under seal and governed by the laws of the Commonwealth of Massachusetts.

[This page ends here. Signature appears on following page.]

IN WITNESS WHEREOF, Grantor has caused this Easement to be executed as of the Effective Date.

GRANTOR:

1165R MASS MA PROPERTY LLC,
a Delaware limited liability company

By: _____

Name: _____

Title: Authorized Signatory

Commonwealth of Massachusetts

County of _____

On this ___ day of _____, 2024, before me, the undersigned notary public, personally appeared _____, as Authorized Signatory of 1165R MASS MA PROPERTY LLC, proved to me through satisfactory evidence of identification, which was _____, to be the person whose name is signed on the preceding document, and acknowledged to me that he/she/they signed it voluntarily for its stated purpose on behalf of said entity and as the voluntary act of said entity.

Notary Public

Print Name of Notary: _____

My commission expires: _____

EXHIBIT A

Stream and Bank Easement Plan

[See attached.]

EXHIBIT B

Stream Easement Area

COMMENCING AT THE SOUTHWESTERLY CORNER OF RYDER STREET (PRIVATE - 40' WIDE), SAID POINT BEING THE NORTHWESTERLY CORNER OF MAP 57, BLOCK 2, LOT 10B (N/F 1165R MASS MA PROPERTY, LLC), THENCE;

- A. ALONG THE SOUTHERLY LINE OF RYDER STREET, ALONG THE DIVIDING LINE BETWEEN SAID LOT 10B AND MAP 57, BLOCK 2, LOT 11 (N/F ABCJ LAND, LLC), SOUTH 40 DEGREES - 22 MINUTES - 10 SECONDS EAST, A DISTANCE OF 203.42 FEET, THENCE;
- B. DEPARTING SAID DIVIDING LINE, RUNNING THROUGH THE INTERIOR OF SAID LOT 10B, NORTH 57 DEGREES - 43 MINUTES - 30 SECONDS EAST, A DISTANCE OF 52.40 FEET TO THE POINT OF BEGINNING, THENCE CONTINUING THROUGH SAID INTERIOR OF LOT 10B THE FOLLOWING EIGHT (8) COURSES
 - 1. NORTH 36 DEGREES - 07 MINUTES - 02 SECONDS WEST, A DISTANCE OF 10.01 FEET TO A POINT, THENCE;
 - 2. NORTH 55 DEGREES - 54 MINUTES - 20 SECONDS EAST, A DISTANCE OF 100.43 FEET TO A POINT, THENCE;
 - 3. SOUTH 41 DEGREES - 12 MINUTES - 55 SECONDS EAST, A DISTANCE OF 92.14 FEET TO A POINT, THENCE;
 - 4. SOUTH 76 DEGREES - 37 MINUTES - 32 SECONDS EAST, A DISTANCE OF 10.35 FEET TO A POINT, THENCE;
 - 5. SOUTH 41 DEGREES - 13 MINUTES - 52 SECONDS EAST, A DISTANCE OF 10.06 FEET TO A POINT, THENCE;
 - 6. SOUTH 48 DEGREES - 47 MINUTES - 06 SECONDS WEST, A DISTANCE OF 15.53 FEET TO A POINT, THENCE;
 - 7. NORTH 41 DEGREES - 14 MINUTES - 46 SECONDS WEST, A DISTANCE FO 101.76 FEET TO A POINT, THENCE;
 - 8. SOUTH 55 DEGREES - 54 MINUTES - 20 SECONDS WEST, A DISTANCE OF 91.67 FEET TO THE POINT AND PLACE OF BEGINNING.

CONTAINING 2,062 SQUARE FEET 0.047 ACRES

EXHIBIT C

Bank Easement Area

COMMENCING AT THE SOUTHWESTERLY CORNER OF RYDER STREET (PRIVATE - 40' WIDE), SAID POINT BEING THE NORTHWESTERLY CORNER OF MAP 57, BLOCK 2, LOT 10B (N/F 1165R MASS MA PROPERTY, LLC), THENCE;

C. ALONG THE SOUTHERLY LINE OF RYDER STREET, ALONG THE DIVIDING LINE BETWEEN SAID LOT 10B AND MAP 57, BLOCK 2, LOT 11 (N/F ABCJ LAND, LLC), SOUTH 40 DEGREES - 22 MINUTES - 10 SECONDS EAST, A DISTANCE OF 203.42 FEET, THENCE;

D. DEPARTING SAID DIVIDING LINE, RUNNING THROUGH THE INTERIOR OF SAID LOT 10B, NORTH 57 DEGREES - 43 MINUTES - 30 SECONDS EAST, A DISTANCE OF 52.40 FEET TO THE POINT OF BEGINNING, THENCE CONTINUING THROUGH SAID INTERIOR OF LOT 10B THE FOLLOWING FOUR (4) COURSES

9. NORTH 55 DEGREES - 54 MINUTES - 20 SECONDS EAST, A DISTANCE OF 91.67 FEET TO A POINT, THENCE;

10. SOUTH 41 DEGREES - 14 MINUTES - 46 SECONDS EAST, A DISTANCE OF 3.02 FEET TO A POINT, THENCE;

11. SOUTH 55 DEGREES - 54 MINUTES - 20 SECONDS WEST, A DISTANCE OF 91.93 FEET TO A POINT, THENCE;

4. NORTH 36 DEGREES - 20 MINUTES - 30 SECONDS WEST, A DISTANCE OF 3.00 FEET TO THE POINT AND PLACE OF BEGINNING.

CONTAINING 276 SQUARE FEET 0.006 ACRES

and

COMMENCING AT THE SOUTHWESTERLY CORNER OF RYDER STREET (PRIVATE - 40' WIDE), SAID POINT BEING THE NORTHWESTERLY CORNER OF MAP 57, BLOCK 2, LOT 10B (N/F 1165R MASS MA PROPERTY, LLC), THENCE;

E. ALONG THE SOUTHERLY LINE OF RYDER STREET, ALONG THE DIVIDING LINE BETWEEN SAID LOT 10B AND MAP 57, BLOCK 2, LOT 11 (N/F ABCJ LAND, LLC), SOUTH 40 DEGREES - 22 MINUTES - 10 SECONDS EAST, A DISTANCE OF 203.42 FEET, THENCE;

F. DEPARTING SAID DIVIDING LINE, RUNNING THROUGH THE INTERIOR OF SAID LOT 10B, NORTH 64 DEGREES - 55 MINUTES - 18 SECONDS EAST, A DISTANCE OF 49.55 FEET TO THE POINT OF BEGINNING, THENCE CONTINUING THROUGH SAID INTERIOR OF LOT 10B THE FOLLOWING SIX (6) COURSES

12. NORTH 37 DEGREES - 12 MINUTES - 24 SECONDS WEST, A DISTANCE OF 2.60 FEET TO A POINT, THENCE;

13. NORTH 53 DEGREES - 37 MINUTES - 00 SECONDS EAST, A DISTANCE OF 105.82 FEET TO A POINT, THENCE;

14. SOUTH 41 DEGREES - 13 MINUTES - 52 SECONDS EAST, A DISTANCE OF 106.71 FEET TO A POINT, THENCE;

15. NORTH 76 DEGREES - 37 MINUTES - 32 SECONDS WEST, A DISTANCE OF 10.35 FEET TO A POINT, THENCE;

16. NORTH 41 DEGREES - 12 MINUTES - 55 SECONDS WEST, A DISTANCE OF 92.14 FEET TO A POINT, THENCE;

17. SOUTH 55 DEGREES - 54 MINUTES - 20 SECONDS WEST, A DISTANCE OF 100.43 FEET TO THE POINT AND PLACE OF BEGINNING.

CONTAINING 1,075 SQUARE FEET 0.025 ACRES



Town of Arlington, Massachusetts

Enforcement Order: 335 Mystic Street.

Summary:

Enforcement Order: 335 Mystic Street.



Town of Arlington, Massachusetts

Enforcement Order: 40 Park Avenue.

Summary:

Enforcement Order: 40 Park Avenue.



Town of Arlington, Massachusetts

Water Bodies Working Group.

Summary:

Water Bodies Working Group.

- Budget Update.

ATTACHMENTS:

	Type	File Name	Description
▢	Reference Material	WBWG_Accounting.pdf	WBWG Accounting

Water Bodies Working Group Account History

Last Updated: 12/19/2024

Net Available Fund Balance \$32,081.88

MUNIS	Description	FY19 Actual	FY20 Actual	FY21 Actual	FY22 Actual	FY23 Budget	FY23 Actual	FY24 Budget	FY24 Actual	FY25 Budget	FY25 Expected	FY26 Budget
0117553-596004	Revenue/Appropriation	60,000	50,000	0	50,000	15,000	15,000	50,000	50,000	85,000	85,000	95,000
32314-483001	Revenue/Donations	4,376	1,800	1,800	1,800	1,800	2,300		3,800			
	Carry forward - Revolving Funds	77,205	76,134	25,325	60,019	93,096	77,314	64,687	64,687	57,958	57,958	32,082
32315-578044	Beginning Balance - 7/1	152,235	153,868	94,896	128,109	109,896	131,589	114,687	118,487	142,958	142,958	127,082
32315-578044	Expenses - Spy Pond	-19,075	-41,177	-34,076	-12,875	-35,000	-34,673	-35,000	-27,370	-35,000	-27,190	-45,000
32315-578044	Expenses - Reservoir	-15,000	-16,000	-24,840	0	-25,000	-26,000	-26,000	-26,000	-27,500	-68,750	-50,000
32315-578044	Expenses - Hills	-3,512	-2,700	-4,670	-946	-5,000	-6,193	-5,000	-7,159	-6,270	-6,201	-6,520
32315-578044	Expenses - McClennen	-12,580	0	0	0	0	0	0	0	-5,000	-500	-1,000
32315-578044	Expenses - CC Other	0	-895	0	0	-5,000	-35	-5,000	0	-5,000	0	-5,000
	Encumbered expenses										-8,235	
	Total Expenses	-50,167	-60,772	-63,587	-13,821	-70,000	-66,901	-71,000	-60,529	-78,770	-110,876	-107,520
	Ending (or Current) Balance - 6/30	102,068	93,096	31,309	114,289	39,896	64,687	43,687	57,958	64,188	32,082	19,562

Proactive monitoring, aquatic and phragmites treatment
 Full (3 weeks) WC harvesting + monitoring
 FoMRP request
 Pond buffer zone etc.(CPA funding \$40k bathymetric/sedimentation survey)
 Contingency

Transfer annual allocation from account 0117553-524015 to account 32314-497006 at the start of each fiscal year.



Town of Arlington, Massachusetts

DEP #091-0356: Notice of Intent: Thorndike Place (Continued from 01/02/2025).

Summary:

DEP #091-0356: Notice of Intent: Thorndike Place (Continued from 01/02/2025).

The Conservation Commission will hold a public hearing under the Wetlands Protection Act to consider a Notice of Intent for the construction of Thorndike Place, a multifamily development on Dorothy Road in Arlington. Areas proposed to be altered include Buffer Zone to Bordering Vegetated Wetland and Bordering Land Subject to Flooding associated with Alewife Brook.

ATTACHMENTS:

Type	File Name	Description
Reference Material	2024-12_Revised_Stormwater_Report.pdf	2024-12 Revised Stormwater Report.pdf
Reference Material	2024-12_Revised_Stormwater-Calcs_Only.pdf	2024-12 Revised Stormwater-Calcs Only.pdf
Reference Material	2024-12-17_Thorndike_Revised_Plan_Set_(Full).pdf	2024-12-17 Thorndike Revised Plan Set (Full).pdf
Reference Material	2025-01-02_Thorndike_Place_ISMP_Summary.pdf	2025-01-02 Thorndike Place ISMP Summary.pdf
Reference Material	2025-01-03_Thorndike_Place_Response_to_Stormwater_Peer_Review.pdf	2025-01-03 Thorndike Place Response to Stormwater Peer Review.pdf

STORMWATER REPORT

**THORNDIKE PLACE
DOROTHY ROAD
ARLINGTON, MA**

NOVEMBER 2020
REVISED: AUGUST 2021
SEPTEMBER 2023
JANUARY 2024
DECEMBER 2024

Owner/Applicant:

ARLINGTON LAND REALTY LLC
c/o Mugar Enterprises, Inc.
116 Huntington Avenue
Boston, MA 02116

BSC Job Number: 23407.00

Prepared by:



803 Summer Street
Boston, MA 02127

TABLE OF CONTENTS

- 1.0 PROJECT INFORMATION
 - 1.01 PROJECT DESCRIPTION
 - 1.02 PRE-DEVELOPMENT CONDITIONS
 - 1.03 POST-DEVELOPMENT CONDITIONS
- 2.0 DRAINAGE SUMMARY
 - 2.01 STORMWATER STANDARD 1 – NEW STORMWATER CONVEYANCES
 - 2.02 STORMWATER STANDARD 2 – STORMWATER RUNOFF RATES
 - 2.03 STORMWATER STANDARD 3 – GROUNDWATER RECHARGE
 - 2.04 STORMWATER STANDARD 4 – TSS REMOVAL
 - 2.05 STORMWATER STANDARD 5 – LUHPPL
 - 2.06 STORMWATER STANDARD 6 – CRITICAL AREAS
 - 2.07 STORMWATER STANDARD 7 – REDEVELOPMENT PROJECTS
 - 2.08 STORMWATER STANDARD 8 – SEDIMENTATION & EROSION CONTROL PLAN
 - 2.09 STORMWATER STANDARD 9 – LONG TERM O&M PLAN
 - 2.10 STORMWATER STANDARD 10 – ILLICIT DISCHARGES
 - 2.11 CONCLUSIONS
 - 2.12 COMPENSATORY FLOOD STORAGE
- 3.0 CONSTRUCTION PERIOD POLLUTION PREVENTION AND EROSION AND SEDIMENTATION CONTROL
- 4.0 LONG-TERM POLLUTION PREVENTION & OPERATION AND MAINTENANCE PLAN
- 5.0 HYDROLOGY CALCULATIONS
 - 5.01 EXISTING WATERSHED PLAN
 - 5.02 EXISTING HYDROLOGY CALCULATIONS (HYDROCAD™ PRINTOUTS)
 - 5.03 PROPOSED WATERSHED PLAN
 - 5.04 PROPOSED HYDROLOGY CALCULATIONS (HYDROCAD™ PRINTOUTS)
- 6.0 ADDITIONAL DRAINAGE CALCULATIONS
 - 6.01 TSS REMOVAL CALCULATIONS
 - 6.02 GROUNDWATER RECHARGE VOLUME CALCULATIONS
 - 6.03 WATER QUALITY VOLUME CALCULATIONS
 - 6.04 RIP-RAP OUTLET PROTECTION SIZING
 - 6.05 GROUNDWATER MOUNDING ANALYSIS
 - 6.06 ILLICIT DISCHARGE COMPLIANCE STATEMENT

APPENDICES

- APPENDIX A – USGS LOCUS MAP
- APPENDIX B – FEMA MAP
- APPENDIX C – WEB SOIL SURVEY
- APPENDIX D – TEST PIT LOGS
- APPENDIX E – NOAA 14++ PRECIPITATION TABLES
- APPENDIX F – STORMWATER CHECKLIST
- APPENDIX G – MCPHAIL GEOTECHNICAL MEMORANDUM

SECTION 1.0

PROJECT INFORMATION

1.01 PROJECT DESCRIPTION

Arlington Land Realty, LLC (The Applicant) is seeking to construct a new age restricted multi-family housing development in Arlington, Massachusetts, hereinafter referred to as “the Project.” The total property area is approximately 17.66 acres and is located off Dorothy Road near the intersection with Littlejohn Street. The project is bounded on the north by Dorothy Road, on the east by residential properties and Thorndike Field, and bounded on the south and west by Concord Turnpike (Route 2).

The Project consists of clearing and grubbing of the northwest section of the property and construction of one 4-story senior living residential building with a lower-level parking garage, six duplex townhouses with covered carports, as well as surface parking, walkways, utility services, and a stormwater management system. The buildings have a combined footprint of approximately 46,100 square feet.

The Project is designed to comply with the Massachusetts General Laws (M.G.L.) Chapter 40B, which allows developers to override certain aspects of municipal zoning bylaws by providing a certain percentage of affordable housing, as well as the Department of Environmental Protection’s Stormwater Management Standards. There are wetland resource areas in the south, west and east portions of the property. The Project is concentrated in the northwest area of the property and minimizes impacts to the 100-foot wetland buffer zones. Part of the site is located within the 1% Chance Annual Flood as defined by FEMA which is regulated under the Wetlands Protection Act as Bordering Land Subject to Flooding (BLSF). Compensatory flood storage is proved at a 2:1 ratio as described in section 2.12 below. This Stormwater Report and design were extensively peer reviewed in November 2020 and August 2021 by BETA Group during the Comprehensive Permit Application process and again by both Hatch Associates Consultants, Inc. and GZA GeoEnvironmental, Inc. during the Conservation Commission’s review of the Project’s Notice of Intent.

1.02 PRE-DEVELOPMENT CONDITIONS

The existing site topography generally slopes southeast across the property towards the wetlands located on the property with slopes ranging from 0-15%. The current site is comprised of forest and the primary soil classification identified by the NRCS Web Soil Survey is udorthents (655), which accounts for the majority of the property and all of the project area. On November 25, 2020, BSC Group conducted three test pits on the site, the locations of which are noted on the Grading and Drainage plan, and the test pit logs attached in Appendix D. The test pits consisted primarily of fill material to a depth of 9-11 feet generally conforming with the soils mapping. Even though the material was fill, all samples textured as sandy loam in test pits TP-1 and TP-2, closest to the proposed stormwater management systems. At the bottom of test pit TP-3, a layer of clay material was found. Based on the fill materials found, runoff calculations have been performed using curve numbers corresponding to Hydrologic Soil Group (HSG) C.

Due to changes to the site design over the course of the Comprehensive Permit process, the proposed infiltration systems were relocated. As such, and to comply with Conditions C.2(k) and I.17 of the Comprehensive Permit that was issued by the Arlington Zoning Board of Appeals for the project in 2021, BSC conducted 8 additional soil test pits on May 18 and 19, 2023. The soil types for these test pits generally consisted of fill materials overlaying fine sandy loam, consistent with the previous test pits conducted in 2020. In accordance with the Comprehensive Permit conditions, BSC coordinated with the Town of Arlington to ensure that Town staff or a representative designated by the Town would be on site during test pit work to witness and confirm the results. BSC contacted Claire Ricker, Director of Planning & Community Development to coordinate a test pit witness for the Town and was referred through Town Engineer, Wayne Chouinard to David Morgan, Environmental Planner and Conservation Agent. Mr. Morgan arranged to have a representative from Whitestone Associates on site to witness the test pits on May 18 and 19, 2023. These test pit locations have been added to the revised Grading and Drainage plan and the additional test pit logs are included in Appendix D.

Five more test pits were conducted on April 17, 2024, to gather additional soil and groundwater data and confirm that the design of the infiltration system would meet the Stormwater Standards per the DEP’s Massachusetts Stormwater Handbook. These test pits were consistent with the others that were conducted previously and consisted mainly of fill

that textured as sandy loam. One test pit, TP-9, found parent material 100-inches down, which was also a fine sandy loam. Additional test pit logs are included in Appendix D.

In November 2024, McPhail Associates, LLC (McPhail) performed two (2) soil borings on the Project site in the areas of proposed Infiltration Systems 1 and 7. These soil borings were performed to better understand the depth to a restrictive layer to more accurately determine the initial saturated thickness to be used in groundwater mounding analyses for the Project. A memorandum documenting this work is included in Appendix G. The borings showed a marine clay layer with a highest elevation between -12.1 and -17.4. Based on this additional data, all groundwater mounding analyses have been performed using an initial saturated thickness of 16-feet representing the depth between ESHGW (4.0) and the marine clay layer (-12.1).

The existing site being largely undeveloped has no existing drainage facilities and the majority of the stormwater runoff is directed to the wetlands on the property. A small portion of the site discharges to the north to Dorothy Road.

1.03 POST-DEVELOPMENT CONDITIONS

The proposed stormwater management system has been designed in a manner that will meet or exceed the provisions of the Department of Environmental Protection (DEP) Stormwater Management Standards for a new construction project.

Stormwater runoff from the site driveway and small parking/drop-off area at the main entrance to the building will be collected via a deep sump catch basin, conveyed through a water quality unit before being directed to an underground infiltration system. Stormwater runoff from a portion the driveway into the garage below the building will be collected via a trench drain and conveyed through a water quality unit before being directed to the underground system. Due to its elevation difference, this leg of the system has been provided with a backflow preventer device. This underground infiltration system provides for recharge to groundwater and provides peak flow rate attenuation. In larger storm events, this system will overflow through an outlet control structure to a flared end section with a rip-rap apron to the south.

Runoff from the townhouse and carport roofs, as well as the landscaped areas between the townhouses and 4-story building will be collected and routed to a second underground infiltration area. This underground infiltration area will also collect runoff from the roof of the 4-story building. This underground infiltration system provides for recharge to groundwater and provides peak flow rate attenuation. In larger storm events, this system will overflow through an outlet control structure to a flared end section with a rip-rap apron to the south.

Stormwater runoff from the townhouse driveways along Dorothy Rd will be collected via individual trench drains and routed to small underground infiltration chamber systems beneath each driveway. These systems provide localized infiltration to groundwater and help meet the required recharge volume for the Project. Overflow from these systems will be routed to the same infiltration system as the townhouse roofs and 4-story building.

Runoff from a small portion of the driveway to the garage will be collected in a trench drain and routed through a water quality unit for treatment prior to discharge through the flared end section with a rip-rap apron to the south.

Although all soils sampled in test pits TP-1 and TP-2, as well as the 8 test pits conducted in May 2023 and 5 conducted in April 2024, were identified as sandy loam (see above), the infiltration rate for silt loam (0.27-inches per hour) has been used in the infiltration system design to account for the materials found being primarily fill. Based upon the test pit data and groundwater monitoring performed in Spring 2024, the estimated seasonal high groundwater has been determined to be elevation 4.0. As such, to provide the minimum 2-feet of separation, the infiltration systems for the townhouse trench drains have been set with a bottom elevation of 7.0, the infiltration system collecting the majority of the driveways and parking areas has been set with a bottom elevation of 7.15, and the infiltration system collecting roofs and overflow from the townhouse trench drains has been set with a bottom elevation of 8.0. Groundwater mounding calculations for the 100-year event have been provided for all infiltration systems with less than 4.0-feet of separation to estimated seasonal high groundwater.

To provide emergency access to the sides and rear of the building, a reinforced grass access lane will be installed. A portion of this access lane will include a 6-foot wide, porous asphalt walkway to allow residents to have ADA/AAB accessible access the rear of the site. Both the reinforced grass and porous asphalt will allow stormwater runoff to freely infiltrate back to the ground and will result in negligible runoff.

Specifics of the project's compliance with the Stormwater Standards are discussed in detail in the following sections.

SECTION 2.0

DRAINAGE SUMMARY

2.01 Stormwater Standard 1 – New Stormwater Conveyances

Per Massachusetts Stormwater Management Standard #1, no new outfalls may discharge untreated stormwater directly to or cause erosion in wetlands or waters of the Commonwealth. No new untreated stormwater discharges are proposed. Rip-rap outlet protection sizing calculations are included in Section 6.0 of this Report.

2.02 Stormwater Standard 2 – Stormwater Runoff Rates

Watershed modeling was performed using HydroCAD Stormwater Modeling Software version 10.20, a computer aided design program that combines SCS runoff methodology with standard hydraulic calculations. A model of the site’s hydrology was developed for both pre- and post-development conditions to assess the effects of the proposed development on the project site and surrounding areas.

Stormwater runoff was modeled using data from the NOAA 14++ rainfall atlas. The NOAA 14++ precipitation values are higher than the TP-40 rainfall values that are required by Wetlands Protection Act (WPA) and consistent with the requirements of the updated Arlington Wetland Bylaw. The following rainfall values have been used in the analysis and the NOAA 14++ data is included in Appendix D:

<u>Storm Frequency</u>	<u>NOAA 14++ Rainfall (Inches)</u>
2-year	4.02
10-year	6.40
25-year	8.30
50-year	9.67
100-year	11.50

The stormwater management system for the project has been designed such that the post-development conditions result in no increase to peak runoff rates off the property for the 2, 10, 25, 50, and 100-year, 24-hour storm events, as detailed in the table below.

Peak Flow Discharge Rates

Node 1L – Flow to Wetlands

Storm Event	Pre-Development Peak Discharge Rate (cfs)	Post-Development Peak Discharge Rate (cfs)	Change in Peak Discharge Rate (cfs)
2-Year	3.7	3.6	-0.1
10-Year	9.0	9.0	0.0
25-Year	13.7	13.7	0.0
50-Year	17.2	17.0	-0.2
100-Year	22.0	21.4	-0.6

Node 2L – Flow Towards Street

Storm Event	Pre-Development Peak Discharge Rate (cfs)	Post-Development Peak Discharge Rate (cfs)	Change in Peak Discharge Rate (cfs)
2-Year	0.3	0.3	0.0
10-Year	0.7	0.6	-0.1
25-Year	1.0	0.9	-0.1
50-Year	1.2	1.1	-0.1
100-Year	1.5	1.3	-0.2

Node 100L – Total Flows

Storm Event	Pre-Development Peak Discharge Rate (cfs)	Post-Development Peak Discharge Rate (cfs)	Change in Peak Discharge Rate (cfs)
2-Year	3.8	3.8	0.0
10-Year	9.4	9.4	0.0
25-Year	14.2	14.2	0.0
50-Year	17.9	17.8	-0.1
100-Year	22.7	22.3	-0.4

2.03 Stormwater Standard 3 – Groundwater Recharge

Groundwater recharge is provided on site via multiple underground structural infiltration systems beneath the surface parking area to the north of the building and smaller systems beneath each individual driveway of the duplex townhouses. Overall, the project will result in no loss of annual recharge to groundwater as required by Standard 3. Refer to Section 6.0 of this Report for groundwater recharge information.

As the townhouse driveway infiltration systems and the infiltration system collecting the majority of the driveway have more than 2-feet but less than 4-feet separation to estimated seasonal high groundwater, a mounding analysis has been performed in accordance with the Hantush Method for each to ensure that a groundwater mound does not extend into the bottom of the infiltration system preventing infiltration of the required recharge volume. This analysis has been performed utilizing the infiltration volume that occurs during the 100-year storm event and is included in Section 6.0 of this Report. As the system that collects the 4-story building roof has 4-feet of separation to groundwater, a mounding analysis is not required for this system.

2.04 Stormwater Standard 4 – TSS Removal

As a new development, the Project stormwater management system will achieve a TSS removal greater than 80%. The proposed stormwater management system has been designed to provide treatment of runoff in order to reduce suspended solids prior to discharge off-site through the implementation of the following best management practices:

- Deep Sump Hooded Catch Basins
- Proprietary Hydrodynamic Separators

- Underground Stormwater Infiltration Systems
- Rain Garden

The water quality volume is defined as the runoff volume requiring TSS Removal for the site and is equal to 0.5-inches of runoff over the total impervious area of the post-development site. The required water quality volume for the project is provided in Section 6.0 of this Report.

The underground infiltration systems have been sized to treat the required water quality volume and calculations are included in Section 6.0 of this Report.

A long-term pollution prevention plan complying with the requirements of Standard 4 is included in Section 4.0 of this Report.

2.05 Stormwater Standard 5 – Land Uses with Higher Potential Pollutant Loads

This standard is not applicable as the proposed project is not a land use with higher potential pollutant loads (LUHPPL).

2.06 Stormwater Standard 6 – Stormwater Discharges to a Critical Area

This standard is not applicable as runoff from the project site does not discharge to a critical area.

2.07 Stormwater Standard 7 – Redevelopment Projects

This project is a new development and therefore has been designed to fully comply with the Stormwater Management Standards.

2.08 Stormwater Standard 8 – Sedimentation and Erosion Control Plan

Erosion and sedimentation controls are shown on the Project Plans. Additionally, a Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan is included in Section 3.0 of this Report.

2.09 Stormwater Standard 9 – Long Term Operation and Maintenance Plan

A Long-Term Operation and Maintenance Plan is included in Section 4.0 of this Report.

2.10 Stormwater Standard 10 – Illicit Discharges

There are no known illicit discharges on the project site, and none are proposed. An illicit discharge compliance statement is included in Section 6.0 and will be signed by the Applicant prior to issuance of any permits.

2.11 Conclusion

The project has been designed in accordance with DEP Stormwater Management Standards. Through the construction of the aforementioned stormwater systems, the project will provide peak rate attenuation, TSS removal and groundwater recharge.

2.12 Compensatory Flood Storage

A portion of the project site is located within the 1% Chance Annual Flood as defined by FEMA, which is regulated under the Wetlands Protection Act as Bordering Land Subject to Flooding (BLSF). In order to protect the values provided by BLSF and prevent downstream flooding impacts, the project is required to provide compensatory flood storage on a 1-foot incremental basis to match whatever is lost due to the project's development. In order to provide this compensatory flood storage, the project will minimize the area of BLSF impacted and regrade a portion of the project property southeast of the proposed building as shown on the Plans. This regraded area will provide compensatory flood storage at a 2 to 1 ratio for any flood storage lost. A breakdown of the flood storage impacts and compensatory storage provided is shown below:

<u>Elevations</u>	<u>Existing Incremental Available Flood Storage (CU.FT.)</u>	<u>Incremental Available Flood Storage with No Compensatory Storage (CU.FT.)</u>	<u>Incremental Flood Storage Change w/No Compensatory Storage (CU.FT.)</u>	<u>Proposed Incremental Compensatory Storage (CU.FT.)</u>	<u>Ratio of Compensatory Storage to Storage Lost</u>
5.0 - 6.0	136.0	67.5	-68.5	146.0	2.1
6.0 - 6.8	9,327.6	5,003.2	-4,324.4	9,014.8	2.1

As shown above, the project will exceed the 2 to 1 ratio of compensatory flood storage for all flood storage lost due to the project development. In addition, as shown on the Plans, the proposed compensatory storage is hydrologically connected to the flood plain impacted by the project. Therefore, the project as proposed meets the applicable requirements for BLSF in the Wetlands Protection Act.

SECTION 3.0

CONSTRUCTION PERIOD POLLUTION PREVENTION AND EROSION AND SEDIMENTATION CONTROL PLAN

3.0 CONSTRUCTION PERIOD POLLUTION PREVENTION AND EROSION AND SEDIMENTATION CONTROL PLAN

This Section specifies requirements and suggestions for implementation of a Stormwater Pollution Prevention Plan (SWPPP) for **Thorndike Place, in Arlington, Massachusetts**. The SWPPP shall be provided and maintained on-site by the Contractor(s) during all construction activities. The SWPPP shall be updated as required to reflect changes to construction activity.

The stormwater pollution prevention measures contained in the SWPPP shall be at least the minimum required by Local Regulations. The Contractor shall provide additional measures to prevent pollution from stormwater discharges in compliance with the National Pollution Discharge Elimination System (NPDES) Phase II permit requirements and all other local, state and federal requirements.

The SWPPP shall include provisions for, but not be limited to, the following:

1. Construction Trailers
2. Lay-down Areas
3. Equipment Storage Areas
4. Stockpile Areas
5. Disturbed Areas

The Contractor shall NOT begin construction without submitting evidence that a NPDES Notice of Intent (NOI) governing the discharge of stormwater from the construction site for the entire construction period has been filed **at least fourteen (14) days prior to construction**. It is the Contractor's responsibility to complete and file the NOI, unless otherwise determined by the project team.

The cost of any fines, construction delays and remedial actions resulting from the Contractor's failure to comply with all provisions of local regulations and Federal NPDES permit requirements shall be paid for by the Contractor at no additional cost to the Owner.

As a requirement of the EPA's NPDES permitting program, each Contractor and Subcontractor responsible for implementing and maintaining stormwater Best Management Practices shall execute a Contractor's Certification form.

Erosion and Sedimentation Control

The Contractor shall be solely responsible for erosion and sedimentation control at the site. The Contractor shall utilize a system of operations and all necessary erosion and sedimentation control measures, even if not specified herein or elsewhere, to minimize erosion damage at the site to prevent the migration of sediment into environmentally sensitive areas. Environmentally sensitive areas include all wetland resource areas within, and downstream of, the site, and those areas of the site that are not being altered.

Erosion and sedimentation control shall be in accordance with this Section, the design drawings, and the following:

- ❑ "National Pollutant Discharge Elimination System General Permit for Discharges from Construction Activities (EPA Construction General Permit February 16, 2022).
- ❑ Massachusetts Stormwater Management Policy Handbook issued by the Massachusetts Department of Environmental Protection, January 2008.
- ❑ Massachusetts Erosion and Sediment Control Guidelines for Urban and Suburban Areas, A Guide for Planners, Designers and Municipal Officials, March 1997.

The BMP's presented herein should be used as a guide for erosion and sedimentation control and are not intended to be considered specifications for construction. The most important BMP is maintaining a rapid

construction process, resulting in prompt stabilization of surfaces, thereby reducing erosion potential. Given the primacy of rapid construction, these guidelines have been designed to allow construction to progress with essentially no hindrance by the erosion control methods prescribed. These guidelines have also been designed with sufficient flexibility to allow the Contractor to modify the suggested methods as required to suit seasonal, atmospheric, and site-specific physical constraints.

Another important BMP is the prevention of concentrated water flow. Sheet flow does not have the erosive potential of a concentrated rivulet. These guidelines recommend construction methods that allow localized erosion control and a system of construction, which inhibits the development of shallow concentrated flow. These BMP's shall be maintained throughout the construction process.

CONTACT INFORMATION AND RESPONSIBLE PARTIES

The following is a list of all project-associated parties:

Owner

Arlington Land Realty, LLC
c/o Mugar Enterprises, Inc.
116 Huntington Avenue
Boston, MA 02116

Contractor

To be determined

Environmental Consultant

BSC Group, Inc.
803 Summer Street
Boston, MA 02127

Contact: Dominic Rinaldi, P.E.
Phone: (617) 896-4300
Email: drinaldi@bscgroup.com

Qualified SWPPP Inspectors

To Be Determined

3.1 Procedural Conditions of the Construction General Permit (CGP)

The following list outlines the Stormwater Responsibilities for all construction operators working on the Project. The operators below agree through a cooperative agreement to abide by the following conditions throughout the duration of the construction project, effective the date of signature of the required SWPPP. These conditions apply to all operators on the project site.

The project is subject to EPA's NPDES General Permit through the CGP. The goal of this permit is to prevent the discharge of pollutants associated with construction activity from entering the existing and proposed storm drain system or surface waters.

All contractors/operators involved in clearing, grading and excavation construction activities must sign the appropriate certification statement required, which will remain with the SWPPP. The owner must also sign

a certification, which is to remain with the SWPPP in accordance with the signatory requirements of the SWPPP.

Once the SWPPP is finalized, a signed copy, plus supporting documents, must be held at the project site during construction. A copy must remain available to EPA, State and Local agencies, and other interested parties during normal business hours.

The following items associated with this SWPPP must be posted in a prominent place at the construction site until final stabilization has been achieved:

- The completed/submitted NOI form
- Location where the public can view the SWPPP during normal business hours
- A copy of the signed/submitted NOI, permit number issued by the EPA and a copy of the current CGP.

Project specific SWPPP documents are not submitted to the US EPA unless the agency specifically requests a copy for review. SWPPP documents requested by a permitting authority, the permittee(s) will submit it in a timely manner.

EPA inspectors will be allowed free and unrestricted access to the project site and all related documentation and records kept under the conditions of the permit.

The permittee is expected to keep all BMP's and Stormwater controls operating correctly and maintained regularly.

Any additions to the project which will significantly change the anticipated discharges of pollutants, must be reported to the EPA. The EPA should also be notified in advance of any anticipated events of noncompliance. The permittee must also orally inform the EPA of any discharge, which may endanger health or the environment within 24 hours, with a written report following within 5 days.

In maintaining the SWPPP, all records and supporting documents will be compiled together in an orderly fashion. Inspection reports and amendments to the SWPPP must remain with the document. Federal regulations require permittee(s) to keep their Project Specific SWPPP and all reports and documents for at least three (3) years after the project is complete.

3.2 Existing Site and Soil Conditions

The total project area is approximately 17.66 acres and is located off Dorothy Road. The project is bounded on the north by Dorothy Road, bounded on the east by residential properties, and bounded on the south and west by Concord Turnpike (Route 2).

The current site is comprised of forest and the primary soil classification identified by the NRCS Web Soil Survey is udorthents (655), which accounts for the majority of the property and all of the project area. On November 25, 2020, BSC Group conducted three test pits on the site, the locations of which are noted on the Grading and Drainage plan, and the test pit logs are attached in Appendix D. The test pits consisted of primarily fill material to a depth of 9-11 feet generally conforming with the soils mapping. Even though the material was fill, all samples textured as sandy loam in test pits TP-1 and TP-2, closest to the proposed stormwater management systems. At the bottom of test pit TP-3, a layer of clay material was found. On May 18 and 19, 2023, BSC Group conducted 8 additional test pits on site, and on April 17, 2024, BSC Group conducted another 5 test pits on site to determine soil conditions at the locations of each of the infiltration systems in the revised drainage design. These test pits were consistent with the 2020 test pits and generally consisted of fill material over fine sandy loam. These test pits have been added to the Grading and Drainage plan and test pit logs are attached in Appendix D as well. Based on the fill materials found,

runoff calculations have been performed using curve numbers corresponding to Hydrologic Soil Group (HSG) C.

3.3 Project Description and Intended Construction Sequence

The site is currently comprised of woods. The proposed activities will include the following major components:

- The construction of one (1) multi-family housing building and six (6) duplex townhouses with associated parking, driveways, walkways, and retaining walls,
- The construction of stormwater management systems,
- Site grading and compensatory flood storage creation, and
- Utility connections and installation.

The proposed project will disturb a total of approximately 175,000± S.F. (4.02± acres).

Soil disturbing activities will include site demolition, installing stabilized construction exits, installation of erosion and sedimentation controls, grading, storm drain inlets, stormwater management systems, utilities, building foundation, construction of site driveways and preparation for final landscaping. Please refer to Table 1 for the projects anticipated construction timetable. A description of BMP’s associated with project timetable and construction-phasing elements is provided in this Erosion and Sediment Control Plan.

Table 1 – Anticipated Construction Timetable

Construction Phasing Activity	Anticipated Timetable
Grubbing and Stripping of Limits of Construction Phase	To be determined
Rough Site Grading and Site Utilities	To be determined
Utility Plan Construction	To be determined
Landscaping	To be determined

3.4 Potential Sources of Pollution

Any project site activities that have the potential to add pollutants to runoff are subject to the requirements of the SWPPP. Listed below are a description of potential sources of pollution from both sedimentation to Stormwater runoff, and pollutants from sources other than sedimentation.

Table 2 – Potential Sources of Sediment to Stormwater Runoff

Potential Source	Activities/Comments
Construction Site Entrance and Site Vehicles	Vehicles leaving the site can track soils onto public roadways. Site Vehicles can readily transport exposed soils throughout the site and off-site areas.
Grading Operations	Exposed soils have the potential for erosion and discharge of sediment to off-site areas.
Material Excavation, Relocation, and Stockpiling	Stockpiling of materials during excavation and relocation of soils can contribute to erosion and sedimentation. In addition, fugitive dust from stockpiled material, vehicle transport and site grading can be deposited in wetlands and waterway.
Landscaping Operations	Landscaping operations specifically associated with exposed soils can contribute to erosion and sedimentation. Hydroseeding, if not properly applied, can runoff to adjacent wetlands and waterways.

Table 3 – Potential Pollutants and Sources, other than Sediment to Stormwater Runoff

Potential Source	Activities/Comments
Staging Areas and Construction Vehicles	Vehicle refueling, minor equipment maintenance, sanitary facilities and hazardous waste storage
Materials Storage Area	General building materials, solvents, adhesives, paving materials, paints, aggregates, trash, etc.
Construction Activities	Construction, paving, curb/gutter installation, concrete pouring/mortar/stucco

3.5 Erosion and Sedimentation Control Best Management Practices

All construction activities will implement Best Management Practices (BMP’s) in order to minimize overall site disturbance and impacts to the sites natural features. Please refer to the following sections for a detailed description of site specific BMP’s. In addition, an Erosion and Sedimentation Control Plan is provided in the Site Plans.

3.6 Timetable and Construction Phasing

This section provides the Owner and Contractor with a suggested order of construction that shall minimize erosion and the transport of sediments. The individual objectives of the construction techniques described herein shall be considered an integral component of the project design intent of each project phase. The construction sequence is not intended to prescribe definitive construction methods and should not be interpreted as a construction specification document. However, the Contractor shall follow the general construction phase principles provided below:

- Protect and maintain existing vegetation wherever possible.
- Minimize the area of disturbance.
- To the extent possible, route unpolluted flows around disturbed areas.
- Install mitigation devices as early as possible.
- Minimize the time disturbed areas are left unstabilized.
- Maintain siltation control devices in proper condition.
- The contractor should use the suggested sequence and techniques as a general guide and modify the suggested methods and procedures as required to best suit seasonal, atmospheric, and site specific physical constraints for the purpose of minimizing the environmental impact of construction.

Demolition, Grubbing and Stripping of Limits of Construction Phase

- Install Temporary Erosion Control (TEC) devices as required to prevent sediment transport into resource areas.
- Place a ring of silt socks and/or haybales around stockpiles.
- Stabilize all exposed surfaces that will not be under immediate construction.
- Store and/or dispose all pavement and building demolition debris as indicated in accordance with all applicable local, state, and federal regulations.

Driveway Area Sub-Base Construction

- Install temporary culverts and diversion ditches and additional TEC devices as required by individual construction area constraints to direct potential runoff toward detention areas designated for the current construction phase.
- Compact gravel as work progresses to control erosion potential.

- Apply water to control air suspension of dust.
- Avoid creating an erosive condition due to over-watering.
- Install piped utility systems as required as work progresses, keeping all inlets sealed until all downstream drainage system components are functional.

Binder Construction

- Fine grade gravel base and install processed gravel to the design grades.
- Compact pavement base as work progresses.
- Install pavement binder coat starting from the downhill end of the site and work toward the top.

Finish Paving

- Repair and stabilize damaged side slopes.
- Clean inverts of drainage structures.
- Install final top coat of pavement.

Final Clean-up

- Clean inverts of culverts and catch basins.
- Remove sediment and debris from rip-rap outlet areas.
- Remove TEC devices only after permanent vegetation and erosion control has been fully established.

3.7 Site Stabilization

Grubbing Stripping and Grading

- Erosion control devices shall be in place as shown on the design plans before grading commences.
- Stripping shall be done in a manner, which will not concentrate runoff. If precipitation is expected, earthen berms shall be constructed around the area being stripped, with a silt sock, silt fence or haybale dike situated in an arc at the low point of the berm.
- If intense precipitation is anticipated, silt socks, haybales, dikes and /or silt fences shall be used as required to prevent erosion and sediment transport. The materials required shall be stored on site at all time.
- If water is required for soil compaction, it shall be added in a uniform manner that does not allow excess water to flow off the area being compacted.
- Dust shall be held at a minimum by sprinkling exposed soil with an appropriate amount of water.

Maintenance of Disturbed Surfaces

- Runoff shall be diverted from disturbed side slopes in both cut and fill.
- Mulching may be used for temporary stabilization.
- Silt sock, haybale or silt fences shall be set where required to trap products of erosion and shall be maintained on a continuing basis during the construction process.

Loaming and Seeding

- Loam shall not be placed unless it is to be seeded directly thereafter.
- All disturbed areas shall have a minimum of 4" of loam placed before seeded and mulched.
- Consideration shall be given to hydro-mulching, especially on slopes in excess of 3 to 1.
- Loamed and seeded slopes shall be protected from washout by mulching or other acceptable slope protection until vegetation begins to grow.

Stormwater Collection System Installation

- The Stormwater drainage system shall be installed from the downstream end up and in a manner which will not allow runoff from disturbed areas to enter pipes.
- Excavation for the drainage system shall not be left open when rainfall is expected overnight. If left open under other circumstances, pipe ends shall be closed by a staked board or by an equivalent method.
- All catch basin openings shall be covered by a silt bag between the grate and the frame or protected from sediment by silt fence surrounding the catch basin grate.
- During the installation of the infiltration systems, ensure that loose material from the construction of the town home roof shingles is swept and removed from the area prior to connecting the roof drains to the infiltration systems. No roof drains shall be connected to the infiltration systems until all tributary roof areas have been thoroughly cleared of debris that could impact the infiltration system functions.

Completion of Paved Areas

- During the placement of sub-base and pavement, the entrance to the Stormwater drainage systems shall be sealed when rain is expected. When these entrances are closed, consideration must be given to the direction of run-off and measures shall be undertaken to minimize erosion and to provide for the collection of sediment.
- In some situations, it may be necessary to keep catch basins open.
- Appropriate arrangements shall be made downstream to remove all sediment deposition.

Stabilization of Surfaces

- Stabilization of surfaces includes the placement of pavement, rip-rap, wood bark mulch and the establishment of vegetated surfaces.
- Upon completion of construction, all surfaces shall be stabilized even though it is apparent that future construction efforts will cause their disturbance.
- Vegetated cover shall be established during the proper growing season and shall be enhanced by soil adjustment for proper pH, nutrients and moisture content.
- Surfaces that are disturbed by erosion processes or vandalism shall be stabilized as soon as possible.
- Areas where construction activities have permanently or temporarily ceased shall be stabilized within 14 days from the last construction activity, except when construction activity will resume within 21 days (e.g., the total time period that construction activity is temporarily ceased is less than 21 days).
- Hydro-mulching of grass surfaces is recommended, especially if seeding of the surfaces is required outside the normal growing season.
- Hay mulch is an effective method of temporarily stabilizing surfaces, but only if it is properly secured by branches, weighted snow fences or weighted chicken wire.

3.8 Temporary Structural Erosion Control Measures

Temporary erosion control measures serve to minimize construction-associated impacts to wetland resource and undisturbed areas. Please refer to the following sections for a description of temporary erosion control measures implemented as part of the project and this sample SWPPP.

3.8.1 Silt Socks, Haybales, and Silt Fencing

The siltation barriers will demarcate the limit of work, form a work envelope and provide additional assurance that construction equipment will not enter the adjacent wetlands or undisturbed portions of the site. All barriers will remain in place until disturbed areas are stabilized.

3.8.2 Temporary Stormwater Diversion Swale

A temporary diversion swale is an effective practice for temporarily diverting stormwater flows and to reduce stormwater runoff velocities during storm events. The swale channel can be installed before infrastructure construction begins at the site, or as needed throughout the construction process. The diversion swale should be routinely compacted or seeded to minimize the amount of exposed soil.

3.8.3 Dewatering Basins

Dewatering may be required during stormwater system, foundation construction and utility installation. Should the need for dewatering arise, groundwater will be pumped directly into a temporary settling basin, which will act as a sediment trap during construction. All temporary settling basins will be located within close proximity of daily work activities. Prior to discharge, all groundwater will be treated by means of the settling basin or acceptable substitute. Discharges from sediment basins will be free of visible floating, suspended and settleable solids that would impair the functions of a wetland or degrade the chemical composition of the wetland resource area receiving ground or surface water flows and will be to the combined system.

3.8.4 Material Stockpiling Locations

Piping and trench excavate associated with the subsurface utility work will be contained with a single row of silt socks and/or haybales.

3.9 Permanent Structural Erosion Control Measures

Permanent erosion control measures serve to minimize post-construction impacts to wetland resource areas and undisturbed areas. Please refer to the Site Plans and Long-Term Operations and Maintenance Plan for a description of permanent erosion control measures implemented as part of the project and this SWPPP.

3.10 Good Housekeeping Best Management Practices

3.10.1 Street Sweeping

Dorothy Road in front of the project property shall be swept clean on a daily basis at the conclusion of the work day of any soils tracked onto it from the project site. All sweepings shall be disposed of off-site in accordance with all applicable laws and regulations.

3.10.2 Material Handling and Waste Management

Solid waste generation during the construction period will be primarily construction debris. The debris will include scrap lumber (used forming and shoring pallets and other shipping containers), waste packaging materials (plastic sheeting and cardboard), scrap cable and wire, roll-off containers (or dumpsters) and will be removed by a contract hauler to a properly licensed landfill. The roll-off containers will be covered with a properly secured tarp before the hauler exits the site. In addition to construction debris, the construction work force will generate some amount of household-type wastes (food packing, soft drink containers, and other paper). Trash containers for these wastes will be located around the site and will be emptied regularly so as to prevent wind-blown litter. This waste will also be removed by a contract hauler.

All hazardous waste material such as oil filters, petroleum products, paint and equipment maintenance fluids will be stored in structurally sound and sealed shipping containers in the hazardous-materials storage area and segregated from other non-waste materials. Secondary containment will be provided for all

materials in the hazardous materials storage area and will consist of commercially available spill pallets. Additionally, all hazardous materials will be disposed of in accordance with federal, state and municipal regulations.

Two temporary sanitary facilities (portable toilets) will be provided at the site in the combined staging area. The toilets will be away from a concentrated flow path and traffic flow and will have collection pans underneath as secondary treatment. All sanitary waste will be collected from an approved party at a minimum of three times per week.

3.10.3 Building Material Staging Areas

Construction equipment and maintenance materials will be stored at the combined staging area and materials storage areas. Silt fence will be installed around the perimeter to designate the staging and materials storage area. A watertight shipping container will be used to store hand tools, small parts and other construction materials.

Non-hazardous building materials such as packaging material (wood, plastic and glass) and construction scrap material (brick, wood, steel, metal scraps, and pine cuttings) will be stored in a separate covered storage facility adjacent to other stored materials. All hazardous-waste materials such as oil filters, petroleum products, paint and equipment maintenance fluids will be stored in structurally sound and sealed containers under cover within the hazardous materials storage area.

Large items such as framing materials and stockpiled lumber will be stored in the open storage area. Such materials will be elevated on wood blocks to minimize contact with runoff.

The combined storage areas are expected to remain clean, well-organized and equipped with ample cleaning supplies as appropriate for the materials being stored. Perimeter controls such as containment structures, covers and liners will be repaired or replaced as necessary to maintain proper function.

3.10.4 Designated Washout Areas

Designated temporary, below-ground concrete washout areas will be constructed, as required, to minimize the pollution potential associated with concrete, paint, stucco, mixers etc. Signs will, if required, be posted marking the location of the washout area to ensure that concrete equipment operators use the proper facility. Concrete pours will not be conducted during or before an anticipated precipitation event. All excess concrete and concrete washout slurries from the concrete mixer trucks and chutes will be discharged to the washout area or hauled off-site for disposal.

3.10.5 Equipment/Vehicle Maintenance and Fueling Areas

Several types of vehicles and equipment will be used on-site throughout the project including graders, scrapers, excavators, loaders, paving equipment, rollers, trucks and trailers, backhoes and forklifts. All major equipment/vehicle fueling and maintenance will be performed off-site. A small, 20-gallon pickup bed fuel tank will be kept on-site in the combined staging area. When vehicle fueling must occur on-site, the fueling activity will occur in the staging area. Only minor equipment maintenance will occur on-site. Vehicular refueling or maintenance shall not be allowed within the Adjacent Upland Resource Area (AURA) or in any protected wetland resource areas as defined by the Town of Arlington Regulations for Wetland Protection. All equipment fluids generated from maintenance activities will be disposed of into designated drums stored on spill pallets. Absorbent, spill-cleanup materials and spill kits will be available at the combined staging and materials storage area. Drip pans will be placed under all equipment receiving maintenance and vehicles and equipment parked overnight.

3.10.6 Equipment/Vehicle Wash down Area

All equipment and vehicle washing will be performed off-site.

3.10.7 Spill Prevention Plan

A spill containment kit will be kept on-site in the Contractor's trailer and/or the designated staging area throughout the duration of construction. Should there be an accidental release of petroleum product into a resource area, the appropriate agencies will be immediately notified.

3.10.8 Inspections

Maintenance of existing and proposed BMP's to address stormwater management facilities during construction is an on-going process. The purpose of the inspections is to observe all sources of stormwater or non-stormwater discharge as identified in the SWPPP as well as the status of the receiving waters and fulfill the requirements of the Order of Conditions. The following sections describe the appropriate inspection measures to adequately implement the project's SWPPP. A blank inspection form is provided at the end of this section. Completed inspection forms are to be maintained on site.

Inspection Personnel

The owner's appointed representative will be responsible for performing regular inspections of erosion controls and ordering repairs as necessary.

Inspection Frequency

Inspections will be performed by qualified personnel once every 7 days, in accordance with the CGP. The inspections must be documented on the inspection form provided at the end of this section, and completed forms will be provided to the on-site supervisor and maintained at the Owner's office throughout the entire duration of construction.

Inspection Reporting

Each inspection report will summarize the scope of the inspection, name(s) and qualifications of personnel making the inspection, and major observations relating to the implementation of the SWPPP, including compliance and non-compliance items. Completed inspection reports will remain with the completed SWPPP on site.

3.10.9 Amendment Requirements

The final SWPPP is intended to be a working document that is utilized regularly on the construction site, and provides guidance to the Contractor. It must reflect changes made to the originally proposed plan and will be updated to include project specific activities and ensure that they are in compliance with the NPDES General Permit and state and local laws and regulations. It should be amended whenever there is a change in design, construction, operation or maintenance that affects discharge of pollutants. The following items should be addressed should an amendment to the SWPPP occur:

- Dates of certain construction activities such as major grading activities, clearing and initiation of and completion of stabilization measures should be recorded.
- Future amendments to the SWPPP will be recorded as required. As this SWPPP is amended, all amendments will be kept on site and made part of the SWPPP.
- Upon completion of site stabilization (completed as designed and/or 70% background vegetative cover), it can be documented and marked on the plans. Inspections are no longer required at this time.
- Inspections often identify areas not included in the original SWPPP, which will require the SWPPP to be amended. These updates should be made within seven days of being recognized by the inspector.

3.11 SWPPP Inspection and Maintenance Report

The following form is an example to be used for SWPPP Inspection Reporting.

Stormwater Construction Site Inspection and Maintenance Report

TO BE COMPLETED AT LEAST EVERY 7 DAYS. AFTER SITE STABILIZATION, TO BE COMPLETED AT LEAST ONCE PER MONTH FOR THREE YEARS OR UNTIL A NOTICE OF TERMINATION IS FILED (IF APPLICABLE).

General Information			
Project Name	Thorndike Place		
NPDES Tracking No. (if applicable)		Location	Dorothy Road Arlington, MA
Date of Inspection		Start/End Time	
Inspector's Name(s)			
Inspector's Title(s)			
Inspector's Contact Information			
Inspector's Qualifications			
Describe present phase of construction			
Type of Inspection:			
<input type="checkbox"/> Regular <input type="checkbox"/> Pre-storm event <input type="checkbox"/> During storm event <input type="checkbox"/> Post-storm event			
Weather Information			
Has there been a storm event since the last inspection? <input type="checkbox"/> Yes <input type="checkbox"/> No			
If yes, provide:			
Storm Start Date & Time:	Storm Duration (hrs):	Approximate Amount of Precipitation (in):	
Weather at time of this inspection?			
<input type="checkbox"/> Clear <input type="checkbox"/> Cloudy <input type="checkbox"/> Rain <input type="checkbox"/> Sleet <input type="checkbox"/> Fog <input type="checkbox"/> Snowing <input type="checkbox"/> High Winds <input type="checkbox"/> Other: _____ Temperature: _____			
Have any discharges occurred since the last inspection? <input type="checkbox"/> Yes <input type="checkbox"/> No			
If yes, describe:			
Are there any discharges at the time of inspection? <input type="checkbox"/> Yes <input type="checkbox"/> No			
If yes, describe:			

Site-specific BMPs

- Number the structural and non-structural BMPs identified in your SWPPP on your site map and list them below (add as many BMPs as necessary). Carry a copy of the numbered site map with you during your inspections. This list will ensure that you are inspecting all required BMPs at your site.
- Describe corrective actions initiated, date completed, and note the person that completed the work in the Corrective Action Log.

	BMP	BMP Installed?	BMP Maintenance Required?	Corrective Action Needed and Notes Action required by whom and when
1	Catch Basin Protection	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	

	BMP	BMP Installed?	BMP Maintenance Required?	Corrective Action Needed and Notes Action required by whom and when
2	Haybale & Silt Fencing	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	
3	Straw Wattles	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	
4	Construction Entrance	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	
5	Sediment Basins	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	
6	Dewatering Pit	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	
7		<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	

Overall Site Issues

Below are some general site issues that should be assessed during inspections. Customize this list as needed for conditions at your site.

	BMP/activity	Implemented?	Maintenance Required?	Corrective Action Needed and Notes Action required by whom and when
1	Are all slopes and disturbed areas not actively being worked properly stabilized?	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	
2	Are natural resource areas (e.g., streams, wetlands, mature trees, etc.) protected with barriers or similar BMPs?	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	
3	Are perimeter controls and sediment barriers adequately installed	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	

	BMP/activity	Implemented?	Maintenance Required?	Corrective Action Needed and Notes Action required by whom and when
	(keyed into substrate) and maintained?			
4	Are discharge points and receiving waters free of any sediment deposits?	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	
5	Are storm drain inlets properly protected?	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	
6	Is the construction exit preventing sediment from being tracked into the street?	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	
7	Is trash/litter from work areas collected and placed in covered dumpsters?	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	
8	Are washout facilities (e.g., paint, stucco, concrete) available, clearly marked, and maintained?	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	
9	Are vehicle and equipment fueling, cleaning, and maintenance areas free of spills, leaks, or any other deleterious material?	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	Vehicle Maintenance not allowed on site
10	Are materials that are potential stormwater contaminants stored inside or under cover?	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	
11	Are non-stormwater discharges (e.g., wash water, dewatering) properly controlled?	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	
12	(Other)	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	

Non-Compliance

Describe any incidents of non-compliance not described above:

CERTIFICATION STATEMENT

“I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.”

Print name and title: _____
(Qualified Person Performing the Inspection)

Signature: _____ **Date:** _____

Print name and title: _____
(Contractor/Operator)

Signature: _____ **Date:** _____

SECTION 4.0

LONG-TERM POLLUTION PREVENTION & OPERATION AND MAINTENANCE PLAN

4.0 LONG-TERM POLLUTION PREVENTION & OPERATION AND MAINTENANCE PLAN

As required by Standard #4 of the Stormwater Management Policy, this Long-Term Pollution Prevention Plan has been developed for source control and pollution prevention at the site after construction.

MAINTENANCE RESPONSIBILITY

Ensuring that the provisions of the Long-Term Pollution Prevention Plan are followed will be the responsibility of The Applicant, Arlington Land Realty, LLC.

GOOD HOUSEKEEPING PRACTICES

The site to be kept clean of trash and debris at all times. Trash, junk, etc. is not to be left outside.

VEHICLE WASHING CONTROLS

The following BMP's, or equivalent measures, methods or practices are required if you are engaged in vehicle washing and/or steam cleaning:

It is allowable to rinse down the body or a vehicle, including the bed of a truck, with just water without doing any wash water control BMP's.

If you wash (with mild detergents) on an area that infiltrates water, such as gravel, grass, or loose soil, it is acceptable to let the wash water infiltrate as long as you only wash the body of vehicles.

However, if you wash on a paved area and use detergents or other cleansers, or if you wash/rinse the engine compartment or the underside of vehicles, you must take the vehicles to a commercial vehicle wash.

REQUIREMENTS FOR ROUTINE INSPECTIONS AND MAINTENANCE OF STORMWATER BMPS

All stormwater BMPs are to be inspected and maintained as follows;

Haybales, Silt Fence, and other temporary measures

The temporary erosion control measures will be installed up gradient of any wetland resource area where any disturbance or alteration might otherwise allow for erosion or sedimentation. They will be regularly inspected to ensure that they are functioning adequately. Additional supplies of these temporary measures will be stockpiled on site for any immediate needs or routine replacement.

Deep Sump Hooded Catch Basins

Regular maintenance is essential. Catch basins remain effective at removing pollutants only if they are cleaned out frequently. Inspect or clean basins at least four times per year and at the end of the foliage and snow removal seasons. Sediments must also be removed four times per year or whenever the depth of the deposits in the catch basin sump is greater than or equal to one half the depth from the bottom of the invert of the lowest pipe in the basin.

Water Quality Treatment Units

The water quality treatment structures require periodic inspection and cleaning to maintain operation and function. Owners should have these units inspected on a semi-annual basis and after periods of intense precipitation. Inspections can be done by using a clear Plexiglas tube ("sludge judge") to extract a water column sample. When sediment accumulation reaches 15% of storage capacity, cleaning of the unit is required.

These water quality structures must and will be checked and cleaned immediately after petroleum spills; contact appropriate regulatory agencies.

Maintenance of these units should be done by a vacuum truck that will remove the water, sediment, debris, floating hydrocarbons and other materials in unit. Proper cleaning and disposal of the removed materials and liquid must be followed.

Underground Infiltration Systems

Maintenance is required for the proper operation of the underground infiltration system. Infiltration systems are prone to failure due to clogging if the upstream water quality units are not maintained. The use of pretreatment BMPs will minimize failure and maintenance requirements.

After construction, the infiltration system shall be inspected after every major storm for the first few months to ensure proper stabilization and function. Water levels in the access ports shall be recorded over several days to check the drainage of the systems. It is recommended that a log book be maintained showing the depth of water in the detention/infiltration systems at each observation in order to determine the rate at which the system dewateres after runoff producing storm events. Once the performance characteristics of the detention/infiltration have been verified, the monitoring schedule can be reduced to an annual basis, unless the performance data suggests that a more frequent schedule is required.

Preventive maintenance on the infiltration system shall be performed at least twice a year, and sediment shall be removed from any and all pretreatment and collection structures. Sediment shall be removed when deposits approach within six inches of the invert heights of connecting pipes between unit rows, or in sumped inlet structures. Pounded water inside the systems (as visible from the access ports) that remains after several days most likely indicates that the bottom of the system is clogged and will require cleaning or replacement.

The system is designed with a defined top portal area at the “down-flow” end of the chamber that can be cut out to accept up to a 10-inch diameter riser pipe. The 10-inch riser can be used as an observation well and as access for a vacuum truck tube for use in removing sediment. The “down flow” ends of the units have end walls that are closed on the bottom. The closed bottom functions like a coffer dam, with most of the sediment depositing prior to flowing into the next chamber, facilitating its removal through the riser pipe, which is positioned directly above this area.

In addition to the routine maintenance described above, an operation and maintenance log. This log must be maintained for a minimum of three years after construction of the system, and include inspection reports and notes on any repairs, replacement, and disposal (including material and location). This log must be made available to MassDEP and the Conservation Commission upon request. In addition, members and agents of MassDEP shall be allowed to enter and inspect the property and drainage system to ensure compliance with this O&M plan.

Pipe Outlet Protection

The outlet protection should be checked at least annually and after every major storm. If the rip-rap has been displaced, undermined or damaged, it should be repaired immediately. The channel immediately below the outlet should be checked to see that erosion is not occurring. The downstream channel should be kept clear of obstructions such as fallen trees, debris, and sediment that could change flow patterns and/or tailwater depths on the pipes. Repairs must be carried out immediately to avoid additional damage to the outlet protection apron.

PROVISIONS FOR MAINTENANCE OF LAWNS, GARDENS AND OTHER LANDSCAPE AREAS

Suggested Maintenance Operations

A. Trees and Shrubs

Disease and Pest Management - Prevention of disease or infestation is the first step of Pest Management. A plant that is in overall good health is far less susceptible to disease. Good general landscape maintenance can reduce problems from disease.

Inspections of plant materials for signs of disease or infestation are to be performed monthly by the Landscape Maintenance Contractor’s Certified Arborist. This is a critical step for early diagnosis. Trees and Shrubs that have been diagnosed to have a plant disease or an infestation of insect pests are to be treated promptly with an appropriate material by a licensed applicator.

Fertilization - Trees and shrubs live outside their natural environment and should be given proper care to maintain health and vigor. Fertilizing trees and shrubs provides the plants with nutrients needed to resist insect attack, to resist drought and to grow thicker foliage. Fertilizing of new and old trees may be done in one of three ways, in either the early spring or the late fall.

- Systemic Injection of new and existing trees on trees 2 inches or greater in diameter. You must be licensed to apply this method.
- Soil Injection – a liquid fertilizer with a product such as Arbor Green or Rapid Grow injected into the soil under the drip zone of a tree or shrub. Material must be used according to manufacturers’ specifications to be effective. Outside contracting is recommended.
- Punch Bar Method – a dry fertilizer such as 10-10-10, may be used by punched holes in the drip zone of the tree 12-18” deep, two feet apart around the circumference, to the edge of the drip line. Three pounds of fertilizer should be used per diameter inch for trees with trunks six inches or more in diameter.
- Fertilizer of shrubs – use a fertilizer such as 10-10-10, broadcast over the planting area according to the manufacturers’ rate and water in.
- All fertilization must be noted on daily maintenance log.

Watering - Trees and Shrubs will need supplemental watering to remain in vigorous health. All new plants need to be watered once a week in cool weather, twice a week during warm weather, and up to three times in a week during periods of extreme heat and drought. Trees and shrubs should be watered in such a manner as to totally saturate the soil in the root zone area. Over-watering or constant saturation of the soil must be avoided as this could lead to root rot and other disease problems. The use of a soil moisture meter can help you monitor the soil’s water intake.

Plant Replacement - Unhealthy plants that may cause widespread infestation of other nearby plants shall be immediately removed from the site. Any vegetation removed from the site must be recorded and submitted with the daily maintenance log. The area shall be treated to prevent further infestation. The plant shall then be replaced with a healthy specimen of the same species and size. This work shall have a pre-established budget allowance for the year.

A spring inspection of all plant materials shall be performed to identify those plant materials that are not in vigorously healthy condition. Unhealthy plant materials shall be evaluated. If the problem is determined to be minor the plant material shall be given appropriate restorative care in accordance with this maintenance guideline until it is restored to a vigorously healthy condition. Unhealthy plant materials that do not respond to restorative care or are determined to be beyond saving shall be replaced with a healthy specimen of the same species and size. In the case of the necessity of replacing extremely large plant materials the Landscape Architect shall determine the size of the replacement plant.

Pruning - Proper pruning is the selective removal of branches without changing the plant’s natural appearance, or habit of growth. All tree pruning is to be performed by a licensed Arborist. All branches that are dead, broken, scared or crossing should be removed. All cuts should be made at the collar and not cut flush with the base.

Pruning on the site shall be done for the following purposes;

- To maintain or reduce the size of a tree or shrub
- To remove dead, diseased or damaged branches
- To rejuvenate old shrubs and encourage new growth
- To stimulate future flower and fruit development
- To maximize the visibility of twig color
- To prevent damage and reduce hazards to people and properties

All shrubs are recommended to be pruned on an annual basis to prevent the shrub from becoming overgrown and eliminate the need for drastic pruning. There are several types of pruning for deciduous shrubs. Hand snips should be used to maintain a more natural look or hand shears can be used for a more formal appearance.

Winter Protection - All trees and shrubs are to be watered, fertilized, and mulched before the first frost. All stakes should be checked and ties adjusted. Damaged branches should be pruned.

Broadleaf and Coniferous Evergreen plant materials are to be sprayed with an anti-desiccant product to prevent winter burn. The application shall be repeated during a suitable mid-winter thaw.

Shrubs located in areas likely to be piled with snow during snow removal (but not designated as Snow Storage Areas) shall be marked by six-foot high poles with bright green banner flags. Stockpiles of snow are not to be located in these areas due to potential damage to the plant materials from both the weight of the snow and the snow melting chemicals.

At the fall landscape maintenance conference parameters will be discussed between the Landscape Maintenance Contractor and the snow removal contractor to assure minimal damage and loss of landscape amenities during the winter season.

Seasonal Clean Up - A thorough spring cleanup is to be performed. This includes the removal and replacement of dead or unhealthy plant materials and the cleanup of plant debris and any general debris that has accumulated over the winter season. Mulch is to be lightly raked to clean debris from the surface without removing any mulch. Twigs and debris are to be removed from the planting beds throughout the growing season.

Mulching - Planting beds shall be mulched with a treated shredded hardwood mulch free from dirt, debris, and insects. A sample of this mulch shall be given to the Owner for approval prior to installation.

Maintain a 2-3" maximum depth and keep free of weeds either by hand weeding or by the use of a pre-emergent weed control such as Treflan or Serfian. Seasonal re-mulching shall occur as necessary in the spring and the fall to maintain this minimum depth. When new mulch is added to the planting bed it shall be spread to create a total depth of no more than three inches. Edges should be maintained in a cleanly edged fashion.

Mulch shall not be placed directly against the trunk of any tree or shrub.

B. *Groundcover and Perennials*

Disease and Pest Management – Pesticides and herbicides should be applied only as problems occur, with the proper chemical applied only by a trained professional or in the case of pesticide, a Certified Pesticide Applicator. Plants should be monitored weekly and treated accordingly.

Fertilizer – The health of the plants can be maintained or improved, and their growth encouraged by an application of complete fertilizer. Apply a fertilizer such as 4-12-4 as growth becomes apparent and before mulching. Apply to all groundcover and perennial planting areas by hand and avoid letting the fertilizer come in contact with the foliage, or use a liquid fertilizer and apply by soaking the soil. Apply according to the manufacturers' specifications.

Fertilization shall stop at the end of July.

Water – Groundcovers and Perennials will need supplemental watering in order to become established, healthy plants. All new plants need to be watered once a week in cool weather, twice a week during warm weather, and up to three times in a week during periods of extreme heat and drought. Until established, groundcovers and perennials should be watered in such a manner as to totally saturate the soil in the root zone area, to a depth of 6 inches. Once established, perennials shall continue to be watered as necessary to maintain them in a vigorous healthy condition. Over-watering or constant saturation of the soil must be avoided as this could lead to root rot and other disease problems. The use of a soil moisture meter can help you monitor the soil's water intake.

On-site water shall be furnished by the Owner. Hose and other watering equipment shall be furnished by the Landscape Maintenance Contractor.

Replacement – Any unhealthy plant/s that may cause widespread infestation of other nearby plants shall be immediately removed from the site. Any vegetation removed from the site must be recorded and submitted with the landscape maintenance log. The area shall be treated to prevent further infestation. The plant/s shall then be replaced with healthy

specimen/s of the same species and size. Old Forge shall have a pre-established budget allowance for this type of replacement, each year.

Plant material that is damaged as a result of other landscape maintenance activities, such as mowing, shall be replaced with healthy specimens of the same species and size, at no additional cost to the owner.

Deadheading – Perennials shall be checked on a weekly basis and dead-headed once flowers have faded or as necessary based on plant type and duration of flower. Spent flowers can be pinched off with the thumb and forefinger. Continue to remove all faded flowers until Fall. All associated debris shall be removed from site daily.

Staking – Upright-growing perennials need support especially when in flower. Use of bamboo stakes, galvanized wire hoops or mesh may be necessary for their support. Supports should be put in place before they have become too difficult to handle. The supports should not be taller than the mature height of the perennial plant.

Division of Perennials – Two or three-year-old perennials are easily divided in the spring if more plants are needed. To divide, cut out the entire section of plant to be divided, including roots. The larger divisions (those with three or more shoots), can be set out immediately in their permanent location, where they can be expected to bloom the same season. Smaller divisions are best planted in an out-of-the-way planting bed until the following autumn or spring, when they can be moved to their permanent location.

Weeding – All planting beds should be kept weed-free. Weed either by hand or with a pre-emergent herbicide such as Treflen used according to manufacturers' specifications. Manual weeding is to be used in combination with the use of spot applications of herbicides. Both live and dead weeds are to be pulled and removed from the site.

All herbicide applications shall be documented in the Landscape Maintenance Log. The actual product label or the manufacturer's product specification sheet for the specific product shall also be included in the Log.

Only personnel with appropriate applicator licenses shall supervise and/or perform the application of pesticide products requiring a license.

Winterizing – Perennial gardens should be cleaned-up when growth ceases in the fall. Remove foliage of plants that normally die down to the ground. Divide and replant over-grown clumps.

C. *Lawn Areas - Turf Systems*

Mowing – Proper mowing is an integral part of any good turf maintenance program. Without it, the finest in fertilization, watering and other vital maintenance practices would be completely ineffective. Proper mowing will help control dicot weeds; help the turf survive during periods of extreme heat, and gain strength and vigor to resist disease and other infestations.

Mowing height – The proper mowing height will vary somewhat according to the type of grass. The most common type of seed & sod lawns contain a mixture of bluegrass, fine fescue and perennial rye, which should be mowed at 2-3 inches.

Mowing frequency – The basic rule of thumb for mowing frequency is to never remove more than 1/3 of the grass blade in one mowing. Example: if you want to mow your turf at 2 inches, you should cut it when it reaches 3 inches. Removing more than 1/2 of the grass plant at a time can put the plant into shock, thus making it more susceptible to stress disease and weed infestation.

Mowing frequency will vary with the growing season and should be set by the plant height and not a set date. It will often be necessary to mow twice a week during periods of surge growth to help maintain plant health and color. Mowing should be cut back during periods of stress.

Grass clippings should be removed whenever they are thick enough to layer the turf. The return of clippings to the soil actually adds nutrients and helps retain moisture. Heavily clumped grass clippings are a sign of infrequent mowing, calling for an adjustment in the mowing schedule.

When mowing any area, try to alternate mowing patterns. This tends to keep grass blades more erect and assures an even cut. A dull mower will cause color loss due to tearing of the turf plant, and since mowing will ultimately determine the appearance of any turf area there is an absolute necessity for a clean sharp cut.

Weed & Pest Control and Fertilizing- In order to maintain turf grass health, vigor color, and nutrients, fertilizer must be added to the soil. Recommendations for fertilization of lawn areas are as follows; fertilize at the rate of one (1) pound of nitrogen per thousand square feet, per year is optimum. Fertilizer should be a balanced slow release, sulfur coated type fertilizer.

Weed Control - All turf areas will require some weed control, for both weed grasses and dicot weeds. Weeds should be treated at the appropriate time and with a material labeled for the target weed. Please refer to the fertilizer weed and pest schedule for timing.

Pest Control - All turf areas will require some pest control. Pests should be treated at the appropriate time with a material labeled for the target pest. Please refer to the fertilizer, weed and pest schedule for timing.

Lime - A common cause for an unhealthy lawn is acidic soil. When the pH is below the neutral range (between 6-7) vital plant nutrients become fixed in the soil and cannot be absorbed by the grass plant. Lime corrects an acid soil condition, supplies calcium for plant growth and improves air and water circulation. Limestone applied at the rate of 50 lbs. per thousand square feet will adjust the soil pH one point over a period of 6-9 months.

D. Fertilizer, Weed & Pest Control Schedule – Turf Systems

Spring - Fertilize one (1) pound of nitrogen per 1,000 square feet
(April) Pre-emergent weed grass control
Broadleaf weed control

Late Spring - Fertilize one (1) pound of nitrogen per 1,000 square feet
(June) Pre-emergent weed grass control
Broadleaf weed control
Insect Control (if needed)

*Summer - Fertilize one (1) pound of nitrogen per 1,000 square feet
(August) Broadleaf weed control (if needed)
Insect Control (if needed)

Fall - Fertilize one (1) pound of nitrogen per 1,000 square feet
(September)

*Omit if area is not to be irrigated

Lawn Maintenance Task Schedule

MARCH (Weather permitting)

- Clean up winter debris, sand, leaves, trash etc.
- Re-edge mulch beds, maintain at 2-3” maximum.
- Fertilize plants
- Aerate and thatch turf (conditions permitting)

APRIL

- Reseed or sod all areas needing attention.
- Fertilize and weed control

- Lime
- Start mowing when grass reaches 2-1/2", mow to 2"

MAY

- Mow turf to 2-2-1/2"
- Weed as necessary.
- Check for disease and pest problems in both turf and plants.

JUNE

- Mow turf to 2-1/2" – 3"
- Fertilize and weed control.
- Weed
- Check for disease and pest problems in both turf and plants, treat as necessary.

PROVISIONS FOR SOLID WASTE MANAGEMENT (SITE TRASH)

Trash will be placed in on-site dumpsters and the Owner will make provisions for its regular and timely removal.

SNOW DISPOSAL AND PLOWING PLANS

The purpose of the snow and snowmelt management plan is to provide guidelines regarding snow disposal site selection, site preparation and maintenance that are acceptable to the Department of Environmental Protection. For the areas that require snow removal, snow storage onsite will largely be accomplished by using pervious areas along the shoulder of the roadway and development as windrowed by plows.

- Avoid dumping of snow into any water body, including rivers, ponds, or wetlands. In addition to water quality impacts and flooding, snow disposed of in open water can cause navigational hazards when it freezes into ice blocks.
- Avoid disposing of snow on top of storm drain catch basins or in stormwater basins. Snow combined with sand and debris may block a storm drainage system, causing localized flooding. A high volume of sand, sediment, and litter released from melting snow also may be quickly transported through the system into surface water.
- In significant storm events, the melting or off-site trucking of snow may be implemented. These activities shall be conducted in accordance with all local, state and federal regulations.
- Snow shall be removed from the areas around on-site fire-hydrants to maintain emergency access to hydrants at all times. Removable flags or markers should be placed on hydrants to allow snow removal crews to more easily locate hydrants and not damage them with plows or other snow removal equipment.

WINTER ROAD SALT AND/OR SAND USE AND STORAGE RESTRICTIONS

The applicant will be responsible for sanding and salting the site. No storage on site.

STREET SWEEPING SCHEDULES

There are three types of sweepers: Mechanical, Regenerative Air, and Vacuum Filter.

- 1) Mechanical: Mechanical sweepers use brooms or rotary brushes to scour the pavement.
- 2) Regenerative Air: These sweepers blow air onto the road or parking lot surface, causing fines to rise where they are vacuumed.
- 3) Vacuum filter: These sweepers remove fines along roads. Two general types of vacuum filter sweepers are available - wet and dry. The dry type uses a broom in combination with the vacuum. The wet type uses water for dust suppression

Regardless of the type chosen, the efficiency of street sweeping is increased when sweepers are operated in tandem. This project has not included street sweeping as part of the TSS removal calculations. However, it is recommended that street sweeping of the parking areas occur four times a year, including once after the spring snow melt.

Reuse and Disposal of Street Sweepings

Once removed from paved surfaces, the sweepings must be handled and disposed of properly. Mass DEP’s Bureau of Waste Prevention has issued a written policy regarding the reuse and disposal of street sweepings. These sweepings are regulated as a solid waste, and can be used in three ways:

- In one of the ways already approved by Mass DEP (e.g., daily cover in a landfill, additive to compost, fill in a public way)
- If approved under a Beneficial Use Determination
- Disposed in a landfill

TRAINING OF STAFF OR PERSONNEL INVOLVED WITH IMPLEMENTING LONG-TERM POLLUTION PREVENTION PLAN

The Long-Term Pollution Prevention Plan is to be implemented by property owner of the site. Trained and, if required, licensed Professionals are to be hired by the owner as applicable to implement the Long-Term Pollution Prevention Plan.

LIST OF EMERGENCY CONTACTS FOR IMPLEMENTING LONG-TERM POLLUTION PREVENTION PLAN

The applicant will be required to implement the Long-Term Pollution Prevention Plan and will create and maintain a list of emergency contacts.

ESTIMATED OPERATION AND MAINTENANCE BUDGET

An estimated operation and maintenance budget in accordance with the schedule for inspections and routine maintenance in for each BMP above is as follows:

Stormwater BMP	Maintenance Schedule	Cost per Cleaning /Inspection	Total Cost (per year)
Catch Basins	4 times per year	\$500	\$2,000
Water Quality Units	Twice per year and after major storm events	\$500	\$1,000
Infiltration Systems	Twice per year and after major storm events	\$2500	\$5,000
Inspections	Annual	\$1000	\$1,000
Total Annual Cost			\$9,000

POST CONSTRUCTION PHASE INSPECTION SCHEDULE AND EVALUATION CHECKLIST


Inspection Date	Inspector	BMP Inspected	Inspection Frequency Requirements	Comments	Recommendation	Follow-up Inspection Required (yes/no)
		Catch Basin	Four times a year			
		Water Quality Units	Four times a year			
		Infiltration System	Twice a year			
		Pipe Outlet Protection	Once a year			

1. Refer to the Massachusetts Stormwater Handbook Volume Two: Stormwater Technical Handbook (February 2008) for recommendations regarding frequency for inspections and maintenance of specific BMP's
2. Inspections to be conducted by a qualified professional such as an environmental scientist or civil engineer.
3. Limited or no use of sodium chloride salts, fertilizers or pesticides recommended.
4. Other Notes: (Include deviations from Conservation Commission Approvals, Planning Board Approvals and Approved Plans)

SECTION 5.0

HYDROLOGY CALCULATIONS

5.01 EXISTING WATERSHED PLAN



THORNDIKE PLACE

DOROTHY ROAD

**ARLINGTON
MASSACHUSETTS
(MIDDLESEX COUNTY)**

**EXISTING WATERSHED
PLAN**




NOVEMBER 3, 2020

PREPARED
FOR:
ARLINGTON LAND REALTY
84 SHERMAN STREET
CAMBRIDGE, MA


BSC GROUP
803 Summer Street
Boston, Massachusetts
02127
617.896.4300

Job No.: 23407.00 Date: 11/3/2020
Scale: 1" = 60' Revised: 08/18/2021
Dwg No: EXW
File: C:\DRAINAGE DESIGN\2340700-EXW

LEGEND

-  SUBCATCHMENT
-  SUBCATCHMENT BOUNDARY
-  TIME OF CONCENTRATION FLOW PATH

SCALE: 1" = 60'



0 30 60 120 FEET

5.02 EXISTING HYDROLOGY CALCULATIONS (HYDROCAD™ PRINTOUTS)

2340702-EX

Prepared by BSC Group


HydroCAD® 10.20-3c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Printed 8/15/2023

Page 2

Area Listing (all nodes)

Area (sq-ft)	CN	Description (subcatchment-numbers)
925	98	Paved parking, HSG C (2S)
157,761	70	Woods, Good, HSG C (1S, 2S)
158,686	70	TOTAL AREA



2340702-EX

Prepared by BSC Group

HydroCAD® 10.20-3c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Printed 8/15/2023

Page 3

Soil Listing (all nodes)

Area (sq-ft)	Soil Group	Subcatchment Numbers
0	HSG A	
0	HSG B	
158,686	HSG C	1S, 2S
0	HSG D	
0	Other	
158,686		TOTAL AREA

2340702-EX

Prepared by BSC Group

HydroCAD® 10.20-3c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Printed 8/15/2023

Page 4

Ground Covers (all nodes)

HSG-A (sq-ft)	HSG-B (sq-ft)	HSG-C (sq-ft)	HSG-D (sq-ft)	Other (sq-ft)	Total (sq-ft)	Ground Cover	Subcatchment Numbers
0	0	925	0	0	925	Paved parking	2 S
0	0	157,761	0	0	157,761	Woods, Good	1 S,
							2 S
0	0	158,686	0	0	158,686	TOTAL AREA	

2340702-EX

Prepared by BSC Group

HydroCAD® 10.20-3c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 2-Year Rainfall=4.02"

Printed 8/15/2023

Page 5

Time span=0.00-24.00 hrs, dt=0.01 hrs, 2401 points

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: Flow to Wetlands

Runoff Area=151,732 sf 0.00% Impervious Runoff Depth>1.34"
Flow Length=310' Tc=17.5 min CN=70 Runoff=3.7 cfs 16,903 cf

Subcatchment 2S: Flow to Street

Runoff Area=6,954 sf 13.30% Impervious Runoff Depth>1.61"
Flow Length=95' Tc=6.0 min CN=74 Runoff=0.3 cfs 932 cf

Link 1L: Towards Wetlands

Inflow=3.7 cfs 16,903 cf
Primary=3.7 cfs 16,903 cf

Link 2L: Towards Street

Inflow=0.3 cfs 932 cf
Primary=0.3 cfs 932 cf

Link 100L: Total Flows

Inflow=3.8 cfs 17,836 cf
Primary=3.8 cfs 17,836 cf

Total Runoff Area = 158,686 sf Runoff Volume = 17,836 cf Average Runoff Depth = 1.35"
99.42% Pervious = 157,761 sf 0.58% Impervious = 925 sf

2340702-EX

Prepared by BSC Group

HydroCAD® 10.20-3c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 2-Year Rainfall=4.02"

Printed 8/15/2023

Page 6

Summary for Subcatchment 1S: Flow to Wetlands


Runoff = 3.7 cfs @ 12.26 hrs, Volume= 16,903 cf, Depth> 1.34"
Routed to Link 1L : Towards Wetlands

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs
Type III 24-hr 2-Year Rainfall=4.02"

Area (sf)	CN	Description
151,732	70	Woods, Good, HSG C
151,732		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.4	50	0.0240	0.07		Sheet Flow, A to B
6.1	260	0.0200	0.71		Woods: Light underbrush n= 0.400 P2= 3.23" Shallow Concentrated Flow, B to C
17.5	310	Total			Woodland Kv= 5.0 fps

Subcatchment 1S: Flow to Wetlands



2340702-EX

Prepared by BSC Group

HydroCAD® 10.20-3c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 2-Year Rainfall=4.02"

Printed 8/15/2023

Page 7

Summary for Subcatchment 2S: Flow to Street


Runoff = 0.3 cfs @ 12.09 hrs, Volume= 932 cf, Depth> 1.61"
 Routed to Link 2L : Towards Street

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs
 Type III 24-hr 2-Year Rainfall=4.02"

Area (sf)	CN	Description
6,029	70	Woods, Good, HSG C
925	98	Paved parking, HSG C
6,954	74	Weighted Average
6,029		86.70% Pervious Area
925		13.30% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.5	20	0.0750	0.10		Sheet Flow, A to B
1.8	75	0.0200	0.71		Woods: Light underbrush n= 0.400 P2= 3.23" Shallow Concentrated Flow, B to C
5.3	95				Woodland Kv= 5.0 fps Total, Increased to minimum Tc = 6.0 min

Subcatchment 2S: Flow to Street



2340702-EX

Prepared by BSC Group

HydroCAD® 10.20-3c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 2-Year Rainfall=4.02"

Printed 8/15/2023


Page 8

Summary for Link 1L: Towards Wetlands

Inflow Area = 151,732 sf, 0.00% Impervious, Inflow Depth > 1.34" for 2-Year event
 Inflow = 3.7 cfs @ 12.26 hrs, Volume= 16,903 cf
 Primary = 3.7 cfs @ 12.26 hrs, Volume= 16,903 cf, Atten= 0%, Lag= 0.0 min
 Routed to Link 100L : Total Flows

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Link 1L: Towards Wetlands



2340702-EX

Prepared by BSC Group

HydroCAD® 10.20-3c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 2-Year Rainfall=4.02"

Printed 8/15/2023

Page 9


Summary for Link 2L: Towards Street

Inflow Area = 6,954 sf, 13.30% Impervious, Inflow Depth > 1.61" for 2-Year event
 Inflow = 0.3 cfs @ 12.09 hrs, Volume= 932 cf
 Primary = 0.3 cfs @ 12.09 hrs, Volume= 932 cf, Atten= 0%, Lag= 0.0 min
 Routed to Link 100L : Total Flows

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Link 2L: Towards Street

Hydrograph



2340702-EX

Prepared by BSC Group

HydroCAD® 10.20-3c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 2-Year Rainfall=4.02"

Printed 8/15/2023

Page 10


Summary for Link 100L: Total Flows

Inflow Area = 158,686 sf, 0.58% Impervious, Inflow Depth > 1.35" for 2-Year event
 Inflow = 3.8 cfs @ 12.26 hrs, Volume= 17,836 cf
 Primary = 3.8 cfs @ 12.26 hrs, Volume= 17,836 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Link 100L: Total Flows

Hydrograph



2340702-EX

Prepared by BSC Group

HydroCAD® 10.20-3c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=6.40"

Printed 8/15/2023

Page 11

Time span=0.00-24.00 hrs, dt=0.01 hrs, 2401 points

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: Flow to Wetlands

Runoff Area=151,732 sf 0.00% Impervious Runoff Depth>3.11"
Flow Length=310' Tc=17.5 min CN=70 Runoff=9.0 cfs 39,374 cf

Subcatchment 2S: Flow to Street

Runoff Area=6,954 sf 13.30% Impervious Runoff Depth>3.52"
Flow Length=95' Tc=6.0 min CN=74 Runoff=0.7 cfs 2,040 cf

Link 1L: Towards Wetlands

Inflow=9.0 cfs 39,374 cf
Primary=9.0 cfs 39,374 cf

Link 2L: Towards Street

Inflow=0.7 cfs 2,040 cf
Primary=0.7 cfs 2,040 cf

Link 100L: Total Flows

Inflow=9.4 cfs 41,414 cf
Primary=9.4 cfs 41,414 cf

Total Runoff Area = 158,686 sf Runoff Volume = 41,414 cf Average Runoff Depth = 3.13"
99.42% Pervious = 157,761 sf 0.58% Impervious = 925 sf

2340702-EX

Prepared by BSC Group

HydroCAD® 10.20-3c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=6.40"

Printed 8/15/2023

Page 12

Summary for Subcatchment 1S: Flow to Wetlands


Runoff = 9.0 cfs @ 12.24 hrs, Volume= 39,374 cf, Depth> 3.11"
Routed to Link 1L : Towards Wetlands

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs
Type III 24-hr 10-Year Rainfall=6.40"

Area (sf)	CN	Description
151,732	70	Woods, Good, HSG C
151,732		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.4	50	0.0240	0.07		Sheet Flow, A to B
6.1	260	0.0200	0.71		Woods: Light underbrush n= 0.400 P2= 3.23"
					Shallow Concentrated Flow, B to C
					Woodland Kv= 5.0 fps
17.5	310	Total			

Subcatchment 1S: Flow to Wetlands



2340702-EX

Prepared by BSC Group

HydroCAD® 10.20-3c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=6.40"

Printed 8/15/2023

Page 13

Summary for Subcatchment 2S: Flow to Street


Runoff = 0.7 cfs @ 12.09 hrs, Volume= 2,040 cf, Depth> 3.52"
Routed to Link 2L : Towards Street

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs
Type III 24-hr 10-Year Rainfall=6.40"

Area (sf)	CN	Description
6,029	70	Woods, Good, HSG C
925	98	Paved parking, HSG C
6,954	74	Weighted Average
6,029		86.70% Pervious Area
925		13.30% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.5	20	0.0750	0.10		Sheet Flow, A to B
					Woods: Light underbrush n= 0.400 P2= 3.23"
1.8	75	0.0200	0.71		Shallow Concentrated Flow, B to C
					Woodland Kv= 5.0 fps
5.3	95	Total, Increased to minimum Tc = 6.0 min			

Subcatchment 2S: Flow to Street



2340702-EX

Prepared by BSC Group

HydroCAD® 10.20-3c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=6.40"

Printed 8/15/2023


Page 14

Summary for Link 1L: Towards Wetlands

Inflow Area = 151,732 sf, 0.00% Impervious, Inflow Depth > 3.11" for 10-Year event
Inflow = 9.0 cfs @ 12.24 hrs, Volume= 39,374 cf
Primary = 9.0 cfs @ 12.24 hrs, Volume= 39,374 cf, Atten= 0%, Lag= 0.0 min
Routed to Link 100L : Total Flows

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Link 1L: Towards Wetlands



2340702-EX

Prepared by BSC Group

HydroCAD® 10.20-3c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=6.40"

Printed 8/15/2023

Page 15


Summary for Link 2L: Towards Street

Inflow Area = 6,954 sf, 13.30% Impervious, Inflow Depth > 3.52" for 10-Year event
 Inflow = 0.7 cfs @ 12.09 hrs, Volume= 2,040 cf
 Primary = 0.7 cfs @ 12.09 hrs, Volume= 2,040 cf, Atten= 0%, Lag= 0.0 min
 Routed to Link 100L : Total Flows

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Link 2L: Towards Street

Hydrograph



2340702-EX

Prepared by BSC Group

HydroCAD® 10.20-3c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=6.40"

Printed 8/15/2023

Page 16


Summary for Link 100L: Total Flows

Inflow Area = 158,686 sf, 0.58% Impervious, Inflow Depth > 3.13" for 10-Year event
 Inflow = 9.4 cfs @ 12.24 hrs, Volume= 41,414 cf
 Primary = 9.4 cfs @ 12.24 hrs, Volume= 41,414 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Link 100L: Total Flows

Hydrograph



2340702-EX

Prepared by BSC Group
HydroCAD® 10.20-3c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=8.30"

Printed 8/15/2023
Page 17

Time span=0.00-24.00 hrs, dt=0.01 hrs, 2401 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: Flow to Wetlands Runoff Area=151,732 sf 0.00% Impervious Runoff Depth>4.71"
Flow Length=310' Tc=17.5 min CN=70 Runoff=13.7 cfs 59,512 cf

Subcatchment 2S: Flow to Street Runoff Area=6,954 sf 13.30% Impervious Runoff Depth>5.19"
Flow Length=95' Tc=6.0 min CN=74 Runoff=1.0 cfs 3,007 cf

Link 1L: Towards Wetlands Inflow=13.7 cfs 59,512 cf
Primary=13.7 cfs 59,512 cf

Link 2L: Towards Street Inflow=1.0 cfs 3,007 cf
Primary=1.0 cfs 3,007 cf

Link 100L: Total Flows Inflow=14.2 cfs 62,519 cf
Primary=14.2 cfs 62,519 cf

Total Runoff Area = 158,686 sf Runoff Volume = 62,519 cf Average Runoff Depth = 4.73"
99.42% Pervious = 157,761 sf 0.58% Impervious = 925 sf

2340702-EX

Prepared by BSC Group
HydroCAD® 10.20-3c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=8.30"

Printed 8/15/2023
Page 18

Summary for Subcatchment 1S: Flow to Wetlands


Runoff = 13.7 cfs @ 12.23 hrs, Volume= 59,512 cf, Depth> 4.71"
Routed to Link 1L : Towards Wetlands

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs
Type III 24-hr 25-Year Rainfall=8.30"

Area (sf)	CN	Description
151,732	70	Woods, Good, HSG C
151,732		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.4	50	0.0240	0.07		Sheet Flow, A to B Woods: Light underbrush n= 0.400 P2= 3.23"
6.1	260	0.0200	0.71		Shallow Concentrated Flow, B to C Woodland Kv= 5.0 fps
17.5	310	Total			

Subcatchment 1S: Flow to Wetlands



2340702-EX

Prepared by BSC Group

HydroCAD® 10.20-3c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=8.30"

Printed 8/15/2023

Page 19

Summary for Subcatchment 2S: Flow to Street


Runoff = 1.0 cfs @ 12.09 hrs, Volume= 3,007 cf, Depth> 5.19"
Routed to Link 2L : Towards Street

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs
Type III 24-hr 25-Year Rainfall=8.30"

Area (sf)	CN	Description
6,029	70	Woods, Good, HSG C
925	98	Paved parking, HSG C
6,954	74	Weighted Average
6,029		86.70% Pervious Area
925		13.30% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.5	20	0.0750	0.10		Sheet Flow, A to B
1.8	75	0.0200	0.71		Woods: Light underbrush n= 0.400 P2= 3.23" Shallow Concentrated Flow, B to C
5.3	95				Woodland Kv= 5.0 fps Total, Increased to minimum Tc = 6.0 min

Subcatchment 2S: Flow to Street



2340702-EX

Prepared by BSC Group

HydroCAD® 10.20-3c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=8.30"

Printed 8/15/2023


Page 20

Summary for Link 1L: Towards Wetlands

Inflow Area = 151,732 sf, 0.00% Impervious, Inflow Depth > 4.71" for 25-Year event
Inflow = 13.7 cfs @ 12.23 hrs, Volume= 59,512 cf
Primary = 13.7 cfs @ 12.23 hrs, Volume= 59,512 cf, Atten= 0%, Lag= 0.0 min
Routed to Link 100L : Total Flows

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Link 1L: Towards Wetlands



2340702-EX

Prepared by BSC Group

HydroCAD® 10.20-3c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=8.30"

Printed 8/15/2023

Page 21


Summary for Link 2L: Towards Street

Inflow Area = 6,954 sf, 13.30% Impervious, Inflow Depth > 5.19" for 25-Year event
Inflow = 1.0 cfs @ 12.09 hrs, Volume= 3,007 cf
Primary = 1.0 cfs @ 12.09 hrs, Volume= 3,007 cf, Atten= 0%, Lag= 0.0 min
Routed to Link 100L : Total Flows

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Link 2L: Towards Street

Hydrograph



2340702-EX

Prepared by BSC Group

HydroCAD® 10.20-3c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=8.30"

Printed 8/15/2023

Page 22


Summary for Link 100L: Total Flows

Inflow Area = 158,686 sf, 0.58% Impervious, Inflow Depth > 4.73" for 25-Year event
Inflow = 14.2 cfs @ 12.23 hrs, Volume= 62,519 cf
Primary = 14.2 cfs @ 12.23 hrs, Volume= 62,519 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Link 100L: Total Flows

Hydrograph



2340702-EX

Prepared by BSC Group
HydroCAD® 10.20-3c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 50-Year Rainfall=9.67"

Printed 8/15/2023
Page 23

Time span=0.00-24.00 hrs, dt=0.01 hrs, 2401 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: Flow to Wetlands Runoff Area=151,732 sf 0.00% Impervious Runoff Depth>5.91"
Flow Length=310' Tc=17.5 min CN=70 Runoff=17.2 cfs 74,721 cf

Subcatchment 2S: Flow to Street Runoff Area=6,954 sf 13.30% Impervious Runoff Depth>6.44"
Flow Length=95' Tc=6.0 min CN=74 Runoff=1.2 cfs 3,730 cf

Link 1L: Towards Wetlands Inflow=17.2 cfs 74,721 cf
Primary=17.2 cfs 74,721 cf

Link 2L: Towards Street Inflow=1.2 cfs 3,730 cf
Primary=1.2 cfs 3,730 cf

Link 100L: Total Flows Inflow=17.9 cfs 78,451 cf
Primary=17.9 cfs 78,451 cf

Total Runoff Area = 158,686 sf Runoff Volume = 78,451 cf Average Runoff Depth = 5.93"
99.42% Pervious = 157,761 sf 0.58% Impervious = 925 sf

2340702-EX

Prepared by BSC Group
HydroCAD® 10.20-3c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 50-Year Rainfall=9.67"

Printed 8/15/2023
Page 24

Summary for Subcatchment 1S: Flow to Wetlands


Runoff = 17.2 cfs @ 12.23 hrs, Volume= 74,721 cf, Depth> 5.91"
Routed to Link 1L : Towards Wetlands

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs
Type III 24-hr 50-Year Rainfall=9.67"

Area (sf)	CN	Description
151,732	70	Woods, Good, HSG C
151,732		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.4	50	0.0240	0.07		Sheet Flow, A to B Woods: Light underbrush n= 0.400 P2= 3.23"
6.1	260	0.0200	0.71		Shallow Concentrated Flow, B to C Woodland Kv= 5.0 fps
17.5	310	Total			

Subcatchment 1S: Flow to Wetlands



2340702-EX

Prepared by BSC Group

HydroCAD® 10.20-3c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 50-Year Rainfall=9.67"

Printed 8/15/2023

Page 25

Summary for Subcatchment 2S: Flow to Street


Runoff = 1.2 cfs @ 12.09 hrs, Volume= 3,730 cf, Depth> 6.44"
Routed to Link 2L : Towards Street

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs
Type III 24-hr 50-Year Rainfall=9.67"

Area (sf)	CN	Description
6,029	70	Woods, Good, HSG C
925	98	Paved parking, HSG C
6,954	74	Weighted Average
6,029		86.70% Pervious Area
925		13.30% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.5	20	0.0750	0.10		Sheet Flow, A to B
1.8	75	0.0200	0.71		Woods: Light underbrush n= 0.400 P2= 3.23" Shallow Concentrated Flow, B to C
5.3	95				Woodland Kv= 5.0 fps Total, Increased to minimum Tc = 6.0 min

Subcatchment 2S: Flow to Street



2340702-EX

Prepared by BSC Group

HydroCAD® 10.20-3c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 50-Year Rainfall=9.67"

Printed 8/15/2023


Page 26

Summary for Link 1L: Towards Wetlands

Inflow Area = 151,732 sf, 0.00% Impervious, Inflow Depth > 5.91" for 50-Year event
Inflow = 17.2 cfs @ 12.23 hrs, Volume= 74,721 cf
Primary = 17.2 cfs @ 12.23 hrs, Volume= 74,721 cf, Atten= 0%, Lag= 0.0 min
Routed to Link 100L : Total Flows

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Link 1L: Towards Wetlands



2340702-EX

Prepared by BSC Group

HydroCAD® 10.20-3c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 50-Year Rainfall=9.67"

Printed 8/15/2023

Page 27


Summary for Link 2L: Towards Street

Inflow Area = 6,954 sf, 13.30% Impervious, Inflow Depth > 6.44" for 50-Year event
 Inflow = 1.2 cfs @ 12.09 hrs, Volume= 3,730 cf
 Primary = 1.2 cfs @ 12.09 hrs, Volume= 3,730 cf, Atten= 0%, Lag= 0.0 min
 Routed to Link 100L : Total Flows

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Link 2L: Towards Street

Hydrograph



2340702-EX

Prepared by BSC Group

HydroCAD® 10.20-3c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 50-Year Rainfall=9.67"

Printed 8/15/2023

Page 28


Summary for Link 100L: Total Flows

Inflow Area = 158,686 sf, 0.58% Impervious, Inflow Depth > 5.93" for 50-Year event
 Inflow = 17.9 cfs @ 12.23 hrs, Volume= 78,451 cf
 Primary = 17.9 cfs @ 12.23 hrs, Volume= 78,451 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Link 100L: Total Flows

Hydrograph



2340702-EX

Prepared by BSC Group
HydroCAD® 10.20-3c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 100-Year Rainfall=11.50"

Printed 8/15/2023
Page 29

Time span=0.00-24.00 hrs, dt=0.01 hrs, 2401 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: Flow to Wetlands Runoff Area=151,732 sf 0.00% Impervious Runoff Depth>7.56"
Flow Length=310' Tc=17.5 min CN=70 Runoff=22.0 cfs 95,631 cf

Subcatchment 2S: Flow to Street Runoff Area=6,954 sf 13.30% Impervious Runoff Depth>8.14"
Flow Length=95' Tc=6.0 min CN=74 Runoff=1.5 cfs 4,716 cf

Link 1L: Towards Wetlands Inflow=22.0 cfs 95,631 cf
Primary=22.0 cfs 95,631 cf

Link 2L: Towards Street Inflow=1.5 cfs 4,716 cf
Primary=1.5 cfs 4,716 cf

Link 100L: Total Flows Inflow=22.7 cfs 100,347 cf
Primary=22.7 cfs 100,347 cf

Total Runoff Area = 158,686 sf Runoff Volume = 100,347 cf Average Runoff Depth = 7.59"
99.42% Pervious = 157,761 sf 0.58% Impervious = 925 sf

2340702-EX

Prepared by BSC Group
HydroCAD® 10.20-3c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 100-Year Rainfall=11.50"

Printed 8/15/2023
Page 30

Summary for Subcatchment 1S: Flow to Wetlands


Runoff = 22.0 cfs @ 12.23 hrs, Volume= 95,631 cf, Depth> 7.56"
Routed to Link 1L : Towards Wetlands

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs
Type III 24-hr 100-Year Rainfall=11.50"

Area (sf)	CN	Description
151,732	70	Woods, Good, HSG C
151,732		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.4	50	0.0240	0.07		Sheet Flow, A to B
6.1	260	0.0200	0.71		Woods: Light underbrush n= 0.400 P2= 3.23" Shallow Concentrated Flow, B to C
17.5	310	Total			Woodland Kv= 5.0 fps

Subcatchment 1S: Flow to Wetlands



2340702-EX

Prepared by BSC Group

HydroCAD® 10.20-3c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 100-Year Rainfall=11.50"

Printed 8/15/2023

Page 31

Summary for Subcatchment 2S: Flow to Street


Runoff = 1.5 cfs @ 12.09 hrs, Volume= 4,716 cf, Depth> 8.14"
Routed to Link 2L : Towards Street

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs
Type III 24-hr 100-Year Rainfall=11.50"

Area (sf)	CN	Description
6,029	70	Woods, Good, HSG C
925	98	Paved parking, HSG C
6,954	74	Weighted Average
6,029		86.70% Pervious Area
925		13.30% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.5	20	0.0750	0.10		Sheet Flow, A to B
					Woods: Light underbrush n= 0.400 P2= 3.23"
1.8	75	0.0200	0.71		Shallow Concentrated Flow, B to C
					Woodland Kv= 5.0 fps
5.3	95	Total, Increased to minimum Tc = 6.0 min			

Subcatchment 2S: Flow to Street



2340702-EX

Prepared by BSC Group

HydroCAD® 10.20-3c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 100-Year Rainfall=11.50"

Printed 8/15/2023


Page 32

Summary for Link 1L: Towards Wetlands

Inflow Area = 151,732 sf, 0.00% Impervious, Inflow Depth > 7.56" for 100-Year event
Inflow = 22.0 cfs @ 12.23 hrs, Volume= 95,631 cf
Primary = 22.0 cfs @ 12.23 hrs, Volume= 95,631 cf, Atten= 0%, Lag= 0.0 min
Routed to Link 100L : Total Flows

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Link 1L: Towards Wetlands



2340702-EX

Prepared by BSC Group

HydroCAD® 10.20-3c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 100-Year Rainfall=11.50"

Printed 8/15/2023

Page 33


Summary for Link 2L: Towards Street

Inflow Area = 6,954 sf, 13.30% Impervious, Inflow Depth > 8.14" for 100-Year event
 Inflow = 1.5 cfs @ 12.09 hrs, Volume= 4,716 cf
 Primary = 1.5 cfs @ 12.09 hrs, Volume= 4,716 cf, Atten= 0%, Lag= 0.0 min
 Routed to Link 100L : Total Flows

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Link 2L: Towards Street

Hydrograph



2340702-EX

Prepared by BSC Group

HydroCAD® 10.20-3c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 100-Year Rainfall=11.50"

Printed 8/15/2023

Page 34


Summary for Link 100L: Total Flows

Inflow Area = 158,686 sf, 0.58% Impervious, Inflow Depth > 7.59" for 100-Year event
 Inflow = 22.7 cfs @ 12.23 hrs, Volume= 100,347 cf
 Primary = 22.7 cfs @ 12.23 hrs, Volume= 100,347 cf, Atten= 0%, Lag= 0.0 min


Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Link 100L: Total Flows

Hydrograph



5.03 PROPOSED WATERSHED PLAN



THORNDIKE PLACE

DOROTHY ROAD

ARLINGTON
MASSACHUSETTS
(MIDDLESEX COUNTY)

PROPOSED WATERSHED
PLAN

NOVEMBER 3, 2020

PREPARED
FOR:
ARLINGTON LAND REALTY
84 SHERMAN STREET
CAMBRIDGE, MA






803 Summer Street
Boston, Massachusetts
02127


617 896 4300

Job No.: 23407.02 Date: 11/3/2020
Scale: 1" = 60' Revised: 12/10/2024
Dwg No: PRW
File: C:\DRAINAGE DESIGN\2340700-PRW

LEGEND

-  SUBCATCHMENT
-  SUBCATCHMENT BOUNDARY
-  TIME OF CONCENTRATION FLOW PATH

SCALE: 1" = 60'



0 30 60 120 FEET

**5.04 PROPOSED HYDROLOGY CALCULATIONS
(HYDROCAD™ PRINTOUTS)**

2340702-PR-2024-12-10

Prepared by BSC Group


HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Printed 12/17/2024

Page 2

Rainfall Events Listing

Event#	Event Name	Storm Type	Curve	Mode	Duration (hours)	B/B	Depth (inches)	AMC
1	2-Year	Type III 24-hr		Default	24.00	1	4.02	2
2	10-Year	Type III 24-hr		Default	24.00	1	6.40	2
3	25-Year	Type III 24-hr		Default	24.00	1	8.30	2
4	50-Year	Type III 24-hr		Default	24.00	1	9.67	2
5	100-Year	Type III 24-hr		Default	24.00	1	11.50	2



Area Listing (all nodes)

Area (sq-ft)	CN	Description (subcatchment-numbers)
74,381	74	>75% Grass cover, Good, HSG C (1S, 3.1S, 4.2S, 4.3S, 4.4S, 4.5S, 4.6S, 5.1S, 5S, 6.1S, 6S, 7S)
220	89	Gravel roads, HSG C (6.1S)
411	89	Gravel sidewalk, HSG C (3.1S)
25,874	98	Paved parking, HSG C (1S, 4.2S, 4.3S, 4.4S, 4.5S, 4.6S, 5.1S, 5S, 7S)
6,444	98	Paved roads w/curbs & sewers, HSG C (6.1S)
46,099	98	Roofs, HSG C (2S, 3S, 6S)
272	98	Unconnected pavement, HSG C (3.1S)
4,985	70	Woods, Good, HSG C (6S)
158,686	86	TOTAL AREA

Soil Listing (all nodes)

Area (sq-ft)	Soil Group	Subcatchment Numbers
0	HSG A	
0	HSG B	
158,686	HSG C	1S, 2S, 3.1S, 3S, 4.2S, 4.3S, 4.4S, 4.5S, 4.6S, 5.1S, 5S, 6.1S, 6S, 7S
0	HSG D	
0	Other	
158,686		TOTAL AREA

Ground Covers (all nodes)

HSG-A (sq-ft)	HSG-B (sq-ft)	HSG-C (sq-ft)	HSG-D (sq-ft)	Other (sq-ft)	Total (sq-ft)	Ground Cover
0	0	74,381	0	0	74,381	>75% Grass cover, Good
0	0	220	0	0	220	Gravel roads
0	0	411	0	0	411	Gravel sidewalk
0	0	25,874	0	0	25,874	Paved parking
0	0	6,444	0	0	6,444	Paved roads w/curbs & sewers
0	0	46,099	0	0	46,099	Roofs
0	0	272	0	0	272	Unconnected pavement
0	0	4,985	0	0	4,985	Woods, Good
0	0	158,686	0	0	158,686	TOTAL AREA

Time span=0.00-72.00 hrs, dt=0.01 hrs, 7201 points
 Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
 Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment1S: CB-1	Runoff Area=22,742 sf 72.16% Impervious Runoff Depth=3.04" Tc=6.0 min CN=91 Runoff=1.8 cfs 5,755 cf
Subcatchment2S: Building Roof	Runoff Area=32,925 sf 100.00% Impervious Runoff Depth=3.79" Tc=6.0 min CN=98 Runoff=3.0 cfs 10,385 cf
Subcatchment3.1S: Backyard ADS	Runoff Area=8,985 sf 3.03% Impervious Runoff Depth=1.68" Flow Length=147' Tc=10.3 min CN=75 Runoff=0.3 cfs 1,259 cf
Subcatchment3S: Townhouse Roofs	Runoff Area=13,067 sf 100.00% Impervious Runoff Depth=3.79" Tc=6.0 min CN=98 Runoff=1.2 cfs 4,122 cf
Subcatchment4.2S: TD-2	Runoff Area=1,112 sf 95.68% Impervious Runoff Depth=3.67" Tc=6.0 min CN=97 Runoff=0.1 cfs 340 cf
Subcatchment4.3S: TD-3	Runoff Area=1,105 sf 97.29% Impervious Runoff Depth=3.67" Tc=6.0 min CN=97 Runoff=0.1 cfs 338 cf
Subcatchment4.4S: TD-4	Runoff Area=1,104 sf 97.46% Impervious Runoff Depth=3.67" Tc=6.0 min CN=97 Runoff=0.1 cfs 338 cf
Subcatchment4.5S: TD-5	Runoff Area=1,082 sf 98.06% Impervious Runoff Depth=3.79" Tc=6.0 min CN=98 Runoff=0.1 cfs 341 cf
Subcatchment4.6S: TD-6	Runoff Area=1,056 sf 99.24% Impervious Runoff Depth=3.79" Tc=6.0 min CN=98 Runoff=0.1 cfs 333 cf
Subcatchment5.1S: TD-1A	Runoff Area=1,389 sf 84.59% Impervious Runoff Depth=3.34" Tc=6.0 min CN=94 Runoff=0.1 cfs 387 cf
Subcatchment5S: TD-1B	Runoff Area=4,462 sf 42.78% Impervious Runoff Depth=2.39" Tc=6.0 min CN=84 Runoff=0.3 cfs 888 cf
Subcatchment6.1S: East driveway	Runoff Area=12,275 sf 52.50% Impervious Runoff Depth=2.66" Tc=6.0 min CN=87 Runoff=0.9 cfs 2,716 cf
Subcatchment6S: Bypass Towards	Runoff Area=51,539 sf 0.21% Impervious Runoff Depth=1.61" Flow Length=125' Tc=14.0 min CN=74 Runoff=1.7 cfs 6,919 cf
Subcatchment7S: To Street	Runoff Area=5,843 sf 18.07% Impervious Runoff Depth=1.90" Tc=6.0 min CN=78 Runoff=0.3 cfs 927 cf
Pond 1P: Inf Syst-1	Peak Elev=9.37' Storage=8,769 cf Inflow=4.8 cfs 16,622 cf Discarded=0.1 cfs 13,377 cf Primary=0.3 cfs 3,246 cf Outflow=0.4 cfs 16,622 cf
Pond 3P: Rain garden	Peak Elev=6.42' Storage=216 cf Inflow=0.9 cfs 2,716 cf Discarded=0.0 cfs 444 cf Primary=0.9 cfs 2,272 cf Outflow=0.9 cfs 2,716 cf

2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 2-Year Rainfall=4.02"

Printed 12/17/2024

Page 7

Pond 4P: Inf Syst-2

Peak Elev=9.41' Storage=129 cf Inflow=0.1 cfs 340 cf
Discarded=0.0 cfs 156 cf Primary=0.1 cfs 171 cf Outflow=0.1 cfs 327 cf

Pond 5P: Inf Syst-3

Peak Elev=9.55' Storage=134 cf Inflow=0.1 cfs 338 cf
Discarded=0.0 cfs 156 cf Primary=0.1 cfs 163 cf Outflow=0.1 cfs 319 cf

Pond 6P: Inf Syst-4

Peak Elev=9.55' Storage=134 cf Inflow=0.1 cfs 338 cf
Discarded=0.0 cfs 156 cf Primary=0.1 cfs 163 cf Outflow=0.1 cfs 319 cf

Pond 7P: Inf Syst-5

Peak Elev=9.18' Storage=117 cf Inflow=0.1 cfs 341 cf
Discarded=0.0 cfs 157 cf Primary=0.1 cfs 183 cf Outflow=0.1 cfs 341 cf

Pond 8P: Inf Syst-6

Peak Elev=9.20' Storage=118 cf Inflow=0.1 cfs 333 cf
Discarded=0.0 cfs 157 cf Primary=0.1 cfs 175 cf Outflow=0.1 cfs 332 cf

Pond 9P: Inf Syst-7

Peak Elev=7.84' Storage=1,431 cf Inflow=1.9 cfs 6,142 cf
Discarded=0.0 cfs 1,379 cf Primary=1.1 cfs 4,762 cf Outflow=1.1 cfs 6,142 cf

Link 1L: Towards Wetlands

Inflow=3.6 cfs 18,088 cf
Primary=3.6 cfs 18,088 cf

Link 2L: Towards Street

Inflow=0.3 cfs 927 cf
Primary=0.3 cfs 927 cf

Link 100L: Total Flows

Inflow=3.8 cfs 19,014 cf
Primary=3.8 cfs 19,014 cf

Total Runoff Area = 158,686 sf Runoff Volume = 35,048 cf Average Runoff Depth = 2.65"
50.41% Pervious = 79,997 sf 49.59% Impervious = 78,689 sf

2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 2-Year Rainfall=4.02"

Printed 12/17/2024

Page 8

Summary for Subcatchment 1S: CB-1


Runoff = 1.8 cfs @ 12.09 hrs, Volume= 5,755 cf, Depth= 3.04"
Routed to Pond 9P : Inf Syst-7

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 2-Year Rainfall=4.02"

Area (sf)	CN	Description
16,410	98	Paved parking, HSG C
6,332	74	>75% Grass cover, Good, HSG C
22,742	91	Weighted Average
6,332		27.84% Pervious Area
16,410		72.16% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 1S: CB-1



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 2-Year Rainfall=4.02"

Printed 12/17/2024

Page 9

Summary for Subcatchment 2S: Building Roof


Runoff = 3.0 cfs @ 12.08 hrs, Volume= 10,385 cf, Depth= 3.79"
Routed to Pond 1P : Inf Syst-1

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 2-Year Rainfall=4.02"

Area (sf)	CN	Description
32,925	98	Roofs, HSG C
32,925		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 2S: Building Roof



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 2-Year Rainfall=4.02"

Printed 12/17/2024

Page 10

Summary for Subcatchment 3.1S: Backyard ADs

Runoff = 0.3 cfs @ 12.15 hrs, Volume= 1,259 cf, Depth= 1.68"
Routed to Pond 1P : Inf Syst-1


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 2-Year Rainfall=4.02"

Area (sf)	CN	Description
272	98	Unconnected pavement, HSG C
8,302	74	>75% Grass cover, Good, HSG C
411	89	Gravel sidewalk, HSG C
8,985	75	Weighted Average
8,713		96.97% Pervious Area
272		3.03% Impervious Area
272		100.00% Unconnected

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
9.4	50	0.0142	0.09		Sheet Flow, Grass: Dense n= 0.240 P2= 3.23"
0.9	97	0.0154	1.86		Shallow Concentrated Flow, Grassed Waterway Kv= 15.0 fps

10.3 147 Total

Subcatchment 3.1S: Backyard ADs



Summary for Subcatchment 3S: Townhouse Roofs


Runoff = 1.2 cfs @ 12.08 hrs, Volume= 4,122 cf, Depth= 3.79"
 Routed to Pond 1P : Inf Syst-1

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 2-Year Rainfall=4.02"

Area (sf)	CN	Description
13,067	98	Roofs, HSG C
13,067		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 3S: Townhouse Roofs



Summary for Subcatchment 4.2S: TD-2


Runoff = 0.1 cfs @ 12.08 hrs, Volume= 340 cf, Depth= 3.67"
 Routed to Pond 4P : Inf Syst-2

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 2-Year Rainfall=4.02"

Area (sf)	CN	Description
1,064	98	Paved parking, HSG C
48	74	>75% Grass cover, Good, HSG C
1,112	97	Weighted Average
48		4.32% Pervious Area
1,064		95.68% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.2S: TD-2



Summary for Subcatchment 4.3S: TD-3

Runoff = 0.1 cfs @ 12.08 hrs, Volume= 338 cf, Depth= 3.67"
 Routed to Pond 5P : Inf Syst-3


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 2-Year Rainfall=4.02"

Area (sf)	CN	Description
1,075	98	Paved parking, HSG C
30	74	>75% Grass cover, Good, HSG C
1,105	97	Weighted Average
30		2.71% Pervious Area
1,075		97.29% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.3S: TD-3

Hydrograph



Summary for Subcatchment 4.4S: TD-4

Runoff = 0.1 cfs @ 12.08 hrs, Volume= 338 cf, Depth= 3.67"
 Routed to Pond 6P : Inf Syst-4


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 2-Year Rainfall=4.02"

Area (sf)	CN	Description
1,076	98	Paved parking, HSG C
28	74	>75% Grass cover, Good, HSG C
1,104	97	Weighted Average
28		2.54% Pervious Area
1,076		97.46% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.4S: TD-4

Hydrograph



Summary for Subcatchment 4.5S: TD-5

Runoff = 0.1 cfs @ 12.08 hrs, Volume= 341 cf, Depth= 3.79"
 Routed to Pond 7P : Inf Syst-5


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 2-Year Rainfall=4.02"

Area (sf)	CN	Description
1,061	98	Paved parking, HSG C
21	74	>75% Grass cover, Good, HSG C
1,082	98	Weighted Average
21		1.94% Pervious Area
1,061		98.06% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.5S: TD-5

Hydrograph



Summary for Subcatchment 4.6S: TD-6

Runoff = 0.1 cfs @ 12.08 hrs, Volume= 333 cf, Depth= 3.79"
 Routed to Pond 8P : Inf Syst-6


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 2-Year Rainfall=4.02"

Area (sf)	CN	Description
1,048	98	Paved parking, HSG C
8	74	>75% Grass cover, Good, HSG C
1,056	98	Weighted Average
8		0.76% Pervious Area
1,048		99.24% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.6S: TD-6

Hydrograph



Summary for Subcatchment 5.1S: TD-1A

Runoff = 0.1 cfs @ 12.08 hrs, Volume= 387 cf, Depth= 3.34"
 Routed to Pond 9P : Inf Syst-7


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 2-Year Rainfall=4.02"

Area (sf)	CN	Description
1,175	98	Paved parking, HSG C
214	74	>75% Grass cover, Good, HSG C
1,389	94	Weighted Average
214		15.41% Pervious Area
1,175		84.59% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 5.1S: TD-1A

Hydrograph



Summary for Subcatchment 5S: TD-1B

Runoff = 0.3 cfs @ 12.09 hrs, Volume= 888 cf, Depth= 2.39"
 Routed to Link 1L : Towards Wetlands


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 2-Year Rainfall=4.02"

Area (sf)	CN	Description
1,909	98	Paved parking, HSG C
2,553	74	>75% Grass cover, Good, HSG C
4,462	84	Weighted Average
2,553		57.22% Pervious Area
1,909		42.78% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 5S: TD-1B

Hydrograph



Summary for Subcatchment 6.1S: East driveway

Runoff = 0.9 cfs @ 12.09 hrs, Volume= 2,716 cf, Depth= 2.66"
 Routed to Pond 3P : Rain garden


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 2-Year Rainfall=4.02"

Area (sf)	CN	Description
5,611	74	>75% Grass cover, Good, HSG C
6,444	98	Paved roads w/curbs & sewers, HSG C
220	89	Gravel roads, HSG C
12,275	87	Weighted Average
5,831		47.50% Pervious Area
6,444		52.50% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

Subcatchment 6.1S: East driveway

Hydrograph



Summary for Subcatchment 6S: Bypass Towards Wetlands

Runoff = 1.7 cfs @ 12.20 hrs, Volume= 6,919 cf, Depth= 1.61"
 Routed to Link 1L : Towards Wetlands


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 2-Year Rainfall=4.02"

Area (sf)	CN	Description
4,985	70	Woods, Good, HSG C
46,447	74	>75% Grass cover, Good, HSG C
107	98	Roofs, HSG C
51,539	74	Weighted Average
51,432		99.79% Pervious Area
107		0.21% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.8	50	0.0220	0.07		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.23"
2.2	75	0.0133	0.58		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
14.0	125	Total			

Subcatchment 6S: Bypass Towards Wetlands

Hydrograph



Summary for Subcatchment 7S: To Street

Runoff = 0.3 cfs @ 12.09 hrs, Volume= 927 cf, Depth= 1.90"
 Routed to Link 2L : Towards Street


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 2-Year Rainfall=4.02"

Area (sf)	CN	Description
1,056	98	Paved parking, HSG C
4,787	74	>75% Grass cover, Good, HSG C
5,843	78	Weighted Average
4,787		81.93% Pervious Area
1,056		18.07% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 7S: To Street

Hydrograph



Summary for Pond 1P: Inf Syst-1

Inflow Area = 60,436 sf, 85.36% Impervious, Inflow Depth = 3.30" for 2-Year event
 Inflow = 4.8 cfs @ 12.09 hrs, Volume= 16,622 cf
 Outflow = 0.4 cfs @ 13.02 hrs, Volume= 16,622 cf, Atten= 91%, Lag= 55.8 min
 Discarded = 0.1 cfs @ 8.25 hrs, Volume= 13,377 cf
 Primary = 0.3 cfs @ 13.02 hrs, Volume= 3,246 cf
 Routed to Link 1L : Towards Wetlands

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.37' @ 13.02 hrs Surf.Area= 7,459 sf Storage= 8,769 cf

Plug-Flow detention time= 660.2 min calculated for 16,620 cf (100% of inflow)
 Center-of-Mass det. time= 660.3 min (1,423.4 - 763.1)

Volume	Invert	Avail.Storage	Storage Description
#1	8.00'	19,245 cf	6.89'W x 14.06'L x 3.00'H StormTrap ST-1 Units (Irregular Shape) 77 22,378 cf Overall x 86.0% Voids


Device	Routing	Invert	Outlet Devices
#1	Discarded	8.00'	0.520 in/hr Exfiltration over Surface area
#2	Primary	8.00'	15.0" Round Culvert L= 26.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 8.00' / 7.13' S= 0.0335 '/ Cc= 0.900 n= 0.013, Flow Area= 1.23 sf
#3	Device 2	9.22'	22.0" W x 4.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 2	10.05'	20.0" W x 4.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 2	10.79'	3.7' long Sharp-Crested Rectangular Weir 2 End Contraction(s)

Discarded OutFlow Max=0.1 cfs @ 8.25 hrs HW=8.03' (Free Discharge)
 1=Exfiltration (Exfiltration Controls 0.1 cfs)

Primary OutFlow Max=0.3 cfs @ 13.02 hrs HW=9.37' (Free Discharge)
 2=Culvert (Passes 0.3 cfs of 5.1 cfs potential flow)
 3=Orifice/Grate (Orifice Controls 0.3 cfs @ 1.23 fps)
 4=Orifice/Grate (Controls 0.0 cfs)
 5=Sharp-Crested Rectangular Weir (Controls 0.0 cfs)

Pond 1P: Inf Syst-1

Hydrograph



Summary for Pond 3P: Rain garden

Inflow Area = 12,275 sf, 52.50% Impervious, Inflow Depth = 2.66" for 2-Year event
 Inflow = 0.9 cfs @ 12.09 hrs, Volume= 2,716 cf
 Outflow = 0.9 cfs @ 12.09 hrs, Volume= 2,716 cf, Atten= 0%, Lag= 0.3 min
 Discarded = 0.0 cfs @ 12.09 hrs, Volume= 444 cf
 Primary = 0.9 cfs @ 12.09 hrs, Volume= 2,272 cf
 Routed to Link 1L : Towards Wetlands

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 6.42' @ 12.09 hrs Surf.Area= 412 sf Storage= 216 cf

Plug-Flow detention time= 90.5 min calculated for 2,715 cf (100% of inflow)
 Center-of-Mass det. time= 90.6 min (900.2 - 809.6)

Volume	Invert	Avail.Storage	Storage Description		
#1	5.60'	253 cf	Custom Stage Data (Irregular) Listed below (Recalc)		
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
5.60	125	46.0	0	0	125
6.00	276	66.0	78	78	305
6.30	350	73.0	94	172	385
6.50	460	87.0	81	253	564


Device	Routing	Invert	Outlet Devices
#1	Discarded	5.60'	0.520 in/hr Exfiltration over Surface area
#2	Primary	6.35'	22.0' long x 5.0' breadth Broad-Crested Rectangular Weir
			Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00
			2.50 3.00 3.50 4.00 4.50 5.00 5.50
			Coef. (English) 2.34 2.50 2.70 2.68 2.68 2.66 2.65 2.65 2.65
			2.65 2.67 2.66 2.68 2.70 2.74 2.79 2.88

Discarded OutFlow Max=0.0 cfs @ 12.09 hrs HW=6.42' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.9 cfs @ 12.09 hrs HW=6.42' (Free Discharge)
 ↳2=Broad-Crested Rectangular Weir (Weir Controls 0.9 cfs @ 0.60 fps)

Pond 3P: Rain garden

Hydrograph



Summary for Pond 4P: Inf Syst-2

Inflow Area = 1,112 sf, 95.68% Impervious, Inflow Depth = 3.67" for 2-Year event
 Inflow = 0.1 cfs @ 12.08 hrs, Volume= 340 cf
 Outflow = 0.1 cfs @ 12.11 hrs, Volume= 327 cf, Atten= 4%, Lag= 1.4 min
 Discarded = 0.0 cfs @ 4.64 hrs, Volume= 156 cf
 Primary = 0.1 cfs @ 12.11 hrs, Volume= 171 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.41' @ 12.11 hrs Surf.Area= 101 sf Storage= 129 cf

Plug-Flow detention time= 773.3 min calculated for 327 cf (96% of inflow)
 Center-of-Mass det. time= 749.8 min (1,510.3 - 760.5)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	84 cf	7.28'W x 13.84'L x 2.72'H Field A 274 cf Overall - 64 cf Embedded = 210 cf x 40.0% Voids
#2A	7.25'	57 cf	Ferguson R-Tank XD 12 x 10 Inside #1 Inside= 19.7"W x 23.6"H => 2.91 sf x 1.97'L = 5.7 cf Outside= 19.7"W x 23.6"H => 3.23 sf x 1.97'L = 6.4 cf 10 Chambers in 2 Rows
		141 cf	Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.23'	6.0" Round Culvert L= 33.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.23' / 8.72' S= 0.0155 '/ Cc= 0.900 n= 0.013, Flow Area= 0.20 sf

Discarded OutFlow Max=0.0 cfs @ 4.64 hrs HW=7.03' (Free Discharge)
 ↕ **1=Exfiltration** (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.1 cfs @ 12.11 hrs HW=9.41' (Free Discharge)
 ↕ **2=Culvert** (Inlet Controls 0.1 cfs @ 1.45 fps)

Pond 4P: Inf Syst-2

Hydrograph



Summary for Pond 5P: Inf Syst-3

Inflow Area = 1,105 sf, 97.29% Impervious, Inflow Depth = 3.67" for 2-Year event
 Inflow = 0.1 cfs @ 12.08 hrs, Volume= 338 cf
 Outflow = 0.1 cfs @ 12.12 hrs, Volume= 319 cf, Atten= 8%, Lag= 2.2 min
 Discarded = 0.0 cfs @ 4.68 hrs, Volume= 156 cf
 Primary = 0.1 cfs @ 12.12 hrs, Volume= 163 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.55' @ 12.12 hrs Surf.Area= 101 sf Storage= 134 cf

Plug-Flow detention time= 799.9 min calculated for 319 cf (94% of inflow)
 Center-of-Mass det. time= 768.5 min (1,529.0 - 760.5)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	84 cf	7.28'W x 13.84'L x 2.72'H Field A 274 cf Overall - 64 cf Embedded = 210 cf x 40.0% Voids
#2A	7.25'	57 cf	Ferguson R-Tank XD 12 x 10 Inside #1 Inside= 19.7"W x 23.6"H => 2.91 sf x 1.97'L = 5.7 cf Outside= 19.7"W x 23.6"H => 3.23 sf x 1.97'L = 6.4 cf 10 Chambers in 2 Rows
		141 cf	Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.37'	6.0" Round Culvert L= 33.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.37' / 8.73' S= 0.0194 '/ Cc= 0.900 n= 0.013, Flow Area= 0.20 sf

Discarded OutFlow Max=0.0 cfs @ 4.68 hrs HW=7.03' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.1 cfs @ 12.12 hrs HW=9.55' (Free Discharge)
 ↳2=Culvert (Inlet Controls 0.1 cfs @ 1.43 fps)

Pond 5P: Inf Syst-3

Hydrograph



Summary for Pond 6P: Inf Syst-4

Inflow Area = 1,104 sf, 97.46% Impervious, Inflow Depth = 3.67" for 2-Year event
 Inflow = 0.1 cfs @ 12.08 hrs, Volume= 338 cf
 Outflow = 0.1 cfs @ 12.12 hrs, Volume= 319 cf, Atten= 9%, Lag= 2.2 min
 Discarded = 0.0 cfs @ 4.68 hrs, Volume= 156 cf
 Primary = 0.1 cfs @ 12.12 hrs, Volume= 163 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.55' @ 12.12 hrs Surf.Area= 101 sf Storage= 134 cf

Plug-Flow detention time= 800.6 min calculated for 319 cf (94% of inflow)
 Center-of-Mass det. time= 769.2 min (1,529.7 - 760.5)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	84 cf	7.28'W x 13.84'L x 2.72'H Field A 274 cf Overall - 64 cf Embedded = 210 cf x 40.0% Voids
#2A	7.25'	57 cf	Ferguson R-Tank XD 12 x 10 Inside #1 Inside= 19.7"W x 23.6"H => 2.91 sf x 1.97'L = 5.7 cf Outside= 19.7"W x 23.6"H => 3.23 sf x 1.97'L = 6.4 cf 10 Chambers in 2 Rows
		141 cf	Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.37'	6.0" Round Culvert L= 51.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.37' / 8.10' S= 0.0249 '/ Cc= 0.900 n= 0.013, Flow Area= 0.20 sf

Discarded OutFlow Max=0.0 cfs @ 4.68 hrs HW=7.03' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.1 cfs @ 12.12 hrs HW=9.55' (Free Discharge)
 ↳2=Culvert (Inlet Controls 0.1 cfs @ 1.43 fps)

Pond 6P: Inf Syst-4

Hydrograph



Summary for Pond 7P: Inf Syst-5

Inflow Area = 1,082 sf, 98.06% Impervious, Inflow Depth = 3.79" for 2-Year event
 Inflow = 0.1 cfs @ 12.08 hrs, Volume= 341 cf
 Outflow = 0.1 cfs @ 12.10 hrs, Volume= 341 cf, Atten= 1%, Lag= 0.7 min
 Discarded = 0.0 cfs @ 3.77 hrs, Volume= 157 cf
 Primary = 0.1 cfs @ 12.10 hrs, Volume= 183 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.18' @ 12.10 hrs Surf.Area= 101 sf Storage= 117 cf

Plug-Flow detention time= 722.0 min calculated for 341 cf (100% of inflow)
 Center-of-Mass det. time= 721.1 min (1,473.0 - 751.9)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	73 cf	7.28'W x 13.84'L x 2.39'H Field A 241 cf Overall - 58 cf Embedded = 182 cf x 40.0% Voids
#2A	7.25'	52 cf	Ferguson R-Tank XD 11 x 10 Inside #1 Inside= 19.7"W x 21.7"H => 2.66 sf x 1.97'L = 5.2 cf Outside= 19.7"W x 21.7"H => 2.96 sf x 1.97'L = 5.8 cf 10 Chambers in 2 Rows
		125 cf	Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.00'	6.0" Round Culvert L= 48.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.00' / 8.35' S= 0.0135 '/ Cc= 0.900 n= 0.013, Flow Area= 0.20 sf

Discarded OutFlow Max=0.0 cfs @ 3.77 hrs HW=7.03' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.1 cfs @ 12.10 hrs HW=9.18' (Free Discharge)
 ↳2=Culvert (Inlet Controls 0.1 cfs @ 1.46 fps)

Pond 7P: Inf Syst-5

Hydrograph



Summary for Pond 8P: Inf Syst-6

Inflow Area = 1,056 sf, 99.24% Impervious, Inflow Depth = 3.79" for 2-Year event
 Inflow = 0.1 cfs @ 12.08 hrs, Volume= 333 cf
 Outflow = 0.1 cfs @ 12.10 hrs, Volume= 332 cf, Atten= 1%, Lag= 0.8 min
 Discarded = 0.0 cfs @ 3.86 hrs, Volume= 157 cf
 Primary = 0.1 cfs @ 12.10 hrs, Volume= 175 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.20' @ 12.10 hrs Surf.Area= 101 sf Storage= 118 cf

Plug-Flow detention time= 739.6 min calculated for 332 cf (100% of inflow)
 Center-of-Mass det. time= 738.4 min (1,490.2 - 751.9)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	73 cf	7.28'W x 13.84'L x 2.39'H Field A 241 cf Overall - 58 cf Embedded = 182 cf x 40.0% Voids
#2A	7.25'	52 cf	Ferguson R-Tank XD 11 x 10 Inside #1 Inside= 19.7"W x 21.7"H => 2.66 sf x 1.97'L = 5.2 cf Outside= 19.7"W x 21.7"H => 2.96 sf x 1.97'L = 5.8 cf 10 Chambers in 2 Rows
		125 cf	Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.00'	8.0" Round Culvert L= 46.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.00' / 8.77' S= 0.0050 '/ S= 0.0050 '/ Cc= 0.900 n= 0.013, Flow Area= 0.35 sf

Discarded OutFlow Max=0.0 cfs @ 3.86 hrs HW=7.03' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.1 cfs @ 12.10 hrs HW=9.20' (Free Discharge)
 ↳2=Culvert (Barrel Controls 0.1 cfs @ 1.58 fps)

Pond 8P: Inf Syst-6

Hydrograph



Summary for Pond 9P: Inf Syst-7

Inflow Area = 24,131 sf, 72.87% Impervious, Inflow Depth = 3.05" for 2-Year event
 Inflow = 1.9 cfs @ 12.09 hrs, Volume= 6,142 cf
 Outflow = 1.1 cfs @ 12.19 hrs, Volume= 6,142 cf, Atten= 41%, Lag= 6.4 min
 Discarded = 0.0 cfs @ 7.94 hrs, Volume= 1,379 cf
 Primary = 1.1 cfs @ 12.19 hrs, Volume= 4,762 cf
 Routed to Link 1L : Towards Wetlands

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 7.84' @ 12.19 hrs Surf.Area= 2,422 sf Storage= 1,431 cf

Plug-Flow detention time= 91.3 min calculated for 6,141 cf (100% of inflow)
 Center-of-Mass det. time= 91.4 min (884.7 - 793.3)

Volume	Invert	Avail.Storage	Storage Description
#1	7.15'	3,645 cf	6.89'W x 14.06'L x 1.75'H StormTrap ST-1 Units (Irregular Shape) x 25 4,238 cf Overall x 86.0% Voids


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.15'	0.270 in/hr Exfiltration over Surface area
#2	Primary	7.15'	12.0" Round Culvert L= 4.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 7.15' / 7.13' S= 0.0050 '/ Cc= 0.900 n= 0.013, Flow Area= 0.79 sf
#3	Device 2	7.35'	22.0" W x 4.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

Discarded OutFlow Max=0.0 cfs @ 7.94 hrs HW=7.17' (Free Discharge)
 1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=1.1 cfs @ 12.19 hrs HW=7.84' (Free Discharge)
 2=Culvert (Barrel Controls 1.1 cfs @ 2.76 fps)
 3=Orifice/Grate (Passes 1.1 cfs of 1.6 cfs potential flow)

Pond 9P: Inf Syst-7

Hydrograph




Summary for Link 1L: Towards Wetlands

Inflow Area = 152,843 sf, 50.79% Impervious, Inflow Depth = 1.42" for 2-Year event
 Inflow = 3.6 cfs @ 12.16 hrs, Volume= 18,088 cf
 Primary = 3.6 cfs @ 12.16 hrs, Volume= 18,088 cf, Atten= 0%, Lag= 0.0 min
 Routed to Link 100L : Total Flows

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link 1L: Towards Wetlands

Hydrograph




Summary for Link 2L: Towards Street

Inflow Area = 5,843 sf, 18.07% Impervious, Inflow Depth = 1.90" for 2-Year event
 Inflow = 0.3 cfs @ 12.09 hrs, Volume= 927 cf
 Primary = 0.3 cfs @ 12.09 hrs, Volume= 927 cf, Atten= 0%, Lag= 0.0 min
 Routed to Link 100L : Total Flows

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link 2L: Towards Street

Hydrograph




Summary for Link 100L: Total Flows

Inflow Area = 158,686 sf, 49.59% Impervious, Inflow Depth = 1.44" for 2-Year event
 Inflow = 3.8 cfs @ 12.15 hrs, Volume= 19,014 cf
 Primary = 3.8 cfs @ 12.15 hrs, Volume= 19,014 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link 100L: Total Flows

Hydrograph



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=6.40"

Printed 12/17/2024

Page 41

Time span=0.00-72.00 hrs, dt=0.01 hrs, 7201 points
 Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
 Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment1S: CB-1	Runoff Area=22,742 sf 72.16% Impervious Runoff Depth=5.35" Tc=6.0 min CN=91 Runoff=3.1 cfs 10,138 cf
Subcatchment2S: Building Roof	Runoff Area=32,925 sf 100.00% Impervious Runoff Depth=6.16" Tc=6.0 min CN=98 Runoff=4.7 cfs 16,905 cf
Subcatchment3.1S: Backyard ADS	Runoff Area=8,985 sf 3.03% Impervious Runoff Depth=3.63" Flow Length=147' Tc=10.3 min CN=75 Runoff=0.8 cfs 2,715 cf
Subcatchment3S: Townhouse Roofs	Runoff Area=13,067 sf 100.00% Impervious Runoff Depth=6.16" Tc=6.0 min CN=98 Runoff=1.9 cfs 6,709 cf
Subcatchment4.2S: TD-2	Runoff Area=1,112 sf 95.68% Impervious Runoff Depth=6.04" Tc=6.0 min CN=97 Runoff=0.2 cfs 560 cf
Subcatchment4.3S: TD-3	Runoff Area=1,105 sf 97.29% Impervious Runoff Depth=6.04" Tc=6.0 min CN=97 Runoff=0.2 cfs 556 cf
Subcatchment4.4S: TD-4	Runoff Area=1,104 sf 97.46% Impervious Runoff Depth=6.04" Tc=6.0 min CN=97 Runoff=0.2 cfs 556 cf
Subcatchment4.5S: TD-5	Runoff Area=1,082 sf 98.06% Impervious Runoff Depth=6.16" Tc=6.0 min CN=98 Runoff=0.2 cfs 556 cf
Subcatchment4.6S: TD-6	Runoff Area=1,056 sf 99.24% Impervious Runoff Depth=6.16" Tc=6.0 min CN=98 Runoff=0.2 cfs 542 cf
Subcatchment5.1S: TD-1A	Runoff Area=1,389 sf 84.59% Impervious Runoff Depth=5.69" Tc=6.0 min CN=94 Runoff=0.2 cfs 659 cf
Subcatchment5S: TD-1B	Runoff Area=4,462 sf 42.78% Impervious Runoff Depth=4.57" Tc=6.0 min CN=84 Runoff=0.5 cfs 1,700 cf
Subcatchment6.1S: East driveway	Runoff Area=12,275 sf 52.50% Impervious Runoff Depth=4.90" Tc=6.0 min CN=87 Runoff=1.6 cfs 5,013 cf
Subcatchment6S: Bypass Towards	Runoff Area=51,539 sf 0.21% Impervious Runoff Depth=3.52" Flow Length=125' Tc=14.0 min CN=74 Runoff=3.8 cfs 15,135 cf
Subcatchment7S: To Street	Runoff Area=5,843 sf 18.07% Impervious Runoff Depth=3.93" Tc=6.0 min CN=78 Runoff=0.6 cfs 1,916 cf
Pond 1P: Inf Syst-1	Peak Elev=9.96' Storage=12,545 cf Inflow=8.0 cfs 28,251 cf Discarded=0.1 cfs 14,540 cf Primary=2.2 cfs 13,710 cf Outflow=2.3 cfs 28,251 cf
Pond 3P: Rain garden	Peak Elev=6.45' Storage=229 cf Inflow=1.6 cfs 5,013 cf Discarded=0.0 cfs 477 cf Primary=1.6 cfs 4,537 cf Outflow=1.6 cfs 5,013 cf

2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=6.40"

Printed 12/17/2024

Page 42

Pond 4P: Inf Syst-2	Peak Elev=9.47' Storage=131 cf Inflow=0.2 cfs 560 cf Discarded=0.0 cfs 159 cf Primary=0.2 cfs 388 cf Outflow=0.2 cfs 547 cf
Pond 5P: Inf Syst-3	Peak Elev=9.61' Storage=137 cf Inflow=0.2 cfs 556 cf Discarded=0.0 cfs 159 cf Primary=0.2 cfs 379 cf Outflow=0.2 cfs 537 cf
Pond 6P: Inf Syst-4	Peak Elev=9.61' Storage=137 cf Inflow=0.2 cfs 556 cf Discarded=0.0 cfs 159 cf Primary=0.2 cfs 378 cf Outflow=0.2 cfs 537 cf
Pond 7P: Inf Syst-5	Peak Elev=9.24' Storage=119 cf Inflow=0.2 cfs 556 cf Discarded=0.0 cfs 160 cf Primary=0.2 cfs 395 cf Outflow=0.2 cfs 555 cf
Pond 8P: Inf Syst-6	Peak Elev=9.26' Storage=120 cf Inflow=0.2 cfs 542 cf Discarded=0.0 cfs 160 cf Primary=0.2 cfs 382 cf Outflow=0.2 cfs 541 cf
Pond 9P: Inf Syst-7	Peak Elev=8.14' Storage=2,069 cf Inflow=3.3 cfs 10,797 cf Discarded=0.0 cfs 1,502 cf Primary=2.1 cfs 9,295 cf Outflow=2.1 cfs 10,797 cf
Link 1L: Towards Wetlands	Inflow=9.0 cfs 44,377 cf Primary=9.0 cfs 44,377 cf
Link 2L: Towards Street	Inflow=0.6 cfs 1,916 cf Primary=0.6 cfs 1,916 cf
Link 100L: Total Flows	Inflow=9.4 cfs 46,293 cf Primary=9.4 cfs 46,293 cf

Total Runoff Area = 158,686 sf Runoff Volume = 63,661 cf Average Runoff Depth = 4.81"
50.41% Pervious = 79,997 sf 49.59% Impervious = 78,689 sf

2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=6.40"

Printed 12/17/2024

Page 43

Summary for Subcatchment 1S: CB-1


Runoff = 3.1 cfs @ 12.08 hrs, Volume= 10,138 cf, Depth= 5.35"
Routed to Pond 9P : Inf Syst-7

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 10-Year Rainfall=6.40"

Area (sf)	CN	Description
16,410	98	Paved parking, HSG C
6,332	74	>75% Grass cover, Good, HSG C
22,742	91	Weighted Average
6,332		27.84% Pervious Area
16,410		72.16% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 1S: CB-1



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=6.40"

Printed 12/17/2024

Page 44

Summary for Subcatchment 2S: Building Roof


Runoff = 4.7 cfs @ 12.08 hrs, Volume= 16,905 cf, Depth= 6.16"
Routed to Pond 1P : Inf Syst-1

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 10-Year Rainfall=6.40"

Area (sf)	CN	Description
32,925	98	Roofs, HSG C
32,925		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 2S: Building Roof



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=6.40"

Printed 12/17/2024

Page 45

Summary for Subcatchment 3.1S: Backyard ADs

Runoff = 0.8 cfs @ 12.14 hrs, Volume= 2,715 cf, Depth= 3.63"
Routed to Pond 1P : Inf Syst-1


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 10-Year Rainfall=6.40"

Area (sf)	CN	Description
272	98	Unconnected pavement, HSG C
8,302	74	>75% Grass cover, Good, HSG C
411	89	Gravel sidewalk, HSG C
8,985	75	Weighted Average
8,713		96.97% Pervious Area
272		3.03% Impervious Area
272		100.00% Unconnected

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
9.4	50	0.0142	0.09		Sheet Flow, Grass: Dense n= 0.240 P2= 3.23"
0.9	97	0.0154	1.86		Shallow Concentrated Flow, Grassed Waterway Kv= 15.0 fps
10.3	147	Total			

Subcatchment 3.1S: Backyard ADs

Hydrograph



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=6.40"

Printed 12/17/2024

Page 46

Summary for Subcatchment 3S: Townhouse Roofs

Runoff = 1.9 cfs @ 12.08 hrs, Volume= 6,709 cf, Depth= 6.16"
Routed to Pond 1P : Inf Syst-1


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 10-Year Rainfall=6.40"

Area (sf)	CN	Description
13,067	98	Roofs, HSG C
13,067		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 3S: Townhouse Roofs

Hydrograph



Summary for Subcatchment 4.2S: TD-2

Runoff = 0.2 cfs @ 12.08 hrs, Volume= 560 cf, Depth= 6.04"
 Routed to Pond 4P : Inf Syst-2


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 10-Year Rainfall=6.40"

Area (sf)	CN	Description
1,064	98	Paved parking, HSG C
48	74	>75% Grass cover, Good, HSG C
1,112	97	Weighted Average
48		4.32% Pervious Area
1,064		95.68% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.2S: TD-2

Hydrograph



Summary for Subcatchment 4.3S: TD-3

Runoff = 0.2 cfs @ 12.08 hrs, Volume= 556 cf, Depth= 6.04"
 Routed to Pond 5P : Inf Syst-3


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 10-Year Rainfall=6.40"

Area (sf)	CN	Description
1,075	98	Paved parking, HSG C
30	74	>75% Grass cover, Good, HSG C
1,105	97	Weighted Average
30		2.71% Pervious Area
1,075		97.29% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.3S: TD-3

Hydrograph



Summary for Subcatchment 4.4S: TD-4

Runoff = 0.2 cfs @ 12.08 hrs, Volume= 556 cf, Depth= 6.04"
 Routed to Pond 6P : Inf Syst-4


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 10-Year Rainfall=6.40"

Area (sf)	CN	Description
1,076	98	Paved parking, HSG C
28	74	>75% Grass cover, Good, HSG C
1,104	97	Weighted Average
28		2.54% Pervious Area
1,076		97.46% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.4S: TD-4

Hydrograph



Summary for Subcatchment 4.5S: TD-5

Runoff = 0.2 cfs @ 12.08 hrs, Volume= 556 cf, Depth= 6.16"
 Routed to Pond 7P : Inf Syst-5


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 10-Year Rainfall=6.40"

Area (sf)	CN	Description
1,061	98	Paved parking, HSG C
21	74	>75% Grass cover, Good, HSG C
1,082	98	Weighted Average
21		1.94% Pervious Area
1,061		98.06% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.5S: TD-5

Hydrograph



Summary for Subcatchment 4.6S: TD-6

Runoff = 0.2 cfs @ 12.08 hrs, Volume= 542 cf, Depth= 6.16"
 Routed to Pond 8P : Inf Syst-6


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 10-Year Rainfall=6.40"

Area (sf)	CN	Description
1,048	98	Paved parking, HSG C
8	74	>75% Grass cover, Good, HSG C
1,056	98	Weighted Average
8		0.76% Pervious Area
1,048		99.24% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.6S: TD-6

Hydrograph



Summary for Subcatchment 5.1S: TD-1A

Runoff = 0.2 cfs @ 12.08 hrs, Volume= 659 cf, Depth= 5.69"
 Routed to Pond 9P : Inf Syst-7


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 10-Year Rainfall=6.40"

Area (sf)	CN	Description
1,175	98	Paved parking, HSG C
214	74	>75% Grass cover, Good, HSG C
1,389	94	Weighted Average
214		15.41% Pervious Area
1,175		84.59% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 5.1S: TD-1A

Hydrograph



Summary for Subcatchment 5S: TD-1B

Runoff = 0.5 cfs @ 12.09 hrs, Volume= 1,700 cf, Depth= 4.57"
 Routed to Link 1L : Towards Wetlands


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 10-Year Rainfall=6.40"

Area (sf)	CN	Description
1,909	98	Paved parking, HSG C
2,553	74	>75% Grass cover, Good, HSG C
4,462	84	Weighted Average
2,553		57.22% Pervious Area
1,909		42.78% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 5S: TD-1B

Hydrograph



Summary for Subcatchment 6.1S: East driveway

Runoff = 1.6 cfs @ 12.09 hrs, Volume= 5,013 cf, Depth= 4.90"
 Routed to Pond 3P : Rain garden


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 10-Year Rainfall=6.40"

Area (sf)	CN	Description
5,611	74	>75% Grass cover, Good, HSG C
6,444	98	Paved roads w/curbs & sewers, HSG C
220	89	Gravel roads, HSG C
12,275	87	Weighted Average
5,831		47.50% Pervious Area
6,444		52.50% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

Subcatchment 6.1S: East driveway

Hydrograph



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=6.40"

Printed 12/17/2024

Page 55

Summary for Subcatchment 6S: Bypass Towards Wetlands

Runoff = 3.8 cfs @ 12.19 hrs, Volume= 15,135 cf, Depth= 3.52"
 Routed to Link 1L : Towards Wetlands


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 10-Year Rainfall=6.40"

Area (sf)	CN	Description
4,985	70	Woods, Good, HSG C
46,447	74	>75% Grass cover, Good, HSG C
107	98	Roofs, HSG C
51,539	74	Weighted Average
51,432		99.79% Pervious Area
107		0.21% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.8	50	0.0220	0.07		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.23"
2.2	75	0.0133	0.58		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
14.0	125	Total			

Subcatchment 6S: Bypass Towards Wetlands

Hydrograph



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=6.40"

Printed 12/17/2024

Page 56

Summary for Subcatchment 7S: To Street

Runoff = 0.6 cfs @ 12.09 hrs, Volume= 1,916 cf, Depth= 3.93"
 Routed to Link 2L : Towards Street


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 10-Year Rainfall=6.40"

Area (sf)	CN	Description
1,056	98	Paved parking, HSG C
4,787	74	>75% Grass cover, Good, HSG C
5,843	78	Weighted Average
4,787		81.93% Pervious Area
1,056		18.07% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 7S: To Street

Hydrograph



Summary for Pond 1P: Inf Syst-1

Inflow Area = 60,436 sf, 85.36% Impervious, Inflow Depth = 5.61" for 10-Year event
 Inflow = 8.0 cfs @ 12.09 hrs, Volume= 28,251 cf
 Outflow = 2.3 cfs @ 12.43 hrs, Volume= 28,251 cf, Atten= 71%, Lag= 20.8 min
 Discarded = 0.1 cfs @ 6.13 hrs, Volume= 14,540 cf
 Primary = 2.2 cfs @ 12.43 hrs, Volume= 13,710 cf
 Routed to Link 1L : Towards Wetlands

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.96' @ 12.43 hrs Surf.Area= 7,459 sf Storage= 12,545 cf

Plug-Flow detention time= 442.3 min calculated for 28,251 cf (100% of inflow)
 Center-of-Mass det. time= 442.2 min (1,198.8 - 756.6)

Volume	Invert	Avail.Storage	Storage Description
#1	8.00'	19,245 cf	6.89'W x 14.06'L x 3.00'H StormTrap ST-1 Units (Irregular Shape) x 77 22,378 cf Overall x 86.0% Voids


Device	Routing	Invert	Outlet Devices
#1	Discarded	8.00'	0.520 in/hr Exfiltration over Surface area
#2	Primary	8.00'	15.0" Round Culvert L= 26.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 8.00' / 7.13' S= 0.0335 '/ Cc= 0.900 n= 0.013, Flow Area= 1.23 sf
#3	Device 2	9.22'	22.0" W x 4.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 2	10.05'	20.0" W x 4.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 2	10.79'	3.7' long Sharp-Crested Rectangular Weir 2 End Contraction(s)

Discarded OutFlow Max=0.1 cfs @ 6.13 hrs HW=8.03' (Free Discharge)
 ↳ **1=Exfiltration** (Exfiltration Controls 0.1 cfs)

Primary OutFlow Max=2.2 cfs @ 12.43 hrs HW=9.96' (Free Discharge)
 ↳ **2=Culvert** (Passes 2.2 cfs of 6.8 cfs potential flow)
 ↳ **3=Orifice/Grate** (Orifice Controls 2.2 cfs @ 3.62 fps)
 ↳ **4=Orifice/Grate** (Controls 0.0 cfs)
 ↳ **5=Sharp-Crested Rectangular Weir** (Controls 0.0 cfs)

Pond 1P: Inf Syst-1

Hydrograph



Summary for Pond 3P: Rain garden

Inflow Area = 12,275 sf, 52.50% Impervious, Inflow Depth = 4.90" for 10-Year event
 Inflow = 1.6 cfs @ 12.09 hrs, Volume= 5,013 cf
 Outflow = 1.6 cfs @ 12.09 hrs, Volume= 5,013 cf, Atten= 0%, Lag= 0.3 min
 Discarded = 0.0 cfs @ 12.09 hrs, Volume= 477 cf
 Primary = 1.6 cfs @ 12.09 hrs, Volume= 4,537 cf
 Routed to Link 1L : Towards Wetlands

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 6.45' @ 12.09 hrs Surf.Area= 429 sf Storage= 229 cf

Plug-Flow detention time= 53.5 min calculated for 5,012 cf (100% of inflow)
 Center-of-Mass det. time= 53.6 min (846.0 - 792.4)

Volume #1	Invert	Avail.Storage	Storage Description		
#1	5.60'	253 cf	Custom Stage Data (Irregular) Listed below (Recalc)		
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
5.60	125	46.0	0	0	125
6.00	276	66.0	78	78	305
6.30	350	73.0	94	172	385
6.50	460	87.0	81	253	564


Device	Routing	Invert	Outlet Devices
#1	Discarded	5.60'	0.520 in/hr Exfiltration over Surface area
#2	Primary	6.35'	22.0' long x 5.0' breadth Broad-Crested Rectangular Weir
Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00			
2.50 3.00 3.50 4.00 4.50 5.00 5.50			
Coef. (English) 2.34 2.50 2.70 2.68 2.68 2.66 2.65 2.65 2.65			
2.65 2.67 2.66 2.68 2.70 2.74 2.79 2.88			

Discarded OutFlow Max=0.0 cfs @ 12.09 hrs HW=6.45' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=1.6 cfs @ 12.09 hrs HW=6.45' (Free Discharge)
 ↳2=Broad-Crested Rectangular Weir (Weir Controls 1.6 cfs @ 0.73 fps)

Pond 3P: Rain garden

Hydrograph



Summary for Pond 4P: Inf Syst-2

Inflow Area = 1,112 sf, 95.68% Impervious, Inflow Depth = 6.04" for 10-Year event
 Inflow = 0.2 cfs @ 12.08 hrs, Volume= 560 cf
 Outflow = 0.2 cfs @ 12.09 hrs, Volume= 547 cf, Atten= 1%, Lag= 0.6 min
 Discarded = 0.0 cfs @ 2.79 hrs, Volume= 159 cf
 Primary = 0.2 cfs @ 12.09 hrs, Volume= 388 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.47' @ 12.09 hrs Surf.Area= 101 sf Storage= 131 cf

Plug-Flow detention time= 483.5 min calculated for 546 cf (98% of inflow)
 Center-of-Mass det. time= 468.6 min (1,219.5 - 751.0)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	84 cf	7.28'W x 13.84'L x 2.72'H Field A 274 cf Overall - 64 cf Embedded = 210 cf x 40.0% Voids
#2A	7.25'	57 cf	Ferguson R-Tank XD 12 x 10 Inside #1 Inside= 19.7"W x 23.6"H => 2.91 sf x 1.97'L = 5.7 cf Outside= 19.7"W x 23.6"H => 3.23 sf x 1.97'L = 6.4 cf 10 Chambers in 2 Rows
		141 cf	Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.23'	6.0" Round Culvert L= 33.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.23' / 8.72' S= 0.0155 ' / Cc= 0.900 n= 0.013, Flow Area= 0.20 sf

Discarded OutFlow Max=0.0 cfs @ 2.79 hrs HW=7.03' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.2 cfs @ 12.09 hrs HW=9.47' (Free Discharge)
 ↳2=Culvert (Inlet Controls 0.2 cfs @ 1.67 fps)

Pond 4P: Inf Syst-2

Hydrograph



Summary for Pond 5P: Inf Syst-3

Inflow Area = 1,105 sf, 97.29% Impervious, Inflow Depth = 6.04" for 10-Year event
 Inflow = 0.2 cfs @ 12.08 hrs, Volume= 556 cf
 Outflow = 0.2 cfs @ 12.09 hrs, Volume= 537 cf, Atten= 1%, Lag= 0.6 min
 Discarded = 0.0 cfs @ 2.83 hrs, Volume= 159 cf
 Primary = 0.2 cfs @ 12.09 hrs, Volume= 379 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.61' @ 12.09 hrs Surf.Area= 101 sf Storage= 137 cf

Plug-Flow detention time= 497.7 min calculated for 537 cf (97% of inflow)
 Center-of-Mass det. time= 476.9 min (1,227.8 - 751.0)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	84 cf	7.28'W x 13.84'L x 2.72'H Field A 274 cf Overall - 64 cf Embedded = 210 cf x 40.0% Voids
#2A	7.25'	57 cf	Ferguson R-Tank XD 12 x 10 Inside #1 Inside= 19.7"W x 23.6"H => 2.91 sf x 1.97'L = 5.7 cf Outside= 19.7"W x 23.6"H => 3.23 sf x 1.97'L = 6.4 cf 10 Chambers in 2 Rows
		141 cf	Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.37'	6.0" Round Culvert L= 33.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.37' / 8.73' S= 0.0194 1' Cc= 0.900 n= 0.013, Flow Area= 0.20 sf

Discarded OutFlow Max=0.0 cfs @ 2.83 hrs HW=7.03' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.2 cfs @ 12.09 hrs HW=9.61' (Free Discharge)
 ↳2=Culvert (Inlet Controls 0.2 cfs @ 1.67 fps)

Pond 5P: Inf Syst-3

Hydrograph



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=6.40"

Printed 12/17/2024

Page 65

Summary for Pond 6P: Inf Syst-4

Inflow Area = 1,104 sf, 97.46% Impervious, Inflow Depth = 6.04" for 10-Year event
 Inflow = 0.2 cfs @ 12.08 hrs, Volume= 556 cf
 Outflow = 0.2 cfs @ 12.09 hrs, Volume= 537 cf, Atten= 1%, Lag= 0.6 min
 Discarded = 0.0 cfs @ 2.83 hrs, Volume= 159 cf
 Primary = 0.2 cfs @ 12.09 hrs, Volume= 378 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.61' @ 12.09 hrs Surf.Area= 101 sf Storage= 137 cf

Plug-Flow detention time= 498.4 min calculated for 537 cf (97% of inflow)
 Center-of-Mass det. time= 477.3 min (1,228.2 - 751.0)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	84 cf	7.28'W x 13.84'L x 2.72'H Field A 274 cf Overall - 64 cf Embedded = 210 cf x 40.0% Voids
#2A	7.25'	57 cf	Ferguson R-Tank XD 12 x 10 Inside #1 Inside= 19.7"W x 23.6"H => 2.91 sf x 1.97'L = 5.7 cf Outside= 19.7"W x 23.6"H => 3.23 sf x 1.97'L = 6.4 cf 10 Chambers in 2 Rows
		141 cf	Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.37'	6.0" Round Culvert L= 51.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.37' / 8.10' S= 0.0249 ' S= 0.0249 ' Cc= 0.900 n= 0.013, Flow Area= 0.20 sf

Discarded OutFlow Max=0.0 cfs @ 2.83 hrs HW=7.03' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.2 cfs @ 12.09 hrs HW=9.61' (Free Discharge)
 ↳2=Culvert (Inlet Controls 0.2 cfs @ 1.67 fps)

2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC


Type III 24-hr 10-Year Rainfall=6.40"

Printed 12/17/2024

Page 66

Pond 6P: Inf Syst-4

Hydrograph



Summary for Pond 7P: Inf Syst-5

Inflow Area = 1,082 sf, 98.06% Impervious, Inflow Depth = 6.16" for 10-Year event
 Inflow = 0.2 cfs @ 12.08 hrs, Volume= 556 cf
 Outflow = 0.2 cfs @ 12.09 hrs, Volume= 555 cf, Atten= 1%, Lag= 0.6 min
 Discarded = 0.0 cfs @ 2.12 hrs, Volume= 160 cf
 Primary = 0.2 cfs @ 12.09 hrs, Volume= 395 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.24' @ 12.09 hrs Surf.Area= 101 sf Storage= 119 cf

Plug-Flow detention time= 464.5 min calculated for 555 cf (100% of inflow)
 Center-of-Mass det. time= 463.9 min (1,208.1 - 744.2)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	73 cf	7.28'W x 13.84'L x 2.39'H Field A 241 cf Overall - 58 cf Embedded = 182 cf x 40.0% Voids
#2A	7.25'	52 cf	Ferguson R-Tank XD 11 x 10 Inside #1 Inside= 19.7"W x 21.7"H => 2.66 sf x 1.97'L = 5.2 cf Outside= 19.7"W x 21.7"H => 2.96 sf x 1.97'L = 5.8 cf 10 Chambers in 2 Rows
		125 cf	Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.00'	6.0" Round Culvert L= 48.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.00' / 8.35' S= 0.0135 '/ Cc= 0.900 n= 0.013, Flow Area= 0.20 sf

Discarded OutFlow Max=0.0 cfs @ 2.12 hrs HW=7.03' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.2 cfs @ 12.09 hrs HW=9.24' (Free Discharge)
 ↳2=Culvert (Inlet Controls 0.2 cfs @ 1.66 fps)

Pond 7P: Inf Syst-5

Hydrograph



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=6.40"

Printed 12/17/2024

Page 69

Summary for Pond 8P: Inf Syst-6

Inflow Area = 1,056 sf, 99.24% Impervious, Inflow Depth = 6.16" for 10-Year event
 Inflow = 0.2 cfs @ 12.08 hrs, Volume= 542 cf
 Outflow = 0.2 cfs @ 12.09 hrs, Volume= 541 cf, Atten= 1%, Lag= 0.6 min
 Discarded = 0.0 cfs @ 2.19 hrs, Volume= 160 cf
 Primary = 0.2 cfs @ 12.09 hrs, Volume= 382 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.26' @ 12.09 hrs Surf.Area= 101 sf Storage= 120 cf

Plug-Flow detention time= 475.6 min calculated for 541 cf (100% of inflow)
 Center-of-Mass det. time= 474.9 min (1,219.1 - 744.2)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	73 cf	7.28'W x 13.84'L x 2.39'H Field A 241 cf Overall - 58 cf Embedded = 182 cf x 40.0% Voids
#2A	7.25'	52 cf	Ferguson R-Tank XD 11 x 10 Inside #1 Inside= 19.7"W x 21.7"H => 2.66 sf x 1.97'L = 5.2 cf Outside= 19.7"W x 21.7"H => 2.96 sf x 1.97'L = 5.8 cf 10 Chambers in 2 Rows
		125 cf	Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.00'	8.0" Round Culvert L= 46.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.00' / 8.77' S= 0.0050 '/ Cc= 0.900 n= 0.013, Flow Area= 0.35 sf

Discarded OutFlow Max=0.0 cfs @ 2.19 hrs HW=7.03' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.1 cfs @ 12.09 hrs HW=9.26' (Free Discharge)
 ↳2=Culvert (Barrel Controls 0.1 cfs @ 1.80 fps)

2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC


Type III 24-hr 10-Year Rainfall=6.40"

Printed 12/17/2024

Page 70

Pond 8P: Inf Syst-6

Hydrograph



Summary for Pond 9P: Inf Syst-7

Inflow Area = 24,131 sf, 72.87% Impervious, Inflow Depth = 5.37" for 10-Year event
 Inflow = 3.3 cfs @ 12.08 hrs, Volume= 10,797 cf
 Outflow = 2.1 cfs @ 12.18 hrs, Volume= 10,797 cf, Atten= 37%, Lag= 5.7 min
 Discarded = 0.0 cfs @ 5.84 hrs, Volume= 1,502 cf
 Primary = 2.1 cfs @ 12.18 hrs, Volume= 9,295 cf
 Routed to Link 1L : Towards Wetlands

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 8.14' @ 12.18 hrs Surf.Area= 2,422 sf Storage= 2,069 cf

Plug-Flow detention time= 63.5 min calculated for 10,795 cf (100% of inflow)
 Center-of-Mass det. time= 63.5 min (841.9 - 778.3)

Volume	Invert	Avail.Storage	Storage Description
#1	7.15'	3,645 cf	6.89'W x 14.06'L x 1.75'H StormTrap ST-1 Units (Irregular Shape) x 25 4,238 cf Overall x 86.0% Voids

Device	Routing	Invert	Outlet Devices
#1	Discarded	7.15'	0.270 in/hr Exfiltration over Surface area
#2	Primary	7.15'	12.0" Round Culvert L= 4.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 7.15' / 7.13' S= 0.0050 /' Cc= 0.900 n= 0.013, Flow Area= 0.79 sf
#3	Device 2	7.35'	22.0" W x 4.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

Discarded OutFlow Max=0.0 cfs @ 5.84 hrs HW=7.17' (Free Discharge)

↳ **1=Exfiltration** (Exfiltration Controls 0.0 cfs)


Primary OutFlow Max=2.1 cfs @ 12.18 hrs HW=8.14' (Free Discharge)

↳ **2=Culvert** (Barrel Controls 2.1 cfs @ 3.29 fps)

↳ **3=Orifice/Grate** (Passes 2.1 cfs of 2.3 cfs potential flow)

Pond 9P: Inf Syst-7

Hydrograph




Summary for Link 1L: Towards Wetlands

Inflow Area = 152,843 sf, 50.79% Impervious, Inflow Depth = 3.48" for 10-Year event
 Inflow = 9.0 cfs @ 12.18 hrs, Volume= 44,377 cf
 Primary = 9.0 cfs @ 12.18 hrs, Volume= 44,377 cf, Atten= 0%, Lag= 0.0 min
 Routed to Link 100L : Total Flows

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link 1L: Towards Wetlands

Hydrograph




Summary for Link 2L: Towards Street

Inflow Area = 5,843 sf, 18.07% Impervious, Inflow Depth = 3.93" for 10-Year event
 Inflow = 0.6 cfs @ 12.09 hrs, Volume= 1,916 cf
 Primary = 0.6 cfs @ 12.09 hrs, Volume= 1,916 cf, Atten= 0%, Lag= 0.0 min
 Routed to Link 100L : Total Flows

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link 2L: Towards Street

Hydrograph




Summary for Link 100L: Total Flows

Inflow Area = 158,686 sf, 49.59% Impervious, Inflow Depth = 3.50" for 10-Year event
 Inflow = 9.4 cfs @ 12.17 hrs, Volume= 46,293 cf
 Primary = 9.4 cfs @ 12.17 hrs, Volume= 46,293 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link 100L: Total Flows

Hydrograph



Time span=0.00-72.00 hrs, dt=0.01 hrs, 7201 points
 Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
 Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment1S: CB-1	Runoff Area=22,742 sf 72.16% Impervious Runoff Depth=7.22" Tc=6.0 min CN=91 Runoff=4.1 cfs 13,685 cf
Subcatchment2S: Building Roof	Runoff Area=32,925 sf 100.00% Impervious Runoff Depth=8.06" Tc=6.0 min CN=98 Runoff=6.2 cfs 22,115 cf
Subcatchment3.1S: Backyard ADS	Runoff Area=8,985 sf 3.03% Impervious Runoff Depth=5.31" Flow Length=147' Tc=10.3 min CN=75 Runoff=1.1 cfs 3,978 cf
Subcatchment3S: Townhouse Roofs	Runoff Area=13,067 sf 100.00% Impervious Runoff Depth=8.06" Tc=6.0 min CN=98 Runoff=2.4 cfs 8,777 cf
Subcatchment4.2S: TD-2	Runoff Area=1,112 sf 95.68% Impervious Runoff Depth=7.94" Tc=6.0 min CN=97 Runoff=0.2 cfs 736 cf
Subcatchment4.3S: TD-3	Runoff Area=1,105 sf 97.29% Impervious Runoff Depth=7.94" Tc=6.0 min CN=97 Runoff=0.2 cfs 731 cf
Subcatchment4.4S: TD-4	Runoff Area=1,104 sf 97.46% Impervious Runoff Depth=7.94" Tc=6.0 min CN=97 Runoff=0.2 cfs 730 cf
Subcatchment4.5S: TD-5	Runoff Area=1,082 sf 98.06% Impervious Runoff Depth=8.06" Tc=6.0 min CN=98 Runoff=0.2 cfs 727 cf
Subcatchment4.6S: TD-6	Runoff Area=1,056 sf 99.24% Impervious Runoff Depth=8.06" Tc=6.0 min CN=98 Runoff=0.2 cfs 709 cf
Subcatchment5.1S: TD-1A	Runoff Area=1,389 sf 84.59% Impervious Runoff Depth=7.58" Tc=6.0 min CN=94 Runoff=0.3 cfs 877 cf
Subcatchment5S: TD-1B	Runoff Area=4,462 sf 42.78% Impervious Runoff Depth=6.38" Tc=6.0 min CN=84 Runoff=0.7 cfs 2,374 cf
Subcatchment6.1S: East driveway	Runoff Area=12,275 sf 52.50% Impervious Runoff Depth=6.74" Tc=6.0 min CN=87 Runoff=2.1 cfs 6,897 cf
Subcatchment6S: Bypass Towards	Runoff Area=51,539 sf 0.21% Impervious Runoff Depth=5.19" Flow Length=125' Tc=14.0 min CN=74 Runoff=5.6 cfs 22,311 cf
Subcatchment7S: To Street	Runoff Area=5,843 sf 18.07% Impervious Runoff Depth=5.67" Tc=6.0 min CN=78 Runoff=0.9 cfs 2,760 cf
Pond 1P: Inf Syst-1	Peak Elev=10.41' Storage=15,470 cf Inflow=10.6 cfs 37,649 cf Discarded=0.1 cfs 14,969 cf Primary=4.1 cfs 22,680 cf Outflow=4.2 cfs 37,649 cf
Pond 3P: Rain garden	Peak Elev=6.47' Storage=239 cf Inflow=2.1 cfs 6,897 cf Discarded=0.0 cfs 495 cf Primary=2.1 cfs 6,401 cf Outflow=2.1 cfs 6,897 cf

2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=8.30"

Printed 12/17/2024

Page 77

Pond 4P: Inf Syst-2

Peak Elev=9.51' Storage=133 cf Inflow=0.2 cfs 736 cf
Discarded=0.0 cfs 160 cf Primary=0.2 cfs 562 cf Outflow=0.2 cfs 722 cf

Pond 5P: Inf Syst-3

Peak Elev=9.65' Storage=139 cf Inflow=0.2 cfs 731 cf
Discarded=0.0 cfs 160 cf Primary=0.2 cfs 552 cf Outflow=0.2 cfs 712 cf

Pond 6P: Inf Syst-4

Peak Elev=9.65' Storage=139 cf Inflow=0.2 cfs 730 cf
Discarded=0.0 cfs 160 cf Primary=0.2 cfs 552 cf Outflow=0.2 cfs 711 cf

Pond 7P: Inf Syst-5

Peak Elev=9.28' Storage=121 cf Inflow=0.2 cfs 727 cf
Discarded=0.0 cfs 161 cf Primary=0.2 cfs 565 cf Outflow=0.2 cfs 726 cf

Pond 8P: Inf Syst-6

Peak Elev=9.29' Storage=122 cf Inflow=0.2 cfs 709 cf
Discarded=0.0 cfs 161 cf Primary=0.2 cfs 548 cf Outflow=0.2 cfs 708 cf

Pond 9P: Inf Syst-7

Peak Elev=8.38' Storage=2,562 cf Inflow=4.3 cfs 14,562 cf
Discarded=0.0 cfs 1,561 cf Primary=2.7 cfs 13,001 cf Outflow=2.7 cfs 14,562 cf

Link 1L: Towards Wetlands

Inflow=13.7 cfs 66,767 cf
Primary=13.7 cfs 66,767 cf

Link 2L: Towards Street

Inflow=0.9 cfs 2,760 cf
Primary=0.9 cfs 2,760 cf

Link 100L: Total Flows

Inflow=14.2 cfs 69,527 cf
Primary=14.2 cfs 69,527 cf

Total Runoff Area = 158,686 sf Runoff Volume = 87,407 cf Average Runoff Depth = 6.61"
50.41% Pervious = 79,997 sf 49.59% Impervious = 78,689 sf

2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=8.30"

Printed 12/17/2024

Page 78

Summary for Subcatchment 1S: CB-1


Runoff = 4.1 cfs @ 12.08 hrs, Volume= 13,685 cf, Depth= 7.22"
Routed to Pond 9P : Inf Syst-7

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 25-Year Rainfall=8.30"

Area (sf)	CN	Description
16,410	98	Paved parking, HSG C
6,332	74	>75% Grass cover, Good, HSG C
22,742	91	Weighted Average
6,332		27.84% Pervious Area
16,410		72.16% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 1S: CB-1



Summary for Subcatchment 2S: Building Roof


Runoff = 6.2 cfs @ 12.08 hrs, Volume= 22,115 cf, Depth= 8.06"
Routed to Pond 1P : Inf Syst-1

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 25-Year Rainfall=8.30"

Area (sf)	CN	Description
32,925	98	Roofs, HSG C
32,925		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 2S: Building Roof



Summary for Subcatchment 3.1S: Backyard ADs


Runoff = 1.1 cfs @ 12.14 hrs, Volume= 3,978 cf, Depth= 5.31"
Routed to Pond 1P : Inf Syst-1

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 25-Year Rainfall=8.30"

Area (sf)	CN	Description
272	98	Unconnected pavement, HSG C
8,302	74	>75% Grass cover, Good, HSG C
411	89	Gravel sidewalk, HSG C
8,985	75	Weighted Average
8,713		96.97% Pervious Area
272		3.03% Impervious Area
272		100.00% Unconnected

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
9.4	50	0.0142	0.09		Sheet Flow, Grass: Dense n= 0.240 P2= 3.23"
0.9	97	0.0154	1.86		Shallow Concentrated Flow, Grassed Waterway Kv= 15.0 fps
10.3	147				Total

Subcatchment 3.1S: Backyard ADs



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=8.30"

Printed 12/17/2024

Page 81

Summary for Subcatchment 3S: Townhouse Roofs


Runoff = 2.4 cfs @ 12.08 hrs, Volume= 8,777 cf, Depth= 8.06"
Routed to Pond 1P : Inf Syst-1

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 25-Year Rainfall=8.30"

Table with 3 columns: Area (sf), CN, Description. Row 1: 13,067, 98, Roofs, HSG C. Row 2: 13,067, 100.00% Impervious Area.

Table with 6 columns: Tc (min), Length (feet), Slope (ft/ft), Velocity (ft/sec), Capacity (cfs), Description. Row 1: 6.0, Direct Entry, Min. Tc.

Subcatchment 3S: Townhouse Roofs



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=8.30"

Printed 12/17/2024

Page 82

Summary for Subcatchment 4.2S: TD-2


Runoff = 0.2 cfs @ 12.08 hrs, Volume= 736 cf, Depth= 7.94"
Routed to Pond 4P : Inf Syst-2

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 25-Year Rainfall=8.30"

Table with 3 columns: Area (sf), CN, Description. Row 1: 1,064, 98, Paved parking, HSG C. Row 2: 48, 74, >75% Grass cover, Good, HSG C. Row 3: 1,112, 97, Weighted Average. Row 4: 48, 4.32% Pervious Area. Row 5: 1,064, 95.68% Impervious Area.

Table with 6 columns: Tc (min), Length (feet), Slope (ft/ft), Velocity (ft/sec), Capacity (cfs), Description. Row 1: 6.0, Direct Entry, Min. Tc.

Subcatchment 4.2S: TD-2



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=8.30"

Printed 12/17/2024

Page 83

Summary for Subcatchment 4.3S: TD-3

Runoff = 0.2 cfs @ 12.08 hrs, Volume= 731 cf, Depth= 7.94"
Routed to Pond 5P : Inf Syst-3


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 25-Year Rainfall=8.30"

Area (sf)	CN	Description
1,075	98	Paved parking, HSG C
30	74	>75% Grass cover, Good, HSG C
1,105	97	Weighted Average
30		2.71% Pervious Area
1,075		97.29% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.3S: TD-3

Hydrograph



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=8.30"

Printed 12/17/2024

Page 84

Summary for Subcatchment 4.4S: TD-4

Runoff = 0.2 cfs @ 12.08 hrs, Volume= 730 cf, Depth= 7.94"
Routed to Pond 6P : Inf Syst-4


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 25-Year Rainfall=8.30"

Area (sf)	CN	Description
1,076	98	Paved parking, HSG C
28	74	>75% Grass cover, Good, HSG C
1,104	97	Weighted Average
28		2.54% Pervious Area
1,076		97.46% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.4S: TD-4

Hydrograph



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=8.30"

Printed 12/17/2024

Page 85

Summary for Subcatchment 4.5S: TD-5

Runoff = 0.2 cfs @ 12.08 hrs, Volume= 727 cf, Depth= 8.06"
Routed to Pond 7P : Inf Syst-5


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 25-Year Rainfall=8.30"

Area (sf)	CN	Description
1,061	98	Paved parking, HSG C
21	74	>75% Grass cover, Good, HSG C
1,082	98	Weighted Average
21		1.94% Pervious Area
1,061		98.06% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.5S: TD-5

Hydrograph



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=8.30"

Printed 12/17/2024

Page 86

Summary for Subcatchment 4.6S: TD-6

Runoff = 0.2 cfs @ 12.08 hrs, Volume= 709 cf, Depth= 8.06"
Routed to Pond 8P : Inf Syst-6


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 25-Year Rainfall=8.30"

Area (sf)	CN	Description
1,048	98	Paved parking, HSG C
8	74	>75% Grass cover, Good, HSG C
1,056	98	Weighted Average
8		0.76% Pervious Area
1,048		99.24% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.6S: TD-6

Hydrograph



Summary for Subcatchment 5.1S: TD-1A

Runoff = 0.3 cfs @ 12.08 hrs, Volume= 877 cf, Depth= 7.58"
 Routed to Pond 9P : Inf Syst-7


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 25-Year Rainfall=8.30"

Area (sf)	CN	Description
1,175	98	Paved parking, HSG C
214	74	>75% Grass cover, Good, HSG C
1,389	94	Weighted Average
214		15.41% Pervious Area
1,175		84.59% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 5.1S: TD-1A

Hydrograph



Summary for Subcatchment 5S: TD-1B

Runoff = 0.7 cfs @ 12.09 hrs, Volume= 2,374 cf, Depth= 6.38"
 Routed to Link 1L : Towards Wetlands


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 25-Year Rainfall=8.30"

Area (sf)	CN	Description
1,909	98	Paved parking, HSG C
2,553	74	>75% Grass cover, Good, HSG C
4,462	84	Weighted Average
2,553		57.22% Pervious Area
1,909		42.78% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 5S: TD-1B

Hydrograph



Summary for Subcatchment 6.1S: East driveway

Runoff = 2.1 cfs @ 12.08 hrs, Volume= 6,897 cf, Depth= 6.74"
 Routed to Pond 3P : Rain garden


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 25-Year Rainfall=8.30"

Area (sf)	CN	Description
5,611	74	>75% Grass cover, Good, HSG C
6,444	98	Paved roads w/curbs & sewers, HSG C
220	89	Gravel roads, HSG C
12,275	87	Weighted Average
5,831		47.50% Pervious Area
6,444		52.50% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

Subcatchment 6.1S: East driveway

Hydrograph



Summary for Subcatchment 6S: Bypass Towards Wetlands

Runoff = 5.6 cfs @ 12.19 hrs, Volume= 22,311 cf, Depth= 5.19"
 Routed to Link 1L : Towards Wetlands


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 25-Year Rainfall=8.30"

Area (sf)	CN	Description
4,985	70	Woods, Good, HSG C
46,447	74	>75% Grass cover, Good, HSG C
107	98	Roofs, HSG C
51,539	74	Weighted Average
51,432		99.79% Pervious Area
107		0.21% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.8	50	0.0220	0.07		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.23"
2.2	75	0.0133	0.58		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
14.0	125	Total			

Subcatchment 6S: Bypass Towards Wetlands

Hydrograph



Summary for Subcatchment 7S: To Street

Runoff = 0.9 cfs @ 12.09 hrs, Volume= 2,760 cf, Depth= 5.67"
 Routed to Link 2L : Towards Street


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 25-Year Rainfall=8.30"

Area (sf)	CN	Description
1,056	98	Paved parking, HSG C
4,787	74	>75% Grass cover, Good, HSG C
5,843	78	Weighted Average
4,787		81.93% Pervious Area
1,056		18.07% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 7S: To Street

Hydrograph



Summary for Pond 1P: Inf Syst-1

Inflow Area = 60,436 sf, 85.36% Impervious, Inflow Depth = 7.48" for 25-Year event
 Inflow = 10.6 cfs @ 12.09 hrs, Volume= 37,649 cf
 Outflow = 4.2 cfs @ 12.32 hrs, Volume= 37,649 cf, Atten= 60%, Lag= 14.1 min
 Discarded = 0.1 cfs @ 4.33 hrs, Volume= 14,969 cf
 Primary = 4.1 cfs @ 12.32 hrs, Volume= 22,680 cf
 Routed to Link 1L : Towards Wetlands

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 10.41' @ 12.32 hrs Surf.Area= 7,459 sf Storage= 15,470 cf

Plug-Flow detention time= 354.1 min calculated for 37,649 cf (100% of inflow)
 Center-of-Mass det. time= 354.1 min (1,107.3 - 753.2)

Volume	Invert	Avail.Storage	Storage Description
#1	8.00'	19,245 cf	6.89'W x 14.06'L x 3.00'H StormTrap ST-1 Units (Irregular Shape) 77 22,378 cf Overall x 86.0% Voids


Device	Routing	Invert	Outlet Devices
#1	Discarded	8.00'	0.520 in/hr Exfiltration over Surface area
#2	Primary	8.00'	15.0" Round Culvert L= 26.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 8.00' / 7.13' S= 0.0335 '/ Cc= 0.900 n= 0.013, Flow Area= 1.23 sf
#3	Device 2	9.22'	22.0" W x 4.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 2	10.05'	20.0" W x 4.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 2	10.79'	3.7' long Sharp-Crested Rectangular Weir 2 End Contraction(s)

Discarded OutFlow Max=0.1 cfs @ 4.33 hrs HW=8.03' (Free Discharge)
 1=Exfiltration (Exfiltration Controls 0.1 cfs)

Primary OutFlow Max=4.1 cfs @ 12.32 hrs HW=10.41' (Free Discharge)
 2=Culvert (Passes 4.1 cfs of 7.9 cfs potential flow)
 3=Orifice/Grate (Orifice Controls 3.0 cfs @ 4.87 fps)
 4=Orifice/Grate (Orifice Controls 1.1 cfs @ 2.05 fps)
 5=Sharp-Crested Rectangular Weir (Controls 0.0 cfs)

Pond 1P: Inf Syst-1

Hydrograph



Summary for Pond 3P: Rain garden

Inflow Area = 12,275 sf, 52.50% Impervious, Inflow Depth = 6.74" for 25-Year event
 Inflow = 2.1 cfs @ 12.08 hrs, Volume= 6,897 cf
 Outflow = 2.1 cfs @ 12.09 hrs, Volume= 6,897 cf, Atten= 0%, Lag= 0.3 min
 Discarded = 0.0 cfs @ 12.09 hrs, Volume= 495 cf
 Primary = 2.1 cfs @ 12.09 hrs, Volume= 6,401 cf
 Routed to Link 1L : Towards Wetlands

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 6.47' @ 12.09 hrs Surf.Area= 442 sf Storage= 239 cf

Plug-Flow detention time= 40.9 min calculated for 6,896 cf (100% of inflow)
 Center-of-Mass det. time= 41.0 min (824.8 - 783.8)

Volume	Invert	Avail.Storage	Storage Description		
#1	5.60'	253 cf	Custom Stage Data (Irregular) Listed below (Recalc)		
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
5.60	125	46.0	0	0	125
6.00	276	66.0	78	78	305
6.30	350	73.0	94	172	385
6.50	460	87.0	81	253	564


Device	Routing	Invert	Outlet Devices
#1	Discarded	5.60'	0.520 in/hr Exfiltration over Surface area
#2	Primary	6.35'	22.0' long x 5.0' breadth Broad-Crested Rectangular Weir
			Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00
			2.50 3.00 3.50 4.00 4.50 5.00 5.50
			Coef. (English) 2.34 2.50 2.70 2.68 2.68 2.66 2.65 2.65 2.65
			2.65 2.67 2.66 2.68 2.70 2.74 2.79 2.88

Discarded OutFlow Max=0.0 cfs @ 12.09 hrs HW=6.47' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=2.1 cfs @ 12.09 hrs HW=6.47' (Free Discharge)
 ↳2=Broad-Crested Rectangular Weir (Weir Controls 2.1 cfs @ 0.81 fps)

Pond 3P: Rain garden

Hydrograph



Summary for Pond 4P: Inf Syst-2

Inflow Area = 1,112 sf, 95.68% Impervious, Inflow Depth = 7.94" for 25-Year event
 Inflow = 0.2 cfs @ 12.08 hrs, Volume= 736 cf
 Outflow = 0.2 cfs @ 12.09 hrs, Volume= 722 cf, Atten= 1%, Lag= 0.5 min
 Discarded = 0.0 cfs @ 2.05 hrs, Volume= 160 cf
 Primary = 0.2 cfs @ 12.09 hrs, Volume= 562 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.51' @ 12.09 hrs Surf.Area= 101 sf Storage= 133 cf

Plug-Flow detention time= 377.3 min calculated for 722 cf (98% of inflow)
 Center-of-Mass det. time= 365.7 min (1,112.2 - 746.5)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	84 cf	7.28'W x 13.84'L x 2.72'H Field A 274 cf Overall - 64 cf Embedded = 210 cf x 40.0% Voids
#2A	7.25'	57 cf	Ferguson R-Tank XD 12 x 10 Inside #1 Inside= 19.7"W x 23.6"H => 2.91 sf x 1.97'L = 5.7 cf Outside= 19.7"W x 23.6"H => 3.23 sf x 1.97'L = 6.4 cf 10 Chambers in 2 Rows
		141 cf	Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.23'	6.0" Round Culvert L= 33.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.23' / 8.72' S= 0.0155 '/ Cc= 0.900 n= 0.013, Flow Area= 0.20 sf

Discarded OutFlow Max=0.0 cfs @ 2.05 hrs HW=7.03' (Free Discharge)
 ↑1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.2 cfs @ 12.09 hrs HW=9.51' (Free Discharge)
 ↑2=Culvert (Inlet Controls 0.2 cfs @ 1.81 fps)

Pond 4P: Inf Syst-2

Hydrograph



Summary for Pond 5P: Inf Syst-3

Inflow Area = 1,105 sf, 97.29% Impervious, Inflow Depth = 7.94" for 25-Year event
 Inflow = 0.2 cfs @ 12.08 hrs, Volume= 731 cf
 Outflow = 0.2 cfs @ 12.09 hrs, Volume= 712 cf, Atten= 1%, Lag= 0.5 min
 Discarded = 0.0 cfs @ 2.08 hrs, Volume= 160 cf
 Primary = 0.2 cfs @ 12.09 hrs, Volume= 552 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.65' @ 12.09 hrs Surf.Area= 101 sf Storage= 139 cf

Plug-Flow detention time= 388.2 min calculated for 712 cf (97% of inflow)
 Center-of-Mass det. time= 371.5 min (1,118.0 - 746.5)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	84 cf	7.28'W x 13.84'L x 2.72'H Field A 274 cf Overall - 64 cf Embedded = 210 cf x 40.0% Voids
#2A	7.25'	57 cf	Ferguson R-Tank XD 12 x 10 Inside #1 Inside= 19.7"W x 23.6"H => 2.91 sf x 1.97'L = 5.7 cf Outside= 19.7"W x 23.6"H => 3.23 sf x 1.97'L = 6.4 cf 10 Chambers in 2 Rows
		141 cf	Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.37'	6.0" Round Culvert L= 33.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.37' / 8.73' S= 0.0194 '/ S= 0.0194 '/ Cc= 0.900 n= 0.013, Flow Area= 0.20 sf

Discarded OutFlow Max=0.0 cfs @ 2.08 hrs HW=7.03' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.2 cfs @ 12.09 hrs HW=9.65' (Free Discharge)
 ↳2=Culvert (Inlet Controls 0.2 cfs @ 1.80 fps)

Pond 5P: Inf Syst-3

Hydrograph



Summary for Pond 6P: Inf Syst-4

Inflow Area = 1,104 sf, 97.46% Impervious, Inflow Depth = 7.94" for 25-Year event
 Inflow = 0.2 cfs @ 12.08 hrs, Volume= 730 cf
 Outflow = 0.2 cfs @ 12.09 hrs, Volume= 711 cf, Atten= 1%, Lag= 0.5 min
 Discarded = 0.0 cfs @ 2.08 hrs, Volume= 160 cf
 Primary = 0.2 cfs @ 12.09 hrs, Volume= 552 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.65' @ 12.09 hrs Surf.Area= 101 sf Storage= 139 cf

Plug-Flow detention time= 388.1 min calculated for 711 cf (97% of inflow)
 Center-of-Mass det. time= 371.8 min (1,118.4 - 746.5)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	84 cf	7.28'W x 13.84'L x 2.72'H Field A 274 cf Overall - 64 cf Embedded = 210 cf x 40.0% Voids
#2A	7.25'	57 cf	Ferguson R-Tank XD 12 x 10 Inside #1 Inside= 19.7"W x 23.6"H => 2.91 sf x 1.97'L = 5.7 cf Outside= 19.7"W x 23.6"H => 3.23 sf x 1.97'L = 6.4 cf 10 Chambers in 2 Rows
		141 cf	Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.37'	6.0" Round Culvert L= 51.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.37' / 8.10' S= 0.0249 '/ Cc= 0.900 n= 0.013, Flow Area= 0.20 sf

Discarded OutFlow Max=0.0 cfs @ 2.08 hrs HW=7.03' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.2 cfs @ 12.09 hrs HW=9.65' (Free Discharge)
 ↳2=Culvert (Inlet Controls 0.2 cfs @ 1.80 fps)

Pond 6P: Inf Syst-4

Hydrograph



Summary for Pond 7P: Inf Syst-5

Inflow Area = 1,082 sf, 98.06% Impervious, Inflow Depth = 8.06" for 25-Year event
 Inflow = 0.2 cfs @ 12.08 hrs, Volume= 727 cf
 Outflow = 0.2 cfs @ 12.09 hrs, Volume= 726 cf, Atten= 1%, Lag= 0.5 min
 Discarded = 0.0 cfs @ 1.52 hrs, Volume= 161 cf
 Primary = 0.2 cfs @ 12.09 hrs, Volume= 565 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.28' @ 12.09 hrs Surf.Area= 101 sf Storage= 121 cf

Plug-Flow detention time= 365.7 min calculated for 726 cf (100% of inflow)
 Center-of-Mass det. time= 365.2 min (1,106.0 - 740.8)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	73 cf	7.28'W x 13.84'L x 2.39'H Field A 241 cf Overall - 58 cf Embedded = 182 cf x 40.0% Voids
#2A	7.25'	52 cf	Ferguson R-Tank XD 11 x 10 Inside #1 Inside= 19.7"W x 21.7"H => 2.66 sf x 1.97'L = 5.2 cf Outside= 19.7"W x 21.7"H => 2.96 sf x 1.97'L = 5.8 cf 10 Chambers in 2 Rows
		125 cf	Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.00'	6.0" Round Culvert L= 48.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.00' / 8.35' S= 0.0135 '/ Cc= 0.900 n= 0.013, Flow Area= 0.20 sf

Discarded OutFlow Max=0.0 cfs @ 1.52 hrs HW=7.03' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.2 cfs @ 12.09 hrs HW=9.28' (Free Discharge)
 ↳2=Culvert (Inlet Controls 0.2 cfs @ 1.79 fps)

Pond 7P: Inf Syst-5

Hydrograph



Summary for Pond 8P: Inf Syst-6

Inflow Area = 1,056 sf, 99.24% Impervious, Inflow Depth = 8.06" for 25-Year event
 Inflow = 0.2 cfs @ 12.08 hrs, Volume= 709 cf
 Outflow = 0.2 cfs @ 12.09 hrs, Volume= 708 cf, Atten= 1%, Lag= 0.6 min
 Discarded = 0.0 cfs @ 1.56 hrs, Volume= 161 cf
 Primary = 0.2 cfs @ 12.09 hrs, Volume= 548 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.29' @ 12.09 hrs Surf.Area= 101 sf Storage= 122 cf

Plug-Flow detention time= 374.4 min calculated for 708 cf (100% of inflow)
 Center-of-Mass det. time= 373.8 min (1,114.6 - 740.8)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	73 cf	7.28'W x 13.84'L x 2.39'H Field A 241 cf Overall - 58 cf Embedded = 182 cf x 40.0% Voids
#2A	7.25'	52 cf	Ferguson R-Tank XD 11 x 10 Inside #1 Inside= 19.7"W x 21.7"H => 2.66 sf x 1.97'L = 5.2 cf Outside= 19.7"W x 21.7"H => 2.96 sf x 1.97'L = 5.8 cf 10 Chambers in 2 Rows
		125 cf	Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.00'	8.0" Round Culvert L= 46.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.00' / 8.77' S= 0.0050 '/ S= 0.0050 '/ Cc= 0.900 n= 0.013, Flow Area= 0.35 sf

Discarded OutFlow Max=0.0 cfs @ 1.56 hrs HW=7.03' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.2 cfs @ 12.09 hrs HW=9.29' (Free Discharge)
 ↳2=Culvert (Barrel Controls 0.2 cfs @ 1.94 fps)

Pond 8P: Inf Syst-6

Hydrograph



Summary for Pond 9P: Inf Syst-7

Inflow Area = 24,131 sf, 72.87% Impervious, Inflow Depth = 7.24" for 25-Year event
 Inflow = 4.3 cfs @ 12.08 hrs, Volume= 14,562 cf
 Outflow = 2.7 cfs @ 12.18 hrs, Volume= 14,562 cf, Atten= 37%, Lag= 5.7 min
 Discarded = 0.0 cfs @ 4.62 hrs, Volume= 1,561 cf
 Primary = 2.7 cfs @ 12.18 hrs, Volume= 13,001 cf
 Routed to Link 1L : Towards Wetlands

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 8.38" @ 12.18 hrs Surf.Area= 2,422 sf Storage= 2,562 cf

Plug-Flow detention time= 53.2 min calculated for 14,562 cf (100% of inflow)
 Center-of-Mass det. time= 53.1 min (824.0 - 770.9)

Volume	Invert	Avail.Storage	Storage Description
#1	7.15'	3,645 cf	6.89'W x 14.06'L x 1.75'H StormTrap ST-1 Units (Irregular Shape) 25 4,238 cf Overall x 86.0% Voids


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.15'	0.270 in/hr Exfiltration over Surface area
#2	Primary	7.15'	12.0" Round Culvert L= 4.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 7.15' / 7.13' S= 0.0050 '/ Cc= 0.900 n= 0.013, Flow Area= 0.79 sf
#3	Device 2	7.35'	22.0" W x 4.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

Discarded OutFlow Max=0.0 cfs @ 4.62 hrs HW=7.17' (Free Discharge)
 1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=2.7 cfs @ 12.18 hrs HW=8.38' (Free Discharge)
 2=Culvert (Passes 2.7 cfs of 2.7 cfs potential flow)
 3=Orifice/Grate (Orifice Controls 2.7 cfs @ 4.47 fps)

Pond 9P: Inf Syst-7

Hydrograph




Summary for Link 1L: Towards Wetlands

Inflow Area = 152,843 sf, 50.79% Impervious, Inflow Depth = 5.24" for 25-Year event
 Inflow = 13.7 cfs @ 12.18 hrs, Volume= 66,767 cf
 Primary = 13.7 cfs @ 12.18 hrs, Volume= 66,767 cf, Atten= 0%, Lag= 0.0 min
 Routed to Link 100L : Total Flows

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link 1L: Towards Wetlands

Hydrograph




Summary for Link 2L: Towards Street

Inflow Area = 5,843 sf, 18.07% Impervious, Inflow Depth = 5.67" for 25-Year event
Inflow = 0.9 cfs @ 12.09 hrs, Volume= 2,760 cf
Primary = 0.9 cfs @ 12.09 hrs, Volume= 2,760 cf, Atten= 0%, Lag= 0.0 min
Routed to Link 100L : Total Flows

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link 2L: Towards Street

Hydrograph




Summary for Link 100L: Total Flows

Inflow Area = 158,686 sf, 49.59% Impervious, Inflow Depth = 5.26" for 25-Year event
Inflow = 14.2 cfs @ 12.18 hrs, Volume= 69,527 cf
Primary = 14.2 cfs @ 12.18 hrs, Volume= 69,527 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link 100L: Total Flows

Hydrograph



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 50-Year Rainfall=9.67"

Printed 12/17/2024

Page 111

Time span=0.00-72.00 hrs, dt=0.01 hrs, 7201 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment1S: CB-1	Runoff Area=22,742 sf 72.16% Impervious Runoff Depth=8.58" Tc=6.0 min CN=91 Runoff=4.8 cfs 16,254 cf
Subcatchment2S: Building Roof	Runoff Area=32,925 sf 100.00% Impervious Runoff Depth=9.43" Tc=6.0 min CN=98 Runoff=7.2 cfs 25,872 cf
Subcatchment3.1S: Backyard ADs	Runoff Area=8,985 sf 3.03% Impervious Runoff Depth=6.57" Flow Length=147' Tc=10.3 min CN=75 Runoff=1.4 cfs 4,920 cf
Subcatchment3S: Townhouse Roofs	Runoff Area=13,067 sf 100.00% Impervious Runoff Depth=9.43" Tc=6.0 min CN=98 Runoff=2.9 cfs 10,268 cf
Subcatchment4.2S: TD-2	Runoff Area=1,112 sf 95.68% Impervious Runoff Depth=9.31" Tc=6.0 min CN=97 Runoff=0.2 cfs 863 cf
Subcatchment4.3S: TD-3	Runoff Area=1,105 sf 97.29% Impervious Runoff Depth=9.31" Tc=6.0 min CN=97 Runoff=0.2 cfs 857 cf
Subcatchment4.4S: TD-4	Runoff Area=1,104 sf 97.46% Impervious Runoff Depth=9.31" Tc=6.0 min CN=97 Runoff=0.2 cfs 856 cf
Subcatchment4.5S: TD-5	Runoff Area=1,082 sf 98.06% Impervious Runoff Depth=9.43" Tc=6.0 min CN=98 Runoff=0.2 cfs 850 cf
Subcatchment4.6S: TD-6	Runoff Area=1,056 sf 99.24% Impervious Runoff Depth=9.43" Tc=6.0 min CN=98 Runoff=0.2 cfs 830 cf
Subcatchment5.1S: TD-1A	Runoff Area=1,389 sf 84.59% Impervious Runoff Depth=8.94" Tc=6.0 min CN=94 Runoff=0.3 cfs 1,035 cf
Subcatchment5S: TD-1B	Runoff Area=4,462 sf 42.78% Impervious Runoff Depth=7.71" Tc=6.0 min CN=84 Runoff=0.9 cfs 2,866 cf
Subcatchment6.1S: East driveway	Runoff Area=12,275 sf 52.50% Impervious Runoff Depth=8.08" Tc=6.0 min CN=87 Runoff=2.5 cfs 8,268 cf
Subcatchment6S: Bypass Towards	Runoff Area=51,539 sf 0.21% Impervious Runoff Depth=6.44" Flow Length=125' Tc=14.0 min CN=74 Runoff=6.9 cfs 27,672 cf
Subcatchment7S: To Street	Runoff Area=5,843 sf 18.07% Impervious Runoff Depth=6.95" Tc=6.0 min CN=78 Runoff=1.1 cfs 3,385 cf
Pond 1P: Inf Syst-1	Peak Elev=10.70' Storage=17,296 cf Inflow=12.4 cfs 44,458 cf Discarded=0.1 cfs 15,169 cf Primary=5.2 cfs 29,289 cf Outflow=5.3 cfs 44,458 cf
Pond 3P: Rain garden	Peak Elev=6.48' Storage=245 cf Inflow=2.5 cfs 8,268 cf Discarded=0.0 cfs 506 cf Primary=2.5 cfs 7,762 cf Outflow=2.5 cfs 8,268 cf

2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 50-Year Rainfall=9.67"

Printed 12/17/2024

Page 112

Pond 4P: Inf Syst-2	Peak Elev=9.54' Storage=134 cf Inflow=0.2 cfs 863 cf Discarded=0.0 cfs 160 cf Primary=0.2 cfs 689 cf Outflow=0.2 cfs 849 cf
Pond 5P: Inf Syst-3	Peak Elev=9.68' Storage=140 cf Inflow=0.2 cfs 857 cf Discarded=0.0 cfs 160 cf Primary=0.2 cfs 678 cf Outflow=0.2 cfs 838 cf
Pond 6P: Inf Syst-4	Peak Elev=9.68' Storage=140 cf Inflow=0.2 cfs 856 cf Discarded=0.0 cfs 160 cf Primary=0.2 cfs 677 cf Outflow=0.2 cfs 837 cf
Pond 7P: Inf Syst-5	Peak Elev=9.30' Storage=122 cf Inflow=0.2 cfs 850 cf Discarded=0.0 cfs 161 cf Primary=0.2 cfs 688 cf Outflow=0.2 cfs 849 cf
Pond 8P: Inf Syst-6	Peak Elev=9.32' Storage=123 cf Inflow=0.2 cfs 830 cf Discarded=0.0 cfs 161 cf Primary=0.2 cfs 668 cf Outflow=0.2 cfs 829 cf
Pond 9P: Inf Syst-7	Peak Elev=8.58' Storage=2,968 cf Inflow=5.1 cfs 17,290 cf Discarded=0.0 cfs 1,591 cf Primary=3.0 cfs 15,699 cf Outflow=3.0 cfs 17,290 cf
Link 1L: Towards Wetlands	Inflow=17.0 cfs 83,287 cf Primary=17.0 cfs 83,287 cf
Link 2L: Towards Street	Inflow=1.1 cfs 3,385 cf Primary=1.1 cfs 3,385 cf
Link 100L: Total Flows	Inflow=17.8 cfs 86,673 cf Primary=17.8 cfs 86,673 cf

Total Runoff Area = 158,686 sf Runoff Volume = 104,796 cf Average Runoff Depth = 7.92"
50.41% Pervious = 79,997 sf 49.59% Impervious = 78,689 sf

2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 50-Year Rainfall=9.67"

Printed 12/17/2024

Page 113

Summary for Subcatchment 1S: CB-1

Runoff = 4.8 cfs @ 12.08 hrs, Volume= 16,254 cf, Depth= 8.58"
Routed to Pond 9P : Inf Syst-7


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 50-Year Rainfall=9.67"

Area (sf)	CN	Description
16,410	98	Paved parking, HSG C
6,332	74	>75% Grass cover, Good, HSG C
22,742	91	Weighted Average
6,332		27.84% Pervious Area
16,410		72.16% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 1S: CB-1

Hydrograph



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 50-Year Rainfall=9.67"

Printed 12/17/2024

Page 114

Summary for Subcatchment 2S: Building Roof

Runoff = 7.2 cfs @ 12.08 hrs, Volume= 25,872 cf, Depth= 9.43"
Routed to Pond 1P : Inf Syst-1


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 50-Year Rainfall=9.67"

Area (sf)	CN	Description
32,925	98	Roofs, HSG C
32,925		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 2S: Building Roof

Hydrograph



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 50-Year Rainfall=9.67"

Printed 12/17/2024

Page 115

Summary for Subcatchment 3.1S: Backyard ADs

Runoff = 1.4 cfs @ 12.14 hrs, Volume= 4,920 cf, Depth= 6.57"
Routed to Pond 1P : Inf Syst-1


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 50-Year Rainfall=9.67"

Area (sf)	CN	Description
272	98	Unconnected pavement, HSG C
8,302	74	>75% Grass cover, Good, HSG C
411	89	Gravel sidewalk, HSG C
8,985	75	Weighted Average
8,713		96.97% Pervious Area
272		3.03% Impervious Area
272		100.00% Unconnected

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
9.4	50	0.0142	0.09		Sheet Flow, Grass: Dense n= 0.240 P2= 3.23"
0.9	97	0.0154	1.86		Shallow Concentrated Flow, Grassed Waterway Kv= 15.0 fps
10.3	147	Total			

Subcatchment 3.1S: Backyard ADs

Hydrograph



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 50-Year Rainfall=9.67"

Printed 12/17/2024

Page 116

Summary for Subcatchment 3S: Townhouse Roofs

Runoff = 2.9 cfs @ 12.08 hrs, Volume= 10,268 cf, Depth= 9.43"
Routed to Pond 1P : Inf Syst-1


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 50-Year Rainfall=9.67"

Area (sf)	CN	Description
13,067	98	Roofs, HSG C
13,067		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 3S: Townhouse Roofs

Hydrograph



Summary for Subcatchment 4.2S: TD-2

Runoff = 0.2 cfs @ 12.08 hrs, Volume= 863 cf, Depth= 9.31"
 Routed to Pond 4P : Inf Syst-2


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 50-Year Rainfall=9.67"

Area (sf)	CN	Description
1,064	98	Paved parking, HSG C
48	74	>75% Grass cover, Good, HSG C
1,112	97	Weighted Average
48		4.32% Pervious Area
1,064		95.68% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.2S: TD-2

Hydrograph



Summary for Subcatchment 4.3S: TD-3

Runoff = 0.2 cfs @ 12.08 hrs, Volume= 857 cf, Depth= 9.31"
 Routed to Pond 5P : Inf Syst-3


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 50-Year Rainfall=9.67"

Area (sf)	CN	Description
1,075	98	Paved parking, HSG C
30	74	>75% Grass cover, Good, HSG C
1,105	97	Weighted Average
30		2.71% Pervious Area
1,075		97.29% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.3S: TD-3

Hydrograph



Summary for Subcatchment 4.4S: TD-4

Runoff = 0.2 cfs @ 12.08 hrs, Volume= 856 cf, Depth= 9.31"
 Routed to Pond 6P : Inf Syst-4


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 50-Year Rainfall=9.67"

Area (sf)	CN	Description
1,076	98	Paved parking, HSG C
28	74	>75% Grass cover, Good, HSG C
1,104	97	Weighted Average
28		2.54% Pervious Area
1,076		97.46% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.4S: TD-4

Hydrograph



Summary for Subcatchment 4.5S: TD-5

Runoff = 0.2 cfs @ 12.08 hrs, Volume= 850 cf, Depth= 9.43"
 Routed to Pond 7P : Inf Syst-5


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 50-Year Rainfall=9.67"

Area (sf)	CN	Description
1,061	98	Paved parking, HSG C
21	74	>75% Grass cover, Good, HSG C
1,082	98	Weighted Average
21		1.94% Pervious Area
1,061		98.06% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.5S: TD-5

Hydrograph



Summary for Subcatchment 4.6S: TD-6

Runoff = 0.2 cfs @ 12.08 hrs, Volume= 830 cf, Depth= 9.43"
 Routed to Pond 8P : Inf Syst-6


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 50-Year Rainfall=9.67"

Area (sf)	CN	Description
1,048	98	Paved parking, HSG C
8	74	>75% Grass cover, Good, HSG C
1,056	98	Weighted Average
8		0.76% Pervious Area
1,048		99.24% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.6S: TD-6

Hydrograph



Summary for Subcatchment 5.1S: TD-1A

Runoff = 0.3 cfs @ 12.08 hrs, Volume= 1,035 cf, Depth= 8.94"
 Routed to Pond 9P : Inf Syst-7


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 50-Year Rainfall=9.67"

Area (sf)	CN	Description
1,175	98	Paved parking, HSG C
214	74	>75% Grass cover, Good, HSG C
1,389	94	Weighted Average
214		15.41% Pervious Area
1,175		84.59% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 5.1S: TD-1A

Hydrograph



Summary for Subcatchment 5S: TD-1B

Runoff = 0.9 cfs @ 12.08 hrs, Volume= 2,866 cf, Depth= 7.71"
 Routed to Link 1L : Towards Wetlands


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 50-Year Rainfall=9.67"

Area (sf)	CN	Description
1,909	98	Paved parking, HSG C
2,553	74	>75% Grass cover, Good, HSG C
4,462	84	Weighted Average
2,553		57.22% Pervious Area
1,909		42.78% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 5S: TD-1B

Hydrograph



Summary for Subcatchment 6.1S: East driveway

Runoff = 2.5 cfs @ 12.08 hrs, Volume= 8,268 cf, Depth= 8.08"
 Routed to Pond 3P : Rain garden


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 50-Year Rainfall=9.67"

Area (sf)	CN	Description
5,611	74	>75% Grass cover, Good, HSG C
6,444	98	Paved roads w/curbs & sewers, HSG C
220	89	Gravel roads, HSG C
12,275	87	Weighted Average
5,831		47.50% Pervious Area
6,444		52.50% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

Subcatchment 6.1S: East driveway

Hydrograph



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 50-Year Rainfall=9.67"

Printed 12/17/2024

Page 125

Summary for Subcatchment 6S: Bypass Towards Wetlands

Runoff = 6.9 cfs @ 12.19 hrs, Volume= 27,672 cf, Depth= 6.44"
 Routed to Link 1L : Towards Wetlands


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 50-Year Rainfall=9.67"

Area (sf)	CN	Description
4,985	70	Woods, Good, HSG C
46,447	74	>75% Grass cover, Good, HSG C
107	98	Roofs, HSG C
51,539	74	Weighted Average
51,432		99.79% Pervious Area
107		0.21% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.8	50	0.0220	0.07		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.23"
2.2	75	0.0133	0.58		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
14.0	125	Total			

Subcatchment 6S: Bypass Towards Wetlands

Hydrograph



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 50-Year Rainfall=9.67"

Printed 12/17/2024

Page 126

Summary for Subcatchment 7S: To Street

Runoff = 1.1 cfs @ 12.09 hrs, Volume= 3,385 cf, Depth= 6.95"
 Routed to Link 2L : Towards Street


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 50-Year Rainfall=9.67"

Area (sf)	CN	Description
1,056	98	Paved parking, HSG C
4,787	74	>75% Grass cover, Good, HSG C
5,843	78	Weighted Average
4,787		81.93% Pervious Area
1,056		18.07% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 7S: To Street

Hydrograph



Summary for Pond 1P: Inf Syst-1

Inflow Area = 60,436 sf, 85.36% Impervious, Inflow Depth = 8.83" for 50-Year event
 Inflow = 12.4 cfs @ 12.09 hrs, Volume= 44,458 cf
 Outflow = 5.3 cfs @ 12.30 hrs, Volume= 44,458 cf, Atten= 57%, Lag= 12.5 min
 Discarded = 0.1 cfs @ 3.50 hrs, Volume= 15,169 cf
 Primary = 5.2 cfs @ 12.30 hrs, Volume= 29,289 cf
 Routed to Link 1L : Towards Wetlands

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 10.70' @ 12.30 hrs Surf.Area= 7,459 sf Storage= 17,296 cf

Plug-Flow detention time= 312.6 min calculated for 44,458 cf (100% of inflow)
 Center-of-Mass det. time= 312.5 min (1,063.8 - 751.2)

Volume	Invert	Avail.Storage	Storage Description
#1	8.00'	19,245 cf	6.89'W x 14.06'L x 3.00'H StormTrap ST-1 Units (Irregular Shape) 22,378 cf Overall x 86.0% Voids


Device	Routing	Invert	Outlet Devices
#1	Discarded	8.00'	0.520 in/hr Exfiltration over Surface area
#2	Primary	8.00'	15.0" Round Culvert L= 26.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 8.00' / 7.13' S= 0.0335' /' Cc= 0.900 n= 0.013, Flow Area= 1.23 sf
#3	Device 2	9.22'	22.0" W x 4.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 2	10.05'	20.0" W x 4.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 2	10.79'	3.7' long Sharp-Crested Rectangular Weir 2 End Contraction(s)

Discarded OutFlow Max=0.1 cfs @ 3.50 hrs HW=8.03' (Free Discharge)
 ↳ **1=Exfiltration** (Exfiltration Controls 0.1 cfs)

Primary OutFlow Max=5.2 cfs @ 12.30 hrs HW=10.70' (Free Discharge)
 ↳ **2=Culvert** (Passes 5.2 cfs of 8.5 cfs potential flow)
 ↳ **3=Orifice/Grate** (Orifice Controls 3.4 cfs @ 5.51 fps)
 ↳ **4=Orifice/Grate** (Orifice Controls 1.8 cfs @ 3.32 fps)
 ↳ **5=Sharp-Crested Rectangular Weir** (Controls 0.0 cfs)

Pond 1P: Inf Syst-1

Hydrograph



Summary for Pond 3P: Rain garden

Inflow Area = 12,275 sf, 52.50% Impervious, Inflow Depth = 8.08" for 50-Year event
 Inflow = 2.5 cfs @ 12.08 hrs, Volume= 8,268 cf
 Outflow = 2.5 cfs @ 12.09 hrs, Volume= 8,268 cf, Atten= 0%, Lag= 0.3 min
 Discarded = 0.0 cfs @ 12.09 hrs, Volume= 506 cf
 Primary = 2.5 cfs @ 12.09 hrs, Volume= 7,762 cf
 Routed to Link 1L : Towards Wetlands

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 6.48' @ 12.09 hrs Surf.Area= 450 sf Storage= 245 cf

Plug-Flow detention time= 35.3 min calculated for 8,268 cf (100% of inflow)
 Center-of-Mass det. time= 35.2 min (814.3 - 779.1)

Volume	Invert	Avail.Storage	Storage Description		
#1	5.60'	253 cf	Custom Stage Data (Irregular) Listed below (Recalc)		
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
5.60	125	46.0	0	0	125
6.00	276	66.0	78	78	305
6.30	350	73.0	94	172	385
6.50	460	87.0	81	253	564


Device	Routing	Invert	Outlet Devices
#1	Discarded	5.60'	0.520 in/hr Exfiltration over Surface area
#2	Primary	6.35'	22.0' long x 5.0' breadth Broad-Crested Rectangular Weir
Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00			
2.50 3.00 3.50 4.00 4.50 5.00 5.50			
Coef. (English) 2.34 2.50 2.70 2.68 2.68 2.66 2.65 2.65 2.65			
2.65 2.67 2.66 2.68 2.70 2.74 2.79 2.88			

Discarded OutFlow Max=0.0 cfs @ 12.09 hrs HW=6.48' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=2.5 cfs @ 12.09 hrs HW=6.48' (Free Discharge)
 ↳2=Broad-Crested Rectangular Weir (Weir Controls 2.5 cfs @ 0.85 fps)

Pond 3P: Rain garden

Hydrograph



Summary for Pond 4P: Inf Syst-2

Inflow Area = 1,112 sf, 95.68% Impervious, Inflow Depth = 9.31" for 50-Year event
 Inflow = 0.2 cfs @ 12.08 hrs, Volume= 863 cf
 Outflow = 0.2 cfs @ 12.09 hrs, Volume= 849 cf, Atten= 1%, Lag= 0.5 min
 Discarded = 0.0 cfs @ 1.70 hrs, Volume= 160 cf
 Primary = 0.2 cfs @ 12.09 hrs, Volume= 689 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.54' @ 12.09 hrs Surf.Area= 101 sf Storage= 134 cf

Plug-Flow detention time= 326.9 min calculated for 849 cf (98% of inflow)
 Center-of-Mass det. time= 316.9 min (1,061.1 - 744.2)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	84 cf	7.28'W x 13.84'L x 2.72'H Field A 274 cf Overall - 64 cf Embedded = 210 cf x 40.0% Voids
#2A	7.25'	57 cf	Ferguson R-Tank XD 12 x 10 Inside #1 Inside= 19.7"W x 23.6"H => 2.91 sf x 1.97'L = 5.7 cf Outside= 19.7"W x 23.6"H => 3.23 sf x 1.97'L = 6.4 cf 10 Chambers in 2 Rows
		141 cf	Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.23'	6.0" Round Culvert L= 33.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.23' / 8.72' S= 0.0155 '/ Cc= 0.900 n= 0.013, Flow Area= 0.20 sf

Discarded OutFlow Max=0.0 cfs @ 1.70 hrs HW=7.03' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.2 cfs @ 12.09 hrs HW=9.54' (Free Discharge)
 ↳2=Culvert (Inlet Controls 0.2 cfs @ 1.89 fps)

Pond 4P: Inf Syst-2

Hydrograph



Summary for Pond 5P: Inf Syst-3

Inflow Area = 1,105 sf, 97.29% Impervious, Inflow Depth = 9.31" for 50-Year event
 Inflow = 0.2 cfs @ 12.08 hrs, Volume= 857 cf
 Outflow = 0.2 cfs @ 12.09 hrs, Volume= 838 cf, Atten= 1%, Lag= 0.5 min
 Discarded = 0.0 cfs @ 1.73 hrs, Volume= 160 cf
 Primary = 0.2 cfs @ 12.09 hrs, Volume= 678 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.68' @ 12.09 hrs Surf.Area= 101 sf Storage= 140 cf

Plug-Flow detention time= 335.8 min calculated for 838 cf (98% of inflow)
 Center-of-Mass det. time= 321.7 min (1,066.0 - 744.2)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	84 cf	7.28'W x 13.84'L x 2.72'H Field A 274 cf Overall - 64 cf Embedded = 210 cf x 40.0% Voids
#2A	7.25'	57 cf	Ferguson R-Tank XD 12 x 10 Inside #1 Inside= 19.7"W x 23.6"H => 2.91 sf x 1.97'L = 5.7 cf Outside= 19.7"W x 23.6"H => 3.23 sf x 1.97'L = 6.4 cf 10 Chambers in 2 Rows
		141 cf	Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.37'	6.0" Round Culvert L= 33.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.37' / 8.73' S= 0.0194 '/ Cc= 0.900 n= 0.013, Flow Area= 0.20 sf

Discarded OutFlow Max=0.0 cfs @ 1.73 hrs HW=7.03' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.2 cfs @ 12.09 hrs HW=9.68' (Free Discharge)
 ↳2=Culvert (Inlet Controls 0.2 cfs @ 1.89 fps)

Pond 5P: Inf Syst-3

Hydrograph



Summary for Pond 6P: Inf Syst-4

Inflow Area = 1,104 sf, 97.46% Impervious, Inflow Depth = 9.31" for 50-Year event
 Inflow = 0.2 cfs @ 12.08 hrs, Volume= 856 cf
 Outflow = 0.2 cfs @ 12.09 hrs, Volume= 837 cf, Atten= 1%, Lag= 0.5 min
 Discarded = 0.0 cfs @ 1.73 hrs, Volume= 160 cf
 Primary = 0.2 cfs @ 12.09 hrs, Volume= 677 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.68' @ 12.09 hrs Surf.Area= 101 sf Storage= 140 cf

Plug-Flow detention time= 336.1 min calculated for 837 cf (98% of inflow)
 Center-of-Mass det. time= 322.0 min (1,066.2 - 744.2)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	84 cf	7.28'W x 13.84'L x 2.72'H Field A 274 cf Overall - 64 cf Embedded = 210 cf x 40.0% Voids
#2A	7.25'	57 cf	Ferguson R-Tank XD 12 x 10 Inside #1 Inside= 19.7"W x 23.6"H => 2.91 sf x 1.97'L = 5.7 cf Outside= 19.7"W x 23.6"H => 3.23 sf x 1.97'L = 6.4 cf 10 Chambers in 2 Rows
		141 cf	Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.37'	6.0" Round Culvert L= 51.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.37' / 8.10' S= 0.0249 ' S= 0.0249 ' Cc= 0.900 n= 0.013, Flow Area= 0.20 sf

Discarded OutFlow Max=0.0 cfs @ 1.73 hrs HW=7.03' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.2 cfs @ 12.09 hrs HW=9.68' (Free Discharge)
 ↳2=Culvert (Inlet Controls 0.2 cfs @ 1.89 fps)

Pond 6P: Inf Syst-4

Hydrograph



Summary for Pond 7P: Inf Syst-5

Inflow Area = 1,082 sf, 98.06% Impervious, Inflow Depth = 9.43" for 50-Year event
 Inflow = 0.2 cfs @ 12.08 hrs, Volume= 850 cf
 Outflow = 0.2 cfs @ 12.09 hrs, Volume= 849 cf, Atten= 1%, Lag= 0.5 min
 Discarded = 0.0 cfs @ 1.27 hrs, Volume= 161 cf
 Primary = 0.2 cfs @ 12.09 hrs, Volume= 688 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.30' @ 12.09 hrs Surf.Area= 101 sf Storage= 122 cf

Plug-Flow detention time= 318.0 min calculated for 849 cf (100% of inflow)
 Center-of-Mass det. time= 317.6 min (1,056.6 - 739.0)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	73 cf	7.28'W x 13.84'L x 2.39'H Field A 241 cf Overall - 58 cf Embedded = 182 cf x 40.0% Voids
#2A	7.25'	52 cf	Ferguson R-Tank XD 11 x 10 Inside #1 Inside= 19.7"W x 21.7"H => 2.66 sf x 1.97'L = 5.2 cf Outside= 19.7"W x 21.7"H => 2.96 sf x 1.97'L = 5.8 cf 10 Chambers in 2 Rows
		125 cf	Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.00'	6.0" Round Culvert L= 48.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.00' / 8.35' S= 0.0135 '/ Cc= 0.900 n= 0.013, Flow Area= 0.20 sf

Discarded OutFlow Max=0.0 cfs @ 1.27 hrs HW=7.03' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.2 cfs @ 12.09 hrs HW=9.30' (Free Discharge)
 ↳2=Culvert (Inlet Controls 0.2 cfs @ 1.88 fps)

Pond 7P: Inf Syst-5

Hydrograph



Summary for Pond 8P: Inf Syst-6

Inflow Area = 1,056 sf, 99.24% Impervious, Inflow Depth = 9.43" for 50-Year event
 Inflow = 0.2 cfs @ 12.08 hrs, Volume= 830 cf
 Outflow = 0.2 cfs @ 12.09 hrs, Volume= 829 cf, Atten= 1%, Lag= 0.5 min
 Discarded = 0.0 cfs @ 1.30 hrs, Volume= 161 cf
 Primary = 0.2 cfs @ 12.09 hrs, Volume= 668 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.32' @ 12.09 hrs Surf.Area= 101 sf Storage= 123 cf

Plug-Flow detention time= 325.6 min calculated for 829 cf (100% of inflow)
 Center-of-Mass det. time= 325.0 min (1,064.0 - 739.0)

Volume	Invert	Avail. Storage	Storage Description
#1A	7.00'	73 cf	7.28'W x 13.84'L x 2.39'H Field A 241 cf Overall - 58 cf Embedded = 182 cf x 40.0% Voids
#2A	7.25'	52 cf	Ferguson R-Tank XD 11 x 10 Inside #1 Inside= 19.7"W x 21.7"H => 2.66 sf x 1.97'L = 5.2 cf Outside= 19.7"W x 21.7"H => 2.96 sf x 1.97'L = 5.8 cf 10 Chambers in 2 Rows
		125 cf	Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.00'	8.0" Round Culvert L= 46.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.00' / 8.77' S= 0.0050 '/ Cc= 0.900 n= 0.013, Flow Area= 0.35 sf

Discarded OutFlow Max=0.0 cfs @ 1.30 hrs HW=7.03' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.2 cfs @ 12.09 hrs HW=9.32' (Free Discharge)
 ↳2=Culvert (Barrel Controls 0.2 cfs @ 2.02 fps)

Pond 8P: Inf Syst-6

Hydrograph



Summary for Pond 9P: Inf Syst-7

Inflow Area = 24,131 sf, 72.87% Impervious, Inflow Depth = 8.60" for 50-Year event
 Inflow = 5.1 cfs @ 12.08 hrs, Volume= 17,290 cf
 Outflow = 3.0 cfs @ 12.19 hrs, Volume= 17,290 cf, Atten= 41%, Lag= 6.3 min
 Discarded = 0.0 cfs @ 4.01 hrs, Volume= 1,591 cf
 Primary = 3.0 cfs @ 12.19 hrs, Volume= 15,699 cf
 Routed to Link 1L : Towards Wetlands

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 8.58' @ 12.19 hrs Surf.Area= 2,422 sf Storage= 2,968 cf

Plug-Flow detention time= 48.3 min calculated for 17,290 cf (100% of inflow)
 Center-of-Mass det. time= 48.2 min (815.1 - 766.9)

Volume	Invert	Avail.Storage	Storage Description
#1	7.15'	3,645 cf	6.89'W x 14.06'L x 1.75'H StormTrap ST-1 Units (Irregular Shape) x 25 4,238 cf Overall x 86.0% Voids

Device	Routing	Invert	Outlet Devices
#1	Discarded	7.15'	0.270 in/hr Exfiltration over Surface area
#2	Primary	7.15'	12.0" Round Culvert L= 4.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 7.15' / 7.13' S= 0.0050 /' Cc= 0.900 n= 0.013, Flow Area= 0.79 sf
#3	Device 2	7.35'	22.0" W x 4.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

Discarded OutFlow Max=0.0 cfs @ 4.01 hrs HW=7.17' (Free Discharge)

↳ **1=Exfiltration** (Exfiltration Controls 0.0 cfs)


Primary OutFlow Max=3.0 cfs @ 12.19 hrs HW=8.58' (Free Discharge)

↳ **2=Culvert** (Passes 3.0 cfs of 3.3 cfs potential flow)

↳ **3=Orifice/Grate** (Orifice Controls 3.0 cfs @ 4.95 fps)

Pond 9P: Inf Syst-7

Hydrograph



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 50-Year Rainfall=9.67"

Printed 12/17/2024

Page 143


Summary for Link 1L: Towards Wetlands

Inflow Area = 152,843 sf, 50.79% Impervious, Inflow Depth = 6.54" for 50-Year event
Inflow = 17.0 cfs @ 12.18 hrs, Volume= 83,287 cf
Primary = 17.0 cfs @ 12.18 hrs, Volume= 83,287 cf, Atten= 0%, Lag= 0.0 min
Routed to Link 100L : Total Flows

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link 1L: Towards Wetlands

Hydrograph



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 50-Year Rainfall=9.67"

Printed 12/17/2024

Page 144


Summary for Link 2L: Towards Street

Inflow Area = 5,843 sf, 18.07% Impervious, Inflow Depth = 6.95" for 50-Year event
Inflow = 1.1 cfs @ 12.09 hrs, Volume= 3,385 cf
Primary = 1.1 cfs @ 12.09 hrs, Volume= 3,385 cf, Atten= 0%, Lag= 0.0 min
Routed to Link 100L : Total Flows

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link 2L: Towards Street

Hydrograph




Summary for Link 100L: Total Flows

Inflow Area = 158,686 sf, 49.59% Impervious, Inflow Depth = 6.55" for 50-Year event
 Inflow = 17.8 cfs @ 12.16 hrs, Volume= 86,673 cf
 Primary = 17.8 cfs @ 12.16 hrs, Volume= 86,673 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link 100L: Total Flows

Hydrograph



Time span=0.00-72.00 hrs, dt=0.01 hrs, 7201 points
 Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
 Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment1S: CB-1	Runoff Area=22,742 sf 72.16% Impervious Runoff Depth=10.39" Tc=6.0 min CN=91 Runoff=5.8 cfs 19,696 cf
Subcatchment2S: Building Roof	Runoff Area=32,925 sf 100.00% Impervious Runoff Depth=11.26" Tc=6.0 min CN=98 Runoff=8.5 cfs 30,891 cf
Subcatchment3.1S: Backyard ADS	Runoff Area=8,985 sf 3.03% Impervious Runoff Depth=8.28" Flow Length=147' Tc=10.3 min CN=75 Runoff=1.7 cfs 6,203 cf
Subcatchment3S: Townhouse Roofs	Runoff Area=13,067 sf 100.00% Impervious Runoff Depth=11.26" Tc=6.0 min CN=98 Runoff=3.4 cfs 12,260 cf
Subcatchment4.2S: TD-2	Runoff Area=1,112 sf 95.68% Impervious Runoff Depth=11.14" Tc=6.0 min CN=97 Runoff=0.3 cfs 1,032 cf
Subcatchment4.3S: TD-3	Runoff Area=1,105 sf 97.29% Impervious Runoff Depth=11.14" Tc=6.0 min CN=97 Runoff=0.3 cfs 1,026 cf
Subcatchment4.4S: TD-4	Runoff Area=1,104 sf 97.46% Impervious Runoff Depth=11.14" Tc=6.0 min CN=97 Runoff=0.3 cfs 1,025 cf
Subcatchment4.5S: TD-5	Runoff Area=1,082 sf 98.06% Impervious Runoff Depth=11.26" Tc=6.0 min CN=98 Runoff=0.3 cfs 1,015 cf
Subcatchment4.6S: TD-6	Runoff Area=1,056 sf 99.24% Impervious Runoff Depth=11.26" Tc=6.0 min CN=98 Runoff=0.3 cfs 991 cf
Subcatchment5.1S: TD-1A	Runoff Area=1,389 sf 84.59% Impervious Runoff Depth=10.77" Tc=6.0 min CN=94 Runoff=0.4 cfs 1,246 cf
Subcatchment5S: TD-1B	Runoff Area=4,462 sf 42.78% Impervious Runoff Depth=9.49" Tc=6.0 min CN=84 Runoff=1.1 cfs 3,530 cf
Subcatchment6.1S: East driveway	Runoff Area=12,275 sf 52.50% Impervious Runoff Depth=9.88" Tc=6.0 min CN=87 Runoff=3.0 cfs 10,109 cf
Subcatchment6S: Bypass Towards	Runoff Area=51,539 sf 0.21% Impervious Runoff Depth=8.15" Flow Length=125' Tc=14.0 min CN=74 Runoff=8.7 cfs 34,988 cf
Subcatchment7S: To Street	Runoff Area=5,843 sf 18.07% Impervious Runoff Depth=8.69" Tc=6.0 min CN=78 Runoff=1.3 cfs 4,233 cf
Pond 1P: Inf Syst-1	Peak Elev=11.00' Storage=19,245 cf Inflow=14.8 cfs 53,582 cf Discarded=0.1 cfs 15,354 cf Primary=7.3 cfs 38,228 cf Outflow=7.4 cfs 53,582 cf
Pond 3P: Rain garden	Peak Elev=6.50' Storage=253 cf Inflow=3.0 cfs 10,109 cf Discarded=0.0 cfs 518 cf Primary=3.0 cfs 9,592 cf Outflow=3.0 cfs 10,109 cf

2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 100-Year Rainfall=11.50"

Printed 12/17/2024

Page 147

Pond 4P: Inf Syst-2

Peak Elev=9.57' Storage=136 cf Inflow=0.3 cfs 1,032 cf
Discarded=0.0 cfs 161 cf Primary=0.3 cfs 858 cf Outflow=0.3 cfs 1,018 cf

Pond 5P: Inf Syst-3

Peak Elev=9.71' Storage=141 cf Inflow=0.3 cfs 1,026 cf
Discarded=0.0 cfs 161 cf Primary=0.3 cfs 846 cf Outflow=0.3 cfs 1,006 cf

Pond 6P: Inf Syst-4

Peak Elev=9.71' Storage=141 cf Inflow=0.3 cfs 1,025 cf
Discarded=0.0 cfs 161 cf Primary=0.3 cfs 845 cf Outflow=0.3 cfs 1,005 cf

Pond 7P: Inf Syst-5

Peak Elev=9.34' Storage=123 cf Inflow=0.3 cfs 1,015 cf
Discarded=0.0 cfs 161 cf Primary=0.3 cfs 853 cf Outflow=0.3 cfs 1,014 cf

Pond 8P: Inf Syst-6

Peak Elev=9.35' Storage=124 cf Inflow=0.3 cfs 991 cf
Discarded=0.0 cfs 161 cf Primary=0.3 cfs 828 cf Outflow=0.3 cfs 990 cf

Pond 9P: Inf Syst-7

Peak Elev=8.86' Storage=3,555 cf Inflow=6.1 cfs 20,942 cf
Discarded=0.0 cfs 1,621 cf Primary=3.4 cfs 19,322 cf Outflow=3.4 cfs 20,942 cf

Link 1L: Towards Wetlands

Inflow=21.4 cfs 105,660 cf
Primary=21.4 cfs 105,660 cf

Link 2L: Towards Street

Inflow=1.3 cfs 4,233 cf
Primary=1.3 cfs 4,233 cf

Link 100L: Total Flows

Inflow=22.3 cfs 109,893 cf
Primary=22.3 cfs 109,893 cf

Total Runoff Area = 158,686 sf Runoff Volume = 128,244 cf Average Runoff Depth = 9.70"
50.41% Pervious = 79,997 sf 49.59% Impervious = 78,689 sf

2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 100-Year Rainfall=11.50"

Printed 12/17/2024

Page 148

Summary for Subcatchment 1S: CB-1

Runoff = 5.8 cfs @ 12.08 hrs, Volume= 19,696 cf, Depth=10.39"
Routed to Pond 9P : Inf Syst-7


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 100-Year Rainfall=11.50"

Area (sf)	CN	Description
16,410	98	Paved parking, HSG C
6,332	74	>75% Grass cover, Good, HSG C
22,742	91	Weighted Average
6,332		27.84% Pervious Area
16,410		72.16% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 1S: CB-1

Hydrograph



Summary for Subcatchment 2S: Building Roof


Runoff = 8.5 cfs @ 12.08 hrs, Volume= 30,891 cf, Depth=11.26"
 Routed to Pond 1P : Inf Syst-1

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 100-Year Rainfall=11.50"

Area (sf)	CN	Description
32,925	98	Roofs, HSG C
32,925		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 2S: Building Roof



Summary for Subcatchment 3.1S: Backyard ADs


Runoff = 1.7 cfs @ 12.14 hrs, Volume= 6,203 cf, Depth= 8.28"
 Routed to Pond 1P : Inf Syst-1

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 100-Year Rainfall=11.50"

Area (sf)	CN	Description
272	98	Unconnected pavement, HSG C
8,302	74	>75% Grass cover, Good, HSG C
411	89	Gravel sidewalk, HSG C
8,985	75	Weighted Average
8,713		96.97% Pervious Area
272		3.03% Impervious Area
272		100.00% Unconnected

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
9.4	50	0.0142	0.09		Sheet Flow, Grass: Dense n= 0.240 P2= 3.23"
0.9	97	0.0154	1.86		Shallow Concentrated Flow, Grassed Waterway Kv= 15.0 fps
10.3	147				Total

Subcatchment 3.1S: Backyard ADs



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 100-Year Rainfall=11.50"

Printed 12/17/2024

Page 151

Summary for Subcatchment 3S: Townhouse Roofs


Runoff = 3.4 cfs @ 12.08 hrs, Volume= 12,260 cf, Depth=11.26"
Routed to Pond 1P : Inf Syst-1

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 100-Year Rainfall=11.50"

Area (sf)	CN	Description
13,067	98	Roofs, HSG C
13,067		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 3S: Townhouse Roofs



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 100-Year Rainfall=11.50"

Printed 12/17/2024

Page 152

Summary for Subcatchment 4.2S: TD-2


Runoff = 0.3 cfs @ 12.08 hrs, Volume= 1,032 cf, Depth=11.14"
Routed to Pond 4P : Inf Syst-2

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 100-Year Rainfall=11.50"

Area (sf)	CN	Description
1,064	98	Paved parking, HSG C
48	74	>75% Grass cover, Good, HSG C
1,112	97	Weighted Average
48		4.32% Pervious Area
1,064		95.68% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.2S: TD-2



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 100-Year Rainfall=11.50"

Printed 12/17/2024

Page 153

Summary for Subcatchment 4.3S: TD-3

Runoff = 0.3 cfs @ 12.08 hrs, Volume= 1,026 cf, Depth=11.14"
Routed to Pond 5P : Inf Syst-3


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 100-Year Rainfall=11.50"

Area (sf)	CN	Description
1,075	98	Paved parking, HSG C
30	74	>75% Grass cover, Good, HSG C
1,105	97	Weighted Average
30		2.71% Pervious Area
1,075		97.29% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.3S: TD-3

Hydrograph



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 100-Year Rainfall=11.50"

Printed 12/17/2024

Page 154

Summary for Subcatchment 4.4S: TD-4

Runoff = 0.3 cfs @ 12.08 hrs, Volume= 1,025 cf, Depth=11.14"
Routed to Pond 6P : Inf Syst-4


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 100-Year Rainfall=11.50"

Area (sf)	CN	Description
1,076	98	Paved parking, HSG C
28	74	>75% Grass cover, Good, HSG C
1,104	97	Weighted Average
28		2.54% Pervious Area
1,076		97.46% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.4S: TD-4

Hydrograph



Summary for Subcatchment 4.5S: TD-5

Runoff = 0.3 cfs @ 12.08 hrs, Volume= 1,015 cf, Depth=11.26"
 Routed to Pond 7P : Inf Syst-5


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 100-Year Rainfall=11.50"

Area (sf)	CN	Description
1,061	98	Paved parking, HSG C
21	74	>75% Grass cover, Good, HSG C
1,082	98	Weighted Average
21		1.94% Pervious Area
1,061		98.06% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.5S: TD-5

Hydrograph



Summary for Subcatchment 4.6S: TD-6

Runoff = 0.3 cfs @ 12.08 hrs, Volume= 991 cf, Depth=11.26"
 Routed to Pond 8P : Inf Syst-6


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 100-Year Rainfall=11.50"

Area (sf)	CN	Description
1,048	98	Paved parking, HSG C
8	74	>75% Grass cover, Good, HSG C
1,056	98	Weighted Average
8		0.76% Pervious Area
1,048		99.24% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.6S: TD-6

Hydrograph



Summary for Subcatchment 5.1S: TD-1A

Runoff = 0.4 cfs @ 12.08 hrs, Volume= 1,246 cf, Depth=10.77"
 Routed to Pond 9P : Inf Syst-7


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 100-Year Rainfall=11.50"

Area (sf)	CN	Description
1,175	98	Paved parking, HSG C
214	74	>75% Grass cover, Good, HSG C
1,389	94	Weighted Average
214		15.41% Pervious Area
1,175		84.59% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 5.1S: TD-1A

Hydrograph



Summary for Subcatchment 5S: TD-1B

Runoff = 1.1 cfs @ 12.08 hrs, Volume= 3,530 cf, Depth= 9.49"
 Routed to Link 1L : Towards Wetlands


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 100-Year Rainfall=11.50"

Area (sf)	CN	Description
1,909	98	Paved parking, HSG C
2,553	74	>75% Grass cover, Good, HSG C
4,462	84	Weighted Average
2,553		57.22% Pervious Area
1,909		42.78% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 5S: TD-1B

Hydrograph



Summary for Subcatchment 6.1S: East driveway

Runoff = 3.0 cfs @ 12.08 hrs, Volume= 10,109 cf, Depth= 9.88"
 Routed to Pond 3P : Rain garden


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 100-Year Rainfall=11.50"

Area (sf)	CN	Description
5,611	74	>75% Grass cover, Good, HSG C
6,444	98	Paved roads w/curbs & sewers, HSG C
220	89	Gravel roads, HSG C
12,275	87	Weighted Average
5,831		47.50% Pervious Area
6,444		52.50% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

Subcatchment 6.1S: East driveway

Hydrograph



Summary for Subcatchment 6S: Bypass Towards Wetlands

Runoff = 8.7 cfs @ 12.18 hrs, Volume= 34,988 cf, Depth= 8.15"
 Routed to Link 1L : Towards Wetlands


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 100-Year Rainfall=11.50"

Area (sf)	CN	Description
4,985	70	Woods, Good, HSG C
46,447	74	>75% Grass cover, Good, HSG C
107	98	Roofs, HSG C
51,539	74	Weighted Average
51,432		99.79% Pervious Area
107		0.21% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.8	50	0.0220	0.07		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.23"
2.2	75	0.0133	0.58		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
14.0	125	Total			

Subcatchment 6S: Bypass Towards Wetlands

Hydrograph



Summary for Subcatchment 7S: To Street


Runoff = 1.3 cfs @ 12.09 hrs, Volume= 4,233 cf, Depth= 8.69"
 Routed to Link 2L : Towards Street

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 100-Year Rainfall=11.50"

Area (sf)	CN	Description
1,056	98	Paved parking, HSG C
4,787	74	>75% Grass cover, Good, HSG C
5,843	78	Weighted Average
4,787		81.93% Pervious Area
1,056		18.07% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 7S: To Street



Summary for Pond 1P: Inf Syst-1

Inflow Area = 60,436 sf, 85.36% Impervious, Inflow Depth = 10.64" for 100-Year event
 Inflow = 14.8 cfs @ 12.09 hrs, Volume= 53,582 cf
 Outflow = 7.4 cfs @ 12.25 hrs, Volume= 53,582 cf, Atten= 50%, Lag= 9.7 min
 Discarded = 0.1 cfs @ 2.72 hrs, Volume= 15,354 cf
 Primary = 7.3 cfs @ 12.25 hrs, Volume= 38,228 cf
 Routed to Link 1L : Towards Wetlands

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 11.00' @ 12.25 hrs Surf.Area= 7,459 sf Storage= 19,245 cf

Plug-Flow detention time= 272.3 min calculated for 53,582 cf (100% of inflow)
 Center-of-Mass det. time= 272.2 min (1,021.3 - 749.0)

Volume	Invert	Avail.Storage	Storage Description
#1	8.00'	19,245 cf	6.89'W x 14.06'L x 3.00'H StormTrap ST-1 Units (Irregular Shape) 77 22,378 cf Overall x 86.0% Voids


Device	Routing	Invert	Outlet Devices
#1	Discarded	8.00'	0.520 in/hr Exfiltration over Surface area
#2	Primary	8.00'	15.0" Round Culvert L= 26.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 8.00' / 7.13' S= 0.0335 '/ Cc= 0.900 n= 0.013, Flow Area= 1.23 sf
#3	Device 2	9.22'	22.0" W x 4.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 2	10.05'	20.0" W x 4.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 2	10.79'	3.7' long Sharp-Crested Rectangular Weir 2 End Contraction(s)

Discarded OutFlow Max=0.1 cfs @ 2.72 hrs HW=8.03' (Free Discharge)
 1=Exfiltration (Exfiltration Controls 0.1 cfs)

Primary OutFlow Max=7.3 cfs @ 12.25 hrs HW=11.00' (Free Discharge)
 2=Culvert (Passes 7.3 cfs of 9.1 cfs potential flow)
 3=Orifice/Grate (Orifice Controls 3.7 cfs @ 6.12 fps)
 4=Orifice/Grate (Orifice Controls 2.4 cfs @ 4.26 fps)
 5=Sharp-Crested Rectangular Weir(Weir Controls 1.2 cfs @ 1.51 fps)

Pond 1P: Inf Syst-1

Hydrograph



Summary for Pond 3P: Rain garden

Inflow Area = 12,275 sf, 52.50% Impervious, Inflow Depth = 9.88" for 100-Year event
 Inflow = 3.0 cfs @ 12.08 hrs, Volume= 10,109 cf
 Outflow = 3.0 cfs @ 12.08 hrs, Volume= 10,109 cf, Atten= 0%, Lag= 0.0 min
 Discarded = 0.0 cfs @ 12.08 hrs, Volume= 518 cf
 Primary = 3.0 cfs @ 12.08 hrs, Volume= 9,592 cf
 Routed to Link 1L : Towards Wetlands

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 6.50' @ 12.08 hrs Surf.Area= 460 sf Storage= 253 cf

Plug-Flow detention time= 29.6 min calculated for 10,108 cf (100% of inflow)
 Center-of-Mass det. time= 29.8 min (803.8 - 774.0)

Volume	Invert	Avail.Storage	Storage Description		
#1	5.60'	253 cf	Custom Stage Data (Irregular) Listed below (Recal)		
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
5.60	125	46.0	0	0	125
6.00	276	66.0	78	78	305
6.30	350	73.0	94	172	385
6.50	460	87.0	81	253	564


Device	Routing	Invert	Outlet Devices
#1	Discarded	5.60'	0.520 in/hr Exfiltration over Surface area
#2	Primary	6.35'	22.0' long x 5.0' breadth Broad-Crested Rectangular Weir
			Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00
			2.50 3.00 3.50 4.00 4.50 5.00 5.50
			Coef. (English) 2.34 2.50 2.70 2.68 2.68 2.66 2.65 2.65 2.65
			2.65 2.67 2.66 2.68 2.70 2.74 2.79 2.88

Discarded OutFlow Max=0.0 cfs @ 12.08 hrs HW=6.50' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=3.0 cfs @ 12.08 hrs HW=6.50' (Free Discharge)
 ↳2=Broad-Crested Rectangular Weir (Weir Controls 3.0 cfs @ 0.91 fps)

Pond 3P: Rain garden

Hydrograph



Summary for Pond 4P: Inf Syst-2

Inflow Area = 1,112 sf, 95.68% Impervious, Inflow Depth = 11.14" for 100-Year event
 Inflow = 0.3 cfs @ 12.08 hrs, Volume= 1,032 cf
 Outflow = 0.3 cfs @ 12.09 hrs, Volume= 1,018 cf, Atten= 1%, Lag= 0.5 min
 Discarded = 0.0 cfs @ 1.40 hrs, Volume= 161 cf
 Primary = 0.3 cfs @ 12.09 hrs, Volume= 858 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.57' @ 12.09 hrs Surf.Area= 101 sf Storage= 136 cf

Plug-Flow detention time= 278.5 min calculated for 1,018 cf (99% of inflow)
 Center-of-Mass det. time= 269.7 min (1,011.6 - 741.9)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	84 cf	7.28'W x 13.84'L x 2.72'H Field A 274 cf Overall - 64 cf Embedded = 210 cf x 40.0% Voids
#2A	7.25'	57 cf	Ferguson R-Tank XD 12 x 10 Inside #1 Inside= 19.7"W x 23.6"H => 2.91 sf x 1.97'L = 5.7 cf Outside= 19.7"W x 23.6"H => 3.23 sf x 1.97'L = 6.4 cf 10 Chambers in 2 Rows
		141 cf	Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.23'	6.0" Round Culvert L= 33.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.23' / 8.72' S= 0.0155 '/ Cc= 0.900 n= 0.013, Flow Area= 0.20 sf

Discarded OutFlow Max=0.0 cfs @ 1.40 hrs HW=7.03' (Free Discharge)
 ↕ **1=Exfiltration** (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.3 cfs @ 12.09 hrs HW=9.57' (Free Discharge)
 ↕ **2=Culvert** (Inlet Controls 0.3 cfs @ 1.99 fps)

Pond 4P: Inf Syst-2

Hydrograph



Summary for Pond 5P: Inf Syst-3

Inflow Area = 1,105 sf, 97.29% Impervious, Inflow Depth = 11.14" for 100-Year event
 Inflow = 0.3 cfs @ 12.08 hrs, Volume= 1,026 cf
 Outflow = 0.3 cfs @ 12.09 hrs, Volume= 1,006 cf, Atten= 1%, Lag= 0.5 min
 Discarded = 0.0 cfs @ 1.42 hrs, Volume= 161 cf
 Primary = 0.3 cfs @ 12.09 hrs, Volume= 846 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.71' @ 12.09 hrs Surf.Area= 101 sf Storage= 141 cf

Plug-Flow detention time= 286.0 min calculated for 1,006 cf (98% of inflow)
 Center-of-Mass det. time= 273.7 min (1,015.6 - 741.9)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	84 cf	7.28'W x 13.84'L x 2.72'H Field A 274 cf Overall - 64 cf Embedded = 210 cf x 40.0% Voids
#2A	7.25'	57 cf	Ferguson R-Tank XD 12 x 10 Inside #1 Inside= 19.7"W x 23.6"H => 2.91 sf x 1.97'L = 5.7 cf Outside= 19.7"W x 23.6"H => 3.23 sf x 1.97'L = 6.4 cf 10 Chambers in 2 Rows
		141 cf	Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.37'	6.0" Round Culvert L= 33.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.37' / 8.73' S= 0.0194 '/ Cc= 0.900 n= 0.013, Flow Area= 0.20 sf

Discarded OutFlow Max=0.0 cfs @ 1.42 hrs HW=7.03' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.3 cfs @ 12.09 hrs HW=9.71' (Free Discharge)
 ↳2=Culvert (Inlet Controls 0.3 cfs @ 1.99 fps)

Pond 5P: Inf Syst-3

Hydrograph



Summary for Pond 6P: Inf Syst-4

Inflow Area = 1,104 sf, 97.46% Impervious, Inflow Depth = 11.14" for 100-Year event
 Inflow = 0.3 cfs @ 12.08 hrs, Volume= 1,025 cf
 Outflow = 0.3 cfs @ 12.09 hrs, Volume= 1,005 cf, Atten= 1%, Lag= 0.5 min
 Discarded = 0.0 cfs @ 1.42 hrs, Volume= 161 cf
 Primary = 0.3 cfs @ 12.09 hrs, Volume= 845 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.71' @ 12.09 hrs Surf.Area= 101 sf Storage= 141 cf

Plug-Flow detention time= 285.9 min calculated for 1,005 cf (98% of inflow)
 Center-of-Mass det. time= 274.0 min (1,015.8 - 741.9)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	84 cf	7.28'W x 13.84'L x 2.72'H Field A 274 cf Overall - 64 cf Embedded = 210 cf x 40.0% Voids
#2A	7.25'	57 cf	Ferguson R-Tank XD 12 x 10 Inside #1 Inside= 19.7"W x 23.6"H => 2.91 sf x 1.97'L = 5.7 cf Outside= 19.7"W x 23.6"H => 3.23 sf x 1.97'L = 6.4 cf 10 Chambers in 2 Rows
		141 cf	Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.37'	6.0" Round Culvert L= 51.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.37' / 8.10' S= 0.0249 '/ Cc= 0.900 n= 0.013, Flow Area= 0.20 sf

Discarded OutFlow Max=0.0 cfs @ 1.42 hrs HW=7.03' (Free Discharge)
 ↕ **1=Exfiltration** (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.3 cfs @ 12.09 hrs HW=9.71' (Free Discharge)
 ↕ **2=Culvert** (Inlet Controls 0.3 cfs @ 1.99 fps)

Pond 6P: Inf Syst-4

Hydrograph



Summary for Pond 7P: Inf Syst-5

Inflow Area = 1,082 sf, 98.06% Impervious, Inflow Depth = 11.26" for 100-Year event
 Inflow = 0.3 cfs @ 12.08 hrs, Volume= 1,015 cf
 Outflow = 0.3 cfs @ 12.09 hrs, Volume= 1,014 cf, Atten= 1%, Lag= 0.5 min
 Discarded = 0.0 cfs @ 1.05 hrs, Volume= 161 cf
 Primary = 0.3 cfs @ 12.09 hrs, Volume= 853 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.34' @ 12.09 hrs Surf.Area= 101 sf Storage= 123 cf

Plug-Flow detention time= 271.3 min calculated for 1,014 cf (100% of inflow)
 Center-of-Mass det. time= 271.0 min (1,008.3 - 737.2)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	73 cf	7.28'W x 13.84'L x 2.39'H Field A 241 cf Overall - 58 cf Embedded = 182 cf x 40.0% Voids
#2A	7.25'	52 cf	Ferguson R-Tank XD 11 x 10 Inside #1 Inside= 19.7"W x 21.7"H => 2.66 sf x 1.97'L = 5.2 cf Outside= 19.7"W x 21.7"H => 2.96 sf x 1.97'L = 5.8 cf 10 Chambers in 2 Rows
		125 cf	Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.00'	6.0" Round Culvert L= 48.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.00' / 8.35' S= 0.0135 '/ Cc= 0.900 n= 0.013, Flow Area= 0.20 sf

Discarded OutFlow Max=0.0 cfs @ 1.05 hrs HW=7.03' (Free Discharge)
 1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.3 cfs @ 12.09 hrs HW=9.34' (Free Discharge)
 2=Culvert (Inlet Controls 0.3 cfs @ 1.98 fps)

Pond 7P: Inf Syst-5

Hydrograph



Summary for Pond 8P: Inf Syst-6

Inflow Area = 1,056 sf, 99.24% Impervious, Inflow Depth = 11.26" for 100-Year event
 Inflow = 0.3 cfs @ 12.08 hrs, Volume= 991 cf
 Outflow = 0.3 cfs @ 12.09 hrs, Volume= 990 cf, Atten= 0%, Lag= 0.5 min
 Discarded = 0.0 cfs @ 1.08 hrs, Volume= 161 cf
 Primary = 0.3 cfs @ 12.09 hrs, Volume= 828 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.35' @ 12.09 hrs Surf.Area= 101 sf Storage= 124 cf

Plug-Flow detention time= 277.9 min calculated for 990 cf (100% of inflow)
 Center-of-Mass det. time= 277.4 min (1,014.7 - 737.2)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	73 cf	7.28'W x 13.84'L x 2.39'H Field A 241 cf Overall - 58 cf Embedded = 182 cf x 40.0% Voids
#2A	7.25'	52 cf	Ferguson R-Tank XD 11 x 10 Inside #1 Inside= 19.7"W x 21.7"H => 2.66 sf x 1.97'L = 5.2 cf Outside= 19.7"W x 21.7"H => 2.96 sf x 1.97'L = 5.8 cf 10 Chambers in 2 Rows
		125 cf	Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.00'	8.0" Round Culvert L= 46.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.00' / 8.77' S= 0.0050 '/ Cc= 0.900 n= 0.013, Flow Area= 0.35 sf

Discarded OutFlow Max=0.0 cfs @ 1.08 hrs HW=7.03' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.3 cfs @ 12.09 hrs HW=9.35' (Free Discharge)
 ↳2=Culvert (Barrel Controls 0.3 cfs @ 2.11 fps)

Pond 8P: Inf Syst-6

Hydrograph



Summary for Pond 9P: Inf Syst-7

Inflow Area = 24,131 sf, 72.87% Impervious, Inflow Depth = 10.41" for 100-Year event
 Inflow = 6.1 cfs @ 12.08 hrs, Volume= 20,942 cf
 Outflow = 3.4 cfs @ 12.20 hrs, Volume= 20,942 cf, Atten= 44%, Lag= 7.0 min
 Discarded = 0.0 cfs @ 3.41 hrs, Volume= 1,621 cf
 Primary = 3.4 cfs @ 12.20 hrs, Volume= 19,322 cf
 Routed to Link 1L : Towards Wetlands

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 8.86' @ 12.20 hrs Surf.Area= 2,422 sf Storage= 3,555 cf

Plug-Flow detention time= 43.5 min calculated for 20,940 cf (100% of inflow)
 Center-of-Mass det. time= 43.6 min (806.2 - 762.6)

Volume	Invert	Avail.Storage	Storage Description
#1	7.15'	3,645 cf	6.89'W x 14.06'L x 1.75'H StormTrap ST-1 Units (Irregular Shape) x 25 4,238 cf Overall x 86.0% Voids


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.15'	0.270 in/hr Exfiltration over Surface area
#2	Primary	7.15'	12.0" Round Culvert L= 4.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 7.15' / 7.13' S= 0.0050 '/ Cc= 0.900 n= 0.013, Flow Area= 0.79 sf
#3	Device 2	7.35'	22.0" W x 4.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

Discarded OutFlow Max=0.0 cfs @ 3.41 hrs HW=7.17' (Free Discharge)
 1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=3.4 cfs @ 12.20 hrs HW=8.86' (Free Discharge)
 2=Culvert (Passes 3.4 cfs of 4.2 cfs potential flow)
 3=Orifice/Grate (Orifice Controls 3.4 cfs @ 5.57 fps)

Pond 9P: Inf Syst-7

Hydrograph




Summary for Link 1L: Towards Wetlands

Inflow Area = 152,843 sf, 50.79% Impervious, Inflow Depth = 8.30" for 100-Year event
 Inflow = 21.4 cfs @ 12.19 hrs, Volume= 105,660 cf
 Primary = 21.4 cfs @ 12.19 hrs, Volume= 105,660 cf, Atten= 0%, Lag= 0.0 min
 Routed to Link 100L : Total Flows

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link 1L: Towards Wetlands

Hydrograph




Summary for Link 2L: Towards Street

Inflow Area = 5,843 sf, 18.07% Impervious, Inflow Depth = 8.69" for 100-Year event
 Inflow = 1.3 cfs @ 12.09 hrs, Volume= 4,233 cf
 Primary = 1.3 cfs @ 12.09 hrs, Volume= 4,233 cf, Atten= 0%, Lag= 0.0 min
 Routed to Link 100L : Total Flows

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link 2L: Towards Street

Hydrograph




Summary for Link 100L: Total Flows

Inflow Area = 158,686 sf, 49.59% Impervious, Inflow Depth = 8.31" for 100-Year event
 Inflow = 22.3 cfs @ 12.18 hrs, Volume= 109,893 cf
 Primary = 22.3 cfs @ 12.18 hrs, Volume= 109,893 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link 100L: Total Flows

Hydrograph



SECTION 6.0

ADDITIONAL DRAINAGE CALCULATIONS

6.01 TSS REMOVAL CALCULATIONS

TSS Removal Calculation Worksheet

Location: Thorndike Place, Arlington, MA

Project: 23407.02



Prepared By: E. Derrig

Date: 12/09/2024

AREA 1 - CB-1
Total Impervious Area, Acres= 0.377

A	B	C	D	E
BMP	TSS Removal Rate	Starting TSS Load*	Amount Removed (BxC)	Remaining Load (C-D)
Deep Sump and Hooded Catchbasins	0.25	1.00	0.25	0.75
Hydrodynamic Separator	0.7	0.75	0.53	0.23
Infiltration Basin	0.8	0.23	0.18	0.05

TSS Removal = 0.96

AREA 2A - TD-1A
Total Impervious Area, Acres= 0.027

A	B	C	D	E
BMP	TSS Removal Rate	Starting TSS Load*	Amount Removed (BxC)	Remaining Load (C-D)
Hydrodynamic Separator	0.7	1.00	0.70	0.30
Infiltration Basin	0.8	0.30	0.24	0.06

TSS Removal = 0.94

AREA 2B - TD-1B
Total Impervious Area, Acres= 0.044

A	B	C	D	E
BMP	TSS Removal Rate	Starting TSS Load*	Amount Removed (BxC)	Remaining Load (C-D)
Hydrodynamic Separator	0.7	1.00	0.70	0.30

TSS Removal = 0.70

AREA 3 - TD-2-6**Total Impervious Area, Acres= 0.122**

A	B	C	D	E
BMP	TSS Removal Rate	Starting TSS Load*	Amount Removed (BxC)	Remaining Load (C-D)
Infiltration Basin	0.8	1.00	0.80	0.20

TSS Removal = **AREA 4 - Bypass to Street****Total Impervious Area, Acres= 0.024**

A	B	C	D	E
BMP	TSS Removal Rate	Starting TSS Load*	Amount Removed (BxC)	Remaining Load (C-D)
		1.00		

TSS Removal = **AREA 5 - East Driveway****Total Impervious Area, Acres= 0.148**

A	B	C	D	E
BMP	TSS Removal Rate	Starting TSS Load*	Amount Removed (BxC)	Remaining Load (C-D)
Rain Garden	0.8	1.00	0.80	0.20

TSS Removal = **Weighted Annual Average TSS Removal Rate**

[TSS Removal-1 (Area-1) + TSS Removal-2 (Area-2)+] / [Area-1 + Area-2 + ...] = 0.85

Project Site TSS Removal =

6.02 GROUNDWATER RECHARGE VOLUME CALCULATIONS

Required Recharge Volume

$$Rv = F \times \text{Impervious Area}$$

Where:

Rv = Recharge Volume

F=Target Depth Factor associated with each Hydrologic Soil Group

(F=0.25-inch for Soil Type C)

Impervious Area = Proposed Pavement and Rooftop area on-site

$$Rv = \left(\frac{0.25in}{12} \right) (78,689sft) =$$

$$Rv = 1,640 \text{ cf (required recharge volume)}$$

As not all impervious surfaces are directed to an infiltration BMP, an adjusted Required Volume must be provided. The adjusted Required Volume (Rva) is calculated as:

$$Rva = \frac{\text{Total Imp.Area}}{\text{Imp.Area to BMP}} (Rv) =$$

$$Rva = \left(\frac{78,689sft}{75,617sft} \right) (1,640cf) =$$

$$Rva = 1,707 \text{ cf}$$

Storage Provided

- Underground Infiltration System 1 = 7,826 cubic feet provided
- Underground Infiltration System 2 = 122 cubic feet provided
- Underground Infiltration System 3/4 = 254 cubic feet provided (systems are the same)
- Underground Infiltration System 5/6 = 218 cubic feet provided (systems are the same)
- Underground Infiltration System 7 = 417 cubic feet provided
- **Underground Infiltration Systems Total = 8,837 cubic feet provided > 1,707 cf required**
Rain garden not required to meet volume, but provides additional infiltration above and beyond that required.
Refer to the HydroCAD storage table provided for more information.

Stage-Area-Storage for Pond 1P: Inf Syst-1

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
8.00	7,459	0	8.52	7,459	3,336
8.01	7,459	64	8.53	7,459	3,400
8.02	7,459	128	8.54	7,459	3,464
8.03	7,459	192	8.55	7,459	3,528
8.04	7,459	257	8.56	7,459	3,592
8.05	7,459	321	8.57	7,459	3,657
8.06	7,459	385	8.58	7,459	3,721
8.07	7,459	449	8.59	7,459	3,785
8.08	7,459	513	8.60	7,459	3,849
8.09	7,459	577	8.61	7,459	3,913
8.10	7,459	641	8.62	7,459	3,977
8.11	7,459	706	8.63	7,459	4,041
8.12	7,459	770	8.64	7,459	4,106
8.13	7,459	834	8.65	7,459	4,170
8.14	7,459	898	8.66	7,459	4,234
8.15	7,459	962	8.67	7,459	4,298
8.16	7,459	1,026	8.68	7,459	4,362
8.17	7,459	1,091	8.69	7,459	4,426
8.18	7,459	1,155	8.70	7,459	4,490
8.19	7,459	1,219	8.71	7,459	4,555
8.20	7,459	1,283	8.72	7,459	4,619
8.21	7,459	1,347	8.73	7,459	4,683
8.22	7,459	1,411	8.74	7,459	4,747
8.23	7,459	1,475	8.75	7,459	4,811
8.24	7,459	1,540	8.76	7,459	4,875
8.25	7,459	1,604	8.77	7,459	4,940
8.26	7,459	1,668	8.78	7,459	5,004
8.27	7,459	1,732	8.79	7,459	5,068
8.28	7,459	1,796	8.80	7,459	5,132
8.29	7,459	1,860	8.81	7,459	5,196
8.30	7,459	1,924	8.82	7,459	5,260
8.31	7,459	1,989	8.83	7,459	5,324
8.32	7,459	2,053	8.84	7,459	5,389
8.33	7,459	2,117	8.85	7,459	5,453
8.34	7,459	2,181	8.86	7,459	5,517
8.35	7,459	2,245	8.87	7,459	5,581
8.36	7,459	2,309	8.88	7,459	5,645
8.37	7,459	2,374	8.89	7,459	5,709
8.38	7,459	2,438	8.90	7,459	5,773
8.39	7,459	2,502	8.91	7,459	5,838
8.40	7,459	2,566	8.92	7,459	5,902
8.41	7,459	2,630	8.93	7,459	5,966
8.42	7,459	2,694	8.94	7,459	6,030
8.43	7,459	2,758	8.95	7,459	6,094
8.44	7,459	2,823	8.96	7,459	6,158
8.45	7,459	2,887	8.97	7,459	6,223
8.46	7,459	2,951	8.98	7,459	6,287
8.47	7,459	3,015	8.99	7,459	6,351
8.48	7,459	3,079	9.00	7,459	6,415
8.49	7,459	3,143	9.01	7,459	6,479
8.50	7,459	3,207	9.02	7,459	6,543
8.51	7,459	3,272	9.03	7,459	6,607

Stage-Area-Storage for Pond 1P: Inf Syst-1 (continued)

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
9.04	7,459	6,672	9.56	7,459	10,007
9.05	7,459	6,736	9.57	7,459	10,071
9.06	7,459	6,800	9.58	7,459	10,136
9.07	7,459	6,864	9.59	7,459	10,200
9.08	7,459	6,928	9.60	7,459	10,264
9.09	7,459	6,992	9.61	7,459	10,328
9.10	7,459	7,056	9.62	7,459	10,392
9.11	7,459	7,121	9.63	7,459	10,456
9.12	7,459	7,185	9.64	7,459	10,521
9.13	7,459	7,249	9.65	7,459	10,585
9.14	7,459	7,313	9.66	7,459	10,649
9.15	7,459	7,377	9.67	7,459	10,713
9.16	7,459	7,441	9.68	7,459	10,777
9.17	7,459	7,505	9.69	7,459	10,841
9.18	7,459	7,570	9.70	7,459	10,905
9.19	7,459	7,634	9.71	7,459	10,970
9.20	7,459	7,698	9.72	7,459	11,034
9.21	7,459	7,762	9.73	7,459	11,098
9.22	7,459	7,826	9.74	7,459	11,162
9.23	7,459	7,890	9.75	7,459	11,226
9.24	7,459	7,955	9.76	7,459	11,290
9.25	7,459	8,019	9.77	7,459	11,354
9.26	7,459	8,083	9.78	7,459	11,419
9.27	7,459	8,147	9.79	7,459	11,483
9.28	7,459	8,211	9.80	7,459	11,547
9.29	7,459	8,275	9.81	7,459	11,611
9.30	7,459	8,339	9.82	7,459	11,675
9.31	7,459	8,404	9.83	7,459	11,739
9.32	7,459	8,468	9.84	7,459	11,804
9.33	7,459	8,532	9.85	7,459	11,868
9.34	7,459	8,596	9.86	7,459	11,932
9.35	7,459	8,660	9.87	7,459	11,996
9.36	7,459	8,724	9.88	7,459	12,060
9.37	7,459	8,788	9.89	7,459	12,124
9.38	7,459	8,853	9.90	7,459	12,188
9.39	7,459	8,917	9.91	7,459	12,253
9.40	7,459	8,981	9.92	7,459	12,317
9.41	7,459	9,045	9.93	7,459	12,381
9.42	7,459	9,109	9.94	7,459	12,445
9.43	7,459	9,173	9.95	7,459	12,509
9.44	7,459	9,238	9.96	7,459	12,573
9.45	7,459	9,302	9.97	7,459	12,637
9.46	7,459	9,366	9.98	7,459	12,702
9.47	7,459	9,430	9.99	7,459	12,766
9.48	7,459	9,494	10.00	7,459	12,830
9.49	7,459	9,558	10.01	7,459	12,894
9.50	7,459	9,622	10.02	7,459	12,958
9.51	7,459	9,687	10.03	7,459	13,022
9.52	7,459	9,751	10.04	7,459	13,087
9.53	7,459	9,815	10.05	7,459	13,151
9.54	7,459	9,879	10.06	7,459	13,215
9.55	7,459	9,943	10.07	7,459	13,279

Stage-Area-Storage for Pond 4P: Inf Syst-2 (continued)

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
9.08	101	113	9.60	101	137
9.09	101	114	9.61	101	137
9.10	101	115	9.62	101	137
9.11	101	115	9.63	101	138
9.12	101	116	9.64	101	138
9.13	101	116	9.65	101	139
9.14	101	117	9.66	101	139
9.15	101	117	9.67	101	139
9.16	101	118	9.68	101	140
9.17	101	118	9.69	101	140
9.18	101	119	9.70	101	141
9.19	101	120	9.71	101	141
9.20	101	120	9.72	101	141
9.21	101	121	9.73	101	141
9.22	101	121			
9.23	101	122			
9.24	101	122			
9.25	101	122			
9.26	101	123			
9.27	101	123			
9.28	101	124			
9.29	101	124			
9.30	101	125			
9.31	101	125			
9.32	101	125			
9.33	101	126			
9.34	101	126			
9.35	101	127			
9.36	101	127			
9.37	101	127			
9.38	101	128			
9.39	101	128			
9.40	101	129			
9.41	101	129			
9.42	101	129			
9.43	101	130			
9.44	101	130			
9.45	101	131			
9.46	101	131			
9.47	101	131			
9.48	101	132			
9.49	101	132			
9.50	101	133			
9.51	101	133			
9.52	101	133			
9.53	101	134			
9.54	101	134			
9.55	101	135			
9.56	101	135			
9.57	101	135			
9.58	101	136			
9.59	101	136			

2340702-PR-2024-12-10

Type III 24-hr 100-Year Rainfall=11.50"

Prepared by BSC Group

Printed 12/10/2024

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Stage-Area-Storage for Pond 5P: Inf Syst-3 (continued)

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
9.08	101	113	9.60	101	137
9.09	101	114	9.61	101	137
9.10	101	115	9.62	101	137
9.11	101	115	9.63	101	138
9.12	101	116	9.64	101	138
9.13	101	116	9.65	101	139
9.14	101	117	9.66	101	139
9.15	101	117	9.67	101	139
9.16	101	118	9.68	101	140
9.17	101	118	9.69	101	140
9.18	101	119	9.70	101	141
9.19	101	120	9.71	101	141
9.20	101	120	9.72	101	141
9.21	101	121	9.73	101	141
9.22	101	121	9.74	101	141
9.23	101	122	9.75	101	141
9.24	101	122	9.76	101	141
9.25	101	122	9.77	101	141
9.26	101	123	9.78	101	141
9.27	101	123	9.79	101	141
9.28	101	124	9.80	101	141
9.29	101	124	9.81	101	141
9.30	101	125	9.82	101	141
9.31	101	125	9.83	101	141
9.32	101	125	9.84	101	141
9.33	101	126	9.85	101	141
9.34	101	126	9.86	101	141
9.35	101	127	9.87	101	141
9.36	101	127			
9.37	101	127			
9.38	101	128			
9.39	101	128			
9.40	101	129			
9.41	101	129			
9.42	101	129			
9.43	101	130			
9.44	101	130			
9.45	101	131			
9.46	101	131			
9.47	101	131			
9.48	101	132			
9.49	101	132			
9.50	101	133			
9.51	101	133			
9.52	101	133			
9.53	101	134			
9.54	101	134			
9.55	101	135			
9.56	101	135			
9.57	101	135			
9.58	101	136			
9.59	101	136			

2340702-PR-2024-12-10

Type III 24-hr 100-Year Rainfall=11.50"

Prepared by BSC Group

Printed 12/10/2024

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Stage-Area-Storage for Pond 7P: Inf Syst-5

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
7.00	101	0
7.05	101	2
7.10	101	4
7.15	101	6
7.20	101	8
7.25	101	10
7.30	101	13
7.35	101	16
7.40	101	19
7.45	101	21
7.50	101	24
7.55	101	27
7.60	101	30
7.65	101	33
7.70	101	35
7.75	101	38
7.80	101	41
7.85	101	44
7.90	101	47
7.95	101	50
8.00	101	52
8.05	101	55
8.10	101	58
8.15	101	61
8.20	101	64
8.25	101	67
8.30	101	69
8.35	101	72
8.40	101	75
8.45	101	78
8.50	101	81
8.55	101	83
8.60	101	86
8.65	101	89
8.70	101	92
8.75	101	95
8.80	101	98
8.85	101	100
8.90	101	103
8.95	101	106
9.00	101	109
9.05	101	112
9.10	101	114
9.15	101	116
9.20	101	118
9.25	101	120
9.30	101	122
9.35	101	124
9.40	101	125
9.45	101	125
9.50	101	125

2340702-PR-2024-12-10

Type III 24-hr 100-Year Rainfall=11.50"

Prepared by BSC Group

Printed 12/10/2024

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Stage-Area-Storage for Pond 9P: Inf Syst-7

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
7.15	2,422	0	8.19	2,422	2,166
7.17	2,422	42	8.21	2,422	2,208
7.19	2,422	83	8.23	2,422	2,249
7.21	2,422	125	8.25	2,422	2,291
7.23	2,422	167	8.27	2,422	2,333
7.25	2,422	208	8.29	2,422	2,374
7.27	2,422	250	8.31	2,422	2,416
7.29	2,422	292	8.33	2,422	2,458
7.31	2,422	333	8.35	2,422	2,499
7.33	2,422	375	8.37	2,422	2,541
7.35	2,422	417	8.39	2,422	2,583
7.37	2,422	458	8.41	2,422	2,624
7.39	2,422	500	8.43	2,422	2,666
7.41	2,422	542	8.45	2,422	2,708
7.43	2,422	583	8.47	2,422	2,749
7.45	2,422	625	8.49	2,422	2,791
7.47	2,422	666	8.51	2,422	2,833
7.49	2,422	708	8.53	2,422	2,874
7.51	2,422	750	8.55	2,422	2,916
7.53	2,422	791	8.57	2,422	2,958
7.55	2,422	833	8.59	2,422	2,999
7.57	2,422	875	8.61	2,422	3,041
7.59	2,422	916	8.63	2,422	3,083
7.61	2,422	958	8.65	2,422	3,124
7.63	2,422	1,000	8.67	2,422	3,166
7.65	2,422	1,041	8.69	2,422	3,207
7.67	2,422	1,083	8.71	2,422	3,249
7.69	2,422	1,125	8.73	2,422	3,291
7.71	2,422	1,166	8.75	2,422	3,332
7.73	2,422	1,208	8.77	2,422	3,374
7.75	2,422	1,250	8.79	2,422	3,416
7.77	2,422	1,291	8.81	2,422	3,457
7.79	2,422	1,333	8.83	2,422	3,499
7.81	2,422	1,375	8.85	2,422	3,541
7.83	2,422	1,416	8.87	2,422	3,582
7.85	2,422	1,458	8.89	2,422	3,624
7.87	2,422	1,500			
7.89	2,422	1,541			
7.91	2,422	1,583			
7.93	2,422	1,625			
7.95	2,422	1,666			
7.97	2,422	1,708			
7.99	2,422	1,750			
8.01	2,422	1,791			
8.03	2,422	1,833			
8.05	2,422	1,875			
8.07	2,422	1,916			
8.09	2,422	1,958			
8.11	2,422	1,999			
8.13	2,422	2,041			
8.15	2,422	2,083			
8.17	2,422	2,124			

Drawdown Within 72-Hours

Pond 1P

Rv = Recharge Volume, 7,826 cu.ft. (see above)

K = Saturated Hydraulic Conductivity, 0.27 in/hr (from Rawls Table) = 0.0225 ft/hr

Bottom Area = Area of Infiltration System Bottom, 7,459 sq.ft. (see HydroCAD)

$$Time = \frac{Rv}{(K)(Bottom\ Area)}$$

$$Time = \left(\frac{7,826\ cu.\ ft.}{(0.0225\ ft/hr)(7,459\ sq.\ ft.)} \right) =$$

Time = 46.6 hours

- 46.6 hours < 72 hours

Pond 3P (Rain Garden)

Rv = Recharge Volume, 190 cu.ft. (see HydroCAD)

K = Saturated Hydraulic Conductivity, 0.27 in/hr (from Rawls Table) = 0.0225 ft/hr

Bottom Area = Area of Infiltration System Bottom, 125 sq.ft. (see HydroCAD)

$$Time = \frac{Rv}{(K)(Bottom\ Area)}$$

$$Time = \left(\frac{190\ cu.\ ft.}{(0.0225\ ft/hr)(125\ sq.\ ft.)} \right) =$$

Time = 67.6 hours

- 67.6 hours < 72 hours

Pond 4P-6P (Townhouse Trench Drain Infiltration Systems)

Same bottom area, worst case provided

Rv = Recharge Volume, 127 cu.ft. (see above)

K = Saturated Hydraulic Conductivity, 0.27 in/hr (from Rawls Table) = 0.0225 ft/hr

Bottom Area = Area of Infiltration System Bottom, 100.75 sq.ft.

$$Time = \frac{Rv}{(K)(Bottom\ Area)}$$

$$Time = \left(\frac{127\ cu.\ ft.}{(0.0225\ ft/hr)(100.75\ sq.\ ft.)} \right) =$$

Time = 56.0 hours

- 56.0 hours < 72 hours

Pond 7P

Rv = Recharge Volume, 417 cu.ft (see HydroCAD)

K = Saturated Hydraulic Conductivity, 0.27 in/hr (from Rawls Table) = 0.0225 ft/hr

Bottom Area = Area of Infiltration System Bottom, 2,421.8 sq.ft.

$$Time = \frac{Rv}{(K)(Bottom\ Area)}$$

$$Time = \left(\frac{417\ cu.\ ft.}{(0.0225\ ft/hr)(2,421\ sq.\ ft.)} \right) =$$

Time = 7.7 hours

- 7.7 hours < 72 hours

6.03 WATER QUALITY VOLUME CALCULATIONS

Water Quality Volume Calculation

$$V_{WQ} = (D_{WQ}/12 \text{ inches/foot}) * (A_{IMP} \text{ square feet})$$

V_{WQ} = Required Water Quality Volume (in cubic feet)

D_{WQ} = Water Quality Depth: **0.5-inch**

A_{IMP} = Total Impervious Area (in acres) used for driveways, parking, etc.

Underground Infiltration Systems and Bio-Retention Areas

$$A_{IMP} = 32,590 \text{ sq.ft.}$$

$$V_{WQ} = (0.5 \text{ inches}/12 \text{ inches/foot}) * (32,590 \text{ sq.ft.})$$

$V_{WQ} = 1,358$ cubic feet (required volume)

Provided volume = 8,783 cubic feet in Underground Infiltration System (refer to the HydroCAD storage tables provided in groundwater recharge section)

6.04 RIP-RAP OUTLET PROTECTION SIZING

OUTLET PROTECTION SIZING



Project No. 23407.02
 Subject Outlet Protection Sizing Calcs
 Location Arlington, MA

Calc By EAD
 Date 12/16/2024
 Checked by DRR
 Date 12/16/2024

FES-1

Q=Design Discharge, (ft³/s) = 11.1 cfs
 D=Culvert Diameter, (ft) = 1.50 ft
 TW=Tailwater Depth, (ft) = 0.6 ft, (0.4xD for unknow tailwater, or enter known tailwater)
 (Tailwater depth is to be limited to between 0.4D and 1.0D)

Riprap Rock Sizing

$$D_{50} = 0.2D \left[\frac{Q}{\sqrt{gD^{2.5}}} \right]^{4/3} \left[\frac{D}{TW} \right]$$

g=32.2 fps
 D₅₀ = median rock size, ft

$$D_{50} = 0.28 \left| \frac{11.10}{15.64} \right|^{(4/3)} \left| \frac{1.50}{0.60} \right| = 0.44 \text{ ft}$$

$$= 5.32 \text{ inches}$$

Table 1 : Riprap Classes and Apron Dimensions

Class	D ₅₀ (in)	Apron Length	Apron Depth
1	5	4D	3.5D ₅₀
2	6	4D	3.5D₅₀
3	10	5D	3.3D ₅₀
4	14	6D	2.2D ₅₀
5	20	7D	2.0D ₅₀
6	22	8D	2.0D ₅₀

Use Class 2

Apron Dimensions

Length, L=5D = **8 ft**
 Depth=3.3D₅₀ = **19.80 Inches**
 Width=3D+(2/3)L = **9.50 ft** (at apron end)

Riprap Rock Sizing Gradation

Given Size	Size of Stone, inches
100	9 to 12
85	8 to 11
50	6 to 9
15	3 to 8

6.05 GROUNDWATER MOUNDING ANALYSIS

Infiltration Systems 2-6

Input Values

1.5979
0.080
5.40
6.920
3.640
1.000
16.000

R
Sy
K
x
y
t
hi(0)

Recharge (infiltration) rate (feet/day)
Specific yield, *Sy* (dimensionless, between 0 and 1)
Horizontal hydraulic conductivity, *Kh* (feet/day)*
1/2 length of basin (*x* direction, in feet)
1/2 width of basin (*y* direction, in feet)
duration of infiltration period (days)
initial thickness of saturated zone (feet)

inch/hour	feet/day
0.67	1.33
2.00	4.00
hours	days
36	1.50

In the repor
(USGS SIR 2
(ft/d) is assu
hydraulic co

16.756
0.756

h(max)
Δh(max)

maximum thickness of saturated zone (beneath center of basin at end of infiltration period)
maximum groundwater mounding (beneath center of basin at end of infiltration period)


Ground- Distance from
water center of basin
Mounding, in in *x* direction, in
feet feet

0.756	0
0.291	20
0.120	40
0.078	50
0.051	60
0.033	70
0.022	80
0.015	90
0.012	100
0.008	120

ESHGW=4.0
Bot System=7.0
Separation=3.0
Mound=0.756 < 3.0



Re-Calculate Now



Disclaimer

This spreadsheet solving the Hantush (1967) equation for ground-water mounding beneath an infiltration basin is made available to the general public as a convenience for those wishing to replicate values documented in the USGS Scientific Investigations Report 2010-5102 "Groundwater mounding beneath hypothetical stormwater infiltration basins" or to calculate values based on user-specified site conditions. Any changes made to the spreadsheet (other than values identified as user-specified) after transmission from the USGS could have unintended, undesirable consequences. These consequences could include, but may not be limited to: erroneous output, numerical instabilities, and violations of underlying assumptions that are inherent in results presented in the accompanying USGS published report. The USGS assumes no responsibility for the consequences of any changes made to the spreadsheet. If changes are made to the spreadsheet, the user is responsible for documenting the changes and justifying the results and conclusions.

Recharge/Infiltration Rate (ft/day) = [Required Recharge Volume (cft)/Bottom Recharge System (sft)]/Duration (day)

100 year recharge volume 161 cft

Bottom Recharge System 100.755 sft

Duration 1 day

Recharge/Infiltration Rate 1.5979 ft/day

Horizontal Hydraulic Conductivity (ft/day) = [Rawls Rate (in/hr) * (1ft/12in) * (24hr/1day)] * 10

Rawls Rate (silt loam) 0.27 in/hr

Horizontal Hydraulic Conductivity 5.40 ft/day

NOTE: All driveway infiltration systems are the same size and have the same discarded volume in the 100-year event

Summary for Pond 8P: Inf Syst-6

Inflow Area = 1,056 sf, 99.24% Impervious, Inflow Depth = 11.26" for 100-Year event
 Inflow = 0.3 cfs @ 12.08 hrs, Volume= 991 cf
 Outflow = 0.3 cfs @ 12.09 hrs, Volume= 990 cf, Atten= 0%, Lag= 0.5 min
 Discarded = 0.0 cfs @ 1.08 hrs, Volume= 161 cf
 Primary = 0.3 cfs @ 12.09 hrs, Volume= 828 cf
 Routed to Pond 1P : Underground Infiltration System

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.35' @ 12.09 hrs Surf.Area= 101 sf Storage= 124 cf

Plug-Flow detention time= 277.9 min calculated for 990 cf (100% of inflow)
 Center-of-Mass det. time= 277.4 min (1,014.7 - 737.2)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	73 cf	7.28'W x 13.84'L x 2.39'H Field A 241 cf Overall - 58 cf Embedded = 182 cf x 40.0% Voids
#2A	7.25'	52 cf	Ferguson R-Tank XD 11 x 10 Inside #1 Inside= 19.7"W x 21.7"H => 2.66 sf x 1.97'L = 5.2 cf Outside= 19.7"W x 21.7"H => 2.96 sf x 1.97'L = 5.8 cf 10 Chambers in 2 Rows
		125 cf	Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.00'	8.0" Round Culvert L= 46.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.00' / 8.77' S= 0.0050 '/' Cc= 0.900 n= 0.013, Flow Area= 0.35 sf

Discarded OutFlow Max=0.0 cfs @ 1.08 hrs HW=7.03' (Free Discharge)
 ↑1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.3 cfs @ 12.09 hrs HW=9.35' (Free Discharge)
 ↑2=Culvert (Barrel Controls 0.3 cfs @ 2.11 fps)

Infiltration System 7

Input Values

0.6631
0.080
5.40
17.225
35.150
1.000
16.000

R
Sy
K
x
y
t
hi(0)

Recharge (infiltration) rate (feet/day)
Specific yield, Sy (dimensionless, between 0 and 1)
Horizontal hydraulic conductivity, Kh (feet/day)*
1/2 length of basin (x direction, in feet)
1/2 width of basin (y direction, in feet)
duration of infiltration period (days)
initial thickness of saturated zone (feet)

inch/hour	feet/day
0.67	1.33
2.00	4.00
hours	days
36	1.50

In the repor
(USGS SIR 20
(ft/d) is assu
hydraulic co

18.946
2.946

h(max)
Δh(max)

maximum thickness of saturated zone (beneath center of basin at end of infiltration period)
maximum groundwater mounding (beneath center of basin at end of infiltration period)

Ground-
water
Mounding, in
feet


Distance from
center of basin
in x direction, in
feet

2.946	0
2.091	20
0.985	40
0.647	50
0.413	60
0.256	70
0.154	80
0.091	90
0.052	100
0.017	120

ESHGW=4.0
Bottom System=7.15
Separation=3.15
Mound=2.946 < 3.15



Re-Calculate Now



Disclaimer

This spreadsheet solving the Hantush (1967) equation for ground-water mounding beneath an infiltration basin is made available to the general public as a convenience for those wishing to replicate values documented in the USGS Scientific Investigations Report 2010-5102 "Groundwater mounding beneath hypothetical stormwater infiltration basins" or to calculate values based on user-specified site conditions. Any changes made to the spreadsheet (other than values identified as user-specified) after transmission from the USGS could have unintended, undesirable consequences. These consequences could include, but may not be limited to: erroneous output, numerical instabilities, and violations of underlying assumptions that are inherent in results presented in the accompanying USGS published report. The USGS assumes no responsibility for the consequences of any changes made to the spreadsheet. If changes are made to the spreadsheet, the user is responsible for documenting the changes and justifying the results and conclusions.

Recharge/Infiltration Rate (ft/day) = [Required Recharge Volume (cft)/Bottom Recharge System (sft)]/Duration (day)

100 year recharge volume 1,606 cft

Bottom Recharge System 2,421.835 sft

Duration 1 day

Recharge/Infiltration Rate 0.6631 ft/day

Horizontal Hydraulic Conductivity (ft/day) = [Rawls Rate (in/hr) * (1ft/12in) * (24hr/1day)] * 10

Rawls Rate (silt loam) 0.27 in/hr

Horizontal Hydraulic Conductivity 5.40 ft/day

Summary for Pond 9P: Inf Syst-7

Inflow Area = 24,698 sf, 71.15% Impervious, Inflow Depth = 10.36" for 100-Year event
 Inflow = 6.3 cfs @ 12.08 hrs, Volume= 21,328 cf
 Outflow = 3.5 cfs @ 12.20 hrs, Volume= 21,328 cf, Atten= 45%, Lag= 7.1 min
Discarded = 0.0 cfs @ 3.69 hrs, Volume= 1,606 cf
 Primary = 3.5 cfs @ 12.20 hrs, Volume= 19,722 cf
 Routed to Link 1L : Towards Wetlands

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 8.89' @ 12.20 hrs Surf.Area= 2,422 sf Storage= 3,633 cf

Plug-Flow detention time= 43.0 min calculated for 21,325 cf (100% of inflow)
 Center-of-Mass det. time= 43.1 min (806.8 - 763.8)

Volume	Invert	Avail.Storage	Storage Description
#1	7.15'	5,207 cf	6.89'W x 14.06'L x 2.50'H StormTrap ST-1 Units (Irregular Shape) 25 6,055 cf Overall x 86.0% Voids

Device	Routing	Invert	Outlet Devices
#1	Discarded	7.15'	0.270 in/hr Exfiltration over Surface area
#2	Primary	7.15'	12.0" Round Culvert L= 4.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 7.15' / 7.13' S= 0.0050 '/ Cc= 0.900 n= 0.013, Flow Area= 0.79 sf
#3	Device 2	7.35'	22.0" W x 4.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

Discarded OutFlow Max=0.0 cfs @ 3.69 hrs HW=7.18' (Free Discharge)
 ↑1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=3.5 cfs @ 12.20 hrs HW=8.89' (Free Discharge)
 ↑2=Culvert (Passes 3.5 cfs of 4.2 cfs potential flow)
 ↑3=Orifice/Grate (Orifice Controls 3.5 cfs @ 5.65 fps)

Specific Yield-- Compilation of Specific Yields for Various Materials

GEOLOGICAL SURVEY WATER SUPPLY PAPER 1662-D

*Prepared in cooperation with the
California Department of
Water Resources*



TABLE 29.—*Compilation of specific yields for various materials*
 [All values rounded off to nearest whole percentage]

Material	Valley fill, California (Eckis, 1934)	Mokelumne area, California (Piper and others, 1939)	Santa Ynez River basin, California (Upson and Thomasson, 1951)	Sacramento Valley, Calif. (Poland and others, 1949)	Smith River plain, California (Back, 1957)	Ventura County, Calif. (Calif. Water Resources Board, 1956)	Santa Margarita Valley, Calif. (Calif. Dept. Public Works, 1956)	Tia Juana Basin, Calif. (Calif. Water Rights Board, 1957)	San Luis Obispo County, Calif. (Calif. Water Resources Board, 1958)	San Joaquin Valley, Calif. (Davis and others, 1959)	Eureka area, California (Evenson, 1959)	Santa Ynez Basin, Calif. (Wilson, 1959)	Rechna Doab, Pakistan (Kazmi, 1961)	Napa-Sonoma Valleys, Calif. (Kunkel and Upson, 1960)	Humboldt River Valley, Nev. (Cohen, 1963)	Unconsolidated alluvium (Preuss and Todd, 1963)	Little Bighorn River valley, Montana (Moulder and Others, 1960)	Average specific yield
Clay.....	1	4	2	3	1	0	1	1	3	3	3	5	3	3	1	4	17	2
Silt.....	10	4	12	3	5	3	10	10	5	5	10	5	5	5	19	4	17	8
Sandy clay.....	10	4	12	3	5	5	5	5	5	5	10	5	5	10	26	23	32	7
Fine sand.....	21	26	12	10	10	25	28	25	25	10	20	20	27	20	28	23	32	21
Medium sand.....	31	26	30	20	15	25	28	30	25	25	20	30	28	20	28	28	32	26
Coarse sand.....	31	35	35	20	25	25	28	32	25	25	20	30	23	20	27	28	32	27
Gravelly sand.....	31	35	35	20	25	21	22	28	21	25	20	23	23	20	22	22	32	25
Fine gravel.....	27	35	35	25	25	21	22	26	21	25	25	25	26	25	19	17	25	25
Medium gravel.....	21	25	25	25	25	21	22	23	21	25	25	25	26	25	26	13	25	23
Coarse gravel.....	14	25	25	25	25	21	22	18	21	25	25	25	26	25	12	12	25	22

6.06 ILLICIT DISCHARGE COMPLIANCE STATEMENT


Illicit Discharge Compliance Statement

This statement is to document that, to the best of my knowledge and belief, there are no and will be no illicit discharges to the stormwater management systems or protected wetland resource areas for the Thorndike Place residential development on Dorothy Road in Arlington, Massachusetts.

Authorized Signature/Title

Date

APPENDIX A
USGS LOCUS MAP



PREPARED FOR:
 ARLINGTON LAND
 REALTY, LLC
 84 SHERMAN ST, 2ND
 FLOOR
 CAMBRIDGE, MA 02140

USGS LOCUS MAP
 THRONDIKE PLACE
 DOROTHY ROAD
 ARLINGTON, MA


BSC GROUP
 803 Summer Street
 Boston, Massachusetts
 02127
 617 896 4300

Job No.: 23407.02 Date: 08/22/2023
 Scale: 1"=1,000' Revised:
 Dwg. No.: _____ Fig. of 504 of 1

APPENDIX B

FEMA MAP

ff1



FHOG

1) 688 85(8) 8888

6882 6886	LWRW %DHJRRGOHDLRQ % -FCH\$ 9 \$ LWK%RUFBVK -FCH\$ 88-9 \$ \$HODWRLJRRG
2682 2686	\$DOD &OHPHRRG-EPUG \$HD/ R DODD FROPHIORRGZWKDHUHD G-SVKOHV WKOQRCHIRW RU ZWKGLD DUHD/R OHV WKOQRCHVDOHEOHCH; XWUH&QGLVLRQ/\$DOD &OHPHRRG-EPUG -FCH; \$HDZWK&GPHRRG&NGHWR HMH GH RVH -FCH; \$HDZWKORRG&NGHWRHMH -FCH
2688	\$HJR OQLD O RRG-EPUG -FCH; (HFWL YHJ \$HJR &GWHUHQG O RRG-EPUG -FCH
6888	&OQD &OYHUW RU &VRURZU HMLNH RU JRRGDO
26	\$URV &FWLRQ/ ZWKSODD &OHPH DVHU &UIDPHOYDLRQ &DWDJ TUDQFW %DHJRRGOHDLRQLQ % LEW R &VXG -XULVLFVLRQ%&OQD &DWDJ TUDQFW %DHLQ \$URLOH%DHLQ \$URUDSLFJHDVUH
6888	LLWDD DWD\$DLODQD RLJWDD DWD\$DLODQD &E88G

74SLQGL VSDHGRQWKHESLV DQDSSURLBDW
SRLQV VHOHFWHGEWKHXHU DQGRVH QRV UHSH
DQDWKULWDLVYHSURSUWOFDVLQ

74LVBSFBDLHVZWKJW WDDQDUG/IRU WKHXHR
GLJWDD IO RRGES/LI LW LV QRV YRLGDV GHVULHGGEORZ
74HEDVBSVRRQFBDLHVZWKJWEDVBS
DFXUR WDDQDUG/

74IORGKQJGLQRUBMLRQLV GULYHGGLUHFVWUURVWK
DVKULWDLVYHZEHVYLPHV SURLGHGE 74LVBS
ZV HSRUWHGRQ DV 3 DQGRVH QRV
UHOHFW FROPHV RU OQDQVW VEHXHQV VRWKLVDGWHQDQ
WLF 74H DQGHIFWLYHLQRUBMLRQB FROPHV
EFFFVSHUVHGGEQZDQDVRVUWLF

74LVBSLBDLHVYRLGLI WKHQHURU RUHR WKHROORZQJES
HOPQWVGRQV DSSDU EDVBSLBDH IO RRGFRODQDQV
OHFHG VDDHEDVBSFHDVLQDQVH FROVWLGQDMLLHV
)SSQD QEHU DQGHIFWLYHGDMH DSLBHVIRU
XCE88GDQXRGUQLJGDVHDFROQV EHXVHGIRU
UHKODWRLJUSRVH

APPENDIX C
WEB SOIL SURVEY




United States
Department of
Agriculture

NRCS

Natural
Resources
Conservation
Service

A product of the National
Cooperative Soil Survey,
a joint effort of the United
States Department of
Agriculture and other
Federal agencies, State
agencies including the
Agricultural Experiment
Stations, and local
participants

Custom Soil Resource Report for Middlesex County, Massachusetts



Preface

Soil surveys contain information that affects land use planning in survey areas. They highlight soil limitations that affect various land uses and provide information about the properties of the soils in the survey areas. Soil surveys are designed for many different users, including farmers, ranchers, foresters, agronomists, urban planners, community officials, engineers, developers, builders, and home buyers. Also, conservationists, teachers, students, and specialists in recreation, waste disposal, and pollution control can use the surveys to help them understand, protect, or enhance the environment.

Various land use regulations of Federal, State, and local governments may impose special restrictions on land use or land treatment. Soil surveys identify soil properties that are used in making various land use or land treatment decisions. The information is intended to help the land users identify and reduce the effects of soil limitations on various land uses. The landowner or user is responsible for identifying and complying with existing laws and regulations.

Although soil survey information can be used for general farm, local, and wider area planning, onsite investigation is needed to supplement this information in some cases. Examples include soil quality assessments (<http://www.nrcs.usda.gov/wps/portal/nrcs/main/soils/health/>) and certain conservation and engineering applications. For more detailed information, contact your local USDA Service Center (<https://offices.sc.egov.usda.gov/locator/app?agency=nrcs>) or your NRCS State Soil Scientist (http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/contactus/?cid=nrcs142p2_053951).

Great differences in soil properties can occur within short distances. Some soils are seasonally wet or subject to flooding. Some are too unstable to be used as a foundation for buildings or roads. Clayey or wet soils are poorly suited to use as septic tank absorption fields. A high water table makes a soil poorly suited to basements or underground installations.

The National Cooperative Soil Survey is a joint effort of the United States Department of Agriculture and other Federal agencies, State agencies including the Agricultural Experiment Stations, and local agencies. The Natural Resources Conservation Service (NRCS) has leadership for the Federal part of the National Cooperative Soil Survey.

Information about soils is updated periodically. Updated information is available through the NRCS Web Soil Survey, the site for official soil survey information.

The U.S. Department of Agriculture (USDA) prohibits discrimination in all its programs and activities on the basis of race, color, national origin, age, disability, and where applicable, sex, marital status, familial status, parental status, religion, sexual orientation, genetic information, political beliefs, reprisal, or because all or a part of an individual's income is derived from any public assistance program. (Not all prohibited bases apply to all programs.) Persons with disabilities who require

alternative means for communication of program information (Braille, large print, audiotape, etc.) should contact USDA's TARGET Center at (202) 720-2600 (voice and TDD). To file a complaint of discrimination, write to USDA, Director, Office of Civil Rights, 1400 Independence Avenue, S.W., Washington, D.C. 20250-9410 or call (800) 795-3272 (voice) or (202) 720-6382 (TDD). USDA is an equal opportunity provider and employer.

Contents

Preface	2
How Soil Surveys Are Made	5
Soil Map	8
Soil Map.....	9
Legend.....	10
Map Unit Legend.....	11
Map Unit Descriptions.....	11
Middlesex County, Massachusetts.....	13
51A—Swansea muck, 0 to 1 percent slopes.....	13
52A—Freetown muck, 0 to 1 percent slopes.....	14
603—Urban land, wet substratum.....	16
626B—Merrimac-Urban land complex, 0 to 8 percent slopes.....	16
655—Udorthents, wet substratum.....	18
References	20

How Soil Surveys Are Made

Soil surveys are made to provide information about the soils and miscellaneous areas in a specific area. They include a description of the soils and miscellaneous areas and their location on the landscape and tables that show soil properties and limitations affecting various uses. Soil scientists observed the steepness, length, and shape of the slopes; the general pattern of drainage; the kinds of crops and native plants; and the kinds of bedrock. They observed and described many soil profiles. A soil profile is the sequence of natural layers, or horizons, in a soil. The profile extends from the surface down into the unconsolidated material in which the soil formed or from the surface down to bedrock. The unconsolidated material is devoid of roots and other living organisms and has not been changed by other biological activity.

Currently, soils are mapped according to the boundaries of major land resource areas (MLRAs). MLRAs are geographically associated land resource units that share common characteristics related to physiography, geology, climate, water resources, soils, biological resources, and land uses (USDA, 2006). Soil survey areas typically consist of parts of one or more MLRA.

The soils and miscellaneous areas in a survey area occur in an orderly pattern that is related to the geology, landforms, relief, climate, and natural vegetation of the area. Each kind of soil and miscellaneous area is associated with a particular kind of landform or with a segment of the landform. By observing the soils and miscellaneous areas in the survey area and relating their position to specific segments of the landform, a soil scientist develops a concept, or model, of how they were formed. Thus, during mapping, this model enables the soil scientist to predict with a considerable degree of accuracy the kind of soil or miscellaneous area at a specific location on the landscape.

Commonly, individual soils on the landscape merge into one another as their characteristics gradually change. To construct an accurate soil map, however, soil scientists must determine the boundaries between the soils. They can observe only a limited number of soil profiles. Nevertheless, these observations, supplemented by an understanding of the soil-vegetation-landscape relationship, are sufficient to verify predictions of the kinds of soil in an area and to determine the boundaries.

Soil scientists recorded the characteristics of the soil profiles that they studied. They noted soil color, texture, size and shape of soil aggregates, kind and amount of rock fragments, distribution of plant roots, reaction, and other features that enable them to identify soils. After describing the soils in the survey area and determining their properties, the soil scientists assigned the soils to taxonomic classes (units). Taxonomic classes are concepts. Each taxonomic class has a set of soil characteristics with precisely defined limits. The classes are used as a basis for comparison to classify soils systematically. Soil taxonomy, the system of taxonomic classification used in the United States, is based mainly on the kind and character of soil properties and the arrangement of horizons within the profile. After the soil

scientists classified and named the soils in the survey area, they compared the individual soils with similar soils in the same taxonomic class in other areas so that they could confirm data and assemble additional data based on experience and research.

The objective of soil mapping is not to delineate pure map unit components; the objective is to separate the landscape into landforms or landform segments that have similar use and management requirements. Each map unit is defined by a unique combination of soil components and/or miscellaneous areas in predictable proportions. Some components may be highly contrasting to the other components of the map unit. The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The delineation of such landforms and landform segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, onsite investigation is needed to define and locate the soils and miscellaneous areas.

Soil scientists make many field observations in the process of producing a soil map. The frequency of observation is dependent upon several factors, including scale of mapping, intensity of mapping, design of map units, complexity of the landscape, and experience of the soil scientist. Observations are made to test and refine the soil-landscape model and predictions and to verify the classification of the soils at specific locations. Once the soil-landscape model is refined, a significantly smaller number of measurements of individual soil properties are made and recorded. These measurements may include field measurements, such as those for color, depth to bedrock, and texture, and laboratory measurements, such as those for content of sand, silt, clay, salt, and other components. Properties of each soil typically vary from one point to another across the landscape.

Observations for map unit components are aggregated to develop ranges of characteristics for the components. The aggregated values are presented. Direct measurements do not exist for every property presented for every map unit component. Values for some properties are estimated from combinations of other properties.

While a soil survey is in progress, samples of some of the soils in the area generally are collected for laboratory analyses and for engineering tests. Soil scientists interpret the data from these analyses and tests as well as the field-observed characteristics and the soil properties to determine the expected behavior of the soils under different uses. Interpretations for all of the soils are field tested through observation of the soils in different uses and under different levels of management. Some interpretations are modified to fit local conditions, and some new interpretations are developed to meet local needs. Data are assembled from other sources, such as research information, production records, and field experience of specialists. For example, data on crop yields under defined levels of management are assembled from farm records and from field or plot experiments on the same kinds of soil.

Predictions about soil behavior are based not only on soil properties but also on such variables as climate and biological activity. Soil conditions are predictable over long periods of time, but they are not predictable from year to year. For example, soil scientists can predict with a fairly high degree of accuracy that a given soil will have a high water table within certain depths in most years, but they cannot predict that a high water table will always be at a specific level in the soil on a specific date.

After soil scientists located and identified the significant natural bodies of soil in the survey area, they drew the boundaries of these bodies on aerial photographs and

Custom Soil Resource Report

identified each as a specific map unit. Aerial photographs show trees, buildings, fields, roads, and rivers, all of which help in locating boundaries accurately.


Soil Map

The soil map section includes the soil map for the defined area of interest, a list of soil map units on the map and extent of each map unit, and cartographic symbols displayed on the map. Also presented are various metadata about data used to produce the map, and a description of each soil map unit.

Custom Soil Resource Report Soil Map




Map Scale: 1:4,500 if printed on A landscape (11" x 8.5") sheet.




MAP LEGEND


Area of Interest (AOI)

 Area of Interest (AOI)




















Soils







 Soil Map Unit Polygons

 Soil Map Unit Lines


 Soil Map Unit Points

Special Point Features






-  Blowout
-  Borrow Pit
-  Clay Spot
-  Closed Depression
-  Gravel Pit
-  Gravelly Spot
-  Landfill
-  Lava Flow
-  Marsh or swamp
-  Mine or Quarry
-  Miscellaneous Water
-  Perennial Water
-  Rock Outcrop
-  Saline Spot
-  Sandy Spot
-  Severely Eroded Spot
-  Sinkhole
-  Slide or Slip
-  Sodic Spot

-  Spoil Area
-  Stony Spot
-  Very Stony Spot
-  Wet Spot
-  Other
-  Special Line Features

Water Features

 Streams and Canals

Transportation

-  Rails
-  Interstate Highways
-  US Routes
-  Major Roads
-  Local Roads

Background

 Aerial Photography

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:25,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service
 Web Soil Survey URL:
 Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Middlesex County, Massachusetts
 Survey Area Data: Version 20, Jun 9, 2020

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Sep 11, 2019—Oct 5, 2019

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Map Unit Legend

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
51A	Swansea muck, 0 to 1 percent slopes	4.3	4.6%
52A	Freetown muck, 0 to 1 percent slopes	10.4	11.2%
603	Urban land, wet substratum	32.1	34.5%
626B	Merrimac-Urban land complex, 0 to 8 percent slopes	14.3	15.4%
655	Udorthents, wet substratum	31.9	34.3%
Totals for Area of Interest		92.9	100.0%

Map Unit Descriptions

The map units delineated on the detailed soil maps in a soil survey represent the soils or miscellaneous areas in the survey area. The map unit descriptions, along with the maps, can be used to determine the composition and properties of a unit.

A map unit delineation on a soil map represents an area dominated by one or more major kinds of soil or miscellaneous areas. A map unit is identified and named according to the taxonomic classification of the dominant soils. Within a taxonomic class there are precisely defined limits for the properties of the soils. On the landscape, however, the soils are natural phenomena, and they have the characteristic variability of all natural phenomena. Thus, the range of some observed properties may extend beyond the limits defined for a taxonomic class. Areas of soils of a single taxonomic class rarely, if ever, can be mapped without including areas of other taxonomic classes. Consequently, every map unit is made up of the soils or miscellaneous areas for which it is named and some minor components that belong to taxonomic classes other than those of the major soils.

Most minor soils have properties similar to those of the dominant soil or soils in the map unit, and thus they do not affect use and management. These are called noncontrasting, or similar, components. They may or may not be mentioned in a particular map unit description. Other minor components, however, have properties and behavioral characteristics divergent enough to affect use or to require different management. These are called contrasting, or dissimilar, components. They generally are in small areas and could not be mapped separately because of the scale used. Some small areas of strongly contrasting soils or miscellaneous areas are identified by a special symbol on the maps. If included in the database for a given area, the contrasting minor components are identified in the map unit descriptions along with some characteristics of each. A few areas of minor components may not have been observed, and consequently they are not mentioned in the descriptions, especially where the pattern was so complex that it was impractical to make enough observations to identify all the soils and miscellaneous areas on the landscape.

Custom Soil Resource Report

The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The objective of mapping is not to delineate pure taxonomic classes but rather to separate the landscape into landforms or landform segments that have similar use and management requirements. The delineation of such segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, however, onsite investigation is needed to define and locate the soils and miscellaneous areas.

An identifying symbol precedes the map unit name in the map unit descriptions. Each description includes general facts about the unit and gives important soil properties and qualities.

Soils that have profiles that are almost alike make up a *soil series*. Except for differences in texture of the surface layer, all the soils of a series have major horizons that are similar in composition, thickness, and arrangement.

Soils of one series can differ in texture of the surface layer, slope, stoniness, salinity, degree of erosion, and other characteristics that affect their use. On the basis of such differences, a soil series is divided into *soil phases*. Most of the areas shown on the detailed soil maps are phases of soil series. The name of a soil phase commonly indicates a feature that affects use or management. For example, Alpha silt loam, 0 to 2 percent slopes, is a phase of the Alpha series.

Some map units are made up of two or more major soils or miscellaneous areas. These map units are complexes, associations, or undifferentiated groups.

A *complex* consists of two or more soils or miscellaneous areas in such an intricate pattern or in such small areas that they cannot be shown separately on the maps. The pattern and proportion of the soils or miscellaneous areas are somewhat similar in all areas. Alpha-Beta complex, 0 to 6 percent slopes, is an example.

An *association* is made up of two or more geographically associated soils or miscellaneous areas that are shown as one unit on the maps. Because of present or anticipated uses of the map units in the survey area, it was not considered practical or necessary to map the soils or miscellaneous areas separately. The pattern and relative proportion of the soils or miscellaneous areas are somewhat similar. Alpha-Beta association, 0 to 2 percent slopes, is an example.

An *undifferentiated group* is made up of two or more soils or miscellaneous areas that could be mapped individually but are mapped as one unit because similar interpretations can be made for use and management. The pattern and proportion of the soils or miscellaneous areas in a mapped area are not uniform. An area can be made up of only one of the major soils or miscellaneous areas, or it can be made up of all of them. Alpha and Beta soils, 0 to 2 percent slopes, is an example.

Some surveys include *miscellaneous areas*. Such areas have little or no soil material and support little or no vegetation. Rock outcrop is an example.

Middlesex County, Massachusetts

51A—Swansea muck, 0 to 1 percent slopes

Map Unit Setting

National map unit symbol: 2trl2
Elevation: 0 to 1,140 feet
Mean annual precipitation: 36 to 71 inches
Mean annual air temperature: 39 to 55 degrees F
Frost-free period: 140 to 240 days
Farmland classification: Not prime farmland

Map Unit Composition

Swansea and similar soils: 80 percent
Minor components: 20 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Swansea

Setting

Landform: Swamps, bogs
Landform position (three-dimensional): Dip
Down-slope shape: Concave
Across-slope shape: Concave
Parent material: Highly decomposed organic material over loose sandy and gravelly glaciofluvial deposits

Typical profile

Oa1 - 0 to 24 inches: muck
Oa2 - 24 to 34 inches: muck
Cg - 34 to 79 inches: coarse sand

Properties and qualities

Slope: 0 to 1 percent
Depth to restrictive feature: More than 80 inches
Drainage class: Very poorly drained
Runoff class: Negligible
Capacity of the most limiting layer to transmit water (Ksat): Moderately low to high
(0.14 to 14.17 in/hr)
Depth to water table: About 0 to 6 inches
Frequency of flooding: Rare
Frequency of ponding: Frequent
Available water capacity: Very high (about 16.5 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 8w
Hydrologic Soil Group: B/D
Ecological site: F144AY043MA - Acidic Organic Wetlands
Hydric soil rating: Yes

Minor Components

Freetown

Percent of map unit: 10 percent
Landform: Bogs, swamps

Custom Soil Resource Report

Landform position (three-dimensional): Dip
Down-slope shape: Concave
Across-slope shape: Concave
Hydric soil rating: Yes

Whitman

Percent of map unit: 5 percent
Landform: Depressions, drainageways
Landform position (two-dimensional): Toeslope
Landform position (three-dimensional): Base slope
Down-slope shape: Concave
Across-slope shape: Concave
Hydric soil rating: Yes

Scarboro

Percent of map unit: 5 percent
Landform: Drainageways, depressions
Landform position (two-dimensional): Toeslope
Landform position (three-dimensional): Base slope, tread, dip
Down-slope shape: Concave
Across-slope shape: Concave
Hydric soil rating: Yes

52A—Freetown muck, 0 to 1 percent slopes

Map Unit Setting

National map unit symbol: 2t2q9
Elevation: 0 to 1,110 feet
Mean annual precipitation: 36 to 71 inches
Mean annual air temperature: 39 to 55 degrees F
Frost-free period: 140 to 240 days
Farmland classification: Not prime farmland

Map Unit Composition

Freetown and similar soils: 85 percent
Minor components: 15 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Freetown

Setting

Landform: Depressions, depressions, bogs, marshes, kettles, swamps
Landform position (two-dimensional): Toeslope
Landform position (three-dimensional): Tread, dip
Down-slope shape: Concave
Across-slope shape: Concave
Parent material: Highly decomposed organic material

Typical profile

Oe - 0 to 2 inches: mucky peat
Oa - 2 to 79 inches: muck

Properties and qualities

Slope: 0 to 1 percent
Surface area covered with cobbles, stones or boulders: 0.0 percent
Depth to restrictive feature: More than 80 inches
Drainage class: Very poorly drained
Runoff class: Negligible
Capacity of the most limiting layer to transmit water (Ksat): Moderately low to high
(0.14 to 14.17 in/hr)
Depth to water table: About 0 to 6 inches
Frequency of flooding: Rare
Frequency of ponding: Frequent
Available water capacity: Very high (about 19.2 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 5w
Hydrologic Soil Group: B/D
Ecological site: F144AY043MA - Acidic Organic Wetlands
Hydric soil rating: Yes

Minor Components

Swansea

Percent of map unit: 5 percent
Landform: Kettles, depressions, depressions, marshes, swamps, bogs
Landform position (two-dimensional): Toeslope
Landform position (three-dimensional): Tread, dip
Down-slope shape: Concave
Across-slope shape: Concave
Hydric soil rating: Yes

Scarboro

Percent of map unit: 5 percent
Landform: Depressions, drainageways
Landform position (two-dimensional): Toeslope
Landform position (three-dimensional): Base slope, tread, dip
Down-slope shape: Concave
Across-slope shape: Concave
Hydric soil rating: Yes

Whitman

Percent of map unit: 5 percent
Landform: Depressions, drainageways
Landform position (two-dimensional): Toeslope
Landform position (three-dimensional): Base slope
Down-slope shape: Concave
Across-slope shape: Concave
Hydric soil rating: Yes

603—Urban land, wet substratum

Map Unit Setting

National map unit symbol: 9951
Mean annual precipitation: 32 to 50 inches
Mean annual air temperature: 45 to 50 degrees F
Frost-free period: 110 to 200 days
Farmland classification: Not prime farmland

Map Unit Composition

Urban land: 85 percent
Minor components: 15 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Urban Land

Setting

Landform position (two-dimensional): Footslope
Landform position (three-dimensional): Base slope
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Excavated and filled land over alluvium and/or marine deposits

Minor Components

Udorthents, loamy

Percent of map unit: 10 percent
Hydric soil rating: No

Rock outcrop

Percent of map unit: 5 percent
Landform: Ledges
Landform position (two-dimensional): Summit
Landform position (three-dimensional): Head slope
Down-slope shape: Concave
Across-slope shape: Concave

626B—Merrimac-Urban land complex, 0 to 8 percent slopes

Map Unit Setting

National map unit symbol: 2tyr9
Elevation: 0 to 820 feet
Mean annual precipitation: 36 to 71 inches
Mean annual air temperature: 39 to 55 degrees F

Custom Soil Resource Report

Frost-free period: 140 to 250 days

Farmland classification: Not prime farmland

Map Unit Composition

Merrimac and similar soils: 45 percent

Urban land: 40 percent

Minor components: 15 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Merrimac

Setting

Landform: Eskers, moraines, outwash terraces, outwash plains, kames

Landform position (two-dimensional): Backslope, footslope, summit, shoulder

Landform position (three-dimensional): Side slope, crest, riser, tread

Down-slope shape: Convex

Across-slope shape: Convex

Parent material: Loamy glaciofluvial deposits derived from granite, schist, and gneiss over sandy and gravelly glaciofluvial deposits derived from granite, schist, and gneiss

Typical profile

Ap - 0 to 10 inches: fine sandy loam

Bw1 - 10 to 22 inches: fine sandy loam

Bw2 - 22 to 26 inches: stratified gravel to gravelly loamy sand

2C - 26 to 65 inches: stratified gravel to very gravelly sand

Properties and qualities

Slope: 0 to 8 percent

Depth to restrictive feature: More than 80 inches

Drainage class: Somewhat excessively drained

Runoff class: Very low

Capacity of the most limiting layer to transmit water (Ksat): Moderately high to very high (1.42 to 99.90 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None

Frequency of ponding: None

Calcium carbonate, maximum content: 2 percent

Maximum salinity: Nonsaline (0.0 to 1.4 mmhos/cm)

Sodium adsorption ratio, maximum: 1.0

Available water capacity: Low (about 4.6 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 2e

Hydrologic Soil Group: A

Ecological site: F144AY022MA - Dry Outwash

Hydric soil rating: No

Description of Urban Land

Typical profile

M - 0 to 10 inches: cemented material

Properties and qualities

Slope: 0 to 8 percent

Depth to restrictive feature: 0 inches to manufactured layer

Custom Soil Resource Report

Runoff class: Very high

Capacity of the most limiting layer to transmit water (Ksat): Very low (0.00 to 0.00 in/hr)

Available water capacity: Very low (about 0.0 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 8

Hydrologic Soil Group: D

Hydric soil rating: Unranked

Minor Components

Windsor

Percent of map unit: 5 percent

Landform: Dunes, outwash terraces, deltas, outwash plains

Landform position (three-dimensional): Tread, riser

Down-slope shape: Convex, linear

Across-slope shape: Convex, linear

Hydric soil rating: No

Sudbury

Percent of map unit: 5 percent

Landform: Outwash plains, terraces, deltas

Landform position (two-dimensional): Footslope

Landform position (three-dimensional): Tread, dip

Down-slope shape: Concave

Across-slope shape: Linear

Hydric soil rating: No

Hinckley

Percent of map unit: 5 percent

Landform: Eskers, kames, deltas, outwash plains

Landform position (two-dimensional): Summit, shoulder, backslope

Landform position (three-dimensional): Nose slope, side slope, crest, head slope, rise

Down-slope shape: Convex

Across-slope shape: Convex, linear

Hydric soil rating: No

655—Udorthents, wet substratum

Map Unit Setting

National map unit symbol: vr1n

Elevation: 0 to 3,000 feet

Mean annual precipitation: 32 to 54 inches

Mean annual air temperature: 43 to 54 degrees F

Frost-free period: 110 to 240 days

Farmland classification: Not prime farmland

Map Unit Composition

Udorthents, wet substratum, and similar soils: 85 percent

Minor components: 15 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Udorthents, Wet Substratum

Setting

Parent material: Loamy alluvium and/or sandy glaciofluvial deposits and/or loamy glaciolacustrine deposits and/or loamy marine deposits and/or loamy basal till and/or loamy lodgment till

Properties and qualities

Slope: 0 to 8 percent

Depth to restrictive feature: More than 80 inches

Depth to water table: More than 80 inches

Frequency of flooding: None

Frequency of ponding: None

Minor Components

Urban land

Percent of map unit: 8 percent

Landform position (two-dimensional): Footslope

Landform position (three-dimensional): Base slope

Down-slope shape: Linear

Across-slope shape: Linear

Freetown

Percent of map unit: 4 percent

Landform: Depressions, bogs

Landform position (two-dimensional): Toeslope

Landform position (three-dimensional): Dip

Down-slope shape: Concave

Across-slope shape: Concave

Hydric soil rating: Yes

Swansea

Percent of map unit: 3 percent

Landform: Bogs, depressions

Landform position (two-dimensional): Toeslope

Landform position (three-dimensional): Dip

Down-slope shape: Concave

Across-slope shape: Concave

Hydric soil rating: Yes

References

- American Association of State Highway and Transportation Officials (AASHTO). 2004. Standard specifications for transportation materials and methods of sampling and testing. 24th edition.
- American Society for Testing and Materials (ASTM). 2005. Standard classification of soils for engineering purposes. ASTM Standard D2487-00.
- Cowardin, L.M., V. Carter, F.C. Golet, and E.T. LaRoe. 1979. Classification of wetlands and deep-water habitats of the United States. U.S. Fish and Wildlife Service FWS/OBS-79/31.
- Federal Register. July 13, 1994. Changes in hydric soils of the United States.
- Federal Register. September 18, 2002. Hydric soils of the United States.
- Hurt, G.W., and L.M. Vasilas, editors. Version 6.0, 2006. Field indicators of hydric soils in the United States.
- National Research Council. 1995. Wetlands: Characteristics and boundaries.
- Soil Survey Division Staff. 1993. Soil survey manual. Soil Conservation Service. U.S. Department of Agriculture Handbook 18. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_054262
- Soil Survey Staff. 1999. Soil taxonomy: A basic system of soil classification for making and interpreting soil surveys. 2nd edition. Natural Resources Conservation Service, U.S. Department of Agriculture Handbook 436. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053577
- Soil Survey Staff. 2010. Keys to soil taxonomy. 11th edition. U.S. Department of Agriculture, Natural Resources Conservation Service. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053580
- Tiner, R.W., Jr. 1985. Wetlands of Delaware. U.S. Fish and Wildlife Service and Delaware Department of Natural Resources and Environmental Control, Wetlands Section.
- United States Army Corps of Engineers, Environmental Laboratory. 1987. Corps of Engineers wetlands delineation manual. Waterways Experiment Station Technical Report Y-87-1.
- United States Department of Agriculture, Natural Resources Conservation Service. National forestry manual. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/home/?cid=nrcs142p2_053374
- United States Department of Agriculture, Natural Resources Conservation Service. National range and pasture handbook. <http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/landuse/rangepasture/?cid=stelprdb1043084>

Custom Soil Resource Report

United States Department of Agriculture, Natural Resources Conservation Service. National soil survey handbook, title 430-VI. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/scientists/?cid=nrcs142p2_054242

United States Department of Agriculture, Natural Resources Conservation Service. 2006. Land resource regions and major land resource areas of the United States, the Caribbean, and the Pacific Basin. U.S. Department of Agriculture Handbook 296. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053624

United States Department of Agriculture, Soil Conservation Service. 1961. Land capability classification. U.S. Department of Agriculture Handbook 210. http://www.nrcs.usda.gov/Internet/FSE_DOCUMENTS/nrcs142p2_052290.pdf

APPENDIX D

TEST PIT LOGS



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

A. Facility Information

Arlington Land Realty, LLC

Owner Name

Dorothy Road

Street Address

Arlington

City

MA

State

16-8-2, 16-8-3, 16-8-4, 16-8-5, 16-8-6, 16-8-7A

Map/Lot #

02474

Zip Code

B. Site Information

1. (Check one) New Construction Upgrade Repair

2. Soil Survey Available? Yes No If yes:

Web Soil Survey
Source

655, 51A
Soil Map Unit

Udorthents, Swansea Muck

Soil Name

Fill throughout site; clay base layer in one test pit

Soil Limitations

Glaciofluvial deposit

Soil Parent material

Depression

Landform

3. Surficial Geological Report Available? Yes No

If yes:

2018/USGS

Year Published/Source

Glaciomarine fine deposits, stagnant ice deposits

Map Unit

fine/very fine sand down to very fine sand, silt, silty clay, and clay

Description of Geologic Map Unit:

4. Flood Rate Insurance Map Within a regulatory floodway? Yes No

5. Within a velocity zone? Yes No

6. Within a Mapped Wetland Area? Yes No

If yes, MassGIS Wetland Data Layer:

Shallow marsh meadow

Wetland Type

7. Current Water Resource Conditions (USGS):

11/25/2020

Month/Day/ Year

Range: Above Normal

Normal

Below Normal

8. Other references reviewed:

Not in Zone I, II, or IWPA (OLIVER)



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review *(minimum of two holes required at every proposed primary and reserve disposal area)*

Deep Observation Hole Number: TP-1 11/25/2020 7:45 AM Cloudy, 30deg 42.40 N 71.15 W
Hole # Date Time Weather Latitude Longitude:
 1. Land Use Woodland adjacent to residential/highway Forest Some large boulders
(e.g., woodland, agricultural field, vacant lot, etc.) Vegetation Surface Stones (e.g., cobbles, stones, boulders, etc.) Slope (%)

Description of Location: _____

2. Soil Parent Material: Glaciofluvial deposits Depression SU
Landform Position on Landscape (SU, SH, BS, FS, TS)

3. Distances from: Open Water Body >100 feet Drainage Way >100 feet Wetlands >100 feet
 Property Line >100 feet Drinking Water Well >100 feet Other _____ feet

4. Unsuitable Materials Present: Yes No If Yes: Disturbed Soil Fill Material Weathered/Fractured Rock Bedrock

5. Groundwater Observed: Yes No If yes: 108" Depth Weeping from Pit 108" Depth Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0"-10	A	SL	7.5YR 2.5/1	--	--	--	0	0	massive	friable	
10"-36"	B (fill)	gravelly sandy loam	10YR 3/3	--	--	--	10	2-4	massive	very friable	
36"-48"											
48"-108"	C1 (fill)	gravelly sandy loam	10YR 2/1	--	--	--	15-20	4-6	massive	very friable	
36"-78"	C2 (fill)	loamy sand	10YR 5/4	--	--	--	0	0	single grain	loose	sandy layer (only on E side of test pit)
78"-108"	2C2 (fill)	gravelly sandy loam	10YR 2/1	--	--	--	15-20	4-6	massive	very friable	gravelly layer below sandy layer on E side of test pit

Additional Notes:

Elevation of TP-1 = 12.0. Groundwater at bottom of test pit (9' - elevation 3.0). Test pit mostly fill



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review *(minimum of two holes required at every proposed primary and reserve disposal area)*

Deep Observation Hole Number: TP-2 11/25/20 8:45AM Cloudy, 35deg 42.40 N 71.15 W
Hole # Date Time Weather Latitude Longitude:
 1. Land Use: Woodland adjacent to residential/highway Forest Some large boulders around 0-2%
(e.g., woodland, agricultural field, vacant lot, etc.) Vegetation Surface Stones (e.g., cobbles, stones, boulders, etc.) Slope (%)

Description of Location: _____

2. Soil Parent Material: Glaciofluvial deposits Depression SU
Landform Position on Landscape (SU, SH, BS, FS, TS)
3. Distances from: Open Water Body >100 feet Drainage Way >100 feet Wetlands >100 feet
 Property Line >100 feet Drinking Water Well >100 feet Other _____ feet
4. Unsuitable
 Materials Present: Yes No If Yes: Disturbed Soil Fill Material Weathered/Fractured Rock Bedrock
5. Groundwater Observed: Yes No If yes: _____ Depth Weeping from Pit _____ Depth Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0-7	A	sandy loam	10YR 2.5/1	--	--	--	0	0	massive	friable	
7-132	C (fill)	gravelly sandy loam	10YR 3/2	--	--	--	15-20	4-6	massive	friable	

Additional Notes:
Elevation of TP-2 = 11.2. Estimated groundwater elevation (to bottom of test pit) = 0.2. Fill throughout test pit. No groundwater observed



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

D. Determination of High Groundwater Elevation

- | | | |
|---|-------------------------|-------------------------|
| 1. Method Used: | Obs. Hole # <u>TP-1</u> | Obs. Hole # <u>TP-2</u> |
| <input checked="" type="checkbox"/> Depth observed standing water in observation hole | <u>108</u> inches | _____ inches |
| <input type="checkbox"/> Depth weeping from side of observation hole | _____ inches | _____ inches |
| <input type="checkbox"/> Depth to soil redoximorphic features (mottles) | _____ inches | _____ inches |
| <input type="checkbox"/> Depth to adjusted seasonal high groundwater (S_h) (USGS methodology) | _____ inches | _____ inches |

_____ Index Well Number

_____ Reading Date

$$S_h = S_c - [S_r \times (OW_c - OW_{max}) / OW_r]$$

Obs. Hole/Well# _____ S_c _____ S_r _____ OW_c _____ OW_{max} _____ OW_r _____ S_h _____

2. Estimated Depth to High Groundwater: 108 inches

E. Depth of Pervious Material

1. Depth of Naturally Occurring Pervious Material

a. Does at least four feet of naturally occurring pervious material exist in all areas observed throughout the area proposed for the soil absorption system?

- Yes No

b. If yes, at what depth was it observed (exclude A and O Horizons)?

Upper boundary: _____ inches Lower boundary: _____ inches

c. If no, at what depth was impervious material observed?

Upper boundary: 108 inches Lower boundary: >108 (fill material) inches



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

F. Certification

I certify that I am currently approved by the Department of Environmental Protection pursuant to 310 CMR 15.017 to conduct soil evaluations and that the above analysis has been performed by me consistent with the required training, expertise and experience described in 310 CMR 15.017. I further certify that the results of my soil evaluation, as indicated in the attached Soil Evaluation Form, are accurate and in accordance with 310 CMR 15.100 through 15.107.

Signature of Soil Evaluator

Emily Derrig SE14158

Typed or Printed Name of Soil Evaluator / License #

11/25/2020

Date

12/1/2020

Expiration Date of License

Name of Approving Authority Witness

Approving Authority

Note: In accordance with 310 CMR 15.018(2) this form must be submitted to the approving authority within 60 days of the date of field testing, and to the designer and the property owner with [Percolation Test Form 12](#).

Field Diagrams: Use this area for field diagrams:



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

A. Facility Information

Arlington Land Realty, LLC

Owner Name

Dorothy Road

Street Address

Arlington

City

MA

State

16-8-2, 16-8-3, 16-8-4, 16-8-5, 16-8-6, 16-8-7A

Map/Lot #

02474

Zip Code

B. Site Information

1. (Check one) New Construction Upgrade Repair

2. Soil Survey Available? Yes No If yes:

Web Soil Survey
Source

655, 51A
Soil Map Unit

Udorthents, Swansea Muck

Soil Name

Fill throughout site; clay base layer in one test pit

Soil Limitations

Glaciofluvial deposit

Soil Parent material

Depression

Landform

3. Surficial Geological Report Available? Yes No

If yes:

2018/USGS

Year Published/Source

Glaciomarine fine deposits, stagnant ice deposits

Map Unit

fine/very fine sand down to very fine sand, silt, silty clay, and clay

Description of Geologic Map Unit:

4. Flood Rate Insurance Map Within a regulatory floodway? Yes No

5. Within a velocity zone? Yes No

6. Within a Mapped Wetland Area? Yes No

If yes, MassGIS Wetland Data Layer:

Shallow marsh meadow

Wetland Type

7. Current Water Resource Conditions (USGS):

11/25/2020

Month/Day/ Year

Range: Above Normal

Normal

Below Normal

8. Other references reviewed:

Not in Zone I, II, or IWPA (OLIVER)



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review *(minimum of two holes required at every proposed primary and reserve disposal area)*

Deep Observation Hole Number: TP-3 11/25/2020 9:45 AM Cloudy, 40deg 42.40 N 71.15 W
Hole # Date Time Weather Latitude Longitude:

1. Land Use Woodland adjacent to residential/highway Forest Some large boulders 0-2%
(e.g., woodland, agricultural field, vacant lot, etc.) Vegetation Surface Stones (e.g., cobbles, stones, boulders, etc.) Slope (%)

Description of Location: _____

2. Soil Parent Material: Glaciofluvial deposits Depression FS
Landform Position on Landscape (SU, SH, BS, FS, TS)

3. Distances from: Open Water Body >100 feet Drainage Way >100 feet Wetlands >100 feet
 Property Line >100 feet Drinking Water Well >100 feet Other feet

4. Unsuitable Materials Present: Yes No If Yes: Disturbed Soil Fill Material Weathered/Fractured Rock Bedrock

5. Groundwater Observed: Yes No If yes: 84" Depth Weeping from Pit 144" Depth Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0"-8"	A	SL	10YR 2/1	--	--	--	0	0	massive	very friable	
8"-84"	B	SL	7.5YR 2.5/2	36"	7.5YR 5/8	2-4%	2-4	0	massive	friable	
84"-108"	C1	Sandy Clay Loam	10YR 2/1	--	--	--	0	0	massive	firm	
108"-144"	C2	Clay	GLE Y 2 4/5B	--	--	--	0	0	massive	very firm	

Additional Notes:

TP-3 Elevation = 6.5. Groundwater observed at bottom of test pit (12') and weeping from sides at 7' - estimated groundwater elevation = -0.5



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review *(minimum of two holes required at every proposed primary and reserve disposal area)*

Deep Observation Hole Number:

Hole # _____ Date _____ Time _____ Weather _____ Latitude _____ Longitude: _____

1. Land Use: _____ (e.g., woodland, agricultural field, vacant lot, etc.)
Vegetation _____ Surface Stones (e.g., cobbles, stones, boulders, etc.) _____ Slope (%) _____

Description of Location: _____

2. Soil Parent Material: _____ Landform _____ Position on Landscape (SU, SH, BS, FS, TS) _____

3. Distances from: Open Water Body _____ feet Drainage Way _____ feet Wetlands _____ feet
Property Line _____ feet Drinking Water Well _____ feet Other _____ feet

4. Unsuitable

Materials Present: Yes No If Yes: Disturbed Soil Fill Material Weathered/Fractured Rock Bedrock

5. Groundwater Observed: Yes No If yes: _____ Depth Weeping from Pit _____ Depth Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			

Additional Notes:



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

D. Determination of High Groundwater Elevation

- | | | |
|---|-------------------------|-------------------|
| 1. Method Used: | Obs. Hole # <u>TP-3</u> | Obs. Hole # _____ |
| <input checked="" type="checkbox"/> Depth observed standing water in observation hole | <u>132</u> inches | _____ inches |
| <input checked="" type="checkbox"/> Depth weeping from side of observation hole | <u>84</u> inches | _____ inches |
| <input type="checkbox"/> Depth to soil redoximorphic features (mottles) | _____ inches | _____ inches |
| <input type="checkbox"/> Depth to adjusted seasonal high groundwater (S_h) (USGS methodology) | _____ inches | _____ inches |

_____ Index Well Number

_____ Reading Date

$$S_h = S_c - [S_r \times (OW_c - OW_{max}) / OW_r]$$

Obs. Hole/Well# _____ S_c _____ S_r _____ OW_c _____ OW_{max} _____ OW_r _____ S_h _____

2. Estimated Depth to High Groundwater: 84 inches

E. Depth of Pervious Material

1. Depth of Naturally Occurring Pervious Material

a. Does at least four feet of naturally occurring pervious material exist in all areas observed throughout the area proposed for the soil absorption system?

- Yes No

b. If yes, at what depth was it observed (exclude A and O Horizons)?

Upper boundary: _____ inches Lower boundary: _____ inches

c. If no, at what depth was impervious material observed?

Upper boundary: 84 inches Lower boundary: 132 inches



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

F. Certification

I certify that I am currently approved by the Department of Environmental Protection pursuant to 310 CMR 15.017 to conduct soil evaluations and that the above analysis has been performed by me consistent with the required training, expertise and experience described in 310 CMR 15.017. I further certify that the results of my soil evaluation, as indicated in the attached Soil Evaluation Form, are accurate and in accordance with 310 CMR 15.100 through 15.107.

Signature of Soil Evaluator

Emily Derrig SE14158

Typed or Printed Name of Soil Evaluator / License #

11/25/2020

Date

12/1/2020

Expiration Date of License

Name of Approving Authority Witness

Approving Authority

Note: In accordance with 310 CMR 15.018(2) this form must be submitted to the approving authority within 60 days of the date of field testing, and to the designer and the property owner with [Percolation Test Form 12](#).

Field Diagrams: Use this area for field diagrams:



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

A. Facility Information

Arlington Land Realty, LLC.

Owner Name

Dorothy Road

Street Address

Arlington

City

MA

State

16-8-2, 16-8-3, 16-8-4, 16-8-5, 16-8-6, 16-8-7A

Map/Lot #

02474

Zip Code

B. Site Information

1. (Check one) New Construction Upgrade

2. Soil Survey NRCS USDA Web Soil Survey

Source

655

Soil Map Unit

Udorthents, wet substratum

Soil Series

Depressions

Landform

Loamy alluvium and/or sandy glaciofluvial deposits and/or loamy glaciolacustrine deposites and/or loamy marine deposits and/or loamy basal till and/or loamy lodgment till

Soil Parent material

Soil Limitations

3. Surficial Geological Report

2018/USGS

Year Published/Source

Artificial fill, glaciomarine fine deposits, stagnant ice deposits

Map Unit

Fine/very fine sand down to very fine sand, silt, silty clay, and clay

Description of Geologic Map Unit:

4. Flood Rate Insurance Map Within a regulatory floodway? Yes No

5. Within a velocity zone? Yes No

6. Within a Mapped Wetland Area? Yes No

If yes, MassGIS Wetland Data Layer:

Wetland Type

7. Current Water Resource Conditions (USGS):

Month/Day/ Year

Range: Above Normal

Normal

Below Normal

8. Other references reviewed:

(Zone II, IWPA, Zone A, EEA Data Portal, etc.)

Not in Zone II or IWPA (MassMapper)



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review *(minimum of two holes required at every proposed primary and reserve disposal area)*

Deep Observation Hole Number: TP-1 5/18/23 9:00AM Clear 42.4' N 71.2' W
Hole # Date Time Weather Latitude Longitude

1. Land Use Wooded lot in residential area Trees Some surface stones, not many 3%
(e.g., woodland, agricultural field, vacant lot, etc.) Vegetation Surface Stones (e.g., cobbles, stones, boulders, etc.) Slope (%)

Description of Location: At the front of the site along Dorothy Road, about 32' in from the edge of the road

2. Soil Parent Material: Glaciofluvial deposits Depression SU
Landform Position on Landscape (SU, SH, BS, FS, TS, Plain)

3. Distances from: Open Water Body >100 feet Drainage Way >100 feet Wetlands 280 feet
 Property Line 22 feet Drinking Water Well >100 feet Other _____ feet

4. Unsuitable Materials Present: Yes No If Yes: Disturbed Soil/Fill Material Weathered/Fractured Rock Bedrock

5. Groundwater Observed: Yes No If yes: 108" Depth to Weeping in Hole 114" Depth to Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0-90	Fill	Sandy Loam	7.5YR 3/2		Cnc : Dpl:		0	4-6	Massive	Friable	
90-120	C	Fine Sandy Loam	7.5YR 5/2		Cnc : Dpl:		0	0	Massive	Friable	
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						

Additional Notes: Top of monitoring well 3'-8" from ground surface



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review *(minimum of two holes required at every proposed primary and reserve disposal area)*

Deep Observation Hole Number: TP-2 5/18/23 1:30PM Clear 42.4' N 71.2' W
Hole # Date Time Weather Latitude Longitude

1. Land Use Wooded lot in residential area Trees Some surface stones, not many 2%
(e.g., woodland, agricultural field, vacant lot, etc.) Vegetation Surface Stones (e.g., cobbles, stones, boulders, etc.) Slope (%)

Description of Location: At the front of the site along Dorothy Road, about 30' in from the edge of the road

2. Soil Parent Material: Glaciofluvial deposits Depression BS
Landform Position on Landscape (SU, SH, BS, FS, TS, Plain)

3. Distances from: Open Water Body >100 feet Drainage Way >100 feet Wetlands 270 feet
 Property Line 22 feet Drinking Water Well >100 feet Other _____ feet

4. Unsuitable Materials Present: Yes No If Yes: Disturbed Soil/Fill Material Weathered/Fractured Rock Bedrock

5. Groundwater Observed: Yes No If yes: _____ Depth to Weeping in Hole 97" Depth to Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0-83	Fill	Sandy Loam	10YR 3/2		Cnc : Dpl:		0	4-6	Massive	Friable	
83-104	C	Fine Sandy Loam	10YR 5/1		Cnc : Dpl:		0	0	Massive	Friable	
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						

Additional Notes:

Shifted back a few feet because of boulder or buried piece of debris

Seemed like there may have been a second layer of sandy material below the point where groundwater broke into the hole



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

D. Determination of High Groundwater Elevation

1. Method Used (Choose one):

Depth to soil redoximorphic features

Obs. Hole # TP-1

Obs. Hole # TP-2

_____ inches

_____ inches

Depth to observed standing water in observation hole

108 inches

97 inches

Depth to adjusted seasonal high groundwater (S_h)
(USGS methodology)

_____ inches

_____ inches

Index Well Number _____

Reading Date _____

$$S_h = S_c - [S_r \times (OW_c - OW_{max}) / OW_r]$$

Obs. Hole/Well# _____

S_c _____

S_r _____

OW_c _____

OW_{max} _____

OW_r _____

S_h _____

E. Depth of Pervious Material

1. Depth of Naturally Occurring Pervious Material

a. Does at least four feet of naturally occurring pervious material exist in all areas observed throughout the area proposed for the soil absorption system?

Yes No

b. If yes, at what depth was it observed (exclude O, A, and E Horizons)?

Upper boundary: _____

Lower boundary: _____

_____ inches

_____ inches

c. If no, at what depth was impervious material observed?

Upper boundary: _____

Lower boundary: _____

97
_____ inches

104
_____ inches



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review *(minimum of two holes required at every proposed primary and reserve disposal area)*

Deep Observation Hole Number: TP-3 5/18/23 2:30PM Clear 42.4' N 71.2' W
Hole # Date Time Weather Latitude Longitude

1. Land Use Wooded lot in residential area Trees Some surface stones, not many 6%
(e.g., woodland, agricultural field, vacant lot, etc.) Vegetation Surface Stones (e.g., cobbles, stones, boulders, etc.) Slope (%)

Description of Location: At the front of the site along Dorothy Road, about 32' in from the edge of the road

2. Soil Parent Material: Glaciofluvial deposits Depression BS
Landform Position on Landscape (SU, SH, BS, FS, TS, Plain)

3. Distances from: Open Water Body >100 feet Drainage Way >100 feet Wetlands 280 feet
 Property Line 22 feet Drinking Water Well >100 feet Other _____ feet

4. Unsuitable Materials Present: Yes No If Yes: Disturbed Soil/Fill Material Weathered/Fractured Rock Bedrock

5. Groundwater Observed: Yes No If yes: _____ Depth to Weeping in Hole 82" Depth to Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0-27	Fill	Sandy Loam	10YR 2/2		Cnc : _____ Dpl: _____		0	4-6	Massive	Friable	Buried A layer at 21"
27-87	C	Fine Sandy Loam	10YR 4/3	51"	Cnc : 7.5YR5/8 Dpl: _____		0	0	Massive	Friable	
					Cnc : _____ Dpl: _____						
					Cnc : _____ Dpl: _____						
					Cnc : _____ Dpl: _____						
					Cnc : _____ Dpl: _____						

Additional Notes:



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review *(minimum of two holes required at every proposed primary and reserve disposal area)*

Deep Observation Hole Number: TP-4 5/19/23 8:15AM Clear 42.4' N 71.2' W
Hole # Date Time Weather Latitude Longitude

1. Land Use Wooded lot in residential area Trees Some surface stones, not many 6%
(e.g., woodland, agricultural field, vacant lot, etc.) Vegetation Surface Stones (e.g., cobbles, stones, boulders, etc.) Slope (%)

Description of Location: At the front of the site along Dorothy Road, about 30' in from the edge of the road

2. Soil Parent Material: Glaciofluvial deposits Depression TS
Landform Position on Landscape (SU, SH, BS, FS, TS, Plain)

3. Distances from: Open Water Body >100 feet Drainage Way >100 feet Wetlands 310 feet
 Property Line 24 feet Drinking Water Well >100 feet Other _____ feet

4. Unsuitable Materials Present: Yes No If Yes: Disturbed Soil/Fill Material Weathered/Fractured Rock Bedrock

5. Groundwater Observed: Yes No If yes: 68" Depth to Weeping in Hole 72" Depth to Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0-64	Fill	Gravelly Sandy Loam	7.5YR 3/1		Cnc : Dpl:		10-15	2-4	Massive	Friable	
64-96	C	Fine Loamy Sand	10YR 4/2		Cnc : Dpl:		2-4	0	Massive	Very Friable	
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						

Additional Notes:



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

D. Determination of High Groundwater Elevation

1. Method Used (Choose one):

Depth to soil redoximorphic features

Obs. Hole # TP-3

51 inches

Obs. Hole # TP-4

_____ inches

Depth to observed standing water in observation hole

82 inches

68 inches

Depth to adjusted seasonal high groundwater (S_h)
(USGS methodology)

_____ inches

_____ inches

Index Well Number _____

Reading Date _____

$$S_h = S_c - [S_r \times (OW_c - OW_{max}) / OW_r]$$

Obs. Hole/Well# _____ S_c _____ S_r _____ OW_c _____ OW_{max} _____ OW_r _____ S_h _____

E. Depth of Pervious Material

1. Depth of Naturally Occurring Pervious Material

a. Does at least four feet of naturally occurring pervious material exist in all areas observed throughout the area proposed for the soil absorption system?

Yes No

b. If yes, at what depth was it observed (exclude O, A, and E Horizons)?

Upper boundary: _____

Lower boundary: _____

_____ inches

_____ inches

c. If no, at what depth was impervious material observed?

Upper boundary: _____

Lower boundary: _____

68

96

_____ inches

_____ inches



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review *(minimum of two holes required at every proposed primary and reserve disposal area)*

Deep Observation Hole Number: TP-5 5/19/23 10:30AM Clear 42.4' N 71.2' W
Hole # Date Time Weather Latitude Longitude

1. Land Use Wooded lot in residential area Trees Some surface stones, not many 10%
(e.g., woodland, agricultural field, vacant lot, etc.) Vegetation Surface Stones (e.g., cobbles, stones, boulders, etc.) Slope (%)

Description of Location: At the front of the site along Dorothy Road, about 35' in from the edge of the road

2. Soil Parent Material: Glaciofluvial deposits Depression BS
Landform Position on Landscape (SU, SH, BS, FS, TS, Plain)

3. Distances from: Open Water Body >100 feet Drainage Way >100 feet Wetlands 230 feet
 Property Line 24 feet Drinking Water Well >100 feet Other _____ feet

4. Unsuitable Materials Present: Yes No If Yes: Disturbed Soil/Fill Material Weathered/Fractured Rock Bedrock

5. Groundwater Observed: Yes No If yes: 60" Depth to Weeping in Hole 60" Depth to Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0-33	Fill	Gravelly Sandy Loam	10YR 3/2		Cnc : Dpl:		10	4-6	Massive	Friable	Buried A layer at 26"
33-74	C	Fine Sandy Loam	10YR 5/2	48"	Cnc : Dpl:		0	0	Massive	Friable	
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						

Additional Notes:



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review *(minimum of two holes required at every proposed primary and reserve disposal area)*

Deep Observation Hole Number: TP-6 5/19/23 9:00AM Clear 42.4' N 71.2' W
Hole # Date Time Weather Latitude Longitude

1. Land Use Wooded lot in residential area Trees Some surface stones, not many 5%
(e.g., woodland, agricultural field, vacant lot, etc.) Vegetation Surface Stones (e.g., cobbles, stones, boulders, etc.) Slope (%)

Description of Location: At the front of the site along Dorothy Road, about 120' in from the edge of the road

2. Soil Parent Material: Glaciofluvial deposits Depression TS
Landform Position on Landscape (SU, SH, BS, FS, TS, Plain)

3. Distances from: Open Water Body >100 feet Drainage Way >100 feet Wetlands 110 feet
 Property Line 12 feet Drinking Water Well >100 feet Other _____ feet

4. Unsuitable Materials Present: Yes No If Yes: Disturbed Soil/Fill Material Weathered/Fractured Rock Bedrock

5. Groundwater Observed: Yes No If yes: 110" Depth to Weeping in Hole 110" Depth to Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0-30	Fill	Gravelly Sandy Loam	7.5YR 3/2		Cnc : _____ Dpl: _____		10-15	4-6	Massive	Friable	
30-132	C	Fine Sandy Loam	10YR 5/2	39"	Cnc : 7.5YR5/8 Dpl: _____		0	0	Massive	Friable	
				64"	Cnc : 7.5YR5/8 Dpl: _____						Second redox band - calling ESGW here
					Cnc : _____ Dpl: _____						
					Cnc : _____ Dpl: _____						
					Cnc : _____ Dpl: _____						

Additional Notes: Multiple redox bands in C horizon
Top of monitoring well 1'-8" from ground surface



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

D. Determination of High Groundwater Elevation

- | | | |
|--|-------------------------|-------------------------|
| 1. Method Used (Choose one): | Obs. Hole # <u>TP-5</u> | Obs. Hole # <u>TP-6</u> |
| <input checked="" type="checkbox"/> Depth to soil redoximorphic features | <u>48</u> inches | <u>64</u> inches |
| <input checked="" type="checkbox"/> Depth to observed standing water in observation hole | <u>60</u> inches | <u>110</u> inches |
| <input type="checkbox"/> Depth to adjusted seasonal high groundwater (S_h)
(USGS methodology) | _____ inches | _____ inches |

Index Well Number _____

Reading Date _____

$$S_h = S_c - [S_r \times (OW_c - OW_{max}) / OW_r]$$

Obs. Hole/Well# _____ S_c _____ S_r _____ OW_c _____ OW_{max} _____ OW_r _____ S_h _____

E. Depth of Pervious Material

1. Depth of Naturally Occurring Pervious Material

- a. Does at least four feet of naturally occurring pervious material exist in all areas observed throughout the area proposed for the soil absorption system?

Yes No

- b. If yes, at what depth was it observed (exclude O, A, and E Horizons)?

Upper boundary: _____

Lower boundary: _____

_____ inches

_____ inches

- c. If no, at what depth was impervious material observed?

Upper boundary: _____

Lower boundary: _____

60
_____ inches

74
_____ inches



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review *(minimum of two holes required at every proposed primary and reserve disposal area)*

Deep Observation Hole Number: TP-7 5/18/23 11:00AM Clear 42.4' N 71.2' W
Hole # Date Time Weather Latitude Longitude

1. Land Use Wooded lot in residential area Trees Some surface stones, not many 3%
(e.g., woodland, agricultural field, vacant lot, etc.) Vegetation Surface Stones (e.g., cobbles, stones, boulders, etc.) Slope (%)

Description of Location: At the front of the site along Dorothy Road, about 110' in from the edge of the road

2. Soil Parent Material: Glaciofluvial deposits Depression BS
Landform Position on Landscape (SU, SH, BS, FS, TS, Plain)

3. Distances from: Open Water Body >100 feet Drainage Way >100 feet Wetlands 190 feet
 Property Line 100 feet Drinking Water Well >100 feet Other _____ feet

4. Unsuitable Materials Present: Yes No If Yes: Disturbed Soil/Fill Material Weathered/Fractured Rock Bedrock

5. Groundwater Observed: Yes No If yes: _____ Depth to Weeping in Hole 110" Depth to Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0-108	Fill	Gravelly Sandy Loam	7.5YR 3/1	Cnc :			10	4-6	Massive	Friable	
				Dpl:							
108-114	C	Fine Sandy Loam	5Y 5/1	Cnc :			0	0	Massive	Friable	
				Dpl:							
				Cnc :							
				Dpl:							
				Cnc :							
				Dpl:							
				Cnc :							
				Dpl:							

Additional Notes: Sand layer was completely saturated
Top of monitoring well 4'-6" from ground surface



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review *(minimum of two holes required at every proposed primary and reserve disposal area)*

Deep Observation Hole Number: TP-8 5/18/23 10:00AM Clear 42.4' N 71.2' W
Hole # Date Time Weather Latitude Longitude

1. Land Use Wooded lot in residential area Trees Some surface stones, not many 4%
(e.g., woodland, agricultural field, vacant lot, etc.) Vegetation Surface Stones (e.g., cobbles, stones, boulders, etc.) Slope (%)

Description of Location: At the front of the site along Dorothy Road, about 110' in from the edge of the road

2. Soil Parent Material: Glaciofluvial deposits Depression TS
Landform Position on Landscape (SU, SH, BS, FS, TS, Plain)

3. Distances from: Open Water Body >100 feet Drainage Way >100 feet Wetlands 210 feet
 Property Line 98 feet Drinking Water Well >100 feet Other _____ feet

4. Unsuitable Materials Present: Yes No If Yes: Disturbed Soil/Fill Material Weathered/Fractured Rock Bedrock

5. Groundwater Observed: Yes No If yes: 112" Depth to Weeping in Hole _____ Depth to Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0-120	Fill	Gravelly Sandy Loam	7.5YR 3/1		Cnc : Dpl:		10	4-6	Massive	Friable	
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						

Additional Notes:



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

D. Determination of High Groundwater Elevation

1. Method Used (Choose one):

Depth to soil redoximorphic features

Obs. Hole # TP-7

Obs. Hole # TP-8

_____ inches

_____ inches

Depth to observed standing water in observation hole

110 inches

112 inches

Depth to adjusted seasonal high groundwater (S_h)
(USGS methodology)

_____ inches

_____ inches

Index Well Number _____

Reading Date _____

$$S_h = S_c - [S_r \times (OW_c - OW_{max}) / OW_r]$$

Obs. Hole/Well# _____

S_c _____

S_r _____

OW_c _____

OW_{max} _____

OW_r _____

S_h _____

E. Depth of Pervious Material

1. Depth of Naturally Occurring Pervious Material

a. Does at least four feet of naturally occurring pervious material exist in all areas observed throughout the area proposed for the soil absorption system?

Yes No

b. If yes, at what depth was it observed (exclude O, A, and E Horizons)?

Upper boundary: _____

Lower boundary: _____

_____ inches

_____ inches

c. If no, at what depth was impervious material observed?

Upper boundary: _____

Lower boundary: _____

120
_____ inches

120
_____ inches



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

F. Certification

I certify that I am currently approved by the Department of Environmental Protection pursuant to 310 CMR 15.017 to conduct soil evaluations and that the above analysis has been performed by me consistent with the required training, expertise and experience described in 310 CMR 15.017. I further certify that the results of my soil evaluation, as indicated in the attached Soil Evaluation Form, are accurate and in accordance with 310 CMR 15.100 through 15.107.

Signature of Soil Evaluator

Emily Derrig, SE 14158

Typed or Printed Name of Soil Evaluator / License #

5/22/2023

Date

6/30/2023


Expiration Date of License

Name of Approving Authority Witness

Approving Authority

Note: In accordance with 310 CMR 15.018(2) this form must be submitted to the approving authority within 60 days of the date of field testing, and to the designer and the property owner with [Percolation Test Form 12](#).

Field Diagrams: Use this area for field diagrams:



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

A. Facility Information

Arlington Land Realty, LLC.

Owner Name

Dorothy Road

Street Address

Arlington

City

MA

State

16-8-2, 16-8-3, 16-8-4, 16-8-5, 16-8-6, 16-8-7A

Map/Lot #

02474

Zip Code

B. Site Information

1. (Check one) New Construction Upgrade

2. Soil Survey NRCS USDA Web Soil Survey

Source

655

Soil Map Unit

Udorthents, wet substratum

Soil Series

Depressions

Landform

Loamy alluvium and/or sandy glaciofluvial deposits and/or loamy glaciolacustrine deposites and/or loamy marine deposits and/or loamy basal till and/or loamy lodgment till

Soil Parent material

Soil Limitations

3. Surficial Geological Report

2018/USGS

Year Published/Source

Artificial fill, glaciomarine fine deposits, stagnant ice deposits

Map Unit

Fine/very fine sand down to very fine sand, silt, silty clay, and clay

Description of Geologic Map Unit:

4. Flood Rate Insurance Map Within a regulatory floodway? Yes No

5. Within a velocity zone? Yes No

6. Within a Mapped Wetland Area? Yes No

If yes, MassGIS Wetland Data Layer:

Wetland Type

7. Current Water Resource Conditions (USGS):

April 17, 2024

Month/Day/ Year

Range: Above Normal

Normal

Below Normal

8. Other references reviewed:

Not in Zone II or IWPA (MassMapper)

(Zone II, IWPA, Zone A, EEA Data Portal, etc.)



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review *(minimum of two holes required at every proposed primary and reserve disposal area)*

Deep Observation Hole Number: TP-9 4/17/24 8:30AM Clear, 50 42.4' N 71.2' W
Hole # Date Time Weather Latitude Longitude

1. Land Use Wooded lot in residential area Trees Some surface stones, not many 7%
(e.g., woodland, agricultural field, vacant lot, etc.) Vegetation Surface Stones (e.g., cobbles, stones, boulders, etc.) Slope (%)

Description of Location: Center of proposed infiltration system (large); between TP-7 and TP-8; about 110 feet from Dorothy Road

2. Soil Parent Material: Glaciofluvial deposits Depression FS
Landform Position on Landscape (SU, SH, BS, FS, TS, Plain)

3. Distances from: Open Water Body >100 feet Drainage Way >100 feet Wetlands 205 feet
 Property Line 110 feet Drinking Water Well >100 feet Other _____ feet

4. Unsuitable Materials Present: Yes No If Yes: Disturbed Soil/Fill Material Weathered/Fractured Rock Bedrock

5. Groundwater Observed: Yes No If yes: 90" Depth to Weeping in Hole 116" Depth to Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0-100	Fill	Sandy Loam	7.5YR 4/7	Cnc :			0	4-6	Massive	Friable	
				Dpl:							
100-118	C	Fine Sandy Loam	10YR 4/1	Cnc :			0	0	Massive	Friable	
				Dpl:							
				Cnc :							
				Dpl:							
				Cnc :							
				Dpl:							
				Cnc :							
				Dpl:							

Additional Notes: Installed monitoring well; groundwater weeping from side of pit and standing water at bottom of pit



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review *(minimum of two holes required at every proposed primary and reserve disposal area)*

Deep Observation Hole Number: TP-10 4/17/24 10:00 AM Clear, 50 42.4' N 71.2' W
Hole # Date Time Weather Latitude Longitude

1. Land Use Wooded lot in residential area Trees Some surface stones, not many 3%
(e.g., woodland, agricultural field, vacant lot, etc.) Vegetation Surface Stones (e.g., cobbles, stones, boulders, etc.) Slope (%)

Description of Location: Northwest corner of infiltration system; about 100' from Dorothy Road

2. Soil Parent Material: Glaciofluvial deposits Depression BS
Landform Position on Landscape (SU, SH, BS, FS, TS, Plain)

3. Distances from: Open Water Body >100 feet Drainage Way >100 feet Wetlands 250 feet
 Property Line 79 feet Drinking Water Well >100 feet Other _____ feet

4. Unsuitable Materials Present: Yes No If Yes: Disturbed Soil/Fill Material Weathered/Fractured Rock Bedrock

5. Groundwater Observed: Yes No If yes: 94" Depth to Weeping in Hole 126" Depth to Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0-130	Fill	Sandy Loam	7.5YR 4/2	Cnc :			0	4-6	Massive	Friable	
				Dpl:							
				Cnc :							
				Dpl:							
				Cnc :							
				Dpl:							
				Cnc :							
				Dpl:							
				Cnc :							
				Dpl:							

Additional Notes: Groundwater weeping from side of hole and standing water at bottom of pit; debris and construction material present throughout fill



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

D. Determination of High Groundwater Elevation

1. Method Used (Choose one):

Depth to soil redoximorphic features

Obs. Hole # TP-9

_____ inches

Obs. Hole # TP-10

_____ inches

Depth to observed standing water in observation hole

90 inches

94 inches

Depth to adjusted seasonal high groundwater (S_h)
(USGS methodology)

_____ inches

_____ inches

Index Well Number _____

Reading Date _____

$$S_h = S_c - [S_r \times (OW_c - OW_{max}) / OW_r]$$

Obs. Hole/Well# _____ S_c _____ S_r _____ OW_c _____ OW_{max} _____ OW_r _____ S_h _____

E. Depth of Pervious Material

1. Depth of Naturally Occurring Pervious Material

a. Does at least four feet of naturally occurring pervious material exist in all areas observed throughout the area proposed for the soil absorption system?

Yes No

b. If yes, at what depth was it observed (exclude O, A, and E Horizons)?

Upper boundary: _____

_____ inches

Lower boundary: _____

_____ inches

c. If no, at what depth was impervious material observed?

Upper boundary: _____

90
_____ inches

Lower boundary: _____

118
_____ inches



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review *(minimum of two holes required at every proposed primary and reserve disposal area)*

Deep Observation Hole Number: TP-11 4/17/24 10:45AM Clear, 55 42.4' N 71.2' W
Hole # Date Time Weather Latitude Longitude

1. Land Use Wooded lot in residential area Trees Some surface stones, not many 6%
(e.g., woodland, agricultural field, vacant lot, etc.) Vegetation Surface Stones (e.g., cobbles, stones, boulders, etc.) Slope (%)

Description of Location: Southwest corner of infiltration system; about 135' from Dorothy Road

2. Soil Parent Material: Glaciofluvial deposits Depression FS
Landform Position on Landscape (SU, SH, BS, FS, TS, Plain)

3. Distances from: Open Water Body >100 feet Drainage Way >100 feet Wetlands 215 feet
 Property Line 46 feet Drinking Water Well >100 feet Other _____ feet

4. Unsuitable Materials Present: Yes No If Yes: Disturbed Soil/Fill Material Weathered/Fractured Rock Bedrock

5. Groundwater Observed: Yes No If yes: 93" Depth to Weeping in Hole 111" Depth to Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0-114	Fill	Sandy Loam	7.5YR 4/2	Cnc :			0	4-6	Massive	Friable	
				Dpl:							
				Cnc :							
				Dpl:							
				Cnc :							
				Dpl:							
				Cnc :							
				Dpl:							
				Cnc :							
				Dpl:							

Additional Notes:



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review *(minimum of two holes required at every proposed primary and reserve disposal area)*

Deep Observation Hole Number: TP-12 4/17/24 11:30AM Clear, 55 42.4' N 71.2' W
Hole # Date Time Weather Latitude Longitude

1. Land Use Wooded lot in residential area Trees Some surface stones, not many 3%
(e.g., woodland, agricultural field, vacant lot, etc.) Vegetation Surface Stones (e.g., cobbles, stones, boulders, etc.) Slope (%)

Description of Location: Northeast corner of infiltration system; about 95' from Dorothy Road

2. Soil Parent Material: Glaciofluvial deposits Depression FS
Landform Position on Landscape (SU, SH, BS, FS, TS, Plain)

3. Distances from: Open Water Body >100 feet Drainage Way >100 feet Wetlands 215 feet
 Property Line 92 feet Drinking Water Well >100 feet Other _____ feet

4. Unsuitable Materials Present: Yes No If Yes: Disturbed Soil/Fill Material Weathered/Fractured Rock Bedrock

5. Groundwater Observed: Yes No If yes: 53" Depth to Weeping in Hole 68" Depth to Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0-76	Fill	Sandy Loam	7.5YR 3/2	Cnc :			0	50	Massive	Friable	
				Dpl:							
				Cnc :							
				Dpl:							
				Cnc :							
				Dpl:							
				Cnc :							
				Dpl:							
				Cnc :							
				Dpl:							

Additional Notes: Larger cobbles/boulders throughout test pit



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

D. Determination of High Groundwater Elevation

1. Method Used (Choose one):

Depth to soil redoximorphic features

Obs. Hole # TP-11

_____ inches

Obs. Hole # TP-12

_____ inches

Depth to observed standing water in observation hole

93 inches

53 inches

Depth to adjusted seasonal high groundwater (S_h)
(USGS methodology)

_____ inches

_____ inches

Index Well Number _____

Reading Date _____

$$S_h = S_c - [S_r \times (OW_c - OW_{max}) / OW_r]$$

Obs. Hole/Well# _____

S_c _____

S_r _____

OW_c _____

OW_{max} _____

OW_r _____

S_h _____

E. Depth of Pervious Material

1. Depth of Naturally Occurring Pervious Material

a. Does at least four feet of naturally occurring pervious material exist in all areas observed throughout the area proposed for the soil absorption system?

Yes No

b. If yes, at what depth was it observed (exclude O, A, and E Horizons)?

Upper boundary: _____

_____ inches

Lower boundary: _____

_____ inches

c. If no, at what depth was impervious material observed?

Upper boundary: _____

53
_____ inches

Lower boundary: _____

76
_____ inches



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review *(minimum of two holes required at every proposed primary and reserve disposal area)*

Deep Observation Hole Number: TP-13 4/17/24 11:45AM Clear, 55 42.4' N 71.2' W
Hole # Date Time Weather Latitude Longitude

1. Land Use Wooded lot in residential area Trees Some surface stones, not many 1%
(e.g., woodland, agricultural field, vacant lot, etc.) Vegetation Surface Stones (e.g., cobbles, stones, boulders, etc.) Slope (%)

Description of Location: Southeast corner of infiltration system; about 135' from Dorothy Road

2. Soil Parent Material: Glaciofluvial deposits Depression TS
Landform Position on Landscape (SU, SH, BS, FS, TS, Plain)

3. Distances from: Open Water Body >100 feet Drainage Way >100 feet Wetlands 180 feet
 Property Line 130 feet Drinking Water Well >100 feet Other _____ feet

4. Unsuitable Materials Present: Yes No If Yes: Disturbed Soil/Fill Material Weathered/Fractured Rock Bedrock

5. Groundwater Observed: Yes No If yes: 57" Depth to Weeping in Hole 67" Depth to Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0-74	Fill	Sandy Loam	7.5YR 3/2		Cnc : _____ Dpl: _____	5-10	0	10-20	Massive	Friable	
					Cnc : _____ Dpl: _____						
					Cnc : _____ Dpl: _____						
					Cnc : _____ Dpl: _____						
					Cnc : _____ Dpl: _____						
					Cnc : _____ Dpl: _____						

Additional Notes:



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

D. Determination of High Groundwater Elevation

1. Method Used (Choose one):
- | | | |
|--|--------------------------|-------------------|
| <input type="checkbox"/> Depth to soil redoximorphic features | Obs. Hole # <u>TP-13</u> | Obs. Hole # _____ |
| | _____ inches | _____ inches |
| <input checked="" type="checkbox"/> Depth to observed standing water in observation hole | <u>57</u> inches | _____ inches |
| <input type="checkbox"/> Depth to adjusted seasonal high groundwater (S_h)
(USGS methodology) | _____ inches | _____ inches |

Index Well Number _____

Reading Date _____

$$S_h = S_c - [S_r \times (OW_c - OW_{max}) / OW_r]$$

Obs. Hole/Well# _____ S_c _____ S_r _____ OW_c _____ OW_{max} _____ OW_r _____ S_h _____

E. Depth of Pervious Material

1. Depth of Naturally Occurring Pervious Material

- a. Does at least four feet of naturally occurring pervious material exist in all areas observed throughout the area proposed for the soil absorption system?

Yes No

- b. If yes, at what depth was it observed (exclude O, A, and E Horizons)?

Upper boundary:	_____ inches	Lower boundary:	_____ inches
	<u>57</u>		<u>74</u>
	_____ inches		_____ inches

- c. If no, at what depth was impervious material observed?

Upper boundary:	_____ inches	Lower boundary:	_____ inches
	<u>57</u>		<u>74</u>
	_____ inches		_____ inches



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

F. Certification

I certify that I am currently approved by the Department of Environmental Protection pursuant to 310 CMR 15.017 to conduct soil evaluations and that the above analysis has been performed by me consistent with the required training, expertise and experience described in 310 CMR 15.017. I further certify that the results of mv soil evaluation, as indicated in the attached Soil Evaluation Form, are accurate and in accordance with 310 CMR 15.100 through 15.107.

Signature of Soil Evaluator

Emily Derrig, SE 14158

Typed or Printed Name of Soil Evaluator / License #

4/17/2024

Date

6/30/2026

Expiration Date of License

Name of Approving Authority Witness

Approving Authority

Note: In accordance with 310 CMR 15.018(2) this form must be submitted to the approving authority within 60 days of the date of field testing, and to the designer and the property owner with [Percolation Test Form 12](#).

Field Diagrams: Use this area for field diagrams:

APPENDIX E

NOAA 14++ PRECIPITATION TABLES



NOAA Atlas 14, Volume 10, Version 3
Location name: Arlington, Massachusetts, USA*
Latitude: 42.4008°, Longitude: -71.1485°
Elevation: 5 ft**
 * source: ESRI Maps
 ** source: USGS



POINT PRECIPITATION FREQUENCY ESTIMATES

Sanja Perica, Sandra Pavlovic, Michael St. Laurent, Carl Trypaluk, Dale Unruh, Orlan Wilhite

NOAA, National Weather Service, Silver Spring, Maryland

[PF_tabular](#) | [PF_graphical](#) | [Maps & aerials](#)

PF tabular

PDS-based point precipitation frequency estimates with 90% confidence intervals (in inches)¹										
Duration	Average recurrence interval (years)									
	1	2	5	10	25	50	100	200	500	1000
5-min	0.303 (0.237-0.383)	0.372 (0.290-0.471)	0.484 (0.377-0.617)	0.578 (0.447-0.739)	0.706 (0.530-0.954)	0.802 (0.590-1.11)	0.905 (0.649-1.31)	1.03 (0.691-1.52)	1.21 (0.784-1.86)	1.36 (0.864-2.14)
10-min	0.429 (0.335-0.543)	0.527 (0.411-0.668)	0.687 (0.535-0.874)	0.819 (0.633-1.05)	1.00 (0.751-1.35)	1.14 (0.837-1.58)	1.28 (0.919-1.86)	1.46 (0.979-2.15)	1.71 (1.11-2.63)	1.93 (1.22-3.03)
15-min	0.505 (0.395-0.639)	0.620 (0.484-0.785)	0.808 (0.628-1.03)	0.963 (0.745-1.23)	1.18 (0.884-1.59)	1.34 (0.983-1.85)	1.51 (1.08-2.18)	1.71 (1.15-2.52)	2.02 (1.31-3.09)	2.28 (1.44-3.56)
30-min	0.690 (0.540-0.874)	0.849 (0.663-1.08)	1.11 (0.862-1.41)	1.32 (1.02-1.70)	1.62 (1.22-2.19)	1.84 (1.36-2.55)	2.08 (1.49-3.02)	2.36 (1.59-3.48)	2.80 (1.81-4.29)	3.17 (2.01-4.96)
60-min	0.876 (0.685-1.11)	1.08 (0.842-1.37)	1.41 (1.10-1.79)	1.68 (1.30-2.16)	2.06 (1.55-2.79)	2.34 (1.73-3.25)	2.64 (1.90-3.85)	3.01 (2.03-4.44)	3.58 (2.32-5.49)	4.06 (2.57-6.37)
2-hr	1.14 (0.896-1.43)	1.40 (1.10-1.77)	1.84 (1.44-2.32)	2.20 (1.71-2.79)	2.69 (2.04-3.62)	3.06 (2.27-4.22)	3.46 (2.51-5.01)	3.96 (2.67-5.79)	4.74 (3.08-7.21)	5.43 (3.45-8.42)
3-hr	1.33 (1.05-1.66)	1.63 (1.29-2.05)	2.14 (1.68-2.69)	2.56 (2.00-3.24)	3.13 (2.38-4.20)	3.55 (2.65-4.90)	4.02 (2.93-5.81)	4.61 (3.12-6.70)	5.54 (3.60-8.36)	6.35 (4.04-9.79)
6-hr	1.72 (1.37-2.14)	2.11 (1.68-2.63)	2.76 (2.18-3.44)	3.29 (2.59-4.14)	4.02 (3.07-5.34)	4.56 (3.42-6.22)	5.15 (3.77-7.37)	5.90 (4.01-8.50)	7.06 (4.61-10.6)	8.08 (5.16-12.3)
12-hr	2.20 (1.76-2.71)	2.69 (2.15-3.33)	3.50 (2.79-4.34)	4.17 (3.31-5.21)	5.10 (3.92-6.71)	5.78 (4.35-7.80)	6.52 (4.79-9.21)	7.44 (5.08-10.6)	8.85 (5.80-13.1)	10.1 (6.45-15.2)
24-hr	2.64 (2.13-3.24)	3.27 (2.64-4.02)	4.31 (3.46-5.31)	5.16 (4.12-6.40)	6.34 (4.91-8.30)	7.21 (5.47-9.67)	8.16 (6.03-11.5)	9.35 (6.41-13.2)	11.2 (7.36-16.4)	12.8 (8.22-19.1)
2-day	3.01 (2.45-3.67)	3.80 (3.09-4.64)	5.10 (4.13-6.24)	6.18 (4.97-7.61)	7.66 (5.97-9.97)	8.74 (6.69-11.7)	9.94 (7.43-13.9)	11.5 (7.91-16.1)	14.0 (9.23-20.3)	16.2 (10.4-23.9)
3-day	3.30 (2.70-4.01)	4.16 (3.39-5.05)	5.56 (4.52-6.78)	6.72 (5.43-8.24)	8.32 (6.52-10.8)	9.48 (7.29-12.6)	10.8 (8.09-15.1)	12.5 (8.60-17.4)	15.2 (10.1-21.9)	17.7 (11.4-25.9)
4-day	3.58 (2.93-4.33)	4.46 (3.65-5.41)	5.91 (4.82-7.18)	7.11 (5.76-8.69)	8.76 (6.88-11.3)	9.96 (7.68-13.2)	11.3 (8.51-15.7)	13.1 (9.02-18.1)	15.9 (10.5-22.8)	18.4 (11.9-26.9)
7-day	4.34 (3.58-5.23)	5.26 (4.33-6.34)	6.77 (5.55-8.18)	8.02 (6.53-9.74)	9.74 (7.68-12.5)	11.0 (8.50-14.4)	12.4 (9.33-17.0)	14.2 (9.85-19.5)	17.1 (11.4-24.3)	19.7 (12.7-28.5)
10-day	5.04 (4.17-6.05)	5.99 (4.95-7.19)	7.54 (6.20-9.07)	8.82 (7.21-10.7)	10.6 (8.37-13.5)	11.9 (9.20-15.5)	13.3 (10.0-18.1)	15.1 (10.5-20.7)	18.0 (12.0-25.4)	20.5 (13.3-29.5)
20-day	7.05 (5.88-8.40)	8.08 (6.73-9.63)	9.76 (8.09-11.7)	11.2 (9.19-13.4)	13.1 (10.4-16.4)	14.5 (11.2-18.6)	16.0 (12.0-21.2)	17.8 (12.5-24.0)	20.3 (13.6-28.4)	22.4 (14.6-32.0)
30-day	8.72 (7.30-10.3)	9.81 (8.20-11.6)	11.6 (9.65-13.8)	13.1 (10.8-15.6)	15.1 (12.0-18.7)	16.7 (12.9-21.1)	18.3 (13.6-23.8)	19.9 (14.0-26.8)	22.2 (14.9-30.9)	24.0 (15.7-34.0)
45-day	10.8 (9.08-12.7)	12.0 (10.0-14.1)	13.9 (11.6-16.4)	15.4 (12.8-18.4)	17.6 (14.0-21.6)	19.3 (14.9-24.1)	20.9 (15.5-26.9)	22.6 (15.9-30.1)	24.6 (16.6-33.9)	26.2 (17.1-36.8)
60-day	12.6 (10.6-14.8)	13.8 (11.6-16.2)	15.8 (13.2-18.6)	17.4 (14.5-20.7)	19.7 (15.7-24.0)	21.4 (16.6-26.7)	23.1 (17.1-29.5)	24.7 (17.5-32.8)	26.7 (18.0-36.6)	28.0 (18.3-39.2)





¹ Precipitation frequency (PF) estimates in this table are based on frequency analysis of partial duration series (PDS). Numbers in parenthesis are PF estimates at lower and upper bounds of the 90% confidence interval. The probability that precipitation frequency estimates (for a given duration and average recurrence interval) will be greater than the upper bound (or less than the lower bound) is 5%. Estimates at upper bounds are not checked against probable maximum precipitation (PMP) estimates and may be higher than currently valid PMP values. Please refer to NOAA Atlas 14 document for more information.

[Back to Top](#)

PF graphical

PDS-based depth-duration-frequency (DDF) curves


Latitude: 42.4008°, Longitude: -71.1485°




[Back to Top](#)

Maps & aeriels

Small scale terrain




Large scale terrain



Large scale map



Large scale aerial



[Back to Top](#)

[US Department of Commerce](#)
[National Oceanic and Atmospheric Administration](#)
[National Weather Service](#)
[National Water Center](#)
1325 East West Highway
Silver Spring, MD 20910
Questions?: HDSC.Questions@noaa.gov

[Disclaimer](#)


APPENDIX F
STORMWATER CHECKLIST



Checklist for Stormwater Report

A. Introduction

Important: When filling out forms on the computer, use only the tab key to move your cursor - do not use the return key.



A Stormwater Report must be submitted with the Notice of Intent permit application to document compliance with the Stormwater Management Standards. The following checklist is NOT a substitute for the Stormwater Report (which should provide more substantive and detailed information) but is offered here as a tool to help the applicant organize their Stormwater Management documentation for their Report and for the reviewer to assess this information in a consistent format. As noted in the Checklist, the Stormwater Report must contain the engineering computations and supporting information set forth in Volume 3 of the [Massachusetts Stormwater Handbook](#). The Stormwater Report must be prepared and certified by a Registered Professional Engineer (RPE) licensed in the Commonwealth.

The Stormwater Report must include:

- The Stormwater Checklist completed and stamped by a Registered Professional Engineer (see page 2) that certifies that the Stormwater Report contains all required submittals.¹ This Checklist is to be used as the cover for the completed Stormwater Report.
- Applicant/Project Name
- Project Address
- Name of Firm and Registered Professional Engineer that prepared the Report
- Long-Term Pollution Prevention Plan required by Standards 4-6
- Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan required by Standard 8²
- Operation and Maintenance Plan required by Standard 9

In addition to all plans and supporting information, the Stormwater Report must include a brief narrative describing stormwater management practices, including environmentally sensitive site design and LID techniques, along with a diagram depicting runoff through the proposed BMP treatment train. Plans are required to show existing and proposed conditions, identify all wetland resource areas, NRCS soil types, critical areas, Land Uses with Higher Potential Pollutant Loads (LUHPPL), and any areas on the site where infiltration rate is greater than 2.4 inches per hour. The Plans shall identify the drainage areas for both existing and proposed conditions at a scale that enables verification of supporting calculations.

As noted in the Checklist, the Stormwater Management Report shall document compliance with each of the Stormwater Management Standards as provided in the Massachusetts Stormwater Handbook. The soils evaluation and calculations shall be done using the methodologies set forth in Volume 3 of the Massachusetts Stormwater Handbook.

To ensure that the Stormwater Report is complete, applicants are required to fill in the Stormwater Report Checklist by checking the box to indicate that the specified information has been included in the Stormwater Report. If any of the information specified in the checklist has not been submitted, the applicant must provide an explanation. The completed Stormwater Report Checklist and Certification must be submitted with the Stormwater Report.

¹ The Stormwater Report may also include the Illicit Discharge Compliance Statement required by Standard 10. If not included in the Stormwater Report, the Illicit Discharge Compliance Statement must be submitted prior to the discharge of stormwater runoff to the post-construction best management practices.

² For some complex projects, it may not be possible to include the Construction Period Erosion and Sedimentation Control Plan in the Stormwater Report. In that event, the issuing authority has the discretion to issue an Order of Conditions that approves the project and includes a condition requiring the proponent to submit the Construction Period Erosion and Sedimentation Control Plan before commencing any land disturbance activity on the site.



Checklist for Stormwater Report

B. Stormwater Checklist and Certification

The following checklist is intended to serve as a guide for applicants as to the elements that ordinarily need to be addressed in a complete Stormwater Report. The checklist is also intended to provide conservation commissions and other reviewing authorities with a summary of the components necessary for a comprehensive Stormwater Report that addresses the ten Stormwater Standards.

Note: Because stormwater requirements vary from project to project, it is possible that a complete Stormwater Report may not include information on some of the subjects specified in the Checklist. If it is determined that a specific item does not apply to the project under review, please note that the item is not applicable (N.A.) and provide the reasons for that determination.

A complete checklist must include the Certification set forth below signed by the Registered Professional Engineer who prepared the Stormwater Report.

Registered Professional Engineer's Certification

I have reviewed the Stormwater Report, including the soil evaluation, computations, Long-term Pollution Prevention Plan, the Construction Period Erosion and Sedimentation Control Plan (if included), the Long-term Post-Construction Operation and Maintenance Plan, the Illicit Discharge Compliance Statement (if included) and the plans showing the stormwater management system, and have determined that they have been prepared in accordance with the requirements of the Stormwater Management Standards as further elaborated by the Massachusetts Stormwater Handbook. I have also determined that the information presented in the Stormwater Checklist is accurate and that the information presented in the Stormwater Report accurately reflects conditions at the site as of the date of this permit application.

Registered Professional Engineer Block and Signature



Signature and Date

Checklist

Project Type: Is the application for new development, redevelopment, or a mix of new and redevelopment?

- New development
- Redevelopment
- Mix of New Development and Redevelopment



Checklist for Stormwater Report

Checklist (continued)

LID Measures: Stormwater Standards require LID measures to be considered. Document what environmentally sensitive design and LID Techniques were considered during the planning and design of the project:

- No disturbance to any Wetland Resource Areas
- Site Design Practices (e.g. clustered development, reduced frontage setbacks)
- Reduced Impervious Area (Redevelopment Only)
- Minimizing disturbance to existing trees and shrubs
- LID Site Design Credit Requested:
 - Credit 1
 - Credit 2
 - Credit 3
- Use of "country drainage" versus curb and gutter conveyance and pipe
- Bioretention Cells (includes Rain Gardens)
- Constructed Stormwater Wetlands (includes Gravel Wetlands designs)
- Treebox Filter
- Water Quality Swale
- Grass Channel
- Green Roof
- Other (describe): _____

Standard 1: No New Untreated Discharges

- No new untreated discharges
- Outlets have been designed so there is no erosion or scour to wetlands and waters of the Commonwealth
- Supporting calculations specified in Volume 3 of the Massachusetts Stormwater Handbook included.



Checklist for Stormwater Report

Checklist (continued)

Standard 2: Peak Rate Attenuation

- Standard 2 waiver requested because the project is located in land subject to coastal storm flowage and stormwater discharge is to a wetland subject to coastal flooding.
- Evaluation provided to determine whether off-site flooding increases during the 100-year 24-hour storm.
- Calculations provided to show that post-development peak discharge rates do not exceed pre-development rates for the 2-year and 10-year 24-hour storms. If evaluation shows that off-site flooding increases during the 100-year 24-hour storm, calculations are also provided to show that post-development peak discharge rates do not exceed pre-development rates for the 100-year 24-hour storm.

Standard 3: Recharge

- Soil Analysis provided.
- Required Recharge Volume calculation provided.
- Required Recharge volume reduced through use of the LID site Design Credits.
- Sizing the infiltration, BMPs is based on the following method: Check the method used.
 - Static
 - Simple Dynamic
 - Dynamic Field¹
- Runoff from all impervious areas at the site discharging to the infiltration BMP.
- Runoff from all impervious areas at the site is *not* discharging to the infiltration BMP and calculations are provided showing that the drainage area contributing runoff to the infiltration BMPs is sufficient to generate the required recharge volume.
- Recharge BMPs have been sized to infiltrate the Required Recharge Volume.
- Recharge BMPs have been sized to infiltrate the Required Recharge Volume *only* to the maximum extent practicable for the following reason:
 - Site is comprised solely of C and D soils and/or bedrock at the land surface
 - M.G.L. c. 21E sites pursuant to 310 CMR 40.0000
 - Solid Waste Landfill pursuant to 310 CMR 19.000
 - Project is otherwise subject to Stormwater Management Standards only to the maximum extent practicable.
- Calculations showing that the infiltration BMPs will drain in 72 hours are provided.
- Property includes a M.G.L. c. 21E site or a solid waste landfill and a mounding analysis is included.

¹ 80% TSS removal is required prior to discharge to infiltration BMP if Dynamic Field method is used.



Checklist for Stormwater Report

Checklist (continued)

Standard 3: Recharge (continued)

- The infiltration BMP is used to attenuate peak flows during storms greater than or equal to the 10-year 24-hour storm and separation to seasonal high groundwater is less than 4 feet and a mounding analysis is provided.
- Documentation is provided showing that infiltration BMPs do not adversely impact nearby wetland resource areas.

Standard 4: Water Quality

The Long-Term Pollution Prevention Plan typically includes the following:

- Good housekeeping practices;
 - Provisions for storing materials and waste products inside or under cover;
 - Vehicle washing controls;
 - Requirements for routine inspections and maintenance of stormwater BMPs;
 - Spill prevention and response plans;
 - Provisions for maintenance of lawns, gardens, and other landscaped areas;
 - Requirements for storage and use of fertilizers, herbicides, and pesticides;
 - Pet waste management provisions;
 - Provisions for operation and management of septic systems;
 - Provisions for solid waste management;
 - Snow disposal and plowing plans relative to Wetland Resource Areas;
 - Winter Road Salt and/or Sand Use and Storage restrictions;
 - Street sweeping schedules;
 - Provisions for prevention of illicit discharges to the stormwater management system;
 - Documentation that Stormwater BMPs are designed to provide for shutdown and containment in the event of a spill or discharges to or near critical areas or from LUHPPL;
 - Training for staff or personnel involved with implementing Long-Term Pollution Prevention Plan;
 - List of Emergency contacts for implementing Long-Term Pollution Prevention Plan.
- A Long-Term Pollution Prevention Plan is attached to Stormwater Report and is included as an attachment to the Wetlands Notice of Intent.
 - Treatment BMPs subject to the 44% TSS removal pretreatment requirement and the one inch rule for calculating the water quality volume are included, and discharge:
 - is within the Zone II or Interim Wellhead Protection Area
 - is near or to other critical areas
 - is within soils with a rapid infiltration rate (greater than 2.4 inches per hour)
 - involves runoff from land uses with higher potential pollutant loads.
 - The Required Water Quality Volume is reduced through use of the LID site Design Credits.
 - Calculations documenting that the treatment train meets the 80% TSS removal requirement and, if applicable, the 44% TSS removal pretreatment requirement, are provided.



Checklist for Stormwater Report

Checklist (continued)

Standard 4: Water Quality (continued)

- The BMP is sized (and calculations provided) based on:
 - The ½" or 1" Water Quality Volume or
 - The equivalent flow rate associated with the Water Quality Volume and documentation is provided showing that the BMP treats the required water quality volume.
- The applicant proposes to use proprietary BMPs, and documentation supporting use of proprietary BMP and proposed TSS removal rate is provided. This documentation may be in the form of the propriety BMP checklist found in Volume 2, Chapter 4 of the Massachusetts Stormwater Handbook and submitting copies of the TARP Report, STEP Report, and/or other third party studies verifying performance of the proprietary BMPs.
- A TMDL exists that indicates a need to reduce pollutants other than TSS and documentation showing that the BMPs selected are consistent with the TMDL is provided.

Standard 5: Land Uses With Higher Potential Pollutant Loads (LUHPPLs)

- The NPDES Multi-Sector General Permit covers the land use and the Stormwater Pollution Prevention Plan (SWPPP) has been included with the Stormwater Report.
- The NPDES Multi-Sector General Permit covers the land use and the SWPPP will be submitted **prior to** the discharge of stormwater to the post-construction stormwater BMPs.
- The NPDES Multi-Sector General Permit does **not** cover the land use.
- LUHPPLs are located at the site and industry specific source control and pollution prevention measures have been proposed to reduce or eliminate the exposure of LUHPPLs to rain, snow, snow melt and runoff, and been included in the long term Pollution Prevention Plan.
- All exposure has been eliminated.
- All exposure has **not** been eliminated and all BMPs selected are on MassDEP LUHPPL list.
- The LUHPPL has the potential to generate runoff with moderate to higher concentrations of oil and grease (e.g. all parking lots with >1000 vehicle trips per day) and the treatment train includes an oil grit separator, a filtering bioretention area, a sand filter or equivalent.

Standard 6: Critical Areas

- The discharge is near or to a critical area and the treatment train includes only BMPs that MassDEP has approved for stormwater discharges to or near that particular class of critical area.
- Critical areas and BMPs are identified in the Stormwater Report.



Checklist for Stormwater Report

Checklist (continued)

Standard 7: Redevelopments and Other Projects Subject to the Standards only to the maximum extent practicable

- The project is subject to the Stormwater Management Standards only to the maximum Extent Practicable as a:
 - Limited Project
 - Small Residential Projects: 5-9 single family houses or 5-9 units in a multi-family development provided there is no discharge that may potentially affect a critical area.
 - Small Residential Projects: 2-4 single family houses or 2-4 units in a multi-family development with a discharge to a critical area
 - Marina and/or boatyard provided the hull painting, service and maintenance areas are protected from exposure to rain, snow, snow melt and runoff
 - Bike Path and/or Foot Path
 - Redevelopment Project
 - Redevelopment portion of mix of new and redevelopment.
- Certain standards are not fully met (Standard No. 1, 8, 9, and 10 must always be fully met) and an explanation of why these standards are not met is contained in the Stormwater Report.
- The project involves redevelopment and a description of all measures that have been taken to improve existing conditions is provided in the Stormwater Report. The redevelopment checklist found in Volume 2 Chapter 3 of the Massachusetts Stormwater Handbook may be used to document that the proposed stormwater management system (a) complies with Standards 2, 3 and the pretreatment and structural BMP requirements of Standards 4-6 to the maximum extent practicable and (b) improves existing conditions.

Standard 8: Construction Period Pollution Prevention and Erosion and Sedimentation Control

A Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan must include the following information:

- Narrative;
 - Construction Period Operation and Maintenance Plan;
 - Names of Persons or Entity Responsible for Plan Compliance;
 - Construction Period Pollution Prevention Measures;
 - Erosion and Sedimentation Control Plan Drawings;
 - Detail drawings and specifications for erosion control BMPs, including sizing calculations;
 - Vegetation Planning;
 - Site Development Plan;
 - Construction Sequencing Plan;
 - Sequencing of Erosion and Sedimentation Controls;
 - Operation and Maintenance of Erosion and Sedimentation Controls;
 - Inspection Schedule;
 - Maintenance Schedule;
 - Inspection and Maintenance Log Form.
- A Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan containing the information set forth above has been included in the Stormwater Report.



Checklist for Stormwater Report

Checklist (continued)

Standard 8: Construction Period Pollution Prevention and Erosion and Sedimentation Control (continued)

- The project is highly complex and information is included in the Stormwater Report that explains why it is not possible to submit the Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan with the application. A Construction Period Pollution Prevention and Erosion and Sedimentation Control has **not** been included in the Stormwater Report but will be submitted **before** land disturbance begins.
- The project is **not** covered by a NPDES Construction General Permit.
- The project is covered by a NPDES Construction General Permit and a copy of the SWPPP is in the Stormwater Report.
- The project is covered by a NPDES Construction General Permit but no SWPPP been submitted. The SWPPP will be submitted BEFORE land disturbance begins.

Standard 9: Operation and Maintenance Plan

- The Post Construction Operation and Maintenance Plan is included in the Stormwater Report and includes the following information:
 - Name of the stormwater management system owners;
 - Party responsible for operation and maintenance;
 - Schedule for implementation of routine and non-routine maintenance tasks;
 - Plan showing the location of all stormwater BMPs maintenance access areas;
 - Description and delineation of public safety features;
 - Estimated operation and maintenance budget; and
 - Operation and Maintenance Log Form.
- The responsible party is **not** the owner of the parcel where the BMP is located and the Stormwater Report includes the following submissions:
 - A copy of the legal instrument (deed, homeowner's association, utility trust or other legal entity) that establishes the terms of and legal responsibility for the operation and maintenance of the project site stormwater BMPs;
 - A plan and easement deed that allows site access for the legal entity to operate and maintain BMP functions.

Standard 10: Prohibition of Illicit Discharges

- The Long-Term Pollution Prevention Plan includes measures to prevent illicit discharges;
- An Illicit Discharge Compliance Statement is attached;
- NO Illicit Discharge Compliance Statement is attached but will be submitted **prior to** the discharge of any stormwater to post-construction BMPs.

APPENDIX G

MCPHAIL GEOTECHNICAL MEMORANDUM



Memorandum

Date: December 9, 2024

Recipient: Arlington Land Manager LLC
c/o Dinosaur Capital Partners LLC – Scott Oran

Sender: Scott S. Smith, P.E.

Project: Thorndike Place; Arlington, MA

Project No: 7679.2.01

Subject: Subsurface Conditions at Proposed Stormwater Infiltration System

Background

This memorandum documents the subsurface soil and groundwater conditions encountered in the borings performed at the Thorndike Place project site during November 2024. The purpose of the borings was to provide supplemental information to the project civil engineer related to stormwater infiltration system design, including the saturated soil thickness within the footprint of the proposed stormwater infiltration system.

The 5.8-acre subject property is bounded by Dorothy Road and residences to the north, residences and undeveloped conservation land to the east, undeveloped conservation land to the south and the Concord Turnpike (Route 2) to the west. The subject property is currently unoccupied, undeveloped wooded land. Refer to the Project Location Plan, **Figure 1**, for the general site locus.

Based on the information provided to us, the proposed development is planned to consist of six (6), 3-story townhouses with footprints of about 1,700 square feet that are planned to include basements, and a 4-story multi-family residential building with a footprint of about 33,000 square feet that is planned to have 1-level of below-grade parking.

It is understood that as part of the proposed development, a stormwater infiltration system with a footprint of about 8,100 square feet will be constructed within the western portion of the site.

Elevations cited herein are in feet and are referenced to the North American Vertical Datum of 1988 (NAVD88).

Subsurface Explorations

The approximate locations of the subsurface explorations are indicated on the enclosed Subsurface Exploration Plan, **Figure 2**. The following subsurface explorations were completed at the project site under contract to McPhail:



Memorandum

- Two (2) borings (MA-1 through MA-2) were completed on November 20, 2024 by Carr-Dee Corp. of Medford, Massachusetts.

The borings were drilled to depths ranging from 37 to 42 feet below the existing ground surface and were terminated within a natural marine clay deposit. The boring logs are attached to this memorandum.

Thirteen (13) test pits were previously excavated at the site by others during May 2023 and April 2024. Additionally, four (4) groundwater monitoring wells were installed within completed test pits TP-1, TP-6, TP-7, and TP-9.

Soil Conditions

A detailed description of the subsurface conditions encountered in the explorations is documented on the boring logs attached to this memorandum. The approximate locations of the subsurface explorations are indicated on the enclosed Subsurface Exploration Plan, **Figure 2**.

Based on the results of the borings performed at the site, the following is a description of the generalized subsurface conditions encountered from ground surface downward.

<i>Generalized Subsurface Strata</i>	<i>Approximate Thickness (Feet)</i>	<i>Top of Soil Strata (Elevation)</i>
Fill	5.5 to 9.5	El. +7.9 to El. +11.1 (Ground Surface)
Peat	2.5 (At boring MA-2 only)	El. +2.4
Alluvium	12 to 19	El. -0.1 to El. +1.6
Marine Clay	Not Penetrated	El. -17.4 to El. -12.1

Fill Material: The fill material generally consists of compact to dense sand and gravel, trace to some silt, varying to a silt and sand, trace gravel and containing brick, wood, ash and cinders.

Organic Deposit: Underlying the fill at boring MA-2, the organic deposit generally consists of soft to firm, brown fibrous peat. The organic deposit was not encountered in boring MA-1 and appears to be discontinuous between MA-1 and MA-2.

Alluvium Deposit: Underlying the fill at boring MA-1 and the organic deposit at boring MA-2, the alluvium deposit generally consists of a compact to dense gray-brown stratified silty sand, varying to sand, trace silt.



Memorandum

Marine Clay Deposit: Underlying the alluvium deposit, the marine clay deposit generally consists of a very soft to stiff, gray silty marine clay deposit with occasional to frequent sand lenses of varying thickness. At boring MA-2, an approximate 2.5-foot-thick sand seam was observed from about Elevation -13.1 to Elevation -15.6. The depth to the top of the marine clay deposit was observed at about 28.5 feet and 20 feet below the existing ground surface at MA-1 and MA-2, respectively. The borings were terminated within the marine clay deposit which is anticipated to extend to depths greater than 100 feet below the existing ground surface and be underlain by glacial till and bedrock.

Groundwater Conditions

Where encountered in the borings during drilling, groundwater was observed at depths ranging from about 12 and 11 feet below the existing ground surface at boring MA-1 and MA-2, corresponding to Elevation -0.9 and Elevation -3.1, respectively.

It is anticipated that future groundwater levels across the site may vary from those reported herein due to factors such as normal seasonal changes, runoff particularly during or following periods of heavy precipitation, and alterations of existing drainage patterns.

Summary and Conclusions

The subsurface soil conditions in borings MA-1 and MA-2 consisted of a granular fill material, underlain by a discontinuous peat deposit, underlain by an alluvium deposit, overlying a marine clay deposit. The depth to the top of the marine clay deposit was observed at about 28.5 feet and 20 feet below the existing ground surface, corresponding to Elevation -17.4 and Elevation -12.1 at MA-1 and MA-2, respectively. The marine clay deposit is anticipated to have a low permeability and would be considered a barrier to groundwater flow, typically signifying the bottom of the permeable soils.


Closing

We trust that the above is sufficient for your present requirements. Should you have any questions concerning the recommendations presented herein, please do not hesitate to contact us.


N:\Working Documents\Jobs\7679 - Thorndike Place\Geotechnical Data Report\7679_ThorndikePlace_GeotechnicalData_Memo-rev2 120924.docx
SSS/ada

Attachments: Figure 1: Project Location Plan
 Figure 2: Subsurface Exploration Plan
 Boring Logs

FIGURE 1



42 3rd Avenue
 Burlington, MA 01803
 617-868-1420
 www.mcphailgeo.com




SCALE 1:25,000

PROJECT LOCATION PLAN


THORNDIKE PLACE

ARLINGTON

MASSACHUSETTS



LEGEND

 — APPROXIMATE LOCATION OF BOREHOLE PERFORMED BY CARR-DEE CORP. ON NOVEMBER 20, 2024 FOR McPHAIL ASSOCIATES, LLC

REFERENCE: THIS PLAN WAS PREPARED FROM AN 80-SCALE DRAWING ENTITLED "EXISTING CONDITIONS" DATED SEPTEMBER 6, 2023 BY BSC GROUP, INC.




42 3rd Avenue
Burlington, MA 01803
617-868-1420
www.mcphailgeo.com

THORNDIKE PLACE			
ARLINGTON		MASSACHUSETTS	
SUBSURFACE EXPLORATION PLAN			
FOR DINOSAUR CAPITAL PARTNERS LLC			
BY McPHAIL ASSOCIATES, LLC			
Date: DECEMBER 2024	Dwn: I.J.M.	Chkd: S.S.S.	Scale: 1" = 50'
Project No:	7679		

Project: Thorndike Place	Job #: 7679.2.01	Boring No.:
Location: See Plan	Date Started: 11-20-24	MA-1
City/State: Arlington, Massachusetts	Date Finished: 11-20-24	

Contractor: Carr-Dee Corp	Casing Type/Depth (ft): 2.25" I.D. HSA/NW Casing	Groundwater Observations	
Driller/Helper: J. DeSimone/C. Smith	Casing Hammer (lbs)/Drop (in): 300 lbs./24 inches	Date	Depth
Logged By/Reviewed By: T. M. Cormican	Sampler Size/Type: 1-3/8" I.D. Split Spoon	11-20-24	12
Surface Elevation (ft): 11.1	Sampler Hammer (lbs)/Drop (in): 140 lbs./30 inches	Elev.	Notes
		-0.9	

Depth (ft)	Elev. (ft)	Symbol	Depth/Elev. to Strata Change (ft)	Stratum	Sample					Sample Description and Boring Notes
					N-Value	No.	Pen./Rec. (in)	Depth (ft)	Blows Per 6"	
1	10			FILL	12	S-1	24/8	0.0-2.0	3 5 7 12	Compact light brown silty SAND and GRAVEL. (FILL)
2	9									
3	8									
4	7									
5	6									
6	5									
7	4									
8	3									
9	2									
10	1									
			9.5 / 1.6							
11	0			ALLUVIUM DEPOSIT	19	S-3	24/0	10.0-12.0	16 12 7 14	No Recovery
12	-1									
13	-2									
14	-3									
15	-4									
16	-5									
17	-6									
18	-7									
19	-8									
20	-9									
21	-10									
22	-11									
					45	S-4	24/14	12.0-14.0	14 23 22 20	Dense, dark gray SAND, trace to some silt. (ALLUVIUM DEPOSIT)
					23	S-5	24/12	15.0-17.0	9 12 11 12	Compact, gray-brown SAND, trace silt. (ALLUVIUM DEPOSIT)
					17	S-6	24/18	20.0-22.0	8 8 9 12	Compact, orange-brown and yellow-brown stratified silty SAND to SAND, trace silt. (ALLUVIUM DEPOSIT)

GRANULAR SOILS	
BLOWS/FT.	DENSITY
0-4	V.LOOSE
4-10	LOOSE
10-30	COMPACT
30-50	DENSE
>50	V.DENSE

SOIL COMPONENT	
DESCRIPTIVE TERM	PROPORTION OF TOTAL
"TRACE"	0-10%
"SOME"	10-20%
"ADJECTIVE" (eg SANDY, SILTY)	20-35%
"AND"	35-50%

SOIL CONTAINING THREE COMPONENTS EACH OF WHICH COMPRISE AT LEAST 25% OF THE TOTAL ARE CLASSIFIED AS "A WELL-GRADED MIXTURE OF"

COHESIVE SOILS	
BLOWS/FT.	CONSISTENCY
<2	V.SOFT
2-4	SOFT
4-8	FIRM
8-15	STIFF
15-30	V.STIFF
>30	HARD

Notes:

- Used Automatic Hammer for SPT.
- Drillers switched to casing after obtaining sample from 12-14'.

Weather: Variable



McPHAIL ASSOCIATES, LLC
 42 3rd AVENUE
 Burlington, MA 01803
 TEL: 617-868-1420
 FAX: 617-868-1423

Project: Thorndike Place	Job #: 7679.2.01	Boring No.
Location: See Plan	Date Started: 11-20-24	MA-1
City/State: Arlington, Massachusetts	Date Finished: 11-20-24	

Contractor: Carr-Dee Corp	Casing Type/Depth (ft): 2.25" I.D. HSA/NW Casing	Groundwater Observations	
Driller/Helper: J. DeSimone/C. Smith	Casing Hammer (lbs)/Drop (in): 300 lbs./24 inches	Date	Depth
Logged By/Reviewed By: T. M. Cormican	Sampler Size/Type: 1-3/8" I.D. Split Spoon	11-20-24	12
Surface Elevation (ft): 11.1	Sampler Hammer (lbs)/Drop (in): 140 lbs./30 inches	Elev.	Notes
		-0.9	

Depth (ft)	Elev. (ft)	Symbol	Depth/Elev. to Strata Change (ft)	Stratum	Sample					Sample Description and Boring Notes		
					N-Value	No.	Pen./Rec. (in)	Depth (ft)	Blows Per 6"			
24	-13			ALLUVIUM DEPOSIT						Dense, gray stratified silty SAND to SAND, trace silt. (ALLUVIUM DEPOSIT)		
25	-14								19			
26	-15						33	S-7	24/18		25.0-27.0	17
27	-16											16
28	-17		28.5 / -17.4									
29	-18	//		MARINE CLAY						Stiff, gray silty CLAY with ~ 6 inch layer of sand. (MARINE CLAY)		
30	-19										3	
31	-20						9	S-8	24/18		30.0-32.0	4
32	-21											5
33	-22											
34	-23											
35	-24											
36	-25											
37	-26		37.0 / -25.9						1/24"	Very soft, gray silty CLAY. (MARINE CLAY)		
38	-27			Bottom of Borehole at 37.0 feet below existing grade.								
39	-28											
40	-29											
41	-30											
42	-31											
43	-32											
44	-33											
45	-34											

GRANULAR SOILS		SOIL COMPONENT	
BLOWS/FT.	DENSITY	DESCRIPTIVE TERM	PROPORTION OF TOTAL
0-4	V.LOOSE	"TRACE"	0-10%
4-10	LOOSE	"SOME"	10-20%
10-30	COMPACT	"ADJECTIVE" (eg SANDY, SILTY)	20-35%
30-50	DENSE	"AND"	35-50%
>50	V.DENSE		
COHESIVE SOILS		Notes:	
BLOWS/FT.	CONSISTENCY	1. Used Automatic Hammer for SPT.	
<2	V.SOFT	2. Drillers switched to casing after obtaining sample from 12-14'.	
2-4	SOFT		
4-8	FIRM		
8-15	STIFF		
15-30	V.STIFF		
>30	HARD	Weather: Variable	



McPHAIL ASSOCIATES, LLC
 42 3rd AVENUE
 Burlington, MA 01803
 TEL: 617-868-1420
 FAX: 617-868-1423

Page 2 of 2
 319 of 504

Project: Thorndike Place	Job #: 7679.2.01	Boring No.
Location: See Plan	Date Started: 11-20-24	MA-2
City/State: Arlington, Massachusetts	Date Finished: 11-20-24	

Contractor: Carr-Dee Corp	Casing Type/Depth (ft): 2.25" I.D. HSA/NW Casing	Groundwater Observations	
Driller/Helper: J. DeSimone/C. Smith	Casing Hammer (lbs)/Drop (in): 300 lbs./24 inches	Date	Depth
Logged By/Reviewed By: T. M. Cormican	Sampler Size/Type: 1-3/8" I.D. Split Spoon	11-20-24	11
Surface Elevation (ft): 7.9	Sampler Hammer (lbs)/Drop (in): 140 lbs./30 inches	Elev.	Notes
		-3.1	

Depth (ft)	Elev. (ft)	Symbol	Depth/Elev. to Strata Change (ft)	Stratum	Sample					Sample Description and Boring Notes	
					N-Value	No.	Pen./Rec. (in)	Depth (ft)	Blows Per 6"		
1	7		0.4 / 7.5	TOPSOIL	4	S-1	24/16	0.0-2.0	3 2 2 3	Very loose to loose, mottled gray-brown SILT and SAND, trace gravel. (FILL)	
2	6			FILL							
3	5										
4	4										
5	3										
6	2		5.5 / 2.4	ORGANIC DEPOSIT	4	S-2	6/6	5.0-5.5	2	Very loose, mottled orange-brown and black SILT and SAND, with wood, ash and cinders. (FILL)	
7	1										Soft to firm, brown FIBROUS PEAT. (ORGANIC DEPOSIT)
8	0										
9	-1		8.0 / -0.1	ALLUVIUM DEPOSIT							
10	-2										
11	-3					17	S-3	24/14	10.0-12.0	9 8 9 9	Compact, gray-brown stratified silty SAND to SAND, trace silt. (ALLUVIUM DEPOSIT)
12	-4										
13	-5										
14	-6										
15	-7										
16	-8					18	S-4	24/16	15.0-17.0	8 8 10 9	Compact, stratified gray silty SAND to SAND, trace silt. (ALLUVIUM DEPOSIT)
17	-9										
18	-10										
19	-11										
20	-12		20.0 / -12.1	MARINE CLAY							
21	-13					5	S-5	12/12	20.0-21.0	3 2	Very soft to soft, gray silty CLAY with silt and sand seams. (MARINE CLAY)
22	-14		21.0 / -13.1	MARINE SAND							
						22	S-5a	12/12	21.0-22.0	8 14	Compact, gray stratified silty SAND to SAND, trace silt. (MARINE SAND)

GRANULAR SOILS	
BLOWS/FT.	DENSITY
0-4	V.LOOSE
4-10	LOOSE
10-30	COMPACT
30-50	DENSE
>50	V.DENSE

SOIL COMPONENT	
DESCRIPTIVE TERM	PROPORTION OF TOTAL
"TRACE"	0-10%
"SOME"	10-20%
"ADJECTIVE" (eg SANDY, SILTY)	20-35%
"AND"	35-50%

SOIL CONTAINING THREE COMPONENTS EACH OF WHICH COMPRISE AT LEAST 25% OF THE TOTAL ARE CLASSIFIED AS "A WELL-GRADED MIXTURE OF"

COHESIVE SOILS	
BLOWS/FT.	CONSISTENCY
<2	V.SOFT
2-4	SOFT
4-8	FIRM
8-15	STIFF
15-30	V.STIFF
>30	HARD

Notes:
 1. Used Automatic Hammer for SPT.
 2. Drillers switched to casing after obtaining sample from 10-12'.

 Weather: Variable



McPHAIL ASSOCIATES, LLC
 42 3rd AVENUE
 Burlington, MA 01803
 TEL: 617-868-1420
 FAX: 617-868-1423

Page 1 of 2
 320 of 504

Project: Thorndike Place	Job #: 7679.2.01	Boring No.
Location: See Plan	Date Started: 11-20-24	MA-2
City/State: Arlington, Massachusetts	Date Finished: 11-20-24	

Contractor: Carr-Dee Corp	Casing Type/Depth (ft): 2.25" I.D. HSA/NW Casing	Groundwater Observations	
Driller/Helper: J. DeSimone/C. Smith	Casing Hammer (lbs)/Drop (in): 300 lbs./24 inches	Date	Depth
Logged By/Reviewed By: T. M. Cormican	Sampler Size/Type: 1-3/8" I.D. Split Spoon	11-20-24	11
Surface Elevation (ft): 7.9	Sampler Hammer (lbs)/Drop (in): 140 lbs./30 inches	Elev.	Notes
		-3.1	

Depth (ft)	Elev. (ft)	Symbol	Depth/Elev. to Strata Change (ft)	Stratum	Sample					Sample Description and Boring Notes	
					N-Value	No.	Pen./Rec. (in)	Depth (ft)	Blows Per 6"		
24	-16		23.5 / -15.6	MARINE SAND							
25	-17										
26	-18					2	S-6	24/24	25.0-27.0	1/12' 1 1	Very soft, gray silty CLAY with frequent sand partings in bottom ~ 10 inches of sample. (MARINE CLAY)
27	-19										
28	-20										
29	-21										
30	-22										
31	-23					1	S-7	24/24	30.0-32.0	WOH WOH 1 1	Very soft, gray silty CLAY with frequent sand partings. (MARINE CLAY)
32	-24										
33	-25				MARINE CLAY						
34	-26										
35	-27										
36	-28				1	S-8	24/24	35.0-37.0	WOH WOH 1 1	Very soft, gray silty CLAY, with occasional sand partings. (MARINE CLAY)	
37	-29										
38	-30										
39	-31										
40	-32										
41	-33				1	S-9	24/24	40.0-42.0	WOH WOH 1 WOH	Very soft, gray silty CLAY, with occasional sand partings. (MARINE CLAY)	
42	-34		42.0 / -34.1								
43	-35			Bottom of Borehole at 42.0 feet below existing grade.							
44	-36										
45	-37										

GRANULAR SOILS	
BLOWS/FT.	DENSITY
0-4	V.LOOSE
4-10	LOOSE
10-30	COMPACT
30-50	DENSE
>50	V.DENSE

SOIL COMPONENT	
DESCRIPTIVE TERM	PROPORTION OF TOTAL
"TRACE"	0-10%
"SOME"	10-20%
"ADJECTIVE" (eg SANDY, SILTY)	20-35%
"AND"	35-50%

SOIL CONTAINING THREE COMPONENTS EACH OF WHICH COMPRISE AT LEAST 25% OF THE TOTAL ARE CLASSIFIED AS "A WELL-GRADED MIXTURE OF"

COHESIVE SOILS	
BLOWS/FT.	CONSISTENCY
<2	V.SOFT
2-4	SOFT
4-8	FIRM
8-15	STIFF
15-30	V.STIFF
>30	HARD

Notes:

- Used Automatic Hammer for SPT.
- Drillers switched to casing after obtaining sample from 10-12'.

Weather: Variable




McPHAIL ASSOCIATES, LLC
 42 3rd AVENUE
 Burlington, MA 01803
 TEL: 617-868-1420
 FAX: 617-868-1423

Page 2 of 2
 321 of 504

REVISIONS TO STORMWATER MANAGEMENT DESIGN DECEMBER 2024

The following attachments are only the portions of the Stormwater Report for Thorndike Place that have been revised in December 2024. This information is all included in the full Stormwater Report but is being provided in this format to help simplify review.



PROFESSIONAL ENGINEER

THORNDIKE PLACE NOTICE OF INTENT

DOROTHY ROAD
IN
ARLINGTON
MASSACHUSETTS
(MIDDLESEX COUNTY)

GRADING & DRAINAGE PLAN

SEPTEMBER 6, 2023

REVISIONS:

NO.	DATE	DESC.
1	9/12/24	INFILTRATION SYSTEM
2	12/10/24	PEER REVIEW REVISIONS

PREPARED FOR:
ARLINGTON LAND REALTY, LLC
84 SHERMAN STREET, 2ND FLOOR
CAMBRIDGE, MA

803 Summer Street
Boston, Massachusetts
02127
617 896 4300

© 2023 BSC Group, Inc.
SCALE: 1" = 30'
0 15 30 60 FEET
FILE: 2340702\C\2340702-GR
DWG.:
JOB. NO: 23407.02 SHEET C-104

ISSUED FOR PERMITTING
NOT FOR CONSTRUCTION

1.01 PROJECT DESCRIPTION

Arlington Land Realty, LLC (The Applicant) is seeking to construct a new age restricted multi-family housing development in Arlington, Massachusetts, hereinafter referred to as “the Project.” The total property area is approximately 17.66 acres and is located off Dorothy Road near the intersection with Littlejohn Street. The project is bounded on the north by Dorothy Road, on the east by residential properties and Thorndike Field, and bounded on the south and west by Concord Turnpike (Route 2).

The Project consists of clearing and grubbing of the northwest section of the property and construction of one 4-story senior living residential building with a lower-level parking garage, six duplex townhouses with covered carports, as well as surface parking, walkways, utility services, and a stormwater management system. The buildings have a combined footprint of approximately 46,100 square feet.

The Project is designed to comply with the Massachusetts General Laws (M.G.L.) Chapter 40B, which allows developers to override certain aspects of municipal zoning bylaws by providing a certain percentage of affordable housing, as well as the Department of Environmental Protection’s Stormwater Management Standards. There are wetland resource areas in the south, west and east portions of the property. The Project is concentrated in the northwest area of the property and minimizes impacts to the 100-foot wetland buffer zones. Part of the site is located within the 1% Chance Annual Flood as defined by FEMA which is regulated under the Wetlands Protection Act as Bordering Land Subject to Flooding (BLSF). Compensatory flood storage is proved at a 2:1 ratio as described in section 2.12 below. This Stormwater Report and design were extensively peer reviewed in November 2020 and August 2021 by BETA Group during the Comprehensive Permit Application process and again by both Hatch Associates Consultants, Inc. and GZA GeoEnvironmental, Inc. during the Conservation Commission’s review of the Project’s Notice of Intent.

1.02 PRE-DEVELOPMENT CONDITIONS

The existing site topography generally slopes southeast across the property towards the wetlands located on the property with slopes ranging from 0-15%. The current site is comprised of forest and the primary soil classification identified by the NRCS Web Soil Survey is udorthents (655), which accounts for the majority of the property and all of the project area. On November 25, 2020, BSC Group conducted three test pits on the site, the locations of which are noted on the Grading and Drainage plan, and the test pit logs attached in Appendix D. The test pits consisted primarily of fill material to a depth of 9-11 feet generally conforming with the soils mapping. Even though the material was fill, all samples textured as sandy loam in test pits TP-1 and TP-2, closest to the proposed stormwater management systems. At the bottom of test pit TP-3, a layer of clay material was found. Based on the fill materials found, runoff calculations have been performed using curve numbers corresponding to Hydrologic Soil Group (HSG) C.

Due to changes to the site design over the course of the Comprehensive Permit process, the proposed infiltration systems were relocated. As such, and to comply with Conditions C.2(k) and I.17 of the Comprehensive Permit that was issued by the Arlington Zoning Board of Appeals for the project in 2021, BSC conducted 8 additional soil test pits on May 18 and 19, 2023. The soil types for these test pits generally consisted of fill materials overlaying fine sandy loam, consistent with the previous test pits conducted in 2020. In accordance with the Comprehensive Permit conditions, BSC coordinated with the Town of Arlington to ensure that Town staff or a representative designated by the Town would be on site during test pit work to witness and confirm the results. BSC contacted Claire Ricker, Director of Planning & Community Development to coordinate a test pit witness for the Town and was referred through Town Engineer, Wayne Chouinard to David Morgan, Environmental Planner and Conservation Agent. Mr. Morgan arranged to have a representative from Whitestone Associates on site to witness the test pits on May 18 and 19, 2023. These test pit locations have been added to the revised Grading and Drainage plan and the additional test pit logs are included in Appendix D.

Five more test pits were conducted on April 17, 2024, to gather additional soil and groundwater data and confirm that the design of the infiltration system would meet the Stormwater Standards per the DEP’s Massachusetts Stormwater Handbook. These test pits were consistent with the others that were conducted previously and consisted mainly of fill

that textured as sandy loam. One test pit, TP-9, found parent material 100-inches down, which was also a fine sandy loam. Additional test pit logs are included in Appendix D.

In November 2024, McPhail Associates, LLC (McPhail) performed two (2) soil borings on the Project site in the areas of proposed Infiltration Systems 1 and 7. These soil borings were performed to better understand the depth to a restrictive layer to more accurately determine the initial saturated thickness to be used in groundwater mounding analyses for the Project. A memorandum documenting this work is included in Appendix G. The borings showed a marine clay layer with a highest elevation between -12.1 and -17.4. Based on this additional data, all groundwater mounding analyses have been performed using an initial saturated thickness of 16-feet representing the depth between ESHGW (4.0) and the marine clay layer (-12.1).

The existing site being largely undeveloped has no existing drainage facilities and the majority of the stormwater runoff is directed to the wetlands on the property. A small portion of the site discharges to the north to Dorothy Road.

1.03 POST-DEVELOPMENT CONDITIONS

The proposed stormwater management system has been designed in a manner that will meet or exceed the provisions of the Department of Environmental Protection (DEP) Stormwater Management Standards for a new construction project.

Stormwater runoff from the site driveway and small parking/drop-off area at the main entrance to the building will be collected via a deep sump catch basin, conveyed through a water quality unit before being directed to an underground infiltration system. Stormwater runoff from a portion the driveway into the garage below the building will be collected via a trench drain and conveyed through a water quality unit before being directed to the underground system. Due to its elevation difference, this leg of the system has been provided with a backflow preventer device. This underground infiltration system provides for recharge to groundwater and provides peak flow rate attenuation. In larger storm events, this system will overflow through an outlet control structure to a flared end section with a rip-rap apron to the south.

Runoff from the townhouse and carport roofs, as well as the landscaped areas between the townhouses and 4-story building will be collected and routed to a second underground infiltration area. This underground infiltration area will also collect runoff from the roof of the 4-story building. This underground infiltration system provides for recharge to groundwater and provides peak flow rate attenuation. In larger storm events, this system will overflow through an outlet control structure to a flared end section with a rip-rap apron to the south.

Stormwater runoff from the townhouse driveways along Dorothy Rd will be collected via individual trench drains and routed to small underground infiltration chamber systems beneath each driveway. These systems provide localized infiltration to groundwater and help meet the required recharge volume for the Project. Overflow from these systems will be routed to the same infiltration system as the townhouse roofs and 4-story building.

Runoff from a small portion of the driveway to the garage will be collected in a trench drain and routed through a water quality unit for treatment prior to discharge through the flared end section with a rip-rap apron to the south.

Although all soils sampled in test pits TP-1 and TP-2, as well as the 8 test pits conducted in May 2023 and 5 conducted in April 2024, were identified as sandy loam (see above), the infiltration rate for silt loam (0.27-inches per hour) has been used in the infiltration system design to account for the materials found being primarily fill. Based upon the test pit data and groundwater monitoring performed in Spring 2024, the estimated seasonal high groundwater has been determined to be elevation 4.0. As such, to provide the minimum 2-feet of separation, the infiltration systems for the townhouse trench drains have been set with a bottom elevation of 7.0, the infiltration system collecting the majority of the driveways and parking areas has been set with a bottom elevation of 7.15, and the infiltration system collecting roofs and overflow from the townhouse trench drains has been set with a bottom elevation of 8.0. Groundwater mounding calculations for the 100-year event have been provided for all infiltration systems with less than 4.0-feet of separation to estimated seasonal high groundwater.

To provide emergency access to the sides and rear of the building, a reinforced grass access lane will be installed. A portion of this access lane will include a 6-foot wide, porous asphalt walkway to allow residents to have ADA/AAB accessible access the rear of the site. Both the reinforced grass and porous asphalt will allow stormwater runoff to freely infiltrate back to the ground and will result in negligible runoff.

Specifics of the project's compliance with the Stormwater Standards are discussed in detail in the following sections.

SECTION 2.0

DRAINAGE SUMMARY

2.01 Stormwater Standard 1 – New Stormwater Conveyances

Per Massachusetts Stormwater Management Standard #1, no new outfalls may discharge untreated stormwater directly to or cause erosion in wetlands or waters of the Commonwealth. No new untreated stormwater discharges are proposed. Rip-rap outlet protection sizing calculations are included in Section 6.0 of this Report.

2.02 Stormwater Standard 2 – Stormwater Runoff Rates

Watershed modeling was performed using HydroCAD Stormwater Modeling Software version 10.20, a computer aided design program that combines SCS runoff methodology with standard hydraulic calculations. A model of the site’s hydrology was developed for both pre- and post-development conditions to assess the effects of the proposed development on the project site and surrounding areas.

Stormwater runoff was modeled using data from the NOAA 14++ rainfall atlas. The NOAA 14++ precipitation values are higher than the TP-40 rainfall values that are required by Wetlands Protection Act (WPA) and consistent with the requirements of the updated Arlington Wetland Bylaw. The following rainfall values have been used in the analysis and the NOAA 14++ data is included in Appendix D:

<u>Storm Frequency</u>	<u>NOAA 14++ Rainfall (Inches)</u>
2-year	4.02
10-year	6.40
25-year	8.30
50-year	9.67
100-year	11.50

The stormwater management system for the project has been designed such that the post-development conditions result in no increase to peak runoff rates off the property for the 2, 10, 25, 50, and 100-year, 24-hour storm events, as detailed in the table below.

Peak Flow Discharge Rates

Node 1L – Flow to Wetlands

Storm Event	Pre-Development Peak Discharge Rate (cfs)	Post-Development Peak Discharge Rate (cfs)	Change in Peak Discharge Rate (cfs)
2-Year	3.7	3.6	-0.1
10-Year	9.0	9.0	0.0
25-Year	13.7	13.7	0.0
50-Year	17.2	17.0	-0.2
100-Year	22.0	21.4	-0.6

Node 2L – Flow Towards Street

Storm Event	Pre-Development Peak Discharge Rate (cfs)	Post-Development Peak Discharge Rate (cfs)	Change in Peak Discharge Rate (cfs)
2-Year	0.3	0.3	0.0
10-Year	0.7	0.6	-0.1
25-Year	1.0	0.9	-0.1
50-Year	1.2	1.1	-0.1
100-Year	1.5	1.3	-0.2

Node 100L – Total Flows

Storm Event	Pre-Development Peak Discharge Rate (cfs)	Post-Development Peak Discharge Rate (cfs)	Change in Peak Discharge Rate (cfs)
2-Year	3.8	3.8	0.0
10-Year	9.4	9.4	0.0
25-Year	14.2	14.2	0.0
50-Year	17.9	17.8	-0.1
100-Year	22.7	22.3	-0.4

2.03 Stormwater Standard 3 – Groundwater Recharge

Groundwater recharge is provided on site via multiple underground structural infiltration systems beneath the surface parking area to the north of the building and smaller systems beneath each individual driveway of the duplex townhouses. Overall, the project will result in no loss of annual recharge to groundwater as required by Standard 3. Refer to Section 6.0 of this Report for groundwater recharge information.

As the townhouse driveway infiltration systems and the infiltration system collecting the majority of the driveway have more than 2-feet but less than 4-feet separation to estimated seasonal high groundwater, a mounding analysis has been performed in accordance with the Hantush Method for each to ensure that a groundwater mound does not extend into the bottom of the infiltration system preventing infiltration of the required recharge volume. This analysis has been performed utilizing the infiltration volume that occurs during the 100-year storm event and is included in Section 6.0 of this Report. As the system that collects the 4-story building roof has 4-feet of separation to groundwater, a mounding analysis is not required for this system.

2.04 Stormwater Standard 4 – TSS Removal

As a new development, the Project stormwater management system will achieve a TSS removal greater than 80%. The proposed stormwater management system has been designed to provide treatment of runoff in order to reduce suspended solids prior to discharge off-site through the implementation of the following best management practices:

- Deep Sump Hooded Catch Basins
- Proprietary Hydrodynamic Separators

- Underground Stormwater Infiltration Systems
- Rain Garden

The water quality volume is defined as the runoff volume requiring TSS Removal for the site and is equal to 0.5-inches of runoff over the total impervious area of the post-development site. The required water quality volume for the project is provided in Section 6.0 of this Report.

The underground infiltration systems have been sized to treat the required water quality volume and calculations are included in Section 6.0 of this Report.

A long-term pollution prevention plan complying with the requirements of Standard 4 is included in Section 4.0 of this Report.

2.05 Stormwater Standard 5 – Land Uses with Higher Potential Pollutant Loads

This standard is not applicable as the proposed project is not a land use with higher potential pollutant loads (LUHPPL).

2.06 Stormwater Standard 6 – Stormwater Discharges to a Critical Area

This standard is not applicable as runoff from the project site does not discharge to a critical area.

2.07 Stormwater Standard 7 – Redevelopment Projects

This project is a new development and therefore has been designed to fully comply with the Stormwater Management Standards.

2.08 Stormwater Standard 8 – Sedimentation and Erosion Control Plan

Erosion and sedimentation controls are shown on the Project Plans. Additionally, a Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan is included in Section 3.0 of this Report.

2.09 Stormwater Standard 9 – Long Term Operation and Maintenance Plan

A Long-Term Operation and Maintenance Plan is included in Section 4.0 of this Report.

2.10 Stormwater Standard 10 – Illicit Discharges

There are no known illicit discharges on the project site, and none are proposed. An illicit discharge compliance statement is included in Section 6.0 and will be signed by the Applicant prior to issuance of any permits.

2.11 Conclusion

The project has been designed in accordance with DEP Stormwater Management Standards. Through the construction of the aforementioned stormwater systems, the project will provide peak rate attenuation, TSS removal and groundwater recharge.

2.12 Compensatory Flood Storage

A portion of the project site is located within the 1% Chance Annual Flood as defined by FEMA, which is regulated under the Wetlands Protection Act as Bordering Land Subject to Flooding (BLSF). In order to protect the values provided by BLSF and prevent downstream flooding impacts, the project is required to provide compensatory flood storage on a 1-foot incremental basis to match whatever is lost due to the project's development. In order to provide this compensatory flood storage, the project will minimize the area of BLSF impacted and regrade a portion of the project property southeast of the proposed building as shown on the Plans. This regraded area will provide compensatory flood storage at a 2 to 1 ratio for any flood storage lost. A breakdown of the flood storage impacts and compensatory storage provided is shown below:


<u>Elevations</u>	<u>Existing Incremental Available Flood Storage (CU.FT.)</u>	<u>Incremental Available Flood Storage with No Compensatory Storage (CU.FT.)</u>	<u>Incremental Flood Storage Change w/No Compensatory Storage (CU.FT.)</u>	<u>Proposed Incremental Compensatory Storage (CU.FT.)</u>	<u>Ratio of Compensatory Storage to Storage Lost</u>
5.0 - 6.0	136.0	67.5	-68.5	146.0	2.1
6.0 - 6.8	9,327.6	5,003.2	-4,324.4	9,014.8	2.1

As shown above, the project will exceed the 2 to 1 ratio of compensatory flood storage for all flood storage lost due to the project development. In addition, as shown on the Plans, the proposed compensatory storage is hydrologically connected to the flood plain impacted by the project. Therefore, the project as proposed meets the applicable requirements for BLSF in the Wetlands Protection Act.

SECTION 5.0

HYDROLOGY CALCULATIONS

5.03 PROPOSED WATERSHED PLAN



THORNDIKE PLACE

DOROTHY ROAD

ARLINGTON
MASSACHUSETTS
(MIDDLESEX COUNTY)

PROPOSED WATERSHED
PLAN

NOVEMBER 3, 2020

PREPARED
FOR:
ARLINGTON LAND REALTY
84 SHERMAN STREET
CAMBRIDGE, MA



803 Summer Street
Boston, Massachusetts
02127

617 896 4300

Job No.: 23407.02 Date: 11/3/2020
Scale: 1" = 60' Revised: 12/10/2024
Dwg No: PRW
File: C:\DRAINAGE DESIGN\2340700-PRW

LEGEND

1S SUBCATCHMENT

— SUBCATCHMENT BOUNDARY

Tc TIME OF CONCENTRATION FLOW PATH

SCALE: 1" = 60'

0 30 60 120 FEET

5.04 PROPOSED HYDROLOGY CALCULATIONS (HYDROCAD™ PRINTOUTS)

2340702-PR-2024-12-10

Prepared by BSC Group


HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Printed 12/17/2024

Page 2

Rainfall Events Listing

Event#	Event Name	Storm Type	Curve	Mode	Duration (hours)	B/B	Depth (inches)	AMC
1	2-Year	Type III 24-hr		Default	24.00	1	4.02	2
2	10-Year	Type III 24-hr		Default	24.00	1	6.40	2
3	25-Year	Type III 24-hr		Default	24.00	1	8.30	2
4	50-Year	Type III 24-hr		Default	24.00	1	9.67	2
5	100-Year	Type III 24-hr		Default	24.00	1	11.50	2



Area Listing (all nodes)

Area (sq-ft)	CN	Description (subcatchment-numbers)
74,381	74	>75% Grass cover, Good, HSG C (1S, 3.1S, 4.2S, 4.3S, 4.4S, 4.5S, 4.6S, 5.1S, 5S, 6.1S, 6S, 7S)
220	89	Gravel roads, HSG C (6.1S)
411	89	Gravel sidewalk, HSG C (3.1S)
25,874	98	Paved parking, HSG C (1S, 4.2S, 4.3S, 4.4S, 4.5S, 4.6S, 5.1S, 5S, 7S)
6,444	98	Paved roads w/curbs & sewers, HSG C (6.1S)
46,099	98	Roofs, HSG C (2S, 3S, 6S)
272	98	Unconnected pavement, HSG C (3.1S)
4,985	70	Woods, Good, HSG C (6S)
158,686	86	TOTAL AREA

Soil Listing (all nodes)

Area (sq-ft)	Soil Group	Subcatchment Numbers
0	HSG A	
0	HSG B	
158,686	HSG C	1S, 2S, 3.1S, 3S, 4.2S, 4.3S, 4.4S, 4.5S, 4.6S, 5.1S, 5S, 6.1S, 6S, 7S
0	HSG D	
0	Other	
158,686		TOTAL AREA

Ground Covers (all nodes)

HSG-A (sq-ft)	HSG-B (sq-ft)	HSG-C (sq-ft)	HSG-D (sq-ft)	Other (sq-ft)	Total (sq-ft)	Ground Cover
0	0	74,381	0	0	74,381	>75% Grass cover, Good
0	0	220	0	0	220	Gravel roads
0	0	411	0	0	411	Gravel sidewalk
0	0	25,874	0	0	25,874	Paved parking
0	0	6,444	0	0	6,444	Paved roads w/curbs & sewers
0	0	46,099	0	0	46,099	Roofs
0	0	272	0	0	272	Unconnected pavement
0	0	4,985	0	0	4,985	Woods, Good
0	0	158,686	0	0	158,686	TOTAL AREA

Time span=0.00-72.00 hrs, dt=0.01 hrs, 7201 points
 Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
 Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment1S: CB-1	Runoff Area=22,742 sf 72.16% Impervious Runoff Depth=3.04" Tc=6.0 min CN=91 Runoff=1.8 cfs 5,755 cf
Subcatchment2S: Building Roof	Runoff Area=32,925 sf 100.00% Impervious Runoff Depth=3.79" Tc=6.0 min CN=98 Runoff=3.0 cfs 10,385 cf
Subcatchment3.1S: Backyard ADS	Runoff Area=8,985 sf 3.03% Impervious Runoff Depth=1.68" Flow Length=147' Tc=10.3 min CN=75 Runoff=0.3 cfs 1,259 cf
Subcatchment3S: Townhouse Roofs	Runoff Area=13,067 sf 100.00% Impervious Runoff Depth=3.79" Tc=6.0 min CN=98 Runoff=1.2 cfs 4,122 cf
Subcatchment4.2S: TD-2	Runoff Area=1,112 sf 95.68% Impervious Runoff Depth=3.67" Tc=6.0 min CN=97 Runoff=0.1 cfs 340 cf
Subcatchment4.3S: TD-3	Runoff Area=1,105 sf 97.29% Impervious Runoff Depth=3.67" Tc=6.0 min CN=97 Runoff=0.1 cfs 338 cf
Subcatchment4.4S: TD-4	Runoff Area=1,104 sf 97.46% Impervious Runoff Depth=3.67" Tc=6.0 min CN=97 Runoff=0.1 cfs 338 cf
Subcatchment4.5S: TD-5	Runoff Area=1,082 sf 98.06% Impervious Runoff Depth=3.79" Tc=6.0 min CN=98 Runoff=0.1 cfs 341 cf
Subcatchment4.6S: TD-6	Runoff Area=1,056 sf 99.24% Impervious Runoff Depth=3.79" Tc=6.0 min CN=98 Runoff=0.1 cfs 333 cf
Subcatchment5.1S: TD-1A	Runoff Area=1,389 sf 84.59% Impervious Runoff Depth=3.34" Tc=6.0 min CN=94 Runoff=0.1 cfs 387 cf
Subcatchment5S: TD-1B	Runoff Area=4,462 sf 42.78% Impervious Runoff Depth=2.39" Tc=6.0 min CN=84 Runoff=0.3 cfs 888 cf
Subcatchment6.1S: East driveway	Runoff Area=12,275 sf 52.50% Impervious Runoff Depth=2.66" Tc=6.0 min CN=87 Runoff=0.9 cfs 2,716 cf
Subcatchment6S: Bypass Towards	Runoff Area=51,539 sf 0.21% Impervious Runoff Depth=1.61" Flow Length=125' Tc=14.0 min CN=74 Runoff=1.7 cfs 6,919 cf
Subcatchment7S: To Street	Runoff Area=5,843 sf 18.07% Impervious Runoff Depth=1.90" Tc=6.0 min CN=78 Runoff=0.3 cfs 927 cf
Pond 1P: Inf Syst-1	Peak Elev=9.37' Storage=8,769 cf Inflow=4.8 cfs 16,622 cf Discarded=0.1 cfs 13,377 cf Primary=0.3 cfs 3,246 cf Outflow=0.4 cfs 16,622 cf
Pond 3P: Rain garden	Peak Elev=6.42' Storage=216 cf Inflow=0.9 cfs 2,716 cf Discarded=0.0 cfs 444 cf Primary=0.9 cfs 2,272 cf Outflow=0.9 cfs 2,716 cf

2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 2-Year Rainfall=4.02"

Printed 12/17/2024

Page 7

Pond 4P: Inf Syst-2

Peak Elev=9.41' Storage=129 cf Inflow=0.1 cfs 340 cf
Discarded=0.0 cfs 156 cf Primary=0.1 cfs 171 cf Outflow=0.1 cfs 327 cf

Pond 5P: Inf Syst-3

Peak Elev=9.55' Storage=134 cf Inflow=0.1 cfs 338 cf
Discarded=0.0 cfs 156 cf Primary=0.1 cfs 163 cf Outflow=0.1 cfs 319 cf

Pond 6P: Inf Syst-4

Peak Elev=9.55' Storage=134 cf Inflow=0.1 cfs 338 cf
Discarded=0.0 cfs 156 cf Primary=0.1 cfs 163 cf Outflow=0.1 cfs 319 cf

Pond 7P: Inf Syst-5

Peak Elev=9.18' Storage=117 cf Inflow=0.1 cfs 341 cf
Discarded=0.0 cfs 157 cf Primary=0.1 cfs 183 cf Outflow=0.1 cfs 341 cf

Pond 8P: Inf Syst-6

Peak Elev=9.20' Storage=118 cf Inflow=0.1 cfs 333 cf
Discarded=0.0 cfs 157 cf Primary=0.1 cfs 175 cf Outflow=0.1 cfs 332 cf

Pond 9P: Inf Syst-7

Peak Elev=7.84' Storage=1,431 cf Inflow=1.9 cfs 6,142 cf
Discarded=0.0 cfs 1,379 cf Primary=1.1 cfs 4,762 cf Outflow=1.1 cfs 6,142 cf

Link 1L: Towards Wetlands

Inflow=3.6 cfs 18,088 cf
Primary=3.6 cfs 18,088 cf

Link 2L: Towards Street

Inflow=0.3 cfs 927 cf
Primary=0.3 cfs 927 cf

Link 100L: Total Flows

Inflow=3.8 cfs 19,014 cf
Primary=3.8 cfs 19,014 cf

Total Runoff Area = 158,686 sf Runoff Volume = 35,048 cf Average Runoff Depth = 2.65"
50.41% Pervious = 79,997 sf 49.59% Impervious = 78,689 sf

2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 2-Year Rainfall=4.02"

Printed 12/17/2024

Page 8

Summary for Subcatchment 1S: CB-1


Runoff = 1.8 cfs @ 12.09 hrs, Volume= 5,755 cf, Depth= 3.04"
Routed to Pond 9P : Inf Syst-7

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 2-Year Rainfall=4.02"

Area (sf)	CN	Description
16,410	98	Paved parking, HSG C
6,332	74	>75% Grass cover, Good, HSG C
22,742	91	Weighted Average
6,332		27.84% Pervious Area
16,410		72.16% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 1S: CB-1



Summary for Subcatchment 2S: Building Roof


Runoff = 3.0 cfs @ 12.08 hrs, Volume= 10,385 cf, Depth= 3.79"
Routed to Pond 1P : Inf Syst-1

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 2-Year Rainfall=4.02"

Area (sf)	CN	Description
32,925	98	Roofs, HSG C
32,925		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 2S: Building Roof



Summary for Subcatchment 3.1S: Backyard ADs

Runoff = 0.3 cfs @ 12.15 hrs, Volume= 1,259 cf, Depth= 1.68"
Routed to Pond 1P : Inf Syst-1


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 2-Year Rainfall=4.02"

Area (sf)	CN	Description
272	98	Unconnected pavement, HSG C
8,302	74	>75% Grass cover, Good, HSG C
411	89	Gravel sidewalk, HSG C
8,985	75	Weighted Average
8,713		96.97% Pervious Area
272		3.03% Impervious Area
272		100.00% Unconnected

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
9.4	50	0.0142	0.09		Sheet Flow, Grass: Dense n= 0.240 P2= 3.23"
0.9	97	0.0154	1.86		Shallow Concentrated Flow, Grassed Waterway Kv= 15.0 fps

10.3 147 Total

Subcatchment 3.1S: Backyard ADs



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 2-Year Rainfall=4.02"

Printed 12/17/2024

Page 11

Summary for Subcatchment 3S: Townhouse Roofs


Runoff = 1.2 cfs @ 12.08 hrs, Volume= 4,122 cf, Depth= 3.79"
Routed to Pond 1P : Inf Syst-1

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 2-Year Rainfall=4.02"

Table with 3 columns: Area (sf), CN, Description. Row 1: 13,067, 98, Roofs, HSG C. Row 2: 13,067, 100.00% Impervious Area.

Table with 6 columns: Tc (min), Length (feet), Slope (ft/ft), Velocity (ft/sec), Capacity (cfs), Description. Row 1: 6.0, Direct Entry, Min. Tc.

Subcatchment 3S: Townhouse Roofs



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 2-Year Rainfall=4.02"

Printed 12/17/2024

Page 12

Summary for Subcatchment 4.2S: TD-2


Runoff = 0.1 cfs @ 12.08 hrs, Volume= 340 cf, Depth= 3.67"
Routed to Pond 4P : Inf Syst-2

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 2-Year Rainfall=4.02"

Table with 3 columns: Area (sf), CN, Description. Row 1: 1,064, 98, Paved parking, HSG C. Row 2: 48, 74, >75% Grass cover, Good, HSG C. Row 3: 1,112, 97, Weighted Average. Row 4: 48, 4.32% Pervious Area. Row 5: 1,064, 95.68% Impervious Area.

Table with 6 columns: Tc (min), Length (feet), Slope (ft/ft), Velocity (ft/sec), Capacity (cfs), Description. Row 1: 6.0, Direct Entry, Min. Tc.

Subcatchment 4.2S: TD-2



Summary for Subcatchment 4.3S: TD-3

Runoff = 0.1 cfs @ 12.08 hrs, Volume= 338 cf, Depth= 3.67"
 Routed to Pond 5P : Inf Syst-3


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 2-Year Rainfall=4.02"

Area (sf)	CN	Description
1,075	98	Paved parking, HSG C
30	74	>75% Grass cover, Good, HSG C
1,105	97	Weighted Average
30		2.71% Pervious Area
1,075		97.29% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.3S: TD-3

Hydrograph



Summary for Subcatchment 4.4S: TD-4

Runoff = 0.1 cfs @ 12.08 hrs, Volume= 338 cf, Depth= 3.67"
 Routed to Pond 6P : Inf Syst-4


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 2-Year Rainfall=4.02"

Area (sf)	CN	Description
1,076	98	Paved parking, HSG C
28	74	>75% Grass cover, Good, HSG C
1,104	97	Weighted Average
28		2.54% Pervious Area
1,076		97.46% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.4S: TD-4

Hydrograph



Summary for Subcatchment 4.5S: TD-5

Runoff = 0.1 cfs @ 12.08 hrs, Volume= 341 cf, Depth= 3.79"
 Routed to Pond 7P : Inf Syst-5


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 2-Year Rainfall=4.02"

Area (sf)	CN	Description
1,061	98	Paved parking, HSG C
21	74	>75% Grass cover, Good, HSG C
1,082	98	Weighted Average
21		1.94% Pervious Area
1,061		98.06% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.5S: TD-5

Hydrograph



Summary for Subcatchment 4.6S: TD-6

Runoff = 0.1 cfs @ 12.08 hrs, Volume= 333 cf, Depth= 3.79"
 Routed to Pond 8P : Inf Syst-6


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 2-Year Rainfall=4.02"

Area (sf)	CN	Description
1,048	98	Paved parking, HSG C
8	74	>75% Grass cover, Good, HSG C
1,056	98	Weighted Average
8		0.76% Pervious Area
1,048		99.24% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.6S: TD-6

Hydrograph



Summary for Subcatchment 5.1S: TD-1A

Runoff = 0.1 cfs @ 12.08 hrs, Volume= 387 cf, Depth= 3.34"
 Routed to Pond 9P : Inf Syst-7


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 2-Year Rainfall=4.02"

Area (sf)	CN	Description
1,175	98	Paved parking, HSG C
214	74	>75% Grass cover, Good, HSG C
1,389	94	Weighted Average
214		15.41% Pervious Area
1,175		84.59% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 5.1S: TD-1A

Hydrograph



Summary for Subcatchment 5S: TD-1B

Runoff = 0.3 cfs @ 12.09 hrs, Volume= 888 cf, Depth= 2.39"
 Routed to Link 1L : Towards Wetlands


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 2-Year Rainfall=4.02"

Area (sf)	CN	Description
1,909	98	Paved parking, HSG C
2,553	74	>75% Grass cover, Good, HSG C
4,462	84	Weighted Average
2,553		57.22% Pervious Area
1,909		42.78% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 5S: TD-1B

Hydrograph



Summary for Subcatchment 6.1S: East driveway

Runoff = 0.9 cfs @ 12.09 hrs, Volume= 2,716 cf, Depth= 2.66"
 Routed to Pond 3P : Rain garden


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 2-Year Rainfall=4.02"

Area (sf)	CN	Description
5,611	74	>75% Grass cover, Good, HSG C
6,444	98	Paved roads w/curbs & sewers, HSG C
220	89	Gravel roads, HSG C
12,275	87	Weighted Average
5,831		47.50% Pervious Area
6,444		52.50% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

Subcatchment 6.1S: East driveway

Hydrograph



Summary for Subcatchment 6S: Bypass Towards Wetlands

Runoff = 1.7 cfs @ 12.20 hrs, Volume= 6,919 cf, Depth= 1.61"
 Routed to Link 1L : Towards Wetlands


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 2-Year Rainfall=4.02"

Area (sf)	CN	Description
4,985	70	Woods, Good, HSG C
46,447	74	>75% Grass cover, Good, HSG C
107	98	Roofs, HSG C
51,539	74	Weighted Average
51,432		99.79% Pervious Area
107		0.21% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.8	50	0.0220	0.07		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.23"
2.2	75	0.0133	0.58		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
14.0	125	Total			

Subcatchment 6S: Bypass Towards Wetlands

Hydrograph



Summary for Subcatchment 7S: To Street

Runoff = 0.3 cfs @ 12.09 hrs, Volume= 927 cf, Depth= 1.90"
 Routed to Link 2L : Towards Street


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 2-Year Rainfall=4.02"

Area (sf)	CN	Description
1,056	98	Paved parking, HSG C
4,787	74	>75% Grass cover, Good, HSG C
5,843	78	Weighted Average
4,787		81.93% Pervious Area
1,056		18.07% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 7S: To Street

Hydrograph



Summary for Pond 1P: Inf Syst-1

Inflow Area = 60,436 sf, 85.36% Impervious, Inflow Depth = 3.30" for 2-Year event
 Inflow = 4.8 cfs @ 12.09 hrs, Volume= 16,622 cf
 Outflow = 0.4 cfs @ 13.02 hrs, Volume= 16,622 cf, Atten= 91%, Lag= 55.8 min
 Discarded = 0.1 cfs @ 8.25 hrs, Volume= 13,377 cf
 Primary = 0.3 cfs @ 13.02 hrs, Volume= 3,246 cf
 Routed to Link 1L : Towards Wetlands

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.37' @ 13.02 hrs Surf.Area= 7,459 sf Storage= 8,769 cf

Plug-Flow detention time= 660.2 min calculated for 16,620 cf (100% of inflow)
 Center-of-Mass det. time= 660.3 min (1,423.4 - 763.1)

Volume	Invert	Avail.Storage	Storage Description
#1	8.00'	19,245 cf	6.89'W x 14.06'L x 3.00'H StormTrap ST-1 Units (Irregular Shape) 77 22,378 cf Overall x 86.0% Voids


Device	Routing	Invert	Outlet Devices
#1	Discarded	8.00'	0.520 in/hr Exfiltration over Surface area
#2	Primary	8.00'	15.0" Round Culvert L= 26.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 8.00' / 7.13' S= 0.0335 '/ Cc= 0.900 n= 0.013, Flow Area= 1.23 sf
#3	Device 2	9.22'	22.0" W x 4.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 2	10.05'	20.0" W x 4.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 2	10.79'	3.7' long Sharp-Crested Rectangular Weir 2 End Contraction(s)

Discarded OutFlow Max=0.1 cfs @ 8.25 hrs HW=8.03' (Free Discharge)
 1=Exfiltration (Exfiltration Controls 0.1 cfs)

Primary OutFlow Max=0.3 cfs @ 13.02 hrs HW=9.37' (Free Discharge)
 2=Culvert (Passes 0.3 cfs of 5.1 cfs potential flow)
 3=Orifice/Grate (Orifice Controls 0.3 cfs @ 1.23 fps)
 4=Orifice/Grate (Controls 0.0 cfs)
 5=Sharp-Crested Rectangular Weir (Controls 0.0 cfs)

Pond 1P: Inf Syst-1

Hydrograph



Summary for Pond 3P: Rain garden

Inflow Area = 12,275 sf, 52.50% Impervious, Inflow Depth = 2.66" for 2-Year event
 Inflow = 0.9 cfs @ 12.09 hrs, Volume= 2,716 cf
 Outflow = 0.9 cfs @ 12.09 hrs, Volume= 2,716 cf, Atten= 0%, Lag= 0.3 min
 Discarded = 0.0 cfs @ 12.09 hrs, Volume= 444 cf
 Primary = 0.9 cfs @ 12.09 hrs, Volume= 2,272 cf
 Routed to Link 1L : Towards Wetlands

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 6.42' @ 12.09 hrs Surf.Area= 412 sf Storage= 216 cf

Plug-Flow detention time= 90.5 min calculated for 2,715 cf (100% of inflow)
 Center-of-Mass det. time= 90.6 min (900.2 - 809.6)

Volume	Invert	Avail.Storage	Storage Description		
#1	5.60'	253 cf	Custom Stage Data (Irregular) Listed below (Recalc)		
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
5.60	125	46.0	0	0	125
6.00	276	66.0	78	78	305
6.30	350	73.0	94	172	385
6.50	460	87.0	81	253	564


Device	Routing	Invert	Outlet Devices
#1	Discarded	5.60'	0.520 in/hr Exfiltration over Surface area
#2	Primary	6.35'	22.0' long x 5.0' breadth Broad-Crested Rectangular Weir
			Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00
			2.50 3.00 3.50 4.00 4.50 5.00 5.50
			Coef. (English) 2.34 2.50 2.70 2.68 2.68 2.66 2.65 2.65 2.65
			2.65 2.67 2.66 2.68 2.70 2.74 2.79 2.88

Discarded OutFlow Max=0.0 cfs @ 12.09 hrs HW=6.42' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.9 cfs @ 12.09 hrs HW=6.42' (Free Discharge)
 ↳2=Broad-Crested Rectangular Weir (Weir Controls 0.9 cfs @ 0.60 fps)

Pond 3P: Rain garden

Hydrograph



Summary for Pond 4P: Inf Syst-2

Inflow Area = 1,112 sf, 95.68% Impervious, Inflow Depth = 3.67" for 2-Year event
 Inflow = 0.1 cfs @ 12.08 hrs, Volume= 340 cf
 Outflow = 0.1 cfs @ 12.11 hrs, Volume= 327 cf, Atten= 4%, Lag= 1.4 min
 Discarded = 0.0 cfs @ 4.64 hrs, Volume= 156 cf
 Primary = 0.1 cfs @ 12.11 hrs, Volume= 171 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.41' @ 12.11 hrs Surf.Area= 101 sf Storage= 129 cf

Plug-Flow detention time= 773.3 min calculated for 327 cf (96% of inflow)
 Center-of-Mass det. time= 749.8 min (1,510.3 - 760.5)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	84 cf	7.28'W x 13.84'L x 2.72'H Field A 274 cf Overall - 64 cf Embedded = 210 cf x 40.0% Voids
#2A	7.25'	57 cf	Ferguson R-Tank XD 12 x 10 Inside #1 Inside= 19.7"W x 23.6"H => 2.91 sf x 1.97'L = 5.7 cf Outside= 19.7"W x 23.6"H => 3.23 sf x 1.97'L = 6.4 cf 10 Chambers in 2 Rows
		141 cf	Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.23'	6.0" Round Culvert L= 33.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.23' / 8.72' S= 0.0155 '/ Cc= 0.900 n= 0.013, Flow Area= 0.20 sf

Discarded OutFlow Max=0.0 cfs @ 4.64 hrs HW=7.03' (Free Discharge)
 ↕ **1=Exfiltration** (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.1 cfs @ 12.11 hrs HW=9.41' (Free Discharge)
 ↕ **2=Culvert** (Inlet Controls 0.1 cfs @ 1.45 fps)

Pond 4P: Inf Syst-2

Hydrograph



Summary for Pond 5P: Inf Syst-3

Inflow Area = 1,105 sf, 97.29% Impervious, Inflow Depth = 3.67" for 2-Year event
 Inflow = 0.1 cfs @ 12.08 hrs, Volume= 338 cf
 Outflow = 0.1 cfs @ 12.12 hrs, Volume= 319 cf, Atten= 8%, Lag= 2.2 min
 Discarded = 0.0 cfs @ 4.68 hrs, Volume= 156 cf
 Primary = 0.1 cfs @ 12.12 hrs, Volume= 163 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.55' @ 12.12 hrs Surf.Area= 101 sf Storage= 134 cf

Plug-Flow detention time= 799.9 min calculated for 319 cf (94% of inflow)
 Center-of-Mass det. time= 768.5 min (1,529.0 - 760.5)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	84 cf	7.28'W x 13.84'L x 2.72'H Field A 274 cf Overall - 64 cf Embedded = 210 cf x 40.0% Voids
#2A	7.25'	57 cf	Ferguson R-Tank XD 12 x 10 Inside #1 Inside= 19.7"W x 23.6"H => 2.91 sf x 1.97'L = 5.7 cf Outside= 19.7"W x 23.6"H => 3.23 sf x 1.97'L = 6.4 cf 10 Chambers in 2 Rows
		141 cf	Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.37'	6.0" Round Culvert L= 33.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.37' / 8.73' S= 0.0194 '/ Cc= 0.900 n= 0.013, Flow Area= 0.20 sf

Discarded OutFlow Max=0.0 cfs @ 4.68 hrs HW=7.03' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.1 cfs @ 12.12 hrs HW=9.55' (Free Discharge)
 ↳2=Culvert (Inlet Controls 0.1 cfs @ 1.43 fps)

Pond 5P: Inf Syst-3

Hydrograph



Summary for Pond 6P: Inf Syst-4

Inflow Area = 1,104 sf, 97.46% Impervious, Inflow Depth = 3.67" for 2-Year event
 Inflow = 0.1 cfs @ 12.08 hrs, Volume= 338 cf
 Outflow = 0.1 cfs @ 12.12 hrs, Volume= 319 cf, Atten= 9%, Lag= 2.2 min
 Discarded = 0.0 cfs @ 4.68 hrs, Volume= 156 cf
 Primary = 0.1 cfs @ 12.12 hrs, Volume= 163 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.55' @ 12.12 hrs Surf.Area= 101 sf Storage= 134 cf

Plug-Flow detention time= 800.6 min calculated for 319 cf (94% of inflow)
 Center-of-Mass det. time= 769.2 min (1,529.7 - 760.5)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	84 cf	7.28'W x 13.84'L x 2.72'H Field A 274 cf Overall - 64 cf Embedded = 210 cf x 40.0% Voids
#2A	7.25'	57 cf	Ferguson R-Tank XD 12 x 10 Inside #1 Inside= 19.7"W x 23.6"H => 2.91 sf x 1.97'L = 5.7 cf Outside= 19.7"W x 23.6"H => 3.23 sf x 1.97'L = 6.4 cf 10 Chambers in 2 Rows
		141 cf	Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.37'	6.0" Round Culvert L= 51.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.37' / 8.10' S= 0.0249 '/ Cc= 0.900 n= 0.013, Flow Area= 0.20 sf

Discarded OutFlow Max=0.0 cfs @ 4.68 hrs HW=7.03' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.1 cfs @ 12.12 hrs HW=9.55' (Free Discharge)
 ↳2=Culvert (Inlet Controls 0.1 cfs @ 1.43 fps)

Pond 6P: Inf Syst-4

Hydrograph



Summary for Pond 7P: Inf Syst-5

Inflow Area = 1,082 sf, 98.06% Impervious, Inflow Depth = 3.79" for 2-Year event
 Inflow = 0.1 cfs @ 12.08 hrs, Volume= 341 cf
 Outflow = 0.1 cfs @ 12.10 hrs, Volume= 341 cf, Atten= 1%, Lag= 0.7 min
 Discarded = 0.0 cfs @ 3.77 hrs, Volume= 157 cf
 Primary = 0.1 cfs @ 12.10 hrs, Volume= 183 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.18' @ 12.10 hrs Surf.Area= 101 sf Storage= 117 cf

Plug-Flow detention time= 722.0 min calculated for 341 cf (100% of inflow)
 Center-of-Mass det. time= 721.1 min (1,473.0 - 751.9)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	73 cf	7.28'W x 13.84'L x 2.39'H Field A 241 cf Overall - 58 cf Embedded = 182 cf x 40.0% Voids
#2A	7.25'	52 cf	Ferguson R-Tank XD 11 x 10 Inside #1 Inside= 19.7"W x 21.7"H => 2.66 sf x 1.97'L = 5.2 cf Outside= 19.7"W x 21.7"H => 2.96 sf x 1.97'L = 5.8 cf 10 Chambers in 2 Rows
		125 cf	Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.00'	6.0" Round Culvert L= 48.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.00' / 8.35' S= 0.0135 '/ Cc= 0.900 n= 0.013, Flow Area= 0.20 sf

Discarded OutFlow Max=0.0 cfs @ 3.77 hrs HW=7.03' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.1 cfs @ 12.10 hrs HW=9.18' (Free Discharge)
 ↳2=Culvert (Inlet Controls 0.1 cfs @ 1.46 fps)

Pond 7P: Inf Syst-5

Hydrograph



Summary for Pond 8P: Inf Syst-6

Inflow Area = 1,056 sf, 99.24% Impervious, Inflow Depth = 3.79" for 2-Year event
 Inflow = 0.1 cfs @ 12.08 hrs, Volume= 332 cf
 Outflow = 0.1 cfs @ 12.10 hrs, Volume= 332 cf, Atten= 1%, Lag= 0.8 min
 Discarded = 0.0 cfs @ 3.86 hrs, Volume= 157 cf
 Primary = 0.1 cfs @ 12.10 hrs, Volume= 175 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.20' @ 12.10 hrs Surf.Area= 101 sf Storage= 118 cf

Plug-Flow detention time= 739.6 min calculated for 332 cf (100% of inflow)
 Center-of-Mass det. time= 738.4 min (1,490.2 - 751.9)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	73 cf	7.28'W x 13.84'L x 2.39'H Field A 241 cf Overall - 58 cf Embedded = 182 cf x 40.0% Voids
#2A	7.25'	52 cf	Ferguson R-Tank XD 11 x 10 Inside #1 Inside= 19.7"W x 21.7"H => 2.66 sf x 1.97'L = 5.2 cf Outside= 19.7"W x 21.7"H => 2.96 sf x 1.97'L = 5.8 cf 10 Chambers in 2 Rows
		125 cf	Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.00'	8.0" Round Culvert L= 46.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.00' / 8.77' S= 0.0050 '/ S= 0.0050 '/ Cc= 0.900 n= 0.013, Flow Area= 0.35 sf

Discarded OutFlow Max=0.0 cfs @ 3.86 hrs HW=7.03' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.1 cfs @ 12.10 hrs HW=9.20' (Free Discharge)
 ↳2=Culvert (Barrel Controls 0.1 cfs @ 1.58 fps)

Pond 8P: Inf Syst-6

Hydrograph



Summary for Pond 9P: Inf Syst-7

Inflow Area = 24,131 sf, 72.87% Impervious, Inflow Depth = 3.05" for 2-Year event
 Inflow = 1.9 cfs @ 12.09 hrs, Volume= 6,142 cf
 Outflow = 1.1 cfs @ 12.19 hrs, Volume= 6,142 cf, Atten= 41%, Lag= 6.4 min
 Discarded = 0.0 cfs @ 7.94 hrs, Volume= 1,379 cf
 Primary = 1.1 cfs @ 12.19 hrs, Volume= 4,762 cf
 Routed to Link 1L : Towards Wetlands

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 7.84' @ 12.19 hrs Surf.Area= 2,422 sf Storage= 1,431 cf

Plug-Flow detention time= 91.3 min calculated for 6,141 cf (100% of inflow)
 Center-of-Mass det. time= 91.4 min (884.7 - 793.3)

Volume	Invert	Avail.Storage	Storage Description
#1	7.15'	3,645 cf	6.89'W x 14.06'L x 1.75'H StormTrap ST-1 Units (Irregular Shape) x 25 4,238 cf Overall x 86.0% Voids


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.15'	0.270 in/hr Exfiltration over Surface area
#2	Primary	7.15'	12.0" Round Culvert L= 4.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 7.15' / 7.13' S= 0.0050 '/ Cc= 0.900 n= 0.013, Flow Area= 0.79 sf
#3	Device 2	7.35'	22.0" W x 4.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

Discarded OutFlow Max=0.0 cfs @ 7.94 hrs HW=7.17' (Free Discharge)
 1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=1.1 cfs @ 12.19 hrs HW=7.84' (Free Discharge)
 2=Culvert (Barrel Controls 1.1 cfs @ 2.76 fps)
 3=Orifice/Grate (Passes 1.1 cfs of 1.6 cfs potential flow)

Pond 9P: Inf Syst-7

Hydrograph




Summary for Link 1L: Towards Wetlands

Inflow Area = 152,843 sf, 50.79% Impervious, Inflow Depth = 1.42" for 2-Year event
 Inflow = 3.6 cfs @ 12.16 hrs, Volume= 18,088 cf
 Primary = 3.6 cfs @ 12.16 hrs, Volume= 18,088 cf, Atten= 0%, Lag= 0.0 min
 Routed to Link 100L : Total Flows

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link 1L: Towards Wetlands

Hydrograph




Summary for Link 2L: Towards Street

Inflow Area = 5,843 sf, 18.07% Impervious, Inflow Depth = 1.90" for 2-Year event
Inflow = 0.3 cfs @ 12.09 hrs, Volume= 927 cf
Primary = 0.3 cfs @ 12.09 hrs, Volume= 927 cf, Atten= 0%, Lag= 0.0 min
Routed to Link 100L : Total Flows

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link 2L: Towards Street

Hydrograph




Summary for Link 100L: Total Flows

Inflow Area = 158,686 sf, 49.59% Impervious, Inflow Depth = 1.44" for 2-Year event
Inflow = 3.8 cfs @ 12.15 hrs, Volume= 19,014 cf
Primary = 3.8 cfs @ 12.15 hrs, Volume= 19,014 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link 100L: Total Flows

Hydrograph



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=6.40"

Printed 12/17/2024

Page 41

Time span=0.00-72.00 hrs, dt=0.01 hrs, 7201 points
 Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
 Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment1S: CB-1	Runoff Area=22,742 sf 72.16% Impervious Runoff Depth=5.35" Tc=6.0 min CN=91 Runoff=3.1 cfs 10,138 cf
Subcatchment2S: Building Roof	Runoff Area=32,925 sf 100.00% Impervious Runoff Depth=6.16" Tc=6.0 min CN=98 Runoff=4.7 cfs 16,905 cf
Subcatchment3.1S: Backyard ADs	Runoff Area=8,985 sf 3.03% Impervious Runoff Depth=3.63" Flow Length=147' Tc=10.3 min CN=75 Runoff=0.8 cfs 2,715 cf
Subcatchment3S: Townhouse Roofs	Runoff Area=13,067 sf 100.00% Impervious Runoff Depth=6.16" Tc=6.0 min CN=98 Runoff=1.9 cfs 6,709 cf
Subcatchment4.2S: TD-2	Runoff Area=1,112 sf 95.68% Impervious Runoff Depth=6.04" Tc=6.0 min CN=97 Runoff=0.2 cfs 560 cf
Subcatchment4.3S: TD-3	Runoff Area=1,105 sf 97.29% Impervious Runoff Depth=6.04" Tc=6.0 min CN=97 Runoff=0.2 cfs 556 cf
Subcatchment4.4S: TD-4	Runoff Area=1,104 sf 97.46% Impervious Runoff Depth=6.04" Tc=6.0 min CN=97 Runoff=0.2 cfs 556 cf
Subcatchment4.5S: TD-5	Runoff Area=1,082 sf 98.06% Impervious Runoff Depth=6.16" Tc=6.0 min CN=98 Runoff=0.2 cfs 556 cf
Subcatchment4.6S: TD-6	Runoff Area=1,056 sf 99.24% Impervious Runoff Depth=6.16" Tc=6.0 min CN=98 Runoff=0.2 cfs 542 cf
Subcatchment5.1S: TD-1A	Runoff Area=1,389 sf 84.59% Impervious Runoff Depth=5.69" Tc=6.0 min CN=94 Runoff=0.2 cfs 659 cf
Subcatchment5S: TD-1B	Runoff Area=4,462 sf 42.78% Impervious Runoff Depth=4.57" Tc=6.0 min CN=84 Runoff=0.5 cfs 1,700 cf
Subcatchment6.1S: East driveway	Runoff Area=12,275 sf 52.50% Impervious Runoff Depth=4.90" Tc=6.0 min CN=87 Runoff=1.6 cfs 5,013 cf
Subcatchment6S: Bypass Towards	Runoff Area=51,539 sf 0.21% Impervious Runoff Depth=3.52" Flow Length=125' Tc=14.0 min CN=74 Runoff=3.8 cfs 15,135 cf
Subcatchment7S: To Street	Runoff Area=5,843 sf 18.07% Impervious Runoff Depth=3.93" Tc=6.0 min CN=78 Runoff=0.6 cfs 1,916 cf
Pond 1P: Inf Syst-1	Peak Elev=9.96' Storage=12,545 cf Inflow=8.0 cfs 28,251 cf Discarded=0.1 cfs 14,540 cf Primary=2.2 cfs 13,710 cf Outflow=2.3 cfs 28,251 cf
Pond 3P: Rain garden	Peak Elev=6.45' Storage=229 cf Inflow=1.6 cfs 5,013 cf Discarded=0.0 cfs 477 cf Primary=1.6 cfs 4,537 cf Outflow=1.6 cfs 5,013 cf

2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=6.40"

Printed 12/17/2024

Page 42

Pond 4P: Inf Syst-2	Peak Elev=9.47' Storage=131 cf Inflow=0.2 cfs 560 cf Discarded=0.0 cfs 159 cf Primary=0.2 cfs 388 cf Outflow=0.2 cfs 547 cf
Pond 5P: Inf Syst-3	Peak Elev=9.61' Storage=137 cf Inflow=0.2 cfs 556 cf Discarded=0.0 cfs 159 cf Primary=0.2 cfs 379 cf Outflow=0.2 cfs 537 cf
Pond 6P: Inf Syst-4	Peak Elev=9.61' Storage=137 cf Inflow=0.2 cfs 556 cf Discarded=0.0 cfs 159 cf Primary=0.2 cfs 378 cf Outflow=0.2 cfs 537 cf
Pond 7P: Inf Syst-5	Peak Elev=9.24' Storage=119 cf Inflow=0.2 cfs 556 cf Discarded=0.0 cfs 160 cf Primary=0.2 cfs 395 cf Outflow=0.2 cfs 555 cf
Pond 8P: Inf Syst-6	Peak Elev=9.26' Storage=120 cf Inflow=0.2 cfs 542 cf Discarded=0.0 cfs 160 cf Primary=0.2 cfs 382 cf Outflow=0.2 cfs 541 cf
Pond 9P: Inf Syst-7	Peak Elev=8.14' Storage=2,069 cf Inflow=3.3 cfs 10,797 cf Discarded=0.0 cfs 1,502 cf Primary=2.1 cfs 9,295 cf Outflow=2.1 cfs 10,797 cf
Link 1L: Towards Wetlands	Inflow=9.0 cfs 44,377 cf Primary=9.0 cfs 44,377 cf
Link 2L: Towards Street	Inflow=0.6 cfs 1,916 cf Primary=0.6 cfs 1,916 cf
Link 100L: Total Flows	Inflow=9.4 cfs 46,293 cf Primary=9.4 cfs 46,293 cf

Total Runoff Area = 158,686 sf Runoff Volume = 63,661 cf Average Runoff Depth = 4.81"
50.41% Pervious = 79,997 sf 49.59% Impervious = 78,689 sf

2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=6.40"

Printed 12/17/2024

Page 43

Summary for Subcatchment 1S: CB-1


Runoff = 3.1 cfs @ 12.08 hrs, Volume= 10,138 cf, Depth= 5.35"
Routed to Pond 9P : Inf Syst-7

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 10-Year Rainfall=6.40"

Area (sf)	CN	Description
16,410	98	Paved parking, HSG C
6,332	74	>75% Grass cover, Good, HSG C
22,742	91	Weighted Average
6,332		27.84% Pervious Area
16,410		72.16% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 1S: CB-1



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=6.40"

Printed 12/17/2024

Page 44

Summary for Subcatchment 2S: Building Roof


Runoff = 4.7 cfs @ 12.08 hrs, Volume= 16,905 cf, Depth= 6.16"
Routed to Pond 1P : Inf Syst-1

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 10-Year Rainfall=6.40"

Area (sf)	CN	Description
32,925	98	Roofs, HSG C
32,925		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 2S: Building Roof



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=6.40"

Printed 12/17/2024

Page 45

Summary for Subcatchment 3.1S: Backyard ADs

Runoff = 0.8 cfs @ 12.14 hrs, Volume= 2,715 cf, Depth= 3.63"
Routed to Pond 1P : Inf Syst-1


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 10-Year Rainfall=6.40"

Area (sf)	CN	Description
272	98	Unconnected pavement, HSG C
8,302	74	>75% Grass cover, Good, HSG C
411	89	Gravel sidewalk, HSG C
8,985	75	Weighted Average
8,713		96.97% Pervious Area
272		3.03% Impervious Area
272		100.00% Unconnected

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
9.4	50	0.0142	0.09		Sheet Flow, Grass: Dense n= 0.240 P2= 3.23"
0.9	97	0.0154	1.86		Shallow Concentrated Flow, Grassed Waterway Kv= 15.0 fps
10.3	147	Total			

Subcatchment 3.1S: Backyard ADs

Hydrograph



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=6.40"

Printed 12/17/2024

Page 46

Summary for Subcatchment 3S: Townhouse Roofs

Runoff = 1.9 cfs @ 12.08 hrs, Volume= 6,709 cf, Depth= 6.16"
Routed to Pond 1P : Inf Syst-1


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 10-Year Rainfall=6.40"

Area (sf)	CN	Description
13,067	98	Roofs, HSG C
13,067		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 3S: Townhouse Roofs

Hydrograph



Summary for Subcatchment 4.2S: TD-2

Runoff = 0.2 cfs @ 12.08 hrs, Volume= 560 cf, Depth= 6.04"
 Routed to Pond 4P : Inf Syst-2


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 10-Year Rainfall=6.40"

Area (sf)	CN	Description
1,064	98	Paved parking, HSG C
48	74	>75% Grass cover, Good, HSG C
1,112	97	Weighted Average
48		4.32% Pervious Area
1,064		95.68% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.2S: TD-2

Hydrograph



Summary for Subcatchment 4.3S: TD-3

Runoff = 0.2 cfs @ 12.08 hrs, Volume= 556 cf, Depth= 6.04"
 Routed to Pond 5P : Inf Syst-3


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 10-Year Rainfall=6.40"

Area (sf)	CN	Description
1,075	98	Paved parking, HSG C
30	74	>75% Grass cover, Good, HSG C
1,105	97	Weighted Average
30		2.71% Pervious Area
1,075		97.29% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.3S: TD-3

Hydrograph



Summary for Subcatchment 4.4S: TD-4

Runoff = 0.2 cfs @ 12.08 hrs, Volume= 556 cf, Depth= 6.04"
 Routed to Pond 6P : Inf Syst-4


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 10-Year Rainfall=6.40"

Area (sf)	CN	Description
1,076	98	Paved parking, HSG C
28	74	>75% Grass cover, Good, HSG C
1,104	97	Weighted Average
28		2.54% Pervious Area
1,076		97.46% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.4S: TD-4

Hydrograph



Summary for Subcatchment 4.5S: TD-5

Runoff = 0.2 cfs @ 12.08 hrs, Volume= 556 cf, Depth= 6.16"
 Routed to Pond 7P : Inf Syst-5


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 10-Year Rainfall=6.40"

Area (sf)	CN	Description
1,061	98	Paved parking, HSG C
21	74	>75% Grass cover, Good, HSG C
1,082	98	Weighted Average
21		1.94% Pervious Area
1,061		98.06% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.5S: TD-5

Hydrograph



Summary for Subcatchment 4.6S: TD-6

Runoff = 0.2 cfs @ 12.08 hrs, Volume= 542 cf, Depth= 6.16"
 Routed to Pond 8P : Inf Syst-6


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 10-Year Rainfall=6.40"

Area (sf)	CN	Description
1,048	98	Paved parking, HSG C
8	74	>75% Grass cover, Good, HSG C
1,056	98	Weighted Average
8		0.76% Pervious Area
1,048		99.24% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.6S: TD-6

Hydrograph



Summary for Subcatchment 5.1S: TD-1A

Runoff = 0.2 cfs @ 12.08 hrs, Volume= 659 cf, Depth= 5.69"
 Routed to Pond 9P : Inf Syst-7


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 10-Year Rainfall=6.40"

Area (sf)	CN	Description
1,175	98	Paved parking, HSG C
214	74	>75% Grass cover, Good, HSG C
1,389	94	Weighted Average
214		15.41% Pervious Area
1,175		84.59% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 5.1S: TD-1A

Hydrograph



Summary for Subcatchment 5S: TD-1B

Runoff = 0.5 cfs @ 12.09 hrs, Volume= 1,700 cf, Depth= 4.57"
 Routed to Link 1L : Towards Wetlands


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 10-Year Rainfall=6.40"

Area (sf)	CN	Description
1,909	98	Paved parking, HSG C
2,553	74	>75% Grass cover, Good, HSG C
4,462	84	Weighted Average
2,553		57.22% Pervious Area
1,909		42.78% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 5S: TD-1B

Hydrograph



Summary for Subcatchment 6.1S: East driveway

Runoff = 1.6 cfs @ 12.09 hrs, Volume= 5,013 cf, Depth= 4.90"
 Routed to Pond 3P : Rain garden


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 10-Year Rainfall=6.40"

Area (sf)	CN	Description
5,611	74	>75% Grass cover, Good, HSG C
6,444	98	Paved roads w/curbs & sewers, HSG C
220	89	Gravel roads, HSG C
12,275	87	Weighted Average
5,831		47.50% Pervious Area
6,444		52.50% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

Subcatchment 6.1S: East driveway

Hydrograph



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=6.40"

Printed 12/17/2024

Page 55

Summary for Subcatchment 6S: Bypass Towards Wetlands

Runoff = 3.8 cfs @ 12.19 hrs, Volume= 15,135 cf, Depth= 3.52"
 Routed to Link 1L : Towards Wetlands


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 10-Year Rainfall=6.40"

Area (sf)	CN	Description
4,985	70	Woods, Good, HSG C
46,447	74	>75% Grass cover, Good, HSG C
107	98	Roofs, HSG C
51,539	74	Weighted Average
51,432		99.79% Pervious Area
107		0.21% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.8	50	0.0220	0.07		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.23"
2.2	75	0.0133	0.58		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
14.0	125	Total			

Subcatchment 6S: Bypass Towards Wetlands

Hydrograph



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=6.40"

Printed 12/17/2024

Page 56

Summary for Subcatchment 7S: To Street

Runoff = 0.6 cfs @ 12.09 hrs, Volume= 1,916 cf, Depth= 3.93"
 Routed to Link 2L : Towards Street


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 10-Year Rainfall=6.40"

Area (sf)	CN	Description
1,056	98	Paved parking, HSG C
4,787	74	>75% Grass cover, Good, HSG C
5,843	78	Weighted Average
4,787		81.93% Pervious Area
1,056		18.07% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 7S: To Street

Hydrograph



Summary for Pond 1P: Inf Syst-1

Inflow Area = 60,436 sf, 85.36% Impervious, Inflow Depth = 5.61" for 10-Year event
 Inflow = 8.0 cfs @ 12.09 hrs, Volume= 28,251 cf
 Outflow = 2.3 cfs @ 12.43 hrs, Volume= 28,251 cf, Atten= 71%, Lag= 20.8 min
 Discarded = 0.1 cfs @ 6.13 hrs, Volume= 14,540 cf
 Primary = 2.2 cfs @ 12.43 hrs, Volume= 13,710 cf
 Routed to Link 1L : Towards Wetlands

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.96' @ 12.43 hrs Surf.Area= 7,459 sf Storage= 12,545 cf

Plug-Flow detention time= 442.3 min calculated for 28,251 cf (100% of inflow)
 Center-of-Mass det. time= 442.2 min (1,198.8 - 756.6)

Volume	Invert	Avail.Storage	Storage Description
#1	8.00'	19,245 cf	6.89'W x 14.06'L x 3.00'H StormTrap ST-1 Units (Irregular Shape) x 77 22,378 cf Overall x 86.0% Voids


Device	Routing	Invert	Outlet Devices
#1	Discarded	8.00'	0.520 in/hr Exfiltration over Surface area
#2	Primary	8.00'	15.0" Round Culvert L= 26.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 8.00' / 7.13' S= 0.0335 '/ Cc= 0.900 n= 0.013, Flow Area= 1.23 sf
#3	Device 2	9.22'	22.0" W x 4.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 2	10.05'	20.0" W x 4.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 2	10.79'	3.7' long Sharp-Crested Rectangular Weir 2 End Contraction(s)

Discarded OutFlow Max=0.1 cfs @ 6.13 hrs HW=8.03' (Free Discharge)
 ↳ **1=Exfiltration** (Exfiltration Controls 0.1 cfs)

Primary OutFlow Max=2.2 cfs @ 12.43 hrs HW=9.96' (Free Discharge)
 ↳ **2=Culvert** (Passes 2.2 cfs of 6.8 cfs potential flow)
 ↳ **3=Orifice/Grate** (Orifice Controls 2.2 cfs @ 3.62 fps)
 ↳ **4=Orifice/Grate** (Controls 0.0 cfs)
 ↳ **5=Sharp-Crested Rectangular Weir** (Controls 0.0 cfs)

Pond 1P: Inf Syst-1

Hydrograph



Summary for Pond 3P: Rain garden

Inflow Area = 12,275 sf, 52.50% Impervious, Inflow Depth = 4.90" for 10-Year event
 Inflow = 1.6 cfs @ 12.09 hrs, Volume= 5,013 cf
 Outflow = 1.6 cfs @ 12.09 hrs, Volume= 5,013 cf, Atten= 0%, Lag= 0.3 min
 Discarded = 0.0 cfs @ 12.09 hrs, Volume= 477 cf
 Primary = 1.6 cfs @ 12.09 hrs, Volume= 4,537 cf
 Routed to Link 1L : Towards Wetlands

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 6.45' @ 12.09 hrs Surf.Area= 429 sf Storage= 229 cf

Plug-Flow detention time= 53.5 min calculated for 5,012 cf (100% of inflow)
 Center-of-Mass det. time= 53.6 min (846.0 - 792.4)

Volume #1	Invert	Avail.Storage	Storage Description		
#1	5.60'	253 cf	Custom Stage Data (Irregular) Listed below (Recalc)		
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
5.60	125	46.0	0	0	125
6.00	276	66.0	78	78	305
6.30	350	73.0	94	172	385
6.50	460	87.0	81	253	564


Device	Routing	Invert	Outlet Devices
#1	Discarded	5.60'	0.520 in/hr Exfiltration over Surface area
#2	Primary	6.35'	22.0' long x 5.0' breadth Broad-Crested Rectangular Weir
Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00			
2.50 3.00 3.50 4.00 4.50 5.00 5.50			
Coef. (English) 2.34 2.50 2.70 2.68 2.68 2.66 2.65 2.65 2.65			
2.65 2.67 2.66 2.68 2.70 2.74 2.79 2.88			

Discarded OutFlow Max=0.0 cfs @ 12.09 hrs HW=6.45' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=1.6 cfs @ 12.09 hrs HW=6.45' (Free Discharge)
 ↳2=Broad-Crested Rectangular Weir (Weir Controls 1.6 cfs @ 0.73 fps)

Pond 3P: Rain garden

Hydrograph



Summary for Pond 4P: Inf Syst-2

Inflow Area = 1,112 sf, 95.68% Impervious, Inflow Depth = 6.04" for 10-Year event
 Inflow = 0.2 cfs @ 12.08 hrs, Volume= 560 cf
 Outflow = 0.2 cfs @ 12.09 hrs, Volume= 547 cf, Atten= 1%, Lag= 0.6 min
 Discarded = 0.0 cfs @ 2.79 hrs, Volume= 159 cf
 Primary = 0.2 cfs @ 12.09 hrs, Volume= 388 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.47' @ 12.09 hrs Surf.Area= 101 sf Storage= 131 cf

Plug-Flow detention time= 483.5 min calculated for 546 cf (98% of inflow)
 Center-of-Mass det. time= 468.6 min (1,219.5 - 751.0)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	84 cf	7.28'W x 13.84'L x 2.72'H Field A 274 cf Overall - 64 cf Embedded = 210 cf x 40.0% Voids
#2A	7.25'	57 cf	Ferguson R-Tank XD 12 x 10 Inside #1 Inside= 19.7"W x 23.6"H => 2.91 sf x 1.97'L = 5.7 cf Outside= 19.7"W x 23.6"H => 3.23 sf x 1.97'L = 6.4 cf 10 Chambers in 2 Rows
		141 cf	Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.23'	6.0" Round Culvert L= 33.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.23' / 8.72' S= 0.0155 '/ Cc= 0.900 n= 0.013, Flow Area= 0.20 sf

Discarded OutFlow Max=0.0 cfs @ 2.79 hrs HW=7.03' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.2 cfs @ 12.09 hrs HW=9.47' (Free Discharge)
 ↳2=Culvert (Inlet Controls 0.2 cfs @ 1.67 fps)

Pond 4P: Inf Syst-2

Hydrograph



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=6.40"

Printed 12/17/2024

Page 63

Summary for Pond 5P: Inf Syst-3

Inflow Area = 1,105 sf, 97.29% Impervious, Inflow Depth = 6.04" for 10-Year event
 Inflow = 0.2 cfs @ 12.08 hrs, Volume= 556 cf
 Outflow = 0.2 cfs @ 12.09 hrs, Volume= 537 cf, Atten= 1%, Lag= 0.6 min
 Discarded = 0.0 cfs @ 2.83 hrs, Volume= 159 cf
 Primary = 0.2 cfs @ 12.09 hrs, Volume= 379 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.61' @ 12.09 hrs Surf.Area= 101 sf Storage= 137 cf

Plug-Flow detention time= 497.7 min calculated for 537 cf (97% of inflow)
 Center-of-Mass det. time= 476.9 min (1,227.8 - 751.0)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	84 cf	7.28'W x 13.84'L x 2.72'H Field A 274 cf Overall - 64 cf Embedded = 210 cf x 40.0% Voids
#2A	7.25'	57 cf	Ferguson R-Tank XD 12 x 10 Inside #1 Inside= 19.7"W x 23.6"H => 2.91 sf x 1.97'L = 5.7 cf Outside= 19.7"W x 23.6"H => 3.23 sf x 1.97'L = 6.4 cf 10 Chambers in 2 Rows
		141 cf	Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.37'	6.0" Round Culvert L= 33.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.37' / 8.73' S= 0.0194 1' Cc= 0.900 n= 0.013, Flow Area= 0.20 sf

Discarded OutFlow Max=0.0 cfs @ 2.83 hrs HW=7.03' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.2 cfs @ 12.09 hrs HW=9.61' (Free Discharge)
 ↳2=Culvert (Inlet Controls 0.2 cfs @ 1.67 fps)

2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC


Type III 24-hr 10-Year Rainfall=6.40"

Printed 12/17/2024

Page 64

Pond 5P: Inf Syst-3

Hydrograph



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=6.40"

Printed 12/17/2024

Page 65

Summary for Pond 6P: Inf Syst-4

Inflow Area = 1,104 sf, 97.46% Impervious, Inflow Depth = 6.04" for 10-Year event
 Inflow = 0.2 cfs @ 12.08 hrs, Volume= 556 cf
 Outflow = 0.2 cfs @ 12.09 hrs, Volume= 537 cf, Atten= 1%, Lag= 0.6 min
 Discarded = 0.0 cfs @ 2.83 hrs, Volume= 159 cf
 Primary = 0.2 cfs @ 12.09 hrs, Volume= 378 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.61' @ 12.09 hrs Surf.Area= 101 sf Storage= 137 cf

Plug-Flow detention time= 498.4 min calculated for 537 cf (97% of inflow)
 Center-of-Mass det. time= 477.3 min (1,228.2 - 751.0)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	84 cf	7.28'W x 13.84'L x 2.72'H Field A 274 cf Overall - 64 cf Embedded = 210 cf x 40.0% Voids
#2A	7.25'	57 cf	Ferguson R-Tank XD 12 x 10 Inside #1 Inside= 19.7"W x 23.6"H => 2.91 sf x 1.97'L = 5.7 cf Outside= 19.7"W x 23.6"H => 3.23 sf x 1.97'L = 6.4 cf 10 Chambers in 2 Rows
		141 cf	Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.37'	6.0" Round Culvert L= 51.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.37' / 8.10' S= 0.0249 ' S= 0.0249 ' Cc= 0.900 n= 0.013, Flow Area= 0.20 sf

Discarded OutFlow Max=0.0 cfs @ 2.83 hrs HW=7.03' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.2 cfs @ 12.09 hrs HW=9.61' (Free Discharge)
 ↳2=Culvert (Inlet Controls 0.2 cfs @ 1.67 fps)

2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC


Type III 24-hr 10-Year Rainfall=6.40"

Printed 12/17/2024

Page 66

Pond 6P: Inf Syst-4

Hydrograph



Summary for Pond 7P: Inf Syst-5

Inflow Area = 1,082 sf, 98.06% Impervious, Inflow Depth = 6.16" for 10-Year event
 Inflow = 0.2 cfs @ 12.08 hrs, Volume= 556 cf
 Outflow = 0.2 cfs @ 12.09 hrs, Volume= 555 cf, Atten= 1%, Lag= 0.6 min
 Discarded = 0.0 cfs @ 2.12 hrs, Volume= 160 cf
 Primary = 0.2 cfs @ 12.09 hrs, Volume= 395 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.24' @ 12.09 hrs Surf.Area= 101 sf Storage= 119 cf

Plug-Flow detention time= 464.5 min calculated for 555 cf (100% of inflow)
 Center-of-Mass det. time= 463.9 min (1,208.1 - 744.2)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	73 cf	7.28'W x 13.84'L x 2.39'H Field A 241 cf Overall - 58 cf Embedded = 182 cf x 40.0% Voids
#2A	7.25'	52 cf	Ferguson R-Tank XD 11 x 10 Inside #1 Inside= 19.7"W x 21.7"H => 2.66 sf x 1.97'L = 5.2 cf Outside= 19.7"W x 21.7"H => 2.96 sf x 1.97'L = 5.8 cf 10 Chambers in 2 Rows
		125 cf	Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.00'	6.0" Round Culvert L= 48.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.00' / 8.35' S= 0.0135 '/ Cc= 0.900 n= 0.013, Flow Area= 0.20 sf

Discarded OutFlow Max=0.0 cfs @ 2.12 hrs HW=7.03' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.2 cfs @ 12.09 hrs HW=9.24' (Free Discharge)
 ↳2=Culvert (Inlet Controls 0.2 cfs @ 1.66 fps)

Pond 7P: Inf Syst-5

Hydrograph



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=6.40"

Printed 12/17/2024

Page 69

Summary for Pond 8P: Inf Syst-6

Inflow Area = 1,056 sf, 99.24% Impervious, Inflow Depth = 6.16" for 10-Year event
 Inflow = 0.2 cfs @ 12.08 hrs, Volume= 542 cf
 Outflow = 0.2 cfs @ 12.09 hrs, Volume= 541 cf, Atten= 1%, Lag= 0.6 min
 Discarded = 0.0 cfs @ 2.19 hrs, Volume= 160 cf
 Primary = 0.2 cfs @ 12.09 hrs, Volume= 382 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.26' @ 12.09 hrs Surf.Area= 101 sf Storage= 120 cf

Plug-Flow detention time= 475.6 min calculated for 541 cf (100% of inflow)
 Center-of-Mass det. time= 474.9 min (1,219.1 - 744.2)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	73 cf	7.28'W x 13.84'L x 2.39'H Field A 241 cf Overall - 58 cf Embedded = 182 cf x 40.0% Voids
#2A	7.25'	52 cf	Ferguson R-Tank XD 11 x 10 Inside #1 Inside= 19.7"W x 21.7"H => 2.66 sf x 1.97'L = 5.2 cf Outside= 19.7"W x 21.7"H => 2.96 sf x 1.97'L = 5.8 cf 10 Chambers in 2 Rows
		125 cf	Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.00'	8.0" Round Culvert L= 46.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.00' / 8.77' S= 0.0050 '/ Cc= 0.900 n= 0.013, Flow Area= 0.35 sf

Discarded OutFlow Max=0.0 cfs @ 2.19 hrs HW=7.03' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.1 cfs @ 12.09 hrs HW=9.26' (Free Discharge)
 ↳2=Culvert (Barrel Controls 0.1 cfs @ 1.80 fps)

2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC


Type III 24-hr 10-Year Rainfall=6.40"

Printed 12/17/2024

Page 70

Pond 8P: Inf Syst-6

Hydrograph



Summary for Pond 9P: Inf Syst-7

Inflow Area = 24,131 sf, 72.87% Impervious, Inflow Depth = 5.37" for 10-Year event
 Inflow = 3.3 cfs @ 12.08 hrs, Volume= 10,797 cf
 Outflow = 2.1 cfs @ 12.18 hrs, Volume= 10,797 cf, Atten= 37%, Lag= 5.7 min
 Discarded = 0.0 cfs @ 5.84 hrs, Volume= 1,502 cf
 Primary = 2.1 cfs @ 12.18 hrs, Volume= 9,295 cf
 Routed to Link 1L : Towards Wetlands

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 8.14' @ 12.18 hrs Surf.Area= 2,422 sf Storage= 2,069 cf

Plug-Flow detention time= 63.5 min calculated for 10,795 cf (100% of inflow)
 Center-of-Mass det. time= 63.5 min (841.9 - 778.3)

Volume	Invert	Avail.Storage	Storage Description
#1	7.15'	3,645 cf	6.89'W x 14.06'L x 1.75'H StormTrap ST-1 Units (Irregular Shape) x 25 4,238 cf Overall x 86.0% Voids

Device	Routing	Invert	Outlet Devices
#1	Discarded	7.15'	0.270 in/hr Exfiltration over Surface area
#2	Primary	7.15'	12.0" Round Culvert L= 4.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 7.15' / 7.13' S= 0.0050 /' Cc= 0.900 n= 0.013, Flow Area= 0.79 sf
#3	Device 2	7.35'	22.0" W x 4.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

Discarded OutFlow Max=0.0 cfs @ 5.84 hrs HW=7.17' (Free Discharge)

↳ **1=Exfiltration** (Exfiltration Controls 0.0 cfs)


Primary OutFlow Max=2.1 cfs @ 12.18 hrs HW=8.14' (Free Discharge)

↳ **2=Culvert** (Barrel Controls 2.1 cfs @ 3.29 fps)

↳ **3=Orifice/Grate** (Passes 2.1 cfs of 2.3 cfs potential flow)

Pond 9P: Inf Syst-7

Hydrograph




Summary for Link 1L: Towards Wetlands

Inflow Area = 152,843 sf, 50.79% Impervious, Inflow Depth = 3.48" for 10-Year event
 Inflow = 9.0 cfs @ 12.18 hrs, Volume= 44,377 cf
 Primary = 9.0 cfs @ 12.18 hrs, Volume= 44,377 cf, Atten= 0%, Lag= 0.0 min
 Routed to Link 100L : Total Flows

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link 1L: Towards Wetlands

Hydrograph




Summary for Link 2L: Towards Street

Inflow Area = 5,843 sf, 18.07% Impervious, Inflow Depth = 3.93" for 10-Year event
 Inflow = 0.6 cfs @ 12.09 hrs, Volume= 1,916 cf
 Primary = 0.6 cfs @ 12.09 hrs, Volume= 1,916 cf, Atten= 0%, Lag= 0.0 min
 Routed to Link 100L : Total Flows

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link 2L: Towards Street

Hydrograph




Summary for Link 100L: Total Flows

Inflow Area = 158,686 sf, 49.59% Impervious, Inflow Depth = 3.50" for 10-Year event
 Inflow = 9.4 cfs @ 12.17 hrs, Volume= 46,293 cf
 Primary = 9.4 cfs @ 12.17 hrs, Volume= 46,293 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link 100L: Total Flows

Hydrograph



Time span=0.00-72.00 hrs, dt=0.01 hrs, 7201 points
 Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
 Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment1S: CB-1	Runoff Area=22,742 sf 72.16% Impervious Runoff Depth=7.22" Tc=6.0 min CN=91 Runoff=4.1 cfs 13,685 cf
Subcatchment2S: Building Roof	Runoff Area=32,925 sf 100.00% Impervious Runoff Depth=8.06" Tc=6.0 min CN=98 Runoff=6.2 cfs 22,115 cf
Subcatchment3.1S: Backyard ADS	Runoff Area=8,985 sf 3.03% Impervious Runoff Depth=5.31" Flow Length=147' Tc=10.3 min CN=75 Runoff=1.1 cfs 3,978 cf
Subcatchment3S: Townhouse Roofs	Runoff Area=13,067 sf 100.00% Impervious Runoff Depth=8.06" Tc=6.0 min CN=98 Runoff=2.4 cfs 8,777 cf
Subcatchment4.2S: TD-2	Runoff Area=1,112 sf 95.68% Impervious Runoff Depth=7.94" Tc=6.0 min CN=97 Runoff=0.2 cfs 736 cf
Subcatchment4.3S: TD-3	Runoff Area=1,105 sf 97.29% Impervious Runoff Depth=7.94" Tc=6.0 min CN=97 Runoff=0.2 cfs 731 cf
Subcatchment4.4S: TD-4	Runoff Area=1,104 sf 97.46% Impervious Runoff Depth=7.94" Tc=6.0 min CN=97 Runoff=0.2 cfs 730 cf
Subcatchment4.5S: TD-5	Runoff Area=1,082 sf 98.06% Impervious Runoff Depth=8.06" Tc=6.0 min CN=98 Runoff=0.2 cfs 727 cf
Subcatchment4.6S: TD-6	Runoff Area=1,056 sf 99.24% Impervious Runoff Depth=8.06" Tc=6.0 min CN=98 Runoff=0.2 cfs 709 cf
Subcatchment5.1S: TD-1A	Runoff Area=1,389 sf 84.59% Impervious Runoff Depth=7.58" Tc=6.0 min CN=94 Runoff=0.3 cfs 877 cf
Subcatchment5S: TD-1B	Runoff Area=4,462 sf 42.78% Impervious Runoff Depth=6.38" Tc=6.0 min CN=84 Runoff=0.7 cfs 2,374 cf
Subcatchment6.1S: East driveway	Runoff Area=12,275 sf 52.50% Impervious Runoff Depth=6.74" Tc=6.0 min CN=87 Runoff=2.1 cfs 6,897 cf
Subcatchment6S: Bypass Towards	Runoff Area=51,539 sf 0.21% Impervious Runoff Depth=5.19" Flow Length=125' Tc=14.0 min CN=74 Runoff=5.6 cfs 22,311 cf
Subcatchment7S: To Street	Runoff Area=5,843 sf 18.07% Impervious Runoff Depth=5.67" Tc=6.0 min CN=78 Runoff=0.9 cfs 2,760 cf
Pond 1P: Inf Syst-1	Peak Elev=10.41' Storage=15,470 cf Inflow=10.6 cfs 37,649 cf Discarded=0.1 cfs 14,969 cf Primary=4.1 cfs 22,680 cf Outflow=4.2 cfs 37,649 cf
Pond 3P: Rain garden	Peak Elev=6.47' Storage=239 cf Inflow=2.1 cfs 6,897 cf Discarded=0.0 cfs 495 cf Primary=2.1 cfs 6,401 cf Outflow=2.1 cfs 6,897 cf

2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=8.30"

Printed 12/17/2024

Page 77

Pond 4P: Inf Syst-2

Peak Elev=9.51' Storage=133 cf Inflow=0.2 cfs 736 cf
Discarded=0.0 cfs 160 cf Primary=0.2 cfs 562 cf Outflow=0.2 cfs 722 cf

Pond 5P: Inf Syst-3

Peak Elev=9.65' Storage=139 cf Inflow=0.2 cfs 731 cf
Discarded=0.0 cfs 160 cf Primary=0.2 cfs 552 cf Outflow=0.2 cfs 712 cf

Pond 6P: Inf Syst-4

Peak Elev=9.65' Storage=139 cf Inflow=0.2 cfs 730 cf
Discarded=0.0 cfs 160 cf Primary=0.2 cfs 552 cf Outflow=0.2 cfs 711 cf

Pond 7P: Inf Syst-5

Peak Elev=9.28' Storage=121 cf Inflow=0.2 cfs 727 cf
Discarded=0.0 cfs 161 cf Primary=0.2 cfs 565 cf Outflow=0.2 cfs 726 cf

Pond 8P: Inf Syst-6

Peak Elev=9.29' Storage=122 cf Inflow=0.2 cfs 709 cf
Discarded=0.0 cfs 161 cf Primary=0.2 cfs 548 cf Outflow=0.2 cfs 708 cf

Pond 9P: Inf Syst-7

Peak Elev=8.38' Storage=2,562 cf Inflow=4.3 cfs 14,562 cf
Discarded=0.0 cfs 1,561 cf Primary=2.7 cfs 13,001 cf Outflow=2.7 cfs 14,562 cf

Link 1L: Towards Wetlands

Inflow=13.7 cfs 66,767 cf
Primary=13.7 cfs 66,767 cf

Link 2L: Towards Street

Inflow=0.9 cfs 2,760 cf
Primary=0.9 cfs 2,760 cf

Link 100L: Total Flows

Inflow=14.2 cfs 69,527 cf
Primary=14.2 cfs 69,527 cf

Total Runoff Area = 158,686 sf Runoff Volume = 87,407 cf Average Runoff Depth = 6.61"
50.41% Pervious = 79,997 sf 49.59% Impervious = 78,689 sf

2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=8.30"

Printed 12/17/2024

Page 78

Summary for Subcatchment 1S: CB-1


Runoff = 4.1 cfs @ 12.08 hrs, Volume= 13,685 cf, Depth= 7.22"
Routed to Pond 9P : Inf Syst-7

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 25-Year Rainfall=8.30"

Area (sf)	CN	Description
16,410	98	Paved parking, HSG C
6,332	74	>75% Grass cover, Good, HSG C
22,742	91	Weighted Average
6,332		27.84% Pervious Area
16,410		72.16% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 1S: CB-1



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=8.30"

Printed 12/17/2024

Page 79

Summary for Subcatchment 2S: Building Roof


Runoff = 6.2 cfs @ 12.08 hrs, Volume= 22,115 cf, Depth= 8.06"
Routed to Pond 1P : Inf Syst-1

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 25-Year Rainfall=8.30"

Area (sf)	CN	Description
32,925	98	Roofs, HSG C
32,925		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 2S: Building Roof



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=8.30"

Printed 12/17/2024

Page 80

Summary for Subcatchment 3.1S: Backyard ADs


Runoff = 1.1 cfs @ 12.14 hrs, Volume= 3,978 cf, Depth= 5.31"
Routed to Pond 1P : Inf Syst-1

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 25-Year Rainfall=8.30"

Area (sf)	CN	Description
272	98	Unconnected pavement, HSG C
8,302	74	>75% Grass cover, Good, HSG C
411	89	Gravel sidewalk, HSG C
8,985	75	Weighted Average
8,713		96.97% Pervious Area
272		3.03% Impervious Area
272		100.00% Unconnected

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
9.4	50	0.0142	0.09		Sheet Flow, Grass: Dense n= 0.240 P2= 3.23"
0.9	97	0.0154	1.86		Shallow Concentrated Flow, Grassed Waterway Kv= 15.0 fps
10.3	147				Total

Subcatchment 3.1S: Backyard ADs



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=8.30"

Printed 12/17/2024

Page 81

Summary for Subcatchment 3S: Townhouse Roofs


Runoff = 2.4 cfs @ 12.08 hrs, Volume= 8,777 cf, Depth= 8.06"
Routed to Pond 1P : Inf Syst-1

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 25-Year Rainfall=8.30"

Table with 3 columns: Area (sf), CN, Description. Row 1: 13,067, 98, Roofs, HSG C. Row 2: 13,067, 100.00% Impervious Area.

Table with 6 columns: Tc (min), Length (feet), Slope (ft/ft), Velocity (ft/sec), Capacity (cfs), Description. Row 1: 6.0, Direct Entry, Min. Tc.

Subcatchment 3S: Townhouse Roofs



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=8.30"

Printed 12/17/2024

Page 82

Summary for Subcatchment 4.2S: TD-2


Runoff = 0.2 cfs @ 12.08 hrs, Volume= 736 cf, Depth= 7.94"
Routed to Pond 4P : Inf Syst-2

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 25-Year Rainfall=8.30"

Table with 3 columns: Area (sf), CN, Description. Row 1: 1,064, 98, Paved parking, HSG C. Row 2: 48, 74, >75% Grass cover, Good, HSG C. Row 3: 1,112, 97, Weighted Average. Row 4: 48, 4.32% Pervious Area. Row 5: 1,064, 95.68% Impervious Area.

Table with 6 columns: Tc (min), Length (feet), Slope (ft/ft), Velocity (ft/sec), Capacity (cfs), Description. Row 1: 6.0, Direct Entry, Min. Tc.

Subcatchment 4.2S: TD-2



Summary for Subcatchment 4.3S: TD-3

Runoff = 0.2 cfs @ 12.08 hrs, Volume= 731 cf, Depth= 7.94"
 Routed to Pond 5P : Inf Syst-3


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 25-Year Rainfall=8.30"

Area (sf)	CN	Description
1,075	98	Paved parking, HSG C
30	74	>75% Grass cover, Good, HSG C
1,105	97	Weighted Average
30		2.71% Pervious Area
1,075		97.29% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.3S: TD-3

Hydrograph



Summary for Subcatchment 4.4S: TD-4

Runoff = 0.2 cfs @ 12.08 hrs, Volume= 730 cf, Depth= 7.94"
 Routed to Pond 6P : Inf Syst-4


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 25-Year Rainfall=8.30"

Area (sf)	CN	Description
1,076	98	Paved parking, HSG C
28	74	>75% Grass cover, Good, HSG C
1,104	97	Weighted Average
28		2.54% Pervious Area
1,076		97.46% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.4S: TD-4

Hydrograph



Summary for Subcatchment 4.5S: TD-5

Runoff = 0.2 cfs @ 12.08 hrs, Volume= 727 cf, Depth= 8.06"
 Routed to Pond 7P : Inf Syst-5


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 25-Year Rainfall=8.30"

Area (sf)	CN	Description
1,061	98	Paved parking, HSG C
21	74	>75% Grass cover, Good, HSG C
1,082	98	Weighted Average
21		1.94% Pervious Area
1,061		98.06% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.5S: TD-5

Hydrograph



Summary for Subcatchment 4.6S: TD-6

Runoff = 0.2 cfs @ 12.08 hrs, Volume= 709 cf, Depth= 8.06"
 Routed to Pond 8P : Inf Syst-6


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 25-Year Rainfall=8.30"

Area (sf)	CN	Description
1,048	98	Paved parking, HSG C
8	74	>75% Grass cover, Good, HSG C
1,056	98	Weighted Average
8		0.76% Pervious Area
1,048		99.24% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.6S: TD-6

Hydrograph



Summary for Subcatchment 5.1S: TD-1A

Runoff = 0.3 cfs @ 12.08 hrs, Volume= 877 cf, Depth= 7.58"
 Routed to Pond 9P : Inf Syst-7


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 25-Year Rainfall=8.30"

Area (sf)	CN	Description
1,175	98	Paved parking, HSG C
214	74	>75% Grass cover, Good, HSG C
1,389	94	Weighted Average
214		15.41% Pervious Area
1,175		84.59% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 5.1S: TD-1A

Hydrograph



Summary for Subcatchment 5S: TD-1B

Runoff = 0.7 cfs @ 12.09 hrs, Volume= 2,374 cf, Depth= 6.38"
 Routed to Link 1L : Towards Wetlands


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 25-Year Rainfall=8.30"

Area (sf)	CN	Description
1,909	98	Paved parking, HSG C
2,553	74	>75% Grass cover, Good, HSG C
4,462	84	Weighted Average
2,553		57.22% Pervious Area
1,909		42.78% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 5S: TD-1B

Hydrograph



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=8.30"

Printed 12/17/2024

Page 89

Summary for Subcatchment 6.1S: East driveway

Runoff = 2.1 cfs @ 12.08 hrs, Volume= 6,897 cf, Depth= 6.74"
Routed to Pond 3P : Rain garden


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 25-Year Rainfall=8.30"

Area (sf)	CN	Description
5,611	74	>75% Grass cover, Good, HSG C
6,444	98	Paved roads w/curbs & sewers, HSG C
220	89	Gravel roads, HSG C
12,275	87	Weighted Average
5,831		47.50% Pervious Area
6,444		52.50% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

Subcatchment 6.1S: East driveway

Hydrograph



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=8.30"

Printed 12/17/2024

Page 90

Summary for Subcatchment 6S: Bypass Towards Wetlands

Runoff = 5.6 cfs @ 12.19 hrs, Volume= 22,311 cf, Depth= 5.19"
Routed to Link 1L : Towards Wetlands


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 25-Year Rainfall=8.30"

Area (sf)	CN	Description
4,985	70	Woods, Good, HSG C
46,447	74	>75% Grass cover, Good, HSG C
107	98	Roofs, HSG C
51,539	74	Weighted Average
51,432		99.79% Pervious Area
107		0.21% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.8	50	0.0220	0.07		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.23"
2.2	75	0.0133	0.58		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
14.0	125	Total			

Subcatchment 6S: Bypass Towards Wetlands

Hydrograph



Summary for Subcatchment 7S: To Street

Runoff = 0.9 cfs @ 12.09 hrs, Volume= 2,760 cf, Depth= 5.67"
 Routed to Link 2L : Towards Street


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 25-Year Rainfall=8.30"

Area (sf)	CN	Description
1,056	98	Paved parking, HSG C
4,787	74	>75% Grass cover, Good, HSG C
5,843	78	Weighted Average
4,787		81.93% Pervious Area
1,056		18.07% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 7S: To Street

Hydrograph



Summary for Pond 1P: Inf Syst-1

Inflow Area = 60,436 sf, 85.36% Impervious, Inflow Depth = 7.48" for 25-Year event
 Inflow = 10.6 cfs @ 12.09 hrs, Volume= 37,649 cf
 Outflow = 4.2 cfs @ 12.32 hrs, Volume= 37,649 cf, Atten= 60%, Lag= 14.1 min
 Discarded = 0.1 cfs @ 4.33 hrs, Volume= 14,969 cf
 Primary = 4.1 cfs @ 12.32 hrs, Volume= 22,680 cf
 Routed to Link 1L : Towards Wetlands

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 10.41' @ 12.32 hrs Surf.Area= 7,459 sf Storage= 15,470 cf

Plug-Flow detention time= 354.1 min calculated for 37,649 cf (100% of inflow)
 Center-of-Mass det. time= 354.1 min (1,107.3 - 753.2)

Volume	Invert	Avail.Storage	Storage Description
#1	8.00'	19,245 cf	6.89'W x 14.06'L x 3.00'H StormTrap ST-1 Units (Irregular Shape) 77 22,378 cf Overall x 86.0% Voids


Device	Routing	Invert	Outlet Devices
#1	Discarded	8.00'	0.520 in/hr Exfiltration over Surface area
#2	Primary	8.00'	15.0" Round Culvert L= 26.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 8.00' / 7.13' S= 0.0335 '/ Cc= 0.900 n= 0.013, Flow Area= 1.23 sf
#3	Device 2	9.22'	22.0" W x 4.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 2	10.05'	20.0" W x 4.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 2	10.79'	3.7' long Sharp-Crested Rectangular Weir 2 End Contraction(s)

Discarded OutFlow Max=0.1 cfs @ 4.33 hrs HW=8.03' (Free Discharge)
 1=Exfiltration (Exfiltration Controls 0.1 cfs)

Primary OutFlow Max=4.1 cfs @ 12.32 hrs HW=10.41' (Free Discharge)
 2=Culvert (Passes 4.1 cfs of 7.9 cfs potential flow)
 3=Orifice/Grate (Orifice Controls 3.0 cfs @ 4.87 fps)
 4=Orifice/Grate (Orifice Controls 1.1 cfs @ 2.05 fps)
 5=Sharp-Crested Rectangular Weir (Controls 0.0 cfs)

Pond 1P: Inf Syst-1

Hydrograph



Summary for Pond 3P: Rain garden

Inflow Area = 12,275 sf, 52.50% Impervious, Inflow Depth = 6.74" for 25-Year event
 Inflow = 2.1 cfs @ 12.08 hrs, Volume= 6,897 cf
 Outflow = 2.1 cfs @ 12.09 hrs, Volume= 6,897 cf, Atten= 0%, Lag= 0.3 min
 Discarded = 0.0 cfs @ 12.09 hrs, Volume= 495 cf
 Primary = 2.1 cfs @ 12.09 hrs, Volume= 6,401 cf
 Routed to Link 1L : Towards Wetlands

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 6.47' @ 12.09 hrs Surf.Area= 442 sf Storage= 239 cf

Plug-Flow detention time= 40.9 min calculated for 6,896 cf (100% of inflow)
 Center-of-Mass det. time= 41.0 min (824.8 - 783.8)

Volume	Invert	Avail.Storage	Storage Description		
#1	5.60'	253 cf	Custom Stage Data (Irregular) Listed below (Recalc)		
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
5.60	125	46.0	0	0	125
6.00	276	66.0	78	78	305
6.30	350	73.0	94	172	385
6.50	460	87.0	81	253	564


Device	Routing	Invert	Outlet Devices
#1	Discarded	5.60'	0.520 in/hr Exfiltration over Surface area
#2	Primary	6.35'	22.0' long x 5.0' breadth Broad-Crested Rectangular Weir
			Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00
			2.50 3.00 3.50 4.00 4.50 5.00 5.50
			Coef. (English) 2.34 2.50 2.70 2.68 2.68 2.66 2.65 2.65 2.65
			2.65 2.67 2.66 2.68 2.70 2.74 2.79 2.88

Discarded OutFlow Max=0.0 cfs @ 12.09 hrs HW=6.47' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=2.1 cfs @ 12.09 hrs HW=6.47' (Free Discharge)
 ↳2=Broad-Crested Rectangular Weir (Weir Controls 2.1 cfs @ 0.81 fps)

Pond 3P: Rain garden

Hydrograph



Summary for Pond 4P: Inf Syst-2

Inflow Area = 1,112 sf, 95.68% Impervious, Inflow Depth = 7.94" for 25-Year event
 Inflow = 0.2 cfs @ 12.08 hrs, Volume= 736 cf
 Outflow = 0.2 cfs @ 12.09 hrs, Volume= 722 cf, Atten= 1%, Lag= 0.5 min
 Discarded = 0.0 cfs @ 2.05 hrs, Volume= 160 cf
 Primary = 0.2 cfs @ 12.09 hrs, Volume= 562 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.51' @ 12.09 hrs Surf.Area= 101 sf Storage= 133 cf

Plug-Flow detention time= 377.3 min calculated for 722 cf (98% of inflow)
 Center-of-Mass det. time= 365.7 min (1,112.2 - 746.5)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	84 cf	7.28'W x 13.84'L x 2.72'H Field A 274 cf Overall - 64 cf Embedded = 210 cf x 40.0% Voids
#2A	7.25'	57 cf	Ferguson R-Tank XD 12 x 10 Inside #1 Inside= 19.7"W x 23.6"H => 2.91 sf x 1.97'L = 5.7 cf Outside= 19.7"W x 23.6"H => 3.23 sf x 1.97'L = 6.4 cf 10 Chambers in 2 Rows
		141 cf	Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.23'	6.0" Round Culvert L= 33.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.23' / 8.72' S= 0.0155 '/ Cc= 0.900 n= 0.013, Flow Area= 0.20 sf

Discarded OutFlow Max=0.0 cfs @ 2.05 hrs HW=7.03' (Free Discharge)
 ↑1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.2 cfs @ 12.09 hrs HW=9.51' (Free Discharge)
 ↑2=Culvert (Inlet Controls 0.2 cfs @ 1.81 fps)

Pond 4P: Inf Syst-2

Hydrograph



Summary for Pond 5P: Inf Syst-3

Inflow Area = 1,105 sf, 97.29% Impervious, Inflow Depth = 7.94" for 25-Year event
 Inflow = 0.2 cfs @ 12.08 hrs, Volume= 731 cf
 Outflow = 0.2 cfs @ 12.09 hrs, Volume= 712 cf, Atten= 1%, Lag= 0.5 min
 Discarded = 0.0 cfs @ 2.08 hrs, Volume= 160 cf
 Primary = 0.2 cfs @ 12.09 hrs, Volume= 552 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.65' @ 12.09 hrs Surf.Area= 101 sf Storage= 139 cf

Plug-Flow detention time= 388.2 min calculated for 712 cf (97% of inflow)
 Center-of-Mass det. time= 371.5 min (1,118.0 - 746.5)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	84 cf	7.28'W x 13.84'L x 2.72'H Field A 274 cf Overall - 64 cf Embedded = 210 cf x 40.0% Voids
#2A	7.25'	57 cf	Ferguson R-Tank XD 12 x 10 Inside #1 Inside= 19.7"W x 23.6"H => 2.91 sf x 1.97'L = 5.7 cf Outside= 19.7"W x 23.6"H => 3.23 sf x 1.97'L = 6.4 cf 10 Chambers in 2 Rows
		141 cf	Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.37'	6.0" Round Culvert L= 33.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.37' / 8.73' S= 0.0194 '/ Cc= 0.900 n= 0.013, Flow Area= 0.20 sf

Discarded OutFlow Max=0.0 cfs @ 2.08 hrs HW=7.03' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.2 cfs @ 12.09 hrs HW=9.65' (Free Discharge)
 ↳2=Culvert (Inlet Controls 0.2 cfs @ 1.80 fps)

Pond 5P: Inf Syst-3

Hydrograph



Summary for Pond 6P: Inf Syst-4

Inflow Area = 1,104 sf, 97.46% Impervious, Inflow Depth = 7.94" for 25-Year event
 Inflow = 0.2 cfs @ 12.08 hrs, Volume= 730 cf
 Outflow = 0.2 cfs @ 12.09 hrs, Volume= 711 cf, Atten= 1%, Lag= 0.5 min
 Discarded = 0.0 cfs @ 2.08 hrs, Volume= 160 cf
 Primary = 0.2 cfs @ 12.09 hrs, Volume= 552 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.65' @ 12.09 hrs Surf.Area= 101 sf Storage= 139 cf

Plug-Flow detention time= 388.1 min calculated for 711 cf (97% of inflow)
 Center-of-Mass det. time= 371.8 min (1,118.4 - 746.5)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	84 cf	7.28'W x 13.84'L x 2.72'H Field A 274 cf Overall - 64 cf Embedded = 210 cf x 40.0% Voids
#2A	7.25'	57 cf	Ferguson R-Tank XD 12 x 10 Inside #1 Inside= 19.7"W x 23.6"H => 2.91 sf x 1.97'L = 5.7 cf Outside= 19.7"W x 23.6"H => 3.23 sf x 1.97'L = 6.4 cf 10 Chambers in 2 Rows
		141 cf	Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.37'	6.0" Round Culvert L= 51.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.37' / 8.10' S= 0.0249 '/ Cc= 0.900 n= 0.013, Flow Area= 0.20 sf

Discarded OutFlow Max=0.0 cfs @ 2.08 hrs HW=7.03' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.2 cfs @ 12.09 hrs HW=9.65' (Free Discharge)
 ↳2=Culvert (Inlet Controls 0.2 cfs @ 1.80 fps)

Pond 6P: Inf Syst-4

Hydrograph



Summary for Pond 7P: Inf Syst-5

Inflow Area = 1,082 sf, 98.06% Impervious, Inflow Depth = 8.06" for 25-Year event
 Inflow = 0.2 cfs @ 12.08 hrs, Volume= 727 cf
 Outflow = 0.2 cfs @ 12.09 hrs, Volume= 726 cf, Atten= 1%, Lag= 0.5 min
 Discarded = 0.0 cfs @ 1.52 hrs, Volume= 161 cf
 Primary = 0.2 cfs @ 12.09 hrs, Volume= 565 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.28' @ 12.09 hrs Surf.Area= 101 sf Storage= 121 cf

Plug-Flow detention time= 365.7 min calculated for 726 cf (100% of inflow)
 Center-of-Mass det. time= 365.2 min (1,106.0 - 740.8)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	73 cf	7.28'W x 13.84'L x 2.39'H Field A 241 cf Overall - 58 cf Embedded = 182 cf x 40.0% Voids
#2A	7.25'	52 cf	Ferguson R-Tank XD 11 x 10 Inside #1 Inside= 19.7"W x 21.7"H => 2.66 sf x 1.97'L = 5.2 cf Outside= 19.7"W x 21.7"H => 2.96 sf x 1.97'L = 5.8 cf 10 Chambers in 2 Rows
		125 cf	Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.00'	6.0" Round Culvert L= 48.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.00' / 8.35' S= 0.0135 '/ Cc= 0.900 n= 0.013, Flow Area= 0.20 sf

Discarded OutFlow Max=0.0 cfs @ 1.52 hrs HW=7.03' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.2 cfs @ 12.09 hrs HW=9.28' (Free Discharge)
 ↳2=Culvert (Inlet Controls 0.2 cfs @ 1.79 fps)

Pond 7P: Inf Syst-5

Hydrograph



Summary for Pond 8P: Inf Syst-6

Inflow Area = 1,056 sf, 99.24% Impervious, Inflow Depth = 8.06" for 25-Year event
 Inflow = 0.2 cfs @ 12.08 hrs, Volume= 709 cf
 Outflow = 0.2 cfs @ 12.09 hrs, Volume= 708 cf, Atten= 1%, Lag= 0.6 min
 Discarded = 0.0 cfs @ 1.56 hrs, Volume= 161 cf
 Primary = 0.2 cfs @ 12.09 hrs, Volume= 548 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.29' @ 12.09 hrs Surf.Area= 101 sf Storage= 122 cf

Plug-Flow detention time= 374.4 min calculated for 708 cf (100% of inflow)
 Center-of-Mass det. time= 373.8 min (1,114.6 - 740.8)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	73 cf	7.28'W x 13.84'L x 2.39'H Field A 241 cf Overall - 58 cf Embedded = 182 cf x 40.0% Voids
#2A	7.25'	52 cf	Ferguson R-Tank XD 11 x 10 Inside #1 Inside= 19.7"W x 21.7"H => 2.66 sf x 1.97'L = 5.2 cf Outside= 19.7"W x 21.7"H => 2.96 sf x 1.97'L = 5.8 cf 10 Chambers in 2 Rows
		125 cf	Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.00'	8.0" Round Culvert L= 46.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.00' / 8.77' S= 0.0050 '/ Cc= 0.900 n= 0.013, Flow Area= 0.35 sf

Discarded OutFlow Max=0.0 cfs @ 1.56 hrs HW=7.03' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.2 cfs @ 12.09 hrs HW=9.29' (Free Discharge)
 ↳2=Culvert (Barrel Controls 0.2 cfs @ 1.94 fps)

Pond 8P: Inf Syst-6

Hydrograph



Summary for Pond 9P: Inf Syst-7

Inflow Area = 24,131 sf, 72.87% Impervious, Inflow Depth = 7.24" for 25-Year event
 Inflow = 4.3 cfs @ 12.08 hrs, Volume= 14,562 cf
 Outflow = 2.7 cfs @ 12.18 hrs, Volume= 14,562 cf, Atten= 37%, Lag= 5.7 min
 Discarded = 0.0 cfs @ 4.62 hrs, Volume= 1,561 cf
 Primary = 2.7 cfs @ 12.18 hrs, Volume= 13,001 cf
 Routed to Link 1L : Towards Wetlands

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 8.38" @ 12.18 hrs Surf.Area= 2,422 sf Storage= 2,562 cf

Plug-Flow detention time= 53.2 min calculated for 14,562 cf (100% of inflow)
 Center-of-Mass det. time= 53.1 min (824.0 - 770.9)

Volume	Invert	Avail.Storage	Storage Description
#1	7.15'	3,645 cf	6.89'W x 14.06'L x 1.75'H StormTrap ST-1 Units (Irregular Shape) 25 4,238 cf Overall x 86.0% Voids


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.15'	0.270 in/hr Exfiltration over Surface area
#2	Primary	7.15'	12.0" Round Culvert L= 4.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 7.15' / 7.13' S= 0.0050 '/ Cc= 0.900 n= 0.013, Flow Area= 0.79 sf
#3	Device 2	7.35'	22.0" W x 4.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

Discarded OutFlow Max=0.0 cfs @ 4.62 hrs HW=7.17' (Free Discharge)
 1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=2.7 cfs @ 12.18 hrs HW=8.38' (Free Discharge)
 2=Culvert (Passes 2.7 cfs of 2.7 cfs potential flow)
 3=Orifice/Grate (Orifice Controls 2.7 cfs @ 4.47 fps)

Pond 9P: Inf Syst-7

Hydrograph




Summary for Link 1L: Towards Wetlands

Inflow Area = 152,843 sf, 50.79% Impervious, Inflow Depth = 5.24" for 25-Year event
 Inflow = 13.7 cfs @ 12.18 hrs, Volume= 66,767 cf
 Primary = 13.7 cfs @ 12.18 hrs, Volume= 66,767 cf, Atten= 0%, Lag= 0.0 min
 Routed to Link 100L : Total Flows

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link 1L: Towards Wetlands

Hydrograph




Summary for Link 2L: Towards Street

Inflow Area = 5,843 sf, 18.07% Impervious, Inflow Depth = 5.67" for 25-Year event
Inflow = 0.9 cfs @ 12.09 hrs, Volume= 2,760 cf
Primary = 0.9 cfs @ 12.09 hrs, Volume= 2,760 cf, Atten= 0%, Lag= 0.0 min
Routed to Link 100L : Total Flows

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link 2L: Towards Street

Hydrograph




Summary for Link 100L: Total Flows

Inflow Area = 158,686 sf, 49.59% Impervious, Inflow Depth = 5.26" for 25-Year event
Inflow = 14.2 cfs @ 12.18 hrs, Volume= 69,527 cf
Primary = 14.2 cfs @ 12.18 hrs, Volume= 69,527 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link 100L: Total Flows

Hydrograph



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 50-Year Rainfall=9.67"

Printed 12/17/2024

Page 111

Time span=0.00-72.00 hrs, dt=0.01 hrs, 7201 points
 Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
 Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment1S: CB-1	Runoff Area=22,742 sf 72.16% Impervious Runoff Depth=8.58" Tc=6.0 min CN=91 Runoff=4.8 cfs 16,254 cf
Subcatchment2S: Building Roof	Runoff Area=32,925 sf 100.00% Impervious Runoff Depth=9.43" Tc=6.0 min CN=98 Runoff=7.2 cfs 25,872 cf
Subcatchment3.1S: Backyard ADs	Runoff Area=8,985 sf 3.03% Impervious Runoff Depth=6.57" Flow Length=147' Tc=10.3 min CN=75 Runoff=1.4 cfs 4,920 cf
Subcatchment3S: Townhouse Roofs	Runoff Area=13,067 sf 100.00% Impervious Runoff Depth=9.43" Tc=6.0 min CN=98 Runoff=2.9 cfs 10,268 cf
Subcatchment4.2S: TD-2	Runoff Area=1,112 sf 95.68% Impervious Runoff Depth=9.31" Tc=6.0 min CN=97 Runoff=0.2 cfs 863 cf
Subcatchment4.3S: TD-3	Runoff Area=1,105 sf 97.29% Impervious Runoff Depth=9.31" Tc=6.0 min CN=97 Runoff=0.2 cfs 857 cf
Subcatchment4.4S: TD-4	Runoff Area=1,104 sf 97.46% Impervious Runoff Depth=9.31" Tc=6.0 min CN=97 Runoff=0.2 cfs 856 cf
Subcatchment4.5S: TD-5	Runoff Area=1,082 sf 98.06% Impervious Runoff Depth=9.43" Tc=6.0 min CN=98 Runoff=0.2 cfs 850 cf
Subcatchment4.6S: TD-6	Runoff Area=1,056 sf 99.24% Impervious Runoff Depth=9.43" Tc=6.0 min CN=98 Runoff=0.2 cfs 830 cf
Subcatchment5.1S: TD-1A	Runoff Area=1,389 sf 84.59% Impervious Runoff Depth=8.94" Tc=6.0 min CN=94 Runoff=0.3 cfs 1,035 cf
Subcatchment5S: TD-1B	Runoff Area=4,462 sf 42.78% Impervious Runoff Depth=7.71" Tc=6.0 min CN=84 Runoff=0.9 cfs 2,866 cf
Subcatchment6.1S: East driveway	Runoff Area=12,275 sf 52.50% Impervious Runoff Depth=8.08" Tc=6.0 min CN=87 Runoff=2.5 cfs 8,268 cf
Subcatchment6S: Bypass Towards	Runoff Area=51,539 sf 0.21% Impervious Runoff Depth=6.44" Flow Length=125' Tc=14.0 min CN=74 Runoff=6.9 cfs 27,672 cf
Subcatchment7S: To Street	Runoff Area=5,843 sf 18.07% Impervious Runoff Depth=6.95" Tc=6.0 min CN=78 Runoff=1.1 cfs 3,385 cf
Pond 1P: Inf Syst-1	Peak Elev=10.70' Storage=17,296 cf Inflow=12.4 cfs 44,458 cf Discarded=0.1 cfs 15,169 cf Primary=5.2 cfs 29,289 cf Outflow=5.3 cfs 44,458 cf
Pond 3P: Rain garden	Peak Elev=6.48' Storage=245 cf Inflow=2.5 cfs 8,268 cf Discarded=0.0 cfs 506 cf Primary=2.5 cfs 7,762 cf Outflow=2.5 cfs 8,268 cf

2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 50-Year Rainfall=9.67"

Printed 12/17/2024

Page 112

Pond 4P: Inf Syst-2	Peak Elev=9.54' Storage=134 cf Inflow=0.2 cfs 863 cf Discarded=0.0 cfs 160 cf Primary=0.2 cfs 689 cf Outflow=0.2 cfs 849 cf
Pond 5P: Inf Syst-3	Peak Elev=9.68' Storage=140 cf Inflow=0.2 cfs 857 cf Discarded=0.0 cfs 160 cf Primary=0.2 cfs 678 cf Outflow=0.2 cfs 838 cf
Pond 6P: Inf Syst-4	Peak Elev=9.68' Storage=140 cf Inflow=0.2 cfs 856 cf Discarded=0.0 cfs 160 cf Primary=0.2 cfs 677 cf Outflow=0.2 cfs 837 cf
Pond 7P: Inf Syst-5	Peak Elev=9.30' Storage=122 cf Inflow=0.2 cfs 850 cf Discarded=0.0 cfs 161 cf Primary=0.2 cfs 688 cf Outflow=0.2 cfs 849 cf
Pond 8P: Inf Syst-6	Peak Elev=9.32' Storage=123 cf Inflow=0.2 cfs 830 cf Discarded=0.0 cfs 161 cf Primary=0.2 cfs 668 cf Outflow=0.2 cfs 829 cf
Pond 9P: Inf Syst-7	Peak Elev=8.58' Storage=2,968 cf Inflow=5.1 cfs 17,290 cf Discarded=0.0 cfs 1,591 cf Primary=3.0 cfs 15,699 cf Outflow=3.0 cfs 17,290 cf
Link 1L: Towards Wetlands	Inflow=17.0 cfs 83,287 cf Primary=17.0 cfs 83,287 cf
Link 2L: Towards Street	Inflow=1.1 cfs 3,385 cf Primary=1.1 cfs 3,385 cf
Link 100L: Total Flows	Inflow=17.8 cfs 86,673 cf Primary=17.8 cfs 86,673 cf

Total Runoff Area = 158,686 sf Runoff Volume = 104,796 cf Average Runoff Depth = 7.92"
50.41% Pervious = 79,997 sf 49.59% Impervious = 78,689 sf

2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 50-Year Rainfall=9.67"

Printed 12/17/2024

Page 113

Summary for Subcatchment 1S: CB-1

Runoff = 4.8 cfs @ 12.08 hrs, Volume= 16,254 cf, Depth= 8.58"
Routed to Pond 9P : Inf Syst-7


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 50-Year Rainfall=9.67"

Area (sf)	CN	Description
16,410	98	Paved parking, HSG C
6,332	74	>75% Grass cover, Good, HSG C
22,742	91	Weighted Average
6,332		27.84% Pervious Area
16,410		72.16% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 1S: CB-1

Hydrograph



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 50-Year Rainfall=9.67"

Printed 12/17/2024

Page 114

Summary for Subcatchment 2S: Building Roof

Runoff = 7.2 cfs @ 12.08 hrs, Volume= 25,872 cf, Depth= 9.43"
Routed to Pond 1P : Inf Syst-1


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 50-Year Rainfall=9.67"

Area (sf)	CN	Description
32,925	98	Roofs, HSG C
32,925		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 2S: Building Roof

Hydrograph



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 50-Year Rainfall=9.67"

Printed 12/17/2024

Page 115

Summary for Subcatchment 3.1S: Backyard ADs

Runoff = 1.4 cfs @ 12.14 hrs, Volume= 4,920 cf, Depth= 6.57"
Routed to Pond 1P : Inf Syst-1


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 50-Year Rainfall=9.67"

Area (sf)	CN	Description
272	98	Unconnected pavement, HSG C
8,302	74	>75% Grass cover, Good, HSG C
411	89	Gravel sidewalk, HSG C
8,985	75	Weighted Average
8,713		96.97% Pervious Area
272		3.03% Impervious Area
272		100.00% Unconnected

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
9.4	50	0.0142	0.09		Sheet Flow, Grass: Dense n= 0.240 P2= 3.23"
0.9	97	0.0154	1.86		Shallow Concentrated Flow, Grassed Waterway Kv= 15.0 fps
10.3	147	Total			

Subcatchment 3.1S: Backyard ADs

Hydrograph



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 50-Year Rainfall=9.67"

Printed 12/17/2024

Page 116

Summary for Subcatchment 3S: Townhouse Roofs

Runoff = 2.9 cfs @ 12.08 hrs, Volume= 10,268 cf, Depth= 9.43"
Routed to Pond 1P : Inf Syst-1


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 50-Year Rainfall=9.67"

Area (sf)	CN	Description
13,067	98	Roofs, HSG C
13,067		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 3S: Townhouse Roofs

Hydrograph



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 50-Year Rainfall=9.67"

Printed 12/17/2024

Page 117

Summary for Subcatchment 4.2S: TD-2

Runoff = 0.2 cfs @ 12.08 hrs, Volume= 863 cf, Depth= 9.31"
Routed to Pond 4P : Inf Syst-2


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 50-Year Rainfall=9.67"

Area (sf)	CN	Description
1,064	98	Paved parking, HSG C
48	74	>75% Grass cover, Good, HSG C
1,112	97	Weighted Average
48		4.32% Pervious Area
1,064		95.68% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.2S: TD-2

Hydrograph



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 50-Year Rainfall=9.67"

Printed 12/17/2024

Page 118

Summary for Subcatchment 4.3S: TD-3

Runoff = 0.2 cfs @ 12.08 hrs, Volume= 857 cf, Depth= 9.31"
Routed to Pond 5P : Inf Syst-3


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 50-Year Rainfall=9.67"

Area (sf)	CN	Description
1,075	98	Paved parking, HSG C
30	74	>75% Grass cover, Good, HSG C
1,105	97	Weighted Average
30		2.71% Pervious Area
1,075		97.29% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.3S: TD-3

Hydrograph



Summary for Subcatchment 4.4S: TD-4

Runoff = 0.2 cfs @ 12.08 hrs, Volume= 856 cf, Depth= 9.31"
 Routed to Pond 6P : Inf Syst-4


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 50-Year Rainfall=9.67"

Area (sf)	CN	Description
1,076	98	Paved parking, HSG C
28	74	>75% Grass cover, Good, HSG C
1,104	97	Weighted Average
28		2.54% Pervious Area
1,076		97.46% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.4S: TD-4

Hydrograph



Summary for Subcatchment 4.5S: TD-5

Runoff = 0.2 cfs @ 12.08 hrs, Volume= 850 cf, Depth= 9.43"
 Routed to Pond 7P : Inf Syst-5


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 50-Year Rainfall=9.67"

Area (sf)	CN	Description
1,061	98	Paved parking, HSG C
21	74	>75% Grass cover, Good, HSG C
1,082	98	Weighted Average
21		1.94% Pervious Area
1,061		98.06% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.5S: TD-5

Hydrograph



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 50-Year Rainfall=9.67"

Printed 12/17/2024

Page 121

Summary for Subcatchment 4.6S: TD-6

Runoff = 0.2 cfs @ 12.08 hrs, Volume= 830 cf, Depth= 9.43"
Routed to Pond 8P : Inf Syst-6


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 50-Year Rainfall=9.67"

Area (sf)	CN	Description
1,048	98	Paved parking, HSG C
8	74	>75% Grass cover, Good, HSG C
1,056	98	Weighted Average
8		0.76% Pervious Area
1,048		99.24% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.6S: TD-6

Hydrograph



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 50-Year Rainfall=9.67"

Printed 12/17/2024

Page 122

Summary for Subcatchment 5.1S: TD-1A

Runoff = 0.3 cfs @ 12.08 hrs, Volume= 1,035 cf, Depth= 8.94"
Routed to Pond 9P : Inf Syst-7


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 50-Year Rainfall=9.67"

Area (sf)	CN	Description
1,175	98	Paved parking, HSG C
214	74	>75% Grass cover, Good, HSG C
1,389	94	Weighted Average
214		15.41% Pervious Area
1,175		84.59% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 5.1S: TD-1A

Hydrograph



Summary for Subcatchment 5S: TD-1B

Runoff = 0.9 cfs @ 12.08 hrs, Volume= 2,866 cf, Depth= 7.71"
 Routed to Link 1L : Towards Wetlands


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 50-Year Rainfall=9.67"

Area (sf)	CN	Description
1,909	98	Paved parking, HSG C
2,553	74	>75% Grass cover, Good, HSG C
4,462	84	Weighted Average
2,553		57.22% Pervious Area
1,909		42.78% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 5S: TD-1B

Hydrograph



Summary for Subcatchment 6.1S: East driveway

Runoff = 2.5 cfs @ 12.08 hrs, Volume= 8,268 cf, Depth= 8.08"
 Routed to Pond 3P : Rain garden


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 50-Year Rainfall=9.67"

Area (sf)	CN	Description
5,611	74	>75% Grass cover, Good, HSG C
6,444	98	Paved roads w/curbs & sewers, HSG C
220	89	Gravel roads, HSG C
12,275	87	Weighted Average
5,831		47.50% Pervious Area
6,444		52.50% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

Subcatchment 6.1S: East driveway

Hydrograph



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 50-Year Rainfall=9.67"

Printed 12/17/2024

Page 125


Summary for Subcatchment 6S: Bypass Towards Wetlands

Runoff = 6.9 cfs @ 12.19 hrs, Volume= 27,672 cf, Depth= 6.44"
Routed to Link 1L : Towards Wetlands

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 50-Year Rainfall=9.67"

Table with 2 columns: Area (sf) and Description. Includes rows for Woods, Grass cover, Roofs, and Weighted Average. Includes a second table with columns: Tc (min), Length (feet), Slope (ft/ft), Velocity (ft/sec), Capacity (cfs), and Description.

Subcatchment 6S: Bypass Towards Wetlands



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 50-Year Rainfall=9.67"

Printed 12/17/2024

Page 126


Summary for Subcatchment 7S: To Street

Runoff = 1.1 cfs @ 12.09 hrs, Volume= 3,385 cf, Depth= 6.95"
Routed to Link 2L : Towards Street

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 50-Year Rainfall=9.67"

Table with 2 columns: Area (sf) and Description. Includes rows for Paved parking, Grass cover, and Weighted Average. Includes a second table with columns: Tc (min), Length (feet), Slope (ft/ft), Velocity (ft/sec), Capacity (cfs), and Description.

Subcatchment 7S: To Street



Summary for Pond 1P: Inf Syst-1

Inflow Area = 60,436 sf, 85.36% Impervious, Inflow Depth = 8.83" for 50-Year event
 Inflow = 12.4 cfs @ 12.09 hrs, Volume= 44,458 cf
 Outflow = 5.3 cfs @ 12.30 hrs, Volume= 44,458 cf, Atten= 57%, Lag= 12.5 min
 Discarded = 0.1 cfs @ 3.50 hrs, Volume= 15,169 cf
 Primary = 5.2 cfs @ 12.30 hrs, Volume= 29,289 cf
 Routed to Link 1L : Towards Wetlands

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 10.70' @ 12.30 hrs Surf.Area= 7,459 sf Storage= 17,296 cf

Plug-Flow detention time= 312.6 min calculated for 44,458 cf (100% of inflow)
 Center-of-Mass det. time= 312.5 min (1,063.8 - 751.2)

Volume	Invert	Avail.Storage	Storage Description
#1	8.00'	19,245 cf	6.89'W x 14.06'L x 3.00'H StormTrap ST-1 Units (Irregular Shape) 77 22,378 cf Overall x 86.0% Voids


Device	Routing	Invert	Outlet Devices
#1	Discarded	8.00'	0.520 in/hr Exfiltration over Surface area
#2	Primary	8.00'	15.0" Round Culvert L= 26.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 8.00' / 7.13' S= 0.0335' /' Cc= 0.900 n= 0.013, Flow Area= 1.23 sf
#3	Device 2	9.22'	22.0" W x 4.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 2	10.05'	20.0" W x 4.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 2	10.79'	3.7' long Sharp-Crested Rectangular Weir 2 End Contraction(s)

Discarded OutFlow Max=0.1 cfs @ 3.50 hrs HW=8.03' (Free Discharge)
 ↳ **1=Exfiltration** (Exfiltration Controls 0.1 cfs)

Primary OutFlow Max=5.2 cfs @ 12.30 hrs HW=10.70' (Free Discharge)
 ↳ **2=Culvert** (Passes 5.2 cfs of 8.5 cfs potential flow)
 ↳ **3=Orifice/Grate** (Orifice Controls 3.4 cfs @ 5.51 fps)
 ↳ **4=Orifice/Grate** (Orifice Controls 1.8 cfs @ 3.32 fps)
 ↳ **5=Sharp-Crested Rectangular Weir** (Controls 0.0 cfs)

Pond 1P: Inf Syst-1

Hydrograph



Summary for Pond 3P: Rain garden

Inflow Area = 12,275 sf, 52.50% Impervious, Inflow Depth = 8.08" for 50-Year event
 Inflow = 2.5 cfs @ 12.08 hrs, Volume= 8,268 cf
 Outflow = 2.5 cfs @ 12.09 hrs, Volume= 8,268 cf, Atten= 0%, Lag= 0.3 min
 Discarded = 0.0 cfs @ 12.09 hrs, Volume= 506 cf
 Primary = 2.5 cfs @ 12.09 hrs, Volume= 7,762 cf
 Routed to Link 1L : Towards Wetlands

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 6.48' @ 12.09 hrs Surf.Area= 450 sf Storage= 245 cf

Plug-Flow detention time= 35.3 min calculated for 8,268 cf (100% of inflow)
 Center-of-Mass det. time= 35.2 min (814.3 - 779.1)

Volume	Invert	Avail.Storage	Storage Description		
#1	5.60'	253 cf	Custom Stage Data (Irregular) Listed below (Recalc)		
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
5.60	125	46.0	0	0	125
6.00	276	66.0	78	78	305
6.30	350	73.0	94	172	385
6.50	460	87.0	81	253	564


Device	Routing	Invert	Outlet Devices										
#1	Discarded	5.60'	0.520 in/hr Exfiltration over Surface area										
#2	Primary	6.35'	22.0' long x 5.0' breadth Broad-Crested Rectangular Weir										
			Head (feet)	0.20	0.40	0.60	0.80	1.00	1.20	1.40	1.60	1.80	2.00
				2.50	3.00	3.50	4.00	4.50	5.00	5.50			
			Coef. (English)	2.34	2.50	2.70	2.68	2.68	2.66	2.65	2.65	2.65	
				2.65	2.67	2.66	2.68	2.70	2.74	2.79	2.88		

Discarded OutFlow Max=0.0 cfs @ 12.09 hrs HW=6.48' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=2.5 cfs @ 12.09 hrs HW=6.48' (Free Discharge)
 ↳2=Broad-Crested Rectangular Weir (Weir Controls 2.5 cfs @ 0.85 fps)

Pond 3P: Rain garden

Hydrograph



Summary for Pond 4P: Inf Syst-2

Inflow Area = 1,112 sf, 95.68% Impervious, Inflow Depth = 9.31" for 50-Year event
 Inflow = 0.2 cfs @ 12.08 hrs, Volume= 863 cf
 Outflow = 0.2 cfs @ 12.09 hrs, Volume= 849 cf, Atten= 1%, Lag= 0.5 min
 Discarded = 0.0 cfs @ 1.70 hrs, Volume= 160 cf
 Primary = 0.2 cfs @ 12.09 hrs, Volume= 689 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.54' @ 12.09 hrs Surf.Area= 101 sf Storage= 134 cf

Plug-Flow detention time= 326.9 min calculated for 849 cf (98% of inflow)
 Center-of-Mass det. time= 316.9 min (1,061.1 - 744.2)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	84 cf	7.28'W x 13.84'L x 2.72'H Field A 274 cf Overall - 64 cf Embedded = 210 cf x 40.0% Voids
#2A	7.25'	57 cf	Ferguson R-Tank XD 12 x 10 Inside #1 Inside= 19.7"W x 23.6"H => 2.91 sf x 1.97'L = 5.7 cf Outside= 19.7"W x 23.6"H => 3.23 sf x 1.97'L = 6.4 cf 10 Chambers in 2 Rows
		141 cf	Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.23'	6.0" Round Culvert L= 33.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.23' / 8.72' S= 0.0155 ' / Cc= 0.900 n= 0.013, Flow Area= 0.20 sf

Discarded OutFlow Max=0.0 cfs @ 1.70 hrs HW=7.03' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.2 cfs @ 12.09 hrs HW=9.54' (Free Discharge)
 ↳2=Culvert (Inlet Controls 0.2 cfs @ 1.89 fps)

Pond 4P: Inf Syst-2

Hydrograph



Summary for Pond 5P: Inf Syst-3

Inflow Area = 1,105 sf, 97.29% Impervious, Inflow Depth = 9.31" for 50-Year event
 Inflow = 0.2 cfs @ 12.08 hrs, Volume= 857 cf
 Outflow = 0.2 cfs @ 12.09 hrs, Volume= 838 cf, Atten= 1%, Lag= 0.5 min
 Discarded = 0.0 cfs @ 1.73 hrs, Volume= 160 cf
 Primary = 0.2 cfs @ 12.09 hrs, Volume= 678 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.68' @ 12.09 hrs Surf.Area= 101 sf Storage= 140 cf

Plug-Flow detention time= 335.8 min calculated for 838 cf (98% of inflow)
 Center-of-Mass det. time= 321.7 min (1,066.0 - 744.2)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	84 cf	7.28'W x 13.84'L x 2.72'H Field A 274 cf Overall - 64 cf Embedded = 210 cf x 40.0% Voids
#2A	7.25'	57 cf	Ferguson R-Tank XD 12 x 10 Inside #1 Inside= 19.7"W x 23.6"H => 2.91 sf x 1.97'L = 5.7 cf Outside= 19.7"W x 23.6"H => 3.23 sf x 1.97'L = 6.4 cf 10 Chambers in 2 Rows
		141 cf	Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.37'	6.0" Round Culvert L= 33.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.37' / 8.73' S= 0.0194 '/ Cc= 0.900 n= 0.013, Flow Area= 0.20 sf

Discarded OutFlow Max=0.0 cfs @ 1.73 hrs HW=7.03' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.2 cfs @ 12.09 hrs HW=9.68' (Free Discharge)
 ↳2=Culvert (Inlet Controls 0.2 cfs @ 1.89 fps)

Pond 5P: Inf Syst-3

Hydrograph



Summary for Pond 6P: Inf Syst-4

Inflow Area = 1,104 sf, 97.46% Impervious, Inflow Depth = 9.31" for 50-Year event
 Inflow = 0.2 cfs @ 12.08 hrs, Volume= 856 cf
 Outflow = 0.2 cfs @ 12.09 hrs, Volume= 837 cf, Atten= 1%, Lag= 0.5 min
 Discarded = 0.0 cfs @ 1.73 hrs, Volume= 160 cf
 Primary = 0.2 cfs @ 12.09 hrs, Volume= 677 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.68' @ 12.09 hrs Surf.Area= 101 sf Storage= 140 cf

Plug-Flow detention time= 336.1 min calculated for 837 cf (98% of inflow)
 Center-of-Mass det. time= 322.0 min (1,066.2 - 744.2)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	84 cf	7.28'W x 13.84'L x 2.72'H Field A 274 cf Overall - 64 cf Embedded = 210 cf x 40.0% Voids
#2A	7.25'	57 cf	Ferguson R-Tank XD 12 x 10 Inside #1 Inside= 19.7"W x 23.6"H => 2.91 sf x 1.97'L = 5.7 cf Outside= 19.7"W x 23.6"H => 3.23 sf x 1.97'L = 6.4 cf 10 Chambers in 2 Rows
		141 cf	Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.37'	6.0" Round Culvert L= 51.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.37' / 8.10' S= 0.0249 ' S= 0.0249 ' Cc= 0.900 n= 0.013, Flow Area= 0.20 sf

Discarded OutFlow Max=0.0 cfs @ 1.73 hrs HW=7.03' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.2 cfs @ 12.09 hrs HW=9.68' (Free Discharge)
 ↳2=Culvert (Inlet Controls 0.2 cfs @ 1.89 fps)

Pond 6P: Inf Syst-4

Hydrograph



Summary for Pond 7P: Inf Syst-5

Inflow Area = 1,082 sf, 98.06% Impervious, Inflow Depth = 9.43" for 50-Year event
 Inflow = 0.2 cfs @ 12.08 hrs, Volume= 850 cf
 Outflow = 0.2 cfs @ 12.09 hrs, Volume= 849 cf, Atten= 1%, Lag= 0.5 min
 Discarded = 0.0 cfs @ 1.27 hrs, Volume= 161 cf
 Primary = 0.2 cfs @ 12.09 hrs, Volume= 688 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.30' @ 12.09 hrs Surf.Area= 101 sf Storage= 122 cf

Plug-Flow detention time= 318.0 min calculated for 849 cf (100% of inflow)
 Center-of-Mass det. time= 317.6 min (1,056.6 - 739.0)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	73 cf	7.28'W x 13.84'L x 2.39'H Field A 241 cf Overall - 58 cf Embedded = 182 cf x 40.0% Voids
#2A	7.25'	52 cf	Ferguson R-Tank XD 11 x 10 Inside #1 Inside= 19.7"W x 21.7"H => 2.66 sf x 1.97'L = 5.2 cf Outside= 19.7"W x 21.7"H => 2.96 sf x 1.97'L = 5.8 cf 10 Chambers in 2 Rows
		125 cf	Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.00'	6.0" Round Culvert L= 48.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.00' / 8.35' S= 0.0135 '/ Cc= 0.900 n= 0.013, Flow Area= 0.20 sf

Discarded OutFlow Max=0.0 cfs @ 1.27 hrs HW=7.03' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.2 cfs @ 12.09 hrs HW=9.30' (Free Discharge)
 ↳2=Culvert (Inlet Controls 0.2 cfs @ 1.88 fps)

Pond 7P: Inf Syst-5

Hydrograph



Summary for Pond 8P: Inf Syst-6

Inflow Area = 1,056 sf, 99.24% Impervious, Inflow Depth = 9.43" for 50-Year event
 Inflow = 0.2 cfs @ 12.08 hrs, Volume= 830 cf
 Outflow = 0.2 cfs @ 12.09 hrs, Volume= 829 cf, Atten= 1%, Lag= 0.5 min
 Discarded = 0.0 cfs @ 1.30 hrs, Volume= 161 cf
 Primary = 0.2 cfs @ 12.09 hrs, Volume= 668 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.32' @ 12.09 hrs Surf.Area= 101 sf Storage= 123 cf

Plug-Flow detention time= 325.6 min calculated for 829 cf (100% of inflow)
 Center-of-Mass det. time= 325.0 min (1,064.0 - 739.0)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	73 cf	7.28'W x 13.84'L x 2.39'H Field A 241 cf Overall - 58 cf Embedded = 182 cf x 40.0% Voids
#2A	7.25'	52 cf	Ferguson R-Tank XD 11 x 10 Inside #1 Inside= 19.7"W x 21.7"H => 2.66 sf x 1.97'L = 5.2 cf Outside= 19.7"W x 21.7"H => 2.96 sf x 1.97'L = 5.8 cf 10 Chambers in 2 Rows
		125 cf	Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.00'	8.0" Round Culvert L= 46.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.00' / 8.77' S= 0.0050 '/ Cc= 0.900 n= 0.013, Flow Area= 0.35 sf

Discarded OutFlow Max=0.0 cfs @ 1.30 hrs HW=7.03' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.2 cfs @ 12.09 hrs HW=9.32' (Free Discharge)
 ↳2=Culvert (Barrel Controls 0.2 cfs @ 2.02 fps)

Pond 8P: Inf Syst-6

Hydrograph



Summary for Pond 9P: Inf Syst-7

Inflow Area = 24,131 sf, 72.87% Impervious, Inflow Depth = 8.60" for 50-Year event
 Inflow = 5.1 cfs @ 12.08 hrs, Volume= 17,290 cf
 Outflow = 3.0 cfs @ 12.19 hrs, Volume= 17,290 cf, Atten= 41%, Lag= 6.3 min
 Discarded = 0.0 cfs @ 4.01 hrs, Volume= 1,591 cf
 Primary = 3.0 cfs @ 12.19 hrs, Volume= 15,699 cf
 Routed to Link 1L : Towards Wetlands

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 8.58' @ 12.19 hrs Surf.Area= 2,422 sf Storage= 2,968 cf

Plug-Flow detention time= 48.3 min calculated for 17,290 cf (100% of inflow)
 Center-of-Mass det. time= 48.2 min (815.1 - 766.9)

Volume	Invert	Avail.Storage	Storage Description
#1	7.15'	3,645 cf	6.89'W x 14.06'L x 1.75'H StormTrap ST-1 Units (Irregular Shape) x 25 4,238 cf Overall x 86.0% Voids


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.15'	0.270 in/hr Exfiltration over Surface area
#2	Primary	7.15'	12.0" Round Culvert L= 4.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 7.15' / 7.13' S= 0.0050 /' Cc= 0.900 n= 0.013, Flow Area= 0.79 sf
#3	Device 2	7.35'	22.0" W x 4.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

Discarded OutFlow Max=0.0 cfs @ 4.01 hrs HW=7.17' (Free Discharge)
 1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=3.0 cfs @ 12.19 hrs HW=8.58' (Free Discharge)
 2=Culvert (Passes 3.0 cfs of 3.3 cfs potential flow)
 3=Orifice/Grate (Orifice Controls 3.0 cfs @ 4.95 fps)

Pond 9P: Inf Syst-7

Hydrograph




Summary for Link 1L: Towards Wetlands

Inflow Area = 152,843 sf, 50.79% Impervious, Inflow Depth = 6.54" for 50-Year event
Inflow = 17.0 cfs @ 12.18 hrs, Volume= 83,287 cf
Primary = 17.0 cfs @ 12.18 hrs, Volume= 83,287 cf, Atten= 0%, Lag= 0.0 min
Routed to Link 100L : Total Flows

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link 1L: Towards Wetlands

Hydrograph




Summary for Link 2L: Towards Street

Inflow Area = 5,843 sf, 18.07% Impervious, Inflow Depth = 6.95" for 50-Year event
Inflow = 1.1 cfs @ 12.09 hrs, Volume= 3,385 cf
Primary = 1.1 cfs @ 12.09 hrs, Volume= 3,385 cf, Atten= 0%, Lag= 0.0 min
Routed to Link 100L : Total Flows

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link 2L: Towards Street

Hydrograph




Summary for Link 100L: Total Flows

Inflow Area = 158,686 sf, 49.59% Impervious, Inflow Depth = 6.55" for 50-Year event
 Inflow = 17.8 cfs @ 12.16 hrs, Volume= 86,673 cf
 Primary = 17.8 cfs @ 12.16 hrs, Volume= 86,673 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link 100L: Total Flows

Hydrograph



Time span=0.00-72.00 hrs, dt=0.01 hrs, 7201 points
 Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
 Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment1S: CB-1	Runoff Area=22,742 sf 72.16% Impervious Runoff Depth=10.39" Tc=6.0 min CN=91 Runoff=5.8 cfs 19,696 cf
Subcatchment2S: Building Roof	Runoff Area=32,925 sf 100.00% Impervious Runoff Depth=11.26" Tc=6.0 min CN=98 Runoff=8.5 cfs 30,891 cf
Subcatchment3.1S: Backyard ADS	Runoff Area=8,985 sf 3.03% Impervious Runoff Depth=8.28" Flow Length=147' Tc=10.3 min CN=75 Runoff=1.7 cfs 6,203 cf
Subcatchment3S: Townhouse Roofs	Runoff Area=13,067 sf 100.00% Impervious Runoff Depth=11.26" Tc=6.0 min CN=98 Runoff=3.4 cfs 12,260 cf
Subcatchment4.2S: TD-2	Runoff Area=1,112 sf 95.68% Impervious Runoff Depth=11.14" Tc=6.0 min CN=97 Runoff=0.3 cfs 1,032 cf
Subcatchment4.3S: TD-3	Runoff Area=1,105 sf 97.29% Impervious Runoff Depth=11.14" Tc=6.0 min CN=97 Runoff=0.3 cfs 1,026 cf
Subcatchment4.4S: TD-4	Runoff Area=1,104 sf 97.46% Impervious Runoff Depth=11.14" Tc=6.0 min CN=97 Runoff=0.3 cfs 1,025 cf
Subcatchment4.5S: TD-5	Runoff Area=1,082 sf 98.06% Impervious Runoff Depth=11.26" Tc=6.0 min CN=98 Runoff=0.3 cfs 1,015 cf
Subcatchment4.6S: TD-6	Runoff Area=1,056 sf 99.24% Impervious Runoff Depth=11.26" Tc=6.0 min CN=98 Runoff=0.3 cfs 991 cf
Subcatchment5.1S: TD-1A	Runoff Area=1,389 sf 84.59% Impervious Runoff Depth=10.77" Tc=6.0 min CN=94 Runoff=0.4 cfs 1,246 cf
Subcatchment5S: TD-1B	Runoff Area=4,462 sf 42.78% Impervious Runoff Depth=9.49" Tc=6.0 min CN=84 Runoff=1.1 cfs 3,530 cf
Subcatchment6.1S: East driveway	Runoff Area=12,275 sf 52.50% Impervious Runoff Depth=9.88" Tc=6.0 min CN=87 Runoff=3.0 cfs 10,109 cf
Subcatchment6S: Bypass Towards	Runoff Area=51,539 sf 0.21% Impervious Runoff Depth=8.15" Flow Length=125' Tc=14.0 min CN=74 Runoff=8.7 cfs 34,988 cf
Subcatchment7S: To Street	Runoff Area=5,843 sf 18.07% Impervious Runoff Depth=8.69" Tc=6.0 min CN=78 Runoff=1.3 cfs 4,233 cf
Pond 1P: Inf Syst-1	Peak Elev=11.00' Storage=19,245 cf Inflow=14.8 cfs 53,582 cf Discarded=0.1 cfs 15,354 cf Primary=7.3 cfs 38,228 cf Outflow=7.4 cfs 53,582 cf
Pond 3P: Rain garden	Peak Elev=6.50' Storage=253 cf Inflow=3.0 cfs 10,109 cf Discarded=0.0 cfs 518 cf Primary=3.0 cfs 9,592 cf Outflow=3.0 cfs 10,109 cf

2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 100-Year Rainfall=11.50"

Printed 12/17/2024

Page 147

Pond 4P: Inf Syst-2

Peak Elev=9.57' Storage=136 cf Inflow=0.3 cfs 1,032 cf
Discarded=0.0 cfs 161 cf Primary=0.3 cfs 858 cf Outflow=0.3 cfs 1,018 cf

Pond 5P: Inf Syst-3

Peak Elev=9.71' Storage=141 cf Inflow=0.3 cfs 1,026 cf
Discarded=0.0 cfs 161 cf Primary=0.3 cfs 846 cf Outflow=0.3 cfs 1,006 cf

Pond 6P: Inf Syst-4

Peak Elev=9.71' Storage=141 cf Inflow=0.3 cfs 1,025 cf
Discarded=0.0 cfs 161 cf Primary=0.3 cfs 845 cf Outflow=0.3 cfs 1,005 cf

Pond 7P: Inf Syst-5

Peak Elev=9.34' Storage=123 cf Inflow=0.3 cfs 1,015 cf
Discarded=0.0 cfs 161 cf Primary=0.3 cfs 853 cf Outflow=0.3 cfs 1,014 cf

Pond 8P: Inf Syst-6

Peak Elev=9.35' Storage=124 cf Inflow=0.3 cfs 991 cf
Discarded=0.0 cfs 161 cf Primary=0.3 cfs 828 cf Outflow=0.3 cfs 990 cf

Pond 9P: Inf Syst-7

Peak Elev=8.86' Storage=3,555 cf Inflow=6.1 cfs 20,942 cf
Discarded=0.0 cfs 1,621 cf Primary=3.4 cfs 19,322 cf Outflow=3.4 cfs 20,942 cf

Link 1L: Towards Wetlands

Inflow=21.4 cfs 105,660 cf
Primary=21.4 cfs 105,660 cf

Link 2L: Towards Street

Inflow=1.3 cfs 4,233 cf
Primary=1.3 cfs 4,233 cf

Link 100L: Total Flows

Inflow=22.3 cfs 109,893 cf
Primary=22.3 cfs 109,893 cf

Total Runoff Area = 158,686 sf Runoff Volume = 128,244 cf Average Runoff Depth = 9.70"
50.41% Pervious = 79,997 sf 49.59% Impervious = 78,689 sf

2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 100-Year Rainfall=11.50"

Printed 12/17/2024

Page 148

Summary for Subcatchment 1S: CB-1

Runoff = 5.8 cfs @ 12.08 hrs, Volume= 19,696 cf, Depth=10.39"
Routed to Pond 9P : Inf Syst-7


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 100-Year Rainfall=11.50"

Area (sf)	CN	Description
16,410	98	Paved parking, HSG C
6,332	74	>75% Grass cover, Good, HSG C
22,742	91	Weighted Average
6,332		27.84% Pervious Area
16,410		72.16% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 1S: CB-1

Hydrograph



Summary for Subcatchment 2S: Building Roof


Runoff = 8.5 cfs @ 12.08 hrs, Volume= 30,891 cf, Depth=11.26"
Routed to Pond 1P : Inf Syst-1

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 100-Year Rainfall=11.50"

Area (sf)	CN	Description
32,925	98	Roofs, HSG C
32,925		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 2S: Building Roof



Summary for Subcatchment 3.1S: Backyard ADs


Runoff = 1.7 cfs @ 12.14 hrs, Volume= 6,203 cf, Depth= 8.28"
Routed to Pond 1P : Inf Syst-1

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 100-Year Rainfall=11.50"

Area (sf)	CN	Description
272	98	Unconnected pavement, HSG C
8,302	74	>75% Grass cover, Good, HSG C
411	89	Gravel sidewalk, HSG C
8,985	75	Weighted Average
8,713		96.97% Pervious Area
272		3.03% Impervious Area
272		100.00% Unconnected

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
9.4	50	0.0142	0.09		Sheet Flow, Grass: Dense n= 0.240 P2= 3.23"
0.9	97	0.0154	1.86		Shallow Concentrated Flow, Grassed Waterway Kv= 15.0 fps
10.3	147				Total

Subcatchment 3.1S: Backyard ADs



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 100-Year Rainfall=11.50"

Printed 12/17/2024

Page 151

Summary for Subcatchment 3S: Townhouse Roofs

Runoff = 3.4 cfs @ 12.08 hrs, Volume= 12,260 cf, Depth=11.26"
Routed to Pond 1P : Inf Syst-1


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 100-Year Rainfall=11.50"

Area (sf)	CN	Description
13,067	98	Roofs, HSG C
13,067		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 3S: Townhouse Roofs

Hydrograph



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 100-Year Rainfall=11.50"

Printed 12/17/2024

Page 152

Summary for Subcatchment 4.2S: TD-2

Runoff = 0.3 cfs @ 12.08 hrs, Volume= 1,032 cf, Depth=11.14"
Routed to Pond 4P : Inf Syst-2


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 100-Year Rainfall=11.50"

Area (sf)	CN	Description
1,064	98	Paved parking, HSG C
48	74	>75% Grass cover, Good, HSG C
1,112	97	Weighted Average
48		4.32% Pervious Area
1,064		95.68% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.2S: TD-2

Hydrograph



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 100-Year Rainfall=11.50"

Printed 12/17/2024

Page 153

Summary for Subcatchment 4.3S: TD-3

Runoff = 0.3 cfs @ 12.08 hrs, Volume= 1,026 cf, Depth=11.14"
Routed to Pond 5P : Inf Syst-3


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 100-Year Rainfall=11.50"

Area (sf)	CN	Description
1,075	98	Paved parking, HSG C
30	74	>75% Grass cover, Good, HSG C
1,105	97	Weighted Average
30		2.71% Pervious Area
1,075		97.29% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.3S: TD-3

Hydrograph



2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 100-Year Rainfall=11.50"

Printed 12/17/2024

Page 154

Summary for Subcatchment 4.4S: TD-4

Runoff = 0.3 cfs @ 12.08 hrs, Volume= 1,025 cf, Depth=11.14"
Routed to Pond 6P : Inf Syst-4


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
Type III 24-hr 100-Year Rainfall=11.50"

Area (sf)	CN	Description
1,076	98	Paved parking, HSG C
28	74	>75% Grass cover, Good, HSG C
1,104	97	Weighted Average
28		2.54% Pervious Area
1,076		97.46% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.4S: TD-4

Hydrograph



Summary for Subcatchment 4.5S: TD-5

Runoff = 0.3 cfs @ 12.08 hrs, Volume= 1,015 cf, Depth=11.26"
 Routed to Pond 7P : Inf Syst-5


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 100-Year Rainfall=11.50"

Area (sf)	CN	Description
1,061	98	Paved parking, HSG C
21	74	>75% Grass cover, Good, HSG C
1,082	98	Weighted Average
21		1.94% Pervious Area
1,061		98.06% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.5S: TD-5

Hydrograph



Summary for Subcatchment 4.6S: TD-6

Runoff = 0.3 cfs @ 12.08 hrs, Volume= 991 cf, Depth=11.26"
 Routed to Pond 8P : Inf Syst-6


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 100-Year Rainfall=11.50"

Area (sf)	CN	Description
1,048	98	Paved parking, HSG C
8	74	>75% Grass cover, Good, HSG C
1,056	98	Weighted Average
8		0.76% Pervious Area
1,048		99.24% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 4.6S: TD-6

Hydrograph



Summary for Subcatchment 5.1S: TD-1A

Runoff = 0.4 cfs @ 12.08 hrs, Volume= 1,246 cf, Depth=10.77"
 Routed to Pond 9P : Inf Syst-7


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 100-Year Rainfall=11.50"

Area (sf)	CN	Description
1,175	98	Paved parking, HSG C
214	74	>75% Grass cover, Good, HSG C
1,389	94	Weighted Average
214		15.41% Pervious Area
1,175		84.59% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 5.1S: TD-1A

Hydrograph



Summary for Subcatchment 5S: TD-1B

Runoff = 1.1 cfs @ 12.08 hrs, Volume= 3,530 cf, Depth= 9.49"
 Routed to Link 1L : Towards Wetlands


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 100-Year Rainfall=11.50"

Area (sf)	CN	Description
1,909	98	Paved parking, HSG C
2,553	74	>75% Grass cover, Good, HSG C
4,462	84	Weighted Average
2,553		57.22% Pervious Area
1,909		42.78% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 5S: TD-1B

Hydrograph



Summary for Subcatchment 6.1S: East driveway

Runoff = 3.0 cfs @ 12.08 hrs, Volume= 10,109 cf, Depth= 9.88"
 Routed to Pond 3P : Rain garden


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 100-Year Rainfall=11.50"

Area (sf)	CN	Description
5,611	74	>75% Grass cover, Good, HSG C
6,444	98	Paved roads w/curbs & sewers, HSG C
220	89	Gravel roads, HSG C
12,275	87	Weighted Average
5,831		47.50% Pervious Area
6,444		52.50% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

Subcatchment 6.1S: East driveway

Hydrograph



Summary for Subcatchment 6S: Bypass Towards Wetlands

Runoff = 8.7 cfs @ 12.18 hrs, Volume= 34,988 cf, Depth= 8.15"
 Routed to Link 1L : Towards Wetlands


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 100-Year Rainfall=11.50"

Area (sf)	CN	Description
4,985	70	Woods, Good, HSG C
46,447	74	>75% Grass cover, Good, HSG C
107	98	Roofs, HSG C
51,539	74	Weighted Average
51,432		99.79% Pervious Area
107		0.21% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.8	50	0.0220	0.07		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.23"
2.2	75	0.0133	0.58		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
14.0	125	Total			

Subcatchment 6S: Bypass Towards Wetlands

Hydrograph



Summary for Subcatchment 7S: To Street


Runoff = 1.3 cfs @ 12.09 hrs, Volume= 4,233 cf, Depth= 8.69"
 Routed to Link 2L : Towards Street

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Type III 24-hr 100-Year Rainfall=11.50"

Area (sf)	CN	Description
1,056	98	Paved parking, HSG C
4,787	74	>75% Grass cover, Good, HSG C
5,843	78	Weighted Average
4,787		81.93% Pervious Area
1,056		18.07% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Min. Tc

Subcatchment 7S: To Street



Summary for Pond 1P: Inf Syst-1

Inflow Area = 60,436 sf, 85.36% Impervious, Inflow Depth = 10.64" for 100-Year event
 Inflow = 14.8 cfs @ 12.09 hrs, Volume= 53,582 cf
 Outflow = 7.4 cfs @ 12.25 hrs, Volume= 53,582 cf, Atten= 50%, Lag= 9.7 min
 Discarded = 0.1 cfs @ 2.72 hrs, Volume= 15,354 cf
 Primary = 7.3 cfs @ 12.25 hrs, Volume= 38,228 cf
 Routed to Link 1L : Towards Wetlands

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 11.00' @ 12.25 hrs Surf.Area= 7,459 sf Storage= 19,245 cf

Plug-Flow detention time= 272.3 min calculated for 53,582 cf (100% of inflow)
 Center-of-Mass det. time= 272.2 min (1,021.3 - 749.0)

Volume	Invert	Avail.Storage	Storage Description
#1	8.00'	19,245 cf	6.89'W x 14.06'L x 3.00'H StormTrap ST-1 Units (Irregular Shape) 77 22,378 cf Overall x 86.0% Voids


Device	Routing	Invert	Outlet Devices
#1	Discarded	8.00'	0.520 in/hr Exfiltration over Surface area
#2	Primary	8.00'	15.0" Round Culvert L= 26.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 8.00' / 7.13' S= 0.0335 '/ Cc= 0.900 n= 0.013, Flow Area= 1.23 sf
#3	Device 2	9.22'	22.0" W x 4.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 2	10.05'	20.0" W x 4.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 2	10.79'	3.7' long Sharp-Crested Rectangular Weir 2 End Contraction(s)

Discarded OutFlow Max=0.1 cfs @ 2.72 hrs HW=8.03' (Free Discharge)
 1=Exfiltration (Exfiltration Controls 0.1 cfs)

Primary OutFlow Max=7.3 cfs @ 12.25 hrs HW=11.00' (Free Discharge)
 2=Culvert (Passes 7.3 cfs of 9.1 cfs potential flow)
 3=Orifice/Grate (Orifice Controls 3.7 cfs @ 6.12 fps)
 4=Orifice/Grate (Orifice Controls 2.4 cfs @ 4.26 fps)
 5=Sharp-Crested Rectangular Weir(Weir Controls 1.2 cfs @ 1.51 fps)

Pond 1P: Inf Syst-1

Hydrograph



Summary for Pond 3P: Rain garden

Inflow Area = 12,275 sf, 52.50% Impervious, Inflow Depth = 9.88" for 100-Year event
 Inflow = 3.0 cfs @ 12.08 hrs, Volume= 10,109 cf
 Outflow = 3.0 cfs @ 12.08 hrs, Volume= 10,109 cf, Atten= 0%, Lag= 0.0 min
 Discarded = 0.0 cfs @ 12.08 hrs, Volume= 518 cf
 Primary = 3.0 cfs @ 12.08 hrs, Volume= 9,592 cf
 Routed to Link 1L : Towards Wetlands

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 6.50' @ 12.08 hrs Surf.Area= 460 sf Storage= 253 cf

Plug-Flow detention time= 29.6 min calculated for 10,108 cf (100% of inflow)
 Center-of-Mass det. time= 29.8 min (803.8 - 774.0)

Volume	Invert	Avail.Storage	Storage Description		
#1	5.60'	253 cf	Custom Stage Data (Irregular) Listed below (Recal)		
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
5.60	125	46.0	0	0	125
6.00	276	66.0	78	78	305
6.30	350	73.0	94	172	385
6.50	460	87.0	81	253	564


Device	Routing	Invert	Outlet Devices										
#1	Discarded	5.60'	0.520 in/hr Exfiltration over Surface area										
#2	Primary	6.35'	22.0' long x 5.0' breadth Broad-Crested Rectangular Weir										
			Head (feet)	0.20	0.40	0.60	0.80	1.00	1.20	1.40	1.60	1.80	2.00
			Coef. (English)	2.34	2.50	2.70	2.68	2.68	2.66	2.66	2.65	2.65	2.65
				2.65	2.67	2.66	2.68	2.70	2.74	2.79	2.88		

Discarded OutFlow Max=0.0 cfs @ 12.08 hrs HW=6.50' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=3.0 cfs @ 12.08 hrs HW=6.50' (Free Discharge)
 ↳2=Broad-Crested Rectangular Weir (Weir Controls 3.0 cfs @ 0.91 fps)

Pond 3P: Rain garden

Hydrograph



Summary for Pond 4P: Inf Syst-2

Inflow Area = 1,112 sf, 95.68% Impervious, Inflow Depth = 11.14" for 100-Year event
 Inflow = 0.3 cfs @ 12.08 hrs, Volume= 1,032 cf
 Outflow = 0.3 cfs @ 12.09 hrs, Volume= 1,018 cf, Atten= 1%, Lag= 0.5 min
 Discarded = 0.0 cfs @ 1.40 hrs, Volume= 161 cf
 Primary = 0.3 cfs @ 12.09 hrs, Volume= 858 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.57' @ 12.09 hrs Surf.Area= 101 sf Storage= 136 cf

Plug-Flow detention time= 278.5 min calculated for 1,018 cf (99% of inflow)
 Center-of-Mass det. time= 269.7 min (1,011.6 - 741.9)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	84 cf	7.28'W x 13.84'L x 2.72'H Field A 274 cf Overall - 64 cf Embedded = 210 cf x 40.0% Voids
#2A	7.25'	57 cf	Ferguson R-Tank XD 12 x 10 Inside #1 Inside= 19.7"W x 23.6"H => 2.91 sf x 1.97'L = 5.7 cf Outside= 19.7"W x 23.6"H => 3.23 sf x 1.97'L = 6.4 cf 10 Chambers in 2 Rows
		141 cf	Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.23'	6.0" Round Culvert L= 33.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.23' / 8.72' S= 0.0155 '/ Cc= 0.900 n= 0.013, Flow Area= 0.20 sf

Discarded OutFlow Max=0.0 cfs @ 1.40 hrs HW=7.03' (Free Discharge)
 ↕ **1=Exfiltration** (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.3 cfs @ 12.09 hrs HW=9.57' (Free Discharge)
 ↕ **2=Culvert** (Inlet Controls 0.3 cfs @ 1.99 fps)

Pond 4P: Inf Syst-2

Hydrograph



Summary for Pond 5P: Inf Syst-3

Inflow Area = 1,105 sf, 97.29% Impervious, Inflow Depth = 11.14" for 100-Year event
 Inflow = 0.3 cfs @ 12.08 hrs, Volume= 1,026 cf
 Outflow = 0.3 cfs @ 12.09 hrs, Volume= 1,006 cf, Atten= 1%, Lag= 0.5 min
 Discarded = 0.0 cfs @ 1.42 hrs, Volume= 161 cf
 Primary = 0.3 cfs @ 12.09 hrs, Volume= 846 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.71' @ 12.09 hrs Surf.Area= 101 sf Storage= 141 cf

Plug-Flow detention time= 286.0 min calculated for 1,006 cf (98% of inflow)
 Center-of-Mass det. time= 273.7 min (1,015.6 - 741.9)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	84 cf	7.28'W x 13.84'L x 2.72'H Field A 274 cf Overall - 64 cf Embedded = 210 cf x 40.0% Voids
#2A	7.25'	57 cf	Ferguson R-Tank XD 12 x 10 Inside #1 Inside= 19.7"W x 23.6"H => 2.91 sf x 1.97'L = 5.7 cf Outside= 19.7"W x 23.6"H => 3.23 sf x 1.97'L = 6.4 cf 10 Chambers in 2 Rows
		141 cf	Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.37'	6.0" Round Culvert L= 33.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.37' / 8.73' S= 0.0194 '/ Cc= 0.900 n= 0.013, Flow Area= 0.20 sf

Discarded OutFlow Max=0.0 cfs @ 1.42 hrs HW=7.03' (Free Discharge)
 1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.3 cfs @ 12.09 hrs HW=9.71' (Free Discharge)
 2=Culvert (Inlet Controls 0.3 cfs @ 1.99 fps)

Pond 5P: Inf Syst-3

Hydrograph



Summary for Pond 6P: Inf Syst-4

Inflow Area = 1,104 sf, 97.46% Impervious, Inflow Depth = 11.14" for 100-Year event
 Inflow = 0.3 cfs @ 12.08 hrs, Volume= 1,025 cf
 Outflow = 0.3 cfs @ 12.09 hrs, Volume= 1,005 cf, Atten= 1%, Lag= 0.5 min
 Discarded = 0.0 cfs @ 1.42 hrs, Volume= 161 cf
 Primary = 0.3 cfs @ 12.09 hrs, Volume= 845 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.71' @ 12.09 hrs Surf.Area= 101 sf Storage= 141 cf

Plug-Flow detention time= 285.9 min calculated for 1,005 cf (98% of inflow)
 Center-of-Mass det. time= 274.0 min (1,015.8 - 741.9)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	84 cf	7.28'W x 13.84'L x 2.72'H Field A 274 cf Overall - 64 cf Embedded = 210 cf x 40.0% Voids
#2A	7.25'	57 cf	Ferguson R-Tank XD 12 x 10 Inside #1 Inside= 19.7"W x 23.6"H => 2.91 sf x 1.97'L = 5.7 cf Outside= 19.7"W x 23.6"H => 3.23 sf x 1.97'L = 6.4 cf 10 Chambers in 2 Rows
		141 cf	Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.37'	6.0" Round Culvert L= 51.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.37' / 8.10' S= 0.0249 '/ Cc= 0.900 n= 0.013, Flow Area= 0.20 sf

Discarded OutFlow Max=0.0 cfs @ 1.42 hrs HW=7.03' (Free Discharge)
 1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.3 cfs @ 12.09 hrs HW=9.71' (Free Discharge)
 2=Culvert (Inlet Controls 0.3 cfs @ 1.99 fps)

Pond 6P: Inf Syst-4

Hydrograph



Summary for Pond 7P: Inf Syst-5

Inflow Area = 1,082 sf, 98.06% Impervious, Inflow Depth = 11.26" for 100-Year event
 Inflow = 0.3 cfs @ 12.08 hrs, Volume= 1,015 cf
 Outflow = 0.3 cfs @ 12.09 hrs, Volume= 1,014 cf, Atten= 1%, Lag= 0.5 min
 Discarded = 0.0 cfs @ 1.05 hrs, Volume= 161 cf
 Primary = 0.3 cfs @ 12.09 hrs, Volume= 853 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.34' @ 12.09 hrs Surf.Area= 101 sf Storage= 123 cf

Plug-Flow detention time= 271.3 min calculated for 1,014 cf (100% of inflow)
 Center-of-Mass det. time= 271.0 min (1,008.3 - 737.2)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	73 cf	7.28'W x 13.84'L x 2.39'H Field A 241 cf Overall - 58 cf Embedded = 182 cf x 40.0% Voids
#2A	7.25'	52 cf	Ferguson R-Tank XD 11 x 10 Inside #1 Inside= 19.7"W x 21.7"H => 2.66 sf x 1.97'L = 5.2 cf Outside= 19.7"W x 21.7"H => 2.96 sf x 1.97'L = 5.8 cf 10 Chambers in 2 Rows
		125 cf	Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.00'	6.0" Round Culvert L= 48.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.00' / 8.35' S= 0.0135 '/ Cc= 0.900 n= 0.013, Flow Area= 0.20 sf

Discarded OutFlow Max=0.0 cfs @ 1.05 hrs HW=7.03' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.3 cfs @ 12.09 hrs HW=9.34' (Free Discharge)
 ↳2=Culvert (Inlet Controls 0.3 cfs @ 1.98 fps)

Pond 7P: Inf Syst-5

Hydrograph



Summary for Pond 8P: Inf Syst-6

Inflow Area = 1,056 sf, 99.24% Impervious, Inflow Depth = 11.26" for 100-Year event
 Inflow = 0.3 cfs @ 12.08 hrs, Volume= 991 cf
 Outflow = 0.3 cfs @ 12.09 hrs, Volume= 990 cf, Atten= 0%, Lag= 0.5 min
 Discarded = 0.0 cfs @ 1.08 hrs, Volume= 161 cf
 Primary = 0.3 cfs @ 12.09 hrs, Volume= 828 cf
 Routed to Pond 1P : Inf Syst-1

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.35' @ 12.09 hrs Surf.Area= 101 sf Storage= 124 cf

Plug-Flow detention time= 277.9 min calculated for 990 cf (100% of inflow)
 Center-of-Mass det. time= 277.4 min (1,014.7 - 737.2)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	73 cf	7.28'W x 13.84'L x 2.39'H Field A 241 cf Overall - 58 cf Embedded = 182 cf x 40.0% Voids
#2A	7.25'	52 cf	Ferguson R-Tank XD 11 x 10 Inside #1 Inside= 19.7"W x 21.7"H => 2.66 sf x 1.97'L = 5.2 cf Outside= 19.7"W x 21.7"H => 2.96 sf x 1.97'L = 5.8 cf 10 Chambers in 2 Rows
		125 cf	Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.00'	8.0" Round Culvert L= 46.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.00' / 8.77' S= 0.0050 '/ S= 0.0050 '/ Cc= 0.900 n= 0.013, Flow Area= 0.35 sf

Discarded OutFlow Max=0.0 cfs @ 1.08 hrs HW=7.03' (Free Discharge)
 ↳1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.3 cfs @ 12.09 hrs HW=9.35' (Free Discharge)
 ↳2=Culvert (Barrel Controls 0.3 cfs @ 2.11 fps)

Pond 8P: Inf Syst-6

Hydrograph



Summary for Pond 9P: Inf Syst-7

Inflow Area = 24,131 sf, 72.87% Impervious, Inflow Depth = 10.41" for 100-Year event
 Inflow = 6.1 cfs @ 12.08 hrs, Volume= 20,942 cf
 Outflow = 3.4 cfs @ 12.20 hrs, Volume= 20,942 cf, Atten= 44%, Lag= 7.0 min
 Discarded = 0.0 cfs @ 3.41 hrs, Volume= 1,621 cf
 Primary = 3.4 cfs @ 12.20 hrs, Volume= 19,322 cf
 Routed to Link 1L : Towards Wetlands

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 8.86' @ 12.20 hrs Surf.Area= 2,422 sf Storage= 3,555 cf

Plug-Flow detention time= 43.5 min calculated for 20,940 cf (100% of inflow)
 Center-of-Mass det. time= 43.6 min (806.2 - 762.6)

Volume	Invert	Avail.Storage	Storage Description
#1	7.15'	3,645 cf	6.89'W x 14.06'L x 1.75'H StormTrap ST-1 Units (Irregular Shape) x 25 4,238 cf Overall x 86.0% Voids


Device	Routing	Invert	Outlet Devices
#1	Discarded	7.15'	0.270 in/hr Exfiltration over Surface area
#2	Primary	7.15'	12.0" Round Culvert L= 4.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 7.15' / 7.13' S= 0.0050 '/ Cc= 0.900 n= 0.013, Flow Area= 0.79 sf
#3	Device 2	7.35'	22.0" W x 4.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

Discarded OutFlow Max=0.0 cfs @ 3.41 hrs HW=7.17' (Free Discharge)
 1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=3.4 cfs @ 12.20 hrs HW=8.86' (Free Discharge)
 2=Culvert (Passes 3.4 cfs of 4.2 cfs potential flow)
 3=Orifice/Grate (Orifice Controls 3.4 cfs @ 5.57 fps)

Pond 9P: Inf Syst-7

Hydrograph




Summary for Link 1L: Towards Wetlands

Inflow Area = 152,843 sf, 50.79% Impervious, Inflow Depth = 8.30" for 100-Year event
 Inflow = 21.4 cfs @ 12.19 hrs, Volume= 105,660 cf
 Primary = 21.4 cfs @ 12.19 hrs, Volume= 105,660 cf, Atten= 0%, Lag= 0.0 min
 Routed to Link 100L : Total Flows

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link 1L: Towards Wetlands

Hydrograph




Summary for Link 2L: Towards Street

Inflow Area = 5,843 sf, 18.07% Impervious, Inflow Depth = 8.69" for 100-Year event
 Inflow = 1.3 cfs @ 12.09 hrs, Volume= 4,233 cf
 Primary = 1.3 cfs @ 12.09 hrs, Volume= 4,233 cf, Atten= 0%, Lag= 0.0 min
 Routed to Link 100L : Total Flows

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link 2L: Towards Street

Hydrograph




Summary for Link 100L: Total Flows

Inflow Area = 158,686 sf, 49.59% Impervious, Inflow Depth = 8.31" for 100-Year event
 Inflow = 22.3 cfs @ 12.18 hrs, Volume= 109,893 cf
 Primary = 22.3 cfs @ 12.18 hrs, Volume= 109,893 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link 100L: Total Flows

Hydrograph



SECTION 6.0

ADDITIONAL DRAINAGE CALCULATIONS

6.01 TSS REMOVAL CALCULATIONS

TSS Removal Calculation Worksheet

Location: Thorndike Place, Arlington, MA

Project: 23407.02



Prepared By: E. Derrig

Date: 12/09/2024

AREA 1 - CB-1
Total Impervious Area, Acres= 0.377

A	B	C	D	E
BMP	TSS Removal Rate	Starting TSS Load*	Amount Removed (BxC)	Remaining Load (C-D)
Deep Sump and Hooded Catchbasins	0.25	1.00	0.25	0.75
Hydrodynamic Separator	0.7	0.75	0.53	0.23
Infiltration Basin	0.8	0.23	0.18	0.05

TSS Removal = 0.96

AREA 2A - TD-1A
Total Impervious Area, Acres= 0.027

A	B	C	D	E
BMP	TSS Removal Rate	Starting TSS Load*	Amount Removed (BxC)	Remaining Load (C-D)
Hydrodynamic Separator	0.7	1.00	0.70	0.30
Infiltration Basin	0.8	0.30	0.24	0.06

TSS Removal = 0.94

AREA 2B - TD-1B
Total Impervious Area, Acres= 0.044

A	B	C	D	E
BMP	TSS Removal Rate	Starting TSS Load*	Amount Removed (BxC)	Remaining Load (C-D)
Hydrodynamic Separator	0.7	1.00	0.70	0.30

TSS Removal = 0.70

AREA 3 - TD-2-6**Total Impervious Area, Acres= 0.122**

A	B	C	D	E
BMP	TSS Removal Rate	Starting TSS Load*	Amount Removed (BxC)	Remaining Load (C-D)
Infiltration Basin	0.8	1.00	0.80	0.20

TSS Removal = **AREA 4 - Bypass to Street****Total Impervious Area, Acres= 0.024**

A	B	C	D	E
BMP	TSS Removal Rate	Starting TSS Load*	Amount Removed (BxC)	Remaining Load (C-D)
		1.00		

TSS Removal = **AREA 5 - East Driveway****Total Impervious Area, Acres= 0.148**

A	B	C	D	E
BMP	TSS Removal Rate	Starting TSS Load*	Amount Removed (BxC)	Remaining Load (C-D)
Rain Garden	0.8	1.00	0.80	0.20

TSS Removal = **Weighted Annual Average TSS Removal Rate**

[TSS Removal-1 (Area-1) + TSS Removal-2 (Area-2)+ ...] / [Area-1 + Area-2 + ...] = 0.85

Project Site TSS Removal =

6.02 GROUNDWATER RECHARGE VOLUME CALCULATIONS

Required Recharge Volume

$$Rv = F \times \text{Impervious Area}$$

Where:

Rv = Recharge Volume

F=Target Depth Factor associated with each Hydrologic Soil Group

(F=0.25-inch for Soil Type C)

Impervious Area = Proposed Pavement and Rooftop area on-site

$$Rv = \left(\frac{0.25in}{12} \right) (78,689sft) =$$

$$Rv = 1,640 \text{ cf (required recharge volume)}$$

As not all impervious surfaces are directed to an infiltration BMP, an adjusted Required Volume must be provided. The adjusted Required Volume (Rva) is calculated as:

$$Rva = \frac{\text{Total Imp.Area}}{\text{Imp.Area to BMP}} (Rv) =$$

$$Rva = \left(\frac{78,689sft}{75,617sft} \right) (1,640cf) =$$

$$Rva = 1,707 \text{ cf}$$

Storage Provided

- Underground Infiltration System 1 = 7,826 cubic feet provided
- Underground Infiltration System 2 = 122 cubic feet provided
- Underground Infiltration System 3/4 = 254 cubic feet provided (systems are the same)
- Underground Infiltration System 5/6 = 218 cubic feet provided (systems are the same)
- Underground Infiltration System 7 = 417 cubic feet provided
- **Underground Infiltration Systems Total = 8,837 cubic feet provided > 1,707 cf required**
Rain garden not required to meet volume, but provides additional infiltration above and beyond that required.
Refer to the HydroCAD storage table provided for more information.

Stage-Area-Storage for Pond 1P: Inf Syst-1

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
8.00	7,459	0	8.52	7,459	3,336
8.01	7,459	64	8.53	7,459	3,400
8.02	7,459	128	8.54	7,459	3,464
8.03	7,459	192	8.55	7,459	3,528
8.04	7,459	257	8.56	7,459	3,592
8.05	7,459	321	8.57	7,459	3,657
8.06	7,459	385	8.58	7,459	3,721
8.07	7,459	449	8.59	7,459	3,785
8.08	7,459	513	8.60	7,459	3,849
8.09	7,459	577	8.61	7,459	3,913
8.10	7,459	641	8.62	7,459	3,977
8.11	7,459	706	8.63	7,459	4,041
8.12	7,459	770	8.64	7,459	4,106
8.13	7,459	834	8.65	7,459	4,170
8.14	7,459	898	8.66	7,459	4,234
8.15	7,459	962	8.67	7,459	4,298
8.16	7,459	1,026	8.68	7,459	4,362
8.17	7,459	1,091	8.69	7,459	4,426
8.18	7,459	1,155	8.70	7,459	4,490
8.19	7,459	1,219	8.71	7,459	4,555
8.20	7,459	1,283	8.72	7,459	4,619
8.21	7,459	1,347	8.73	7,459	4,683
8.22	7,459	1,411	8.74	7,459	4,747
8.23	7,459	1,475	8.75	7,459	4,811
8.24	7,459	1,540	8.76	7,459	4,875
8.25	7,459	1,604	8.77	7,459	4,940
8.26	7,459	1,668	8.78	7,459	5,004
8.27	7,459	1,732	8.79	7,459	5,068
8.28	7,459	1,796	8.80	7,459	5,132
8.29	7,459	1,860	8.81	7,459	5,196
8.30	7,459	1,924	8.82	7,459	5,260
8.31	7,459	1,989	8.83	7,459	5,324
8.32	7,459	2,053	8.84	7,459	5,389
8.33	7,459	2,117	8.85	7,459	5,453
8.34	7,459	2,181	8.86	7,459	5,517
8.35	7,459	2,245	8.87	7,459	5,581
8.36	7,459	2,309	8.88	7,459	5,645
8.37	7,459	2,374	8.89	7,459	5,709
8.38	7,459	2,438	8.90	7,459	5,773
8.39	7,459	2,502	8.91	7,459	5,838
8.40	7,459	2,566	8.92	7,459	5,902
8.41	7,459	2,630	8.93	7,459	5,966
8.42	7,459	2,694	8.94	7,459	6,030
8.43	7,459	2,758	8.95	7,459	6,094
8.44	7,459	2,823	8.96	7,459	6,158
8.45	7,459	2,887	8.97	7,459	6,223
8.46	7,459	2,951	8.98	7,459	6,287
8.47	7,459	3,015	8.99	7,459	6,351
8.48	7,459	3,079	9.00	7,459	6,415
8.49	7,459	3,143	9.01	7,459	6,479
8.50	7,459	3,207	9.02	7,459	6,543
8.51	7,459	3,272	9.03	7,459	6,607

Stage-Area-Storage for Pond 1P: Inf Syst-1 (continued)

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
9.04	7,459	6,672	9.56	7,459	10,007
9.05	7,459	6,736	9.57	7,459	10,071
9.06	7,459	6,800	9.58	7,459	10,136
9.07	7,459	6,864	9.59	7,459	10,200
9.08	7,459	6,928	9.60	7,459	10,264
9.09	7,459	6,992	9.61	7,459	10,328
9.10	7,459	7,056	9.62	7,459	10,392
9.11	7,459	7,121	9.63	7,459	10,456
9.12	7,459	7,185	9.64	7,459	10,521
9.13	7,459	7,249	9.65	7,459	10,585
9.14	7,459	7,313	9.66	7,459	10,649
9.15	7,459	7,377	9.67	7,459	10,713
9.16	7,459	7,441	9.68	7,459	10,777
9.17	7,459	7,505	9.69	7,459	10,841
9.18	7,459	7,570	9.70	7,459	10,905
9.19	7,459	7,634	9.71	7,459	10,970
9.20	7,459	7,698	9.72	7,459	11,034
9.21	7,459	7,762	9.73	7,459	11,098
9.22	7,459	7,826	9.74	7,459	11,162
9.23	7,459	7,890	9.75	7,459	11,226
9.24	7,459	7,955	9.76	7,459	11,290
9.25	7,459	8,019	9.77	7,459	11,354
9.26	7,459	8,083	9.78	7,459	11,419
9.27	7,459	8,147	9.79	7,459	11,483
9.28	7,459	8,211	9.80	7,459	11,547
9.29	7,459	8,275	9.81	7,459	11,611
9.30	7,459	8,339	9.82	7,459	11,675
9.31	7,459	8,404	9.83	7,459	11,739
9.32	7,459	8,468	9.84	7,459	11,804
9.33	7,459	8,532	9.85	7,459	11,868
9.34	7,459	8,596	9.86	7,459	11,932
9.35	7,459	8,660	9.87	7,459	11,996
9.36	7,459	8,724	9.88	7,459	12,060
9.37	7,459	8,788	9.89	7,459	12,124
9.38	7,459	8,853	9.90	7,459	12,188
9.39	7,459	8,917	9.91	7,459	12,253
9.40	7,459	8,981	9.92	7,459	12,317
9.41	7,459	9,045	9.93	7,459	12,381
9.42	7,459	9,109	9.94	7,459	12,445
9.43	7,459	9,173	9.95	7,459	12,509
9.44	7,459	9,238	9.96	7,459	12,573
9.45	7,459	9,302	9.97	7,459	12,637
9.46	7,459	9,366	9.98	7,459	12,702
9.47	7,459	9,430	9.99	7,459	12,766
9.48	7,459	9,494	10.00	7,459	12,830
9.49	7,459	9,558	10.01	7,459	12,894
9.50	7,459	9,622	10.02	7,459	12,958
9.51	7,459	9,687	10.03	7,459	13,022
9.52	7,459	9,751	10.04	7,459	13,087
9.53	7,459	9,815	10.05	7,459	13,151
9.54	7,459	9,879	10.06	7,459	13,215
9.55	7,459	9,943	10.07	7,459	13,279

2340702-PR-2024-12-10

Prepared by BSC Group

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 100-Year Rainfall=11.50"

Printed 12/10/2024

Stage-Area-Storage for Pond 4P: Inf Syst-2 (continued)

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
9.08	101	113	9.60	101	137
9.09	101	114	9.61	101	137
9.10	101	115	9.62	101	137
9.11	101	115	9.63	101	138
9.12	101	116	9.64	101	138
9.13	101	116	9.65	101	139
9.14	101	117	9.66	101	139
9.15	101	117	9.67	101	139
9.16	101	118	9.68	101	140
9.17	101	118	9.69	101	140
9.18	101	119	9.70	101	141
9.19	101	120	9.71	101	141
9.20	101	120	9.72	101	141
9.21	101	121	9.73	101	141
9.22	101	121			
9.23	101	122			
9.24	101	122			
9.25	101	122			
9.26	101	123			
9.27	101	123			
9.28	101	124			
9.29	101	124			
9.30	101	125			
9.31	101	125			
9.32	101	125			
9.33	101	126			
9.34	101	126			
9.35	101	127			
9.36	101	127			
9.37	101	127			
9.38	101	128			
9.39	101	128			
9.40	101	129			
9.41	101	129			
9.42	101	129			
9.43	101	130			
9.44	101	130			
9.45	101	131			
9.46	101	131			
9.47	101	131			
9.48	101	132			
9.49	101	132			
9.50	101	133			
9.51	101	133			
9.52	101	133			
9.53	101	134			
9.54	101	134			
9.55	101	135			
9.56	101	135			
9.57	101	135			
9.58	101	136			
9.59	101	136			

2340702-PR-2024-12-10

Type III 24-hr 100-Year Rainfall=11.50"

Prepared by BSC Group

Printed 12/10/2024

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Stage-Area-Storage for Pond 5P: Inf Syst-3 (continued)

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
9.08	101	113	9.60	101	137
9.09	101	114	9.61	101	137
9.10	101	115	9.62	101	137
9.11	101	115	9.63	101	138
9.12	101	116	9.64	101	138
9.13	101	116	9.65	101	139
9.14	101	117	9.66	101	139
9.15	101	117	9.67	101	139
9.16	101	118	9.68	101	140
9.17	101	118	9.69	101	140
9.18	101	119	9.70	101	141
9.19	101	120	9.71	101	141
9.20	101	120	9.72	101	141
9.21	101	121	9.73	101	141
9.22	101	121	9.74	101	141
9.23	101	122	9.75	101	141
9.24	101	122	9.76	101	141
9.25	101	122	9.77	101	141
9.26	101	123	9.78	101	141
9.27	101	123	9.79	101	141
9.28	101	124	9.80	101	141
9.29	101	124	9.81	101	141
9.30	101	125	9.82	101	141
9.31	101	125	9.83	101	141
9.32	101	125	9.84	101	141
9.33	101	126	9.85	101	141
9.34	101	126	9.86	101	141
9.35	101	127	9.87	101	141
9.36	101	127			
9.37	101	127			
9.38	101	128			
9.39	101	128			
9.40	101	129			
9.41	101	129			
9.42	101	129			
9.43	101	130			
9.44	101	130			
9.45	101	131			
9.46	101	131			
9.47	101	131			
9.48	101	132			
9.49	101	132			
9.50	101	133			
9.51	101	133			
9.52	101	133			
9.53	101	134			
9.54	101	134			
9.55	101	135			
9.56	101	135			
9.57	101	135			
9.58	101	136			
9.59	101	136			

2340702-PR-2024-12-10

Type III 24-hr 100-Year Rainfall=11.50"

Prepared by BSC Group

Printed 12/10/2024

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Stage-Area-Storage for Pond 7P: Inf Syst-5

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
7.00	101	0
7.05	101	2
7.10	101	4
7.15	101	6
7.20	101	8
7.25	101	10
7.30	101	13
7.35	101	16
7.40	101	19
7.45	101	21
7.50	101	24
7.55	101	27
7.60	101	30
7.65	101	33
7.70	101	35
7.75	101	38
7.80	101	41
7.85	101	44
7.90	101	47
7.95	101	50
8.00	101	52
8.05	101	55
8.10	101	58
8.15	101	61
8.20	101	64
8.25	101	67
8.30	101	69
8.35	101	72
8.40	101	75
8.45	101	78
8.50	101	81
8.55	101	83
8.60	101	86
8.65	101	89
8.70	101	92
8.75	101	95
8.80	101	98
8.85	101	100
8.90	101	103
8.95	101	106
9.00	101	109
9.05	101	112
9.10	101	114
9.15	101	116
9.20	101	118
9.25	101	120
9.30	101	122
9.35	101	124
9.40	101	125
9.45	101	125
9.50	101	125

2340702-PR-2024-12-10

Type III 24-hr 100-Year Rainfall=11.50"

Prepared by BSC Group

Printed 12/10/2024

HydroCAD® 10.20-5c s/n 00904 © 2023 HydroCAD Software Solutions LLC

Stage-Area-Storage for Pond 9P: Inf Syst-7

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
7.15	2,422	0	8.19	2,422	2,166
7.17	2,422	42	8.21	2,422	2,208
7.19	2,422	83	8.23	2,422	2,249
7.21	2,422	125	8.25	2,422	2,291
7.23	2,422	167	8.27	2,422	2,333
7.25	2,422	208	8.29	2,422	2,374
7.27	2,422	250	8.31	2,422	2,416
7.29	2,422	292	8.33	2,422	2,458
7.31	2,422	333	8.35	2,422	2,499
7.33	2,422	375	8.37	2,422	2,541
7.35	2,422	417	8.39	2,422	2,583
7.37	2,422	458	8.41	2,422	2,624
7.39	2,422	500	8.43	2,422	2,666
7.41	2,422	542	8.45	2,422	2,708
7.43	2,422	583	8.47	2,422	2,749
7.45	2,422	625	8.49	2,422	2,791
7.47	2,422	666	8.51	2,422	2,833
7.49	2,422	708	8.53	2,422	2,874
7.51	2,422	750	8.55	2,422	2,916
7.53	2,422	791	8.57	2,422	2,958
7.55	2,422	833	8.59	2,422	2,999
7.57	2,422	875	8.61	2,422	3,041
7.59	2,422	916	8.63	2,422	3,083
7.61	2,422	958	8.65	2,422	3,124
7.63	2,422	1,000	8.67	2,422	3,166
7.65	2,422	1,041	8.69	2,422	3,207
7.67	2,422	1,083	8.71	2,422	3,249
7.69	2,422	1,125	8.73	2,422	3,291
7.71	2,422	1,166	8.75	2,422	3,332
7.73	2,422	1,208	8.77	2,422	3,374
7.75	2,422	1,250	8.79	2,422	3,416
7.77	2,422	1,291	8.81	2,422	3,457
7.79	2,422	1,333	8.83	2,422	3,499
7.81	2,422	1,375	8.85	2,422	3,541
7.83	2,422	1,416	8.87	2,422	3,582
7.85	2,422	1,458	8.89	2,422	3,624
7.87	2,422	1,500			
7.89	2,422	1,541			
7.91	2,422	1,583			
7.93	2,422	1,625			
7.95	2,422	1,666			
7.97	2,422	1,708			
7.99	2,422	1,750			
8.01	2,422	1,791			
8.03	2,422	1,833			
8.05	2,422	1,875			
8.07	2,422	1,916			
8.09	2,422	1,958			
8.11	2,422	1,999			
8.13	2,422	2,041			
8.15	2,422	2,083			
8.17	2,422	2,124			

Drawdown Within 72-Hours

Pond 1P

Rv = Recharge Volume, 7,826 cu.ft. (see above)

K = Saturated Hydraulic Conductivity, 0.27 in/hr (from Rawls Table) = 0.0225 ft/hr

Bottom Area = Area of Infiltration System Bottom, 7,459 sq.ft. (see HydroCAD)

$$Time = \frac{Rv}{(K)(Bottom\ Area)}$$

$$Time = \left(\frac{7,826\ cu.\ ft.}{(0.0225\ ft/hr)(7,459\ sq.\ ft.)} \right) =$$

$$Time = 46.6\ hours$$

- 46.6 hours < 72 hours

Pond 3P (Rain Garden)

Rv = Recharge Volume, 190 cu.ft. (see HydroCAD)

K = Saturated Hydraulic Conductivity, 0.27 in/hr (from Rawls Table) = 0.0225 ft/hr

Bottom Area = Area of Infiltration System Bottom, 125 sq.ft. (see HydroCAD)

$$Time = \frac{Rv}{(K)(Bottom\ Area)}$$

$$Time = \left(\frac{190\ cu.\ ft.}{(0.0225\ ft/hr)(125\ sq.\ ft.)} \right) =$$

$$Time = 67.6\ hours$$

- 67.6 hours < 72 hours

Pond 4P-6P (Townhouse Trench Drain Infiltration Systems)

Same bottom area, worst case provided

Rv = Recharge Volume, 127 cu.ft. (see above)

K = Saturated Hydraulic Conductivity, 0.27 in/hr (from Rawls Table) = 0.0225 ft/hr

Bottom Area = Area of Infiltration System Bottom, 100.75 sq.ft.

$$Time = \frac{Rv}{(K)(Bottom\ Area)}$$

$$Time = \left(\frac{127\ cu.\ ft.}{(0.0225\ ft/hr)(100.75\ sq.\ ft.)} \right) =$$

Time = 56.0 hours

- 56.0 hours < 72 hours

Pond 7P

Rv = Recharge Volume, 417 cu.ft (see HydroCAD)

K = Saturated Hydraulic Conductivity, 0.27 in/hr (from Rawls Table) = 0.0225 ft/hr

Bottom Area = Area of Infiltration System Bottom, 2,421.8 sq.ft.

$$Time = \frac{Rv}{(K)(Bottom\ Area)}$$

$$Time = \left(\frac{417\ cu.\ ft.}{(0.0225\ ft/hr)(2,421\ sq.\ ft.)} \right) =$$

Time = 7.7 hours

- 7.7 hours < 72 hours

6.03 WATER QUALITY VOLUME CALCULATIONS

Water Quality Volume Calculation

$$V_{WQ} = (D_{WQ}/12 \text{ inches/foot}) * (A_{IMP} \text{ square feet})$$

V_{WQ} = Required Water Quality Volume (in cubic feet)

D_{WQ} = Water Quality Depth: **0.5-inch**

A_{IMP} = Total Impervious Area (in acres) used for driveways, parking, etc.

Underground Infiltration Systems and Bio-Retention Areas

$$A_{IMP} = 32,590 \text{ sq.ft.}$$

$$V_{WQ} = (0.5 \text{ inches}/12 \text{ inches/foot}) * (32,590 \text{ sq.ft.})$$

$V_{WQ} = 1,358$ cubic feet (required volume)

Provided volume = 8,783 cubic feet in Underground Infiltration System (refer to the HydroCAD storage tables provided in groundwater recharge section)

6.04 RIP-RAP OUTLET PROTECTION SIZING

OUTLET PROTECTION SIZING



Project No. 23407.02
 Subject Outlet Protection Sizing Calcs
 Location Arlington, MA

Calc By EAD
 Date 12/16/2024
 Checked by DRR
 Date 12/16/2024

FES-1

Q=Design Discharge, (ft³/s) = 11.1 cfs
 D=Culvert Diameter, (ft) = 1.50 ft
 TW=Tailwater Depth, (ft) = 0.6 ft, (0.4xD for unknow tailwater, or enter known tailwater)
 (Tailwater depth is to be limited to between 0.4D and 1.0D)

Riprap Rock Sizing

$$D_{50} = 0.2D \left[\frac{Q}{\sqrt{gD^{2.5}}} \right]^{4/3} \left[\frac{D}{TW} \right]$$

g=32.2 fps
 D₅₀ = median rock size, ft

$$D_{50} = 0.28 \left| \frac{11.10}{15.64} \right|^{(4/3)} \left| \frac{1.50}{0.60} \right| = 0.44 \text{ ft}$$

$$= 5.32 \text{ inches}$$

Table 1 : Riprap Classes and Apron Dimensions

Class	D ₅₀ (in)	Apron Length	Apron Depth
1	5	4D	3.5D ₅₀
2	6	4D	3.5D₅₀
3	10	5D	3.3D ₅₀
4	14	6D	2.2D ₅₀
5	20	7D	2.0D ₅₀
6	22	8D	2.0D ₅₀

Use Class 2

Apron Dimensions

Length, L=5D = **8 ft**
 Depth=3.3D₅₀ = **19.80 Inches**
 Width=3D+(2/3)L = **9.50 ft** (at apron end)

Riprap Rock Sizing Gradation

Given Size	Size of Stone, inches
100	9 to 12
85	8 to 11
50	6 to 9
15	3 to 8

6.05 GROUNDWATER MOUNDING ANALYSIS

Infiltration Systems 2-6

Input Values

1.5979
0.080
5.40
6.920
3.640
1.000
16.000

R
Sy
K
x
y
t
hi(0)

Recharge (infiltration) rate (feet/day)
Specific yield, *Sy* (dimensionless, between 0 and 1)
Horizontal hydraulic conductivity, *Kh* (feet/day)*
1/2 length of basin (*x* direction, in feet)
1/2 width of basin (*y* direction, in feet)
duration of infiltration period (days)
initial thickness of saturated zone (feet)

inch/hour	feet/day
0.67	1.33
2.00	4.00
hours	days
36	1.50

In the repor
(USGS SIR 2
(ft/d) is assu
hydraulic co

16.756
0.756

h(max)
Δh(max)

maximum thickness of saturated zone (beneath center of basin at end of infiltration period)
maximum groundwater mounding (beneath center of basin at end of infiltration period)

Ground-
water
Mounding, in
feet


Distance from
center of basin
in *x* direction, in
feet

0.756	0
0.291	20
0.120	40
0.078	50
0.051	60
0.033	70
0.022	80
0.015	90
0.012	100
0.008	120

ESHGW=4.0
Bot System=7.0
Separation=3.0
Mound=0.756 < 3.0



Re-Calculate Now



Disclaimer

This spreadsheet solving the Hantush (1967) equation for ground-water mounding beneath an infiltration basin is made available to the general public as a convenience for those wishing to replicate values documented in the USGS Scientific Investigations Report 2010-5102 "Groundwater mounding beneath hypothetical stormwater infiltration basins" or to calculate values based on user-specified site conditions. Any changes made to the spreadsheet (other than values identified as user-specified) after transmission from the USGS could have unintended, undesirable consequences. These consequences could include, but may not be limited to: erroneous output, numerical instabilities, and violations of underlying assumptions that are inherent in results presented in the accompanying USGS published report. The USGS assumes no responsibility for the consequences of any changes made to the spreadsheet. If changes are made to the spreadsheet, the user is responsible for documenting the changes and justifying the results and conclusions.

Recharge/Infiltration Rate (ft/day) = [Required Recharge Volume (cft)/Bottom Recharge System (sft)]/Duration (day)

100 year recharge volume 161 cft

Bottom Recharge System 100.755 sft

Duration 1 day

Recharge/Infiltration Rate 1.5979 ft/day

Horizontal Hydraulic Conductivity (ft/day) = [Rawls Rate (in/hr) * (1ft/12in) * (24hr/1day)] * 10

Rawls Rate (silt loam) 0.27 in/hr

Horizontal Hydraulic Conductivity 5.40 ft/day

NOTE: All driveway infiltration systems are the same size and have the same discarded volume in the 100-year event

Summary for Pond 8P: Inf Syst-6

Inflow Area = 1,056 sf, 99.24% Impervious, Inflow Depth = 11.26" for 100-Year event
 Inflow = 0.3 cfs @ 12.08 hrs, Volume= 991 cf
 Outflow = 0.3 cfs @ 12.09 hrs, Volume= 990 cf, Atten= 0%, Lag= 0.5 min
 Discarded = 0.0 cfs @ 1.08 hrs, Volume= 161 cf
 Primary = 0.3 cfs @ 12.09 hrs, Volume= 828 cf
 Routed to Pond 1P : Underground Infiltration System

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 9.35' @ 12.09 hrs Surf.Area= 101 sf Storage= 124 cf

Plug-Flow detention time= 277.9 min calculated for 990 cf (100% of inflow)
 Center-of-Mass det. time= 277.4 min (1,014.7 - 737.2)

Volume	Invert	Avail.Storage	Storage Description
#1A	7.00'	73 cf	7.28'W x 13.84'L x 2.39'H Field A 241 cf Overall - 58 cf Embedded = 182 cf x 40.0% Voids
#2A	7.25'	52 cf	Ferguson R-Tank XD 11 x 10 Inside #1 Inside= 19.7"W x 21.7"H => 2.66 sf x 1.97'L = 5.2 cf Outside= 19.7"W x 21.7"H => 2.96 sf x 1.97'L = 5.8 cf 10 Chambers in 2 Rows
		125 cf	Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Discarded	7.00'	0.270 in/hr Exfiltration over Surface area
#2	Primary	9.00'	8.0" Round Culvert L= 46.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 9.00' / 8.77' S= 0.0050 '/' Cc= 0.900 n= 0.013, Flow Area= 0.35 sf

Discarded OutFlow Max=0.0 cfs @ 1.08 hrs HW=7.03' (Free Discharge)
 ↑1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=0.3 cfs @ 12.09 hrs HW=9.35' (Free Discharge)
 ↑2=Culvert (Barrel Controls 0.3 cfs @ 2.11 fps)

Infiltration System 7

Input Values

0.6631
0.080
5.40
17.225
35.150
1.000
16.000

R
Sy
K
x
y
t
hi(0)

Recharge (infiltration) rate (feet/day)
Specific yield, Sy (dimensionless, between 0 and 1)
Horizontal hydraulic conductivity, Kh (feet/day)*
1/2 length of basin (x direction, in feet)
1/2 width of basin (y direction, in feet)
duration of infiltration period (days)
initial thickness of saturated zone (feet)

inch/hour	feet/day
0.67	1.33
2.00	4.00
hours	days
36	1.50

In the repor
(USGS SIR 20
(ft/d) is assu
hydraulic co

18.946
2.946

h(max)
Δh(max)

maximum thickness of saturated zone (beneath center of basin at end of infiltration period)
maximum groundwater mounding (beneath center of basin at end of infiltration period)

Ground-
water
Mounding, in
feet


Distance from
center of basin
in x direction, in
feet

2.946	0
2.091	20
0.985	40
0.647	50
0.413	60
0.256	70
0.154	80
0.091	90
0.052	100
0.017	120

ESHGW=4.0
Bottom System=7.15
Separation=3.15
Mound=2.946 < 3.15



Re-Calculate Now



Disclaimer

This spreadsheet solving the Hantush (1967) equation for ground-water mounding beneath an infiltration basin is made available to the general public as a convenience for those wishing to replicate values documented in the USGS Scientific Investigations Report 2010-5102 "Groundwater mounding beneath hypothetical stormwater infiltration basins" or to calculate values based on user-specified site conditions. Any changes made to the spreadsheet (other than values identified as user-specified) after transmission from the USGS could have unintended, undesirable consequences. These consequences could include, but may not be limited to: erroneous output, numerical instabilities, and violations of underlying assumptions that are inherent in results presented in the accompanying USGS published report. The USGS assumes no responsibility for the consequences of any changes made to the spreadsheet. If changes are made to the spreadsheet, the user is responsible for documenting the changes and justifying the results and conclusions.

Recharge/Infiltration Rate (ft/day) = [Required Recharge Volume (cft)/Bottom Recharge System (sft)]/Duration (day)

100 year recharge volume 1,606 cft

Bottom Recharge System 2,421.835 sft

Duration 1 day

Recharge/Infiltration Rate 0.6631 ft/day

Horizontal Hydraulic Conductivity (ft/day) = [Rawls Rate (in/hr) * (1ft/12in) * (24hr/1day)] * 10

Rawls Rate (silt loam) 0.27 in/hr

Horizontal Hydraulic Conductivity 5.40 ft/day

Summary for Pond 9P: Inf Syst-7

Inflow Area = 24,698 sf, 71.15% Impervious, Inflow Depth = 10.36" for 100-Year event
 Inflow = 6.3 cfs @ 12.08 hrs, Volume= 21,328 cf
 Outflow = 3.5 cfs @ 12.20 hrs, Volume= 21,328 cf, Atten= 45%, Lag= 7.1 min
Discarded = 0.0 cfs @ 3.69 hrs, Volume= 1,606 cf
 Primary = 3.5 cfs @ 12.20 hrs, Volume= 19,722 cf
 Routed to Link 1L : Towards Wetlands

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 8.89' @ 12.20 hrs Surf.Area= 2,422 sf Storage= 3,633 cf

Plug-Flow detention time= 43.0 min calculated for 21,325 cf (100% of inflow)
 Center-of-Mass det. time= 43.1 min (806.8 - 763.8)

Volume	Invert	Avail.Storage	Storage Description
#1	7.15'	5,207 cf	6.89'W x 14.06'L x 2.50'H StormTrap ST-1 Units (Irregular Shape) 25 6,055 cf Overall x 86.0% Voids

Device	Routing	Invert	Outlet Devices
#1	Discarded	7.15'	0.270 in/hr Exfiltration over Surface area
#2	Primary	7.15'	12.0" Round Culvert L= 4.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 7.15' / 7.13' S= 0.0050 '/ Cc= 0.900 n= 0.013, Flow Area= 0.79 sf
#3	Device 2	7.35'	22.0" W x 4.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

Discarded OutFlow Max=0.0 cfs @ 3.69 hrs HW=7.18' (Free Discharge)
 ↑1=Exfiltration (Exfiltration Controls 0.0 cfs)

Primary OutFlow Max=3.5 cfs @ 12.20 hrs HW=8.89' (Free Discharge)
 ↑2=Culvert (Passes 3.5 cfs of 4.2 cfs potential flow)
 ↑3=Orifice/Grate (Orifice Controls 3.5 cfs @ 5.65 fps)

Specific Yield-- Compilation of Specific Yields for Various Materials

GEOLOGICAL SURVEY WATER SUPPLY PAPER 1662-D

*Prepared in cooperation with the
California Department of
Water Resources*



TABLE 29.—*Compilation of specific yields for various materials*
 [All values rounded off to nearest whole percentage]

Material	Valley fill, California (Eckis, 1934)	Mokelumne area, California (Piper and others, 1939)	Santa Ynez River basin, California (Upson and Thomasson, 1951)	Sacramento Valley, Calif. (Poland and others, 1949)	Smith River plain, California (Back, 1957)	Ventura County, Calif. (Calif. Water Resources Board, 1956)	Santa Margarita Valley, Calif. (Calif. Dept. Public Works, 1956)	Tia Juana Basin, Calif. (Calif. Water Rights Board, 1957)	San Luis Obispo County, Calif. (Calif. Water Resources Board, 1958)	San Joaquin Valley, Calif. (Davis and others, 1959)	Eureka area, California (Evenson, 1959)	Santa Ynez Basin, Calif. (Wilson, 1959)	Rechna Doab, Pakistan (Kazmi, 1961)	Napa-Sonoma Valleys, Calif. (Kunkel and Upson, 1960)	Humboldt River Valley, Nev. (Cohen, 1963)	Unconsolidated alluvium (Preuss and Todd, 1963)	Little Bighorn River valley, Montana (Moulder and Others, 1960)	Average specific yield
Clay.....	1	4	2	3	1	0	1	1	3	3	3	5	3	3	1	4	17	2
Silt.....	10	4	12	3	5	3	10	10	5	5	10	5	5	5	19	4	17	8
Sandy clay.....	10	4	12	3	5	5	5	5	5	5	10	5	5	10	26	23	32	17
Fine sand.....	21	26	12	10	10	25	28	25	25	10	20	20	27	20	28	23	32	21
Medium sand.....	31	26	30	20	15	25	28	30	25	25	20	30	28	20	28	28	32	26
Coarse sand.....	31	35	35	20	25	25	28	32	25	25	20	30	23	20	27	28	32	27
Gravelly sand.....	31	35	35	20	25	21	22	28	21	25	20	23	23	20	22	22	32	25
Fine gravel.....	27	35	35	25	25	21	22	26	21	25	25	25	26	25	19	17	25	25
Medium gravel.....	21	25	25	25	25	21	22	23	21	25	25	25	26	25	26	13	25	23
Coarse gravel.....	14	25	25	25	25	21	22	18	21	25	25	25	26	25	12	12	25	22

APPENDIX G

MCPHAIL GEOTECHNICAL MEMORANDUM



Memorandum

Date: December 9, 2024

Recipient: Arlington Land Manager LLC
c/o Dinosaur Capital Partners LLC – Scott Oran

Sender: Scott S. Smith, P.E.

Project: Thorndike Place; Arlington, MA

Project No: 7679.2.01

Subject: Subsurface Conditions at Proposed Stormwater Infiltration System

Background

This memorandum documents the subsurface soil and groundwater conditions encountered in the borings performed at the Thorndike Place project site during November 2024. The purpose of the borings was to provide supplemental information to the project civil engineer related to stormwater infiltration system design, including the saturated soil thickness within the footprint of the proposed stormwater infiltration system.

The 5.8-acre subject property is bounded by Dorothy Road and residences to the north, residences and undeveloped conservation land to the east, undeveloped conservation land to the south and the Concord Turnpike (Route 2) to the west. The subject property is currently unoccupied, undeveloped wooded land. Refer to the Project Location Plan, **Figure 1**, for the general site locus.

Based on the information provided to us, the proposed development is planned to consist of six (6), 3-story townhouses with footprints of about 1,700 square feet that are planned to include basements, and a 4-story multi-family residential building with a footprint of about 33,000 square feet that is planned to have 1-level of below-grade parking.

It is understood that as part of the proposed development, a stormwater infiltration system with a footprint of about 8,100 square feet will be constructed within the western portion of the site.

Elevations cited herein are in feet and are referenced to the North American Vertical Datum of 1988 (NAVD88).

Subsurface Explorations

The approximate locations of the subsurface explorations are indicated on the enclosed Subsurface Exploration Plan, **Figure 2**. The following subsurface explorations were completed at the project site under contract to McPhail:



Memorandum

- Two (2) borings (MA-1 through MA-2) were completed on November 20, 2024 by Carr-Dee Corp. of Medford, Massachusetts.

The borings were drilled to depths ranging from 37 to 42 feet below the existing ground surface and were terminated within a natural marine clay deposit. The boring logs are attached to this memorandum.

Thirteen (13) test pits were previously excavated at the site by others during May 2023 and April 2024. Additionally, four (4) groundwater monitoring wells were installed within completed test pits TP-1, TP-6, TP-7, and TP-9.

Soil Conditions

A detailed description of the subsurface conditions encountered in the explorations is documented on the boring logs attached to this memorandum. The approximate locations of the subsurface explorations are indicated on the enclosed Subsurface Exploration Plan, **Figure 2**.

Based on the results of the borings performed at the site, the following is a description of the generalized subsurface conditions encountered from ground surface downward.

<i>Generalized Subsurface Strata</i>	<i>Approximate Thickness (Feet)</i>	<i>Top of Soil Strata (Elevation)</i>
Fill	5.5 to 9.5	El. +7.9 to El. +11.1 (Ground Surface)
Peat	2.5 (At boring MA-2 only)	El. +2.4
Alluvium	12 to 19	El. -0.1 to El. +1.6
Marine Clay	Not Penetrated	El. -17.4 to El. -12.1

Fill Material: The fill material generally consists of compact to dense sand and gravel, trace to some silt, varying to a silt and sand, trace gravel and containing brick, wood, ash and cinders.

Organic Deposit: Underlying the fill at boring MA-2, the organic deposit generally consists of soft to firm, brown fibrous peat. The organic deposit was not encountered in boring MA-1 and appears to be discontinuous between MA-1 and MA-2.

Alluvium Deposit: Underlying the fill at boring MA-1 and the organic deposit at boring MA-2, the alluvium deposit generally consists of a compact to dense gray-brown stratified silty sand, varying to sand, trace silt.



Memorandum

Marine Clay Deposit: Underlying the alluvium deposit, the marine clay deposit generally consists of a very soft to stiff, gray silty marine clay deposit with occasional to frequent sand lenses of varying thickness. At boring MA-2, an approximate 2.5-foot-thick sand seam was observed from about Elevation -13.1 to Elevation -15.6. The depth to the top of the marine clay deposit was observed at about 28.5 feet and 20 feet below the existing ground surface at MA-1 and MA-2, respectively. The borings were terminated within the marine clay deposit which is anticipated to extend to depths greater than 100 feet below the existing ground surface and be underlain by glacial till and bedrock.

Groundwater Conditions

Where encountered in the borings during drilling, groundwater was observed at depths ranging from about 12 and 11 feet below the existing ground surface at boring MA-1 and MA-2, corresponding to Elevation -0.9 and Elevation -3.1, respectively.

It is anticipated that future groundwater levels across the site may vary from those reported herein due to factors such as normal seasonal changes, runoff particularly during or following periods of heavy precipitation, and alterations of existing drainage patterns.

Summary and Conclusions

The subsurface soil conditions in borings MA-1 and MA-2 consisted of a granular fill material, underlain by a discontinuous peat deposit, underlain by an alluvium deposit, overlying a marine clay deposit. The depth to the top of the marine clay deposit was observed at about 28.5 feet and 20 feet below the existing ground surface, corresponding to Elevation -17.4 and Elevation -12.1 at MA-1 and MA-2, respectively. The marine clay deposit is anticipated to have a low permeability and would be considered a barrier to groundwater flow, typically signifying the bottom of the permeable soils.


Closing

We trust that the above is sufficient for your present requirements. Should you have any questions concerning the recommendations presented herein, please do not hesitate to contact us.


N:\Working Documents\Jobs\7679 - Thorndike Place\Geotechnical Data Report\7679_ThorndikePlace_GeotechnicalData_Memo-rev2 120924.docx
SSS/ada

Attachments: Figure 1: Project Location Plan
 Figure 2: Subsurface Exploration Plan
 Boring Logs

FIGURE 1



42 3rd Avenue
 Burlington, MA 01803
 617-868-1420
 www.mcphailgeo.com




SCALE 1:25,000

PROJECT LOCATION PLAN

THORNDIKE PLACE

ARLINGTON


MASSACHUSETTS



LEGEND

— APPROXIMATE LOCATION OF BOREHOLE PERFORMED BY CARR-DEE CORP. ON NOVEMBER 20, 2024 FOR McPHAIL ASSOCIATES, LLC

REFERENCE: THIS PLAN WAS PREPARED FROM AN 80-SCALE DRAWING ENTITLED "EXISTING CONDITIONS" DATED SEPTEMBER 6, 2023 BY BSC GROUP, INC.



42 3rd Avenue
Burlington, MA 01803
617-868-1420
www.mcphailgeo.com

THORNDIKE PLACE			
ARLINGTON		MASSACHUSETTS	
SUBSURFACE EXPLORATION PLAN			
FOR DINOSAUR CAPITAL PARTNERS LLC			
BY McPHAIL ASSOCIATES, LLC			
Date: DECEMBER 2024	Dwn: I.J.M.	Chkd: S.S.S.	Scale: 1" = 50'
Project No:	7679		

Project: Thorndike Place	Job #: 7679.2.01	Boring No.
Location: See Plan	Date Started: 11-20-24	MA-1
City/State: Arlington, Massachusetts	Date Finished: 11-20-24	

Contractor: Carr-Dee Corp	Casing Type/Depth (ft): 2.25" I.D. HSA/NW Casing	Groundwater Observations	
Driller/Helper: J. DeSimone/C. Smith	Casing Hammer (lbs)/Drop (in): 300 lbs./24 inches	Date	Depth
Logged By/Reviewed By: T. M. Cormican	Sampler Size/Type: 1-3/8" I.D. Split Spoon	11-20-24	12
Surface Elevation (ft): 11.1	Sampler Hammer (lbs)/Drop (in): 140 lbs./30 inches	Elev.	Notes
		-0.9	

Depth (ft)	Elev. (ft)	Symbol	Depth/Elev. to Strata Change (ft)	Stratum	Sample					Sample Description and Boring Notes			
					N-Value	No.	Pen./Rec. (in)	Depth (ft)	Blows Per 6"				
1	10	[Cross-hatch symbol]		FILL	12	S-1	24/8	0.0-2.0	3 5 7 12	Compact light brown silty SAND and GRAVEL. (FILL)			
2	9												
3	8												
4	7												
5	6												
6	5							70	S-2	24/16	5.0-7.0	14 37 33 49	Very dense, gray-brown SAND and GRAVEL, trace to some silt to BRICK. (FILL)
7	4												
8	3												
9	2												
10	1					9.5 / 1.6							
11	0	[Vertical lines symbol]		ALLUVIUM DEPOSIT	19	S-3	24/0	10.0-12.0	16 12 7 14	No Recovery			
12	-1												
13	-2							45	S-4	24/14	12.0-14.0	14 23 22 20	Dense, dark gray SAND, trace to some silt. (ALLUVIUM DEPOSIT)
14	-3												
15	-4												
16	-5							23	S-5	24/12	15.0-17.0	9 12 11 12	Compact, gray-brown SAND, trace silt. (ALLUVIUM DEPOSIT)
17	-6												
18	-7												
19	-8												
20	-9												
21	-10							17	S-6	24/18	20.0-22.0	8 8 9 12	Compact, orange-brown and yellow-brown stratified silty SAND to SAND, trace silt. (ALLUVIUM DEPOSIT)
22	-11												

GRANULAR SOILS	
BLOWS/FT.	DENSITY
0-4	V.LOOSE
4-10	LOOSE
10-30	COMPACT
30-50	DENSE
>50	V.DENSE

SOIL COMPONENT	
DESCRIPTIVE TERM	PROPORTION OF TOTAL
"TRACE"	0-10%
"SOME"	10-20%
"ADJECTIVE" (eg SANDY, SILTY)	20-35%
"AND"	35-50%

SOIL CONTAINING THREE COMPONENTS EACH OF WHICH COMPRISE AT LEAST 25% OF THE TOTAL ARE CLASSIFIED AS "A WELL-GRADED MIXTURE OF"

COHESIVE SOILS	
BLOWS/FT.	CONSISTENCY
<2	V.SOFT
2-4	SOFT
4-8	FIRM
8-15	STIFF
15-30	V.STIFF
>30	HARD

Notes:
1. Used Automatic Hammer for SPT.
2. Drillers switched to casing after obtaining sample from 12-14'.

Weather: Variable



McPHAIL ASSOCIATES, LLC
42 3rd AVENUE
Burlington, MA 01803
TEL: 617-868-1420
FAX: 617-868-1423

Project: Thorndike Place	Job #: 7679.2.01	Boring No.
Location: See Plan	Date Started: 11-20-24	MA-1
City/State: Arlington, Massachusetts	Date Finished: 11-20-24	

Contractor: Carr-Dee Corp	Casing Type/Depth (ft): 2.25" I.D. HSA/NW Casing	Groundwater Observations	
Driller/Helper: J. DeSimone/C. Smith	Casing Hammer (lbs)/Drop (in): 300 lbs./24 inches	Date	Depth
Logged By/Reviewed By: T. M. Cormican	Sampler Size/Type: 1-3/8" I.D. Split Spoon	11-20-24	12
Surface Elevation (ft): 11.1	Sampler Hammer (lbs)/Drop (in): 140 lbs./30 inches	Elev.	Notes
		-0.9	

Depth (ft)	Elev. (ft)	Symbol	Depth/EL to Strata Change (ft)	Stratum	Sample					Sample Description and Boring Notes		
					N-Value	No.	Pen./Rec. (in)	Depth (ft)	Blows Per 6"			
24	-13			ALLUVIUM DEPOSIT						Dense, gray stratified silty SAND to SAND, trace silt. (ALLUVIUM DEPOSIT)		
25	-14								19			
26	-15						33	S-7	24/18		25.0-27.0	17
27	-16											16
28	-17					28.5 / -17.4						15
29	-18			MARINE CLAY						Stiff, gray silty CLAY with ~ 6 inch layer of sand. (MARINE CLAY)		
30	-19										3	
31	-20						9	S-8	24/18		30.0-32.0	4
32	-21											5
33	-22											3
34	-23			MARINE CLAY						Very soft, gray silty CLAY. (MARINE CLAY)		
35	-24											1/24"
36	-25						1/24"	S-9	24/22		35.0-37.0	
37	-26					37.0 / -25.9						
38	-27						Bottom of Borehole at 37.0 feet below existing grade.					
39	-28											
40	-29											
41	-30											
42	-31											
43	-32											
44	-33											
45	-34											

GRANULAR SOILS		SOIL COMPONENT	
BLOWS/FT.	DENSITY	DESCRIPTIVE TERM	PROPORTION OF TOTAL
0-4	V.LOOSE	"TRACE"	0-10%
4-10	LOOSE	"SOME"	10-20%
10-30	COMPACT	"ADJECTIVE" (eg SANDY, SILTY)	20-35%
30-50	DENSE	"AND"	35-50%
>50	V.DENSE		
COHESIVE SOILS		Notes: 1. Used Automatic Hammer for SPT. 2. Drillers switched to casing after obtaining sample from 12-14'. Weather: Variable	
BLOWS/FT.	CONSISTENCY		
<2	V.SOFT		
2-4	SOFT		
4-8	FIRM		
8-15	STIFF		
15-30	V.STIFF		
>30	HARD		



McPHAIL ASSOCIATES, LLC
 42 3rd AVENUE
 Burlington, MA 01803
 TEL: 617-868-1420
 FAX: 617-868-1423

Page 2 of 2
 461 of 504

Project: Thorndike Place	Job #: 7679.2.01	Boring No.
Location: See Plan	Date Started: 11-20-24	MA-2
City/State: Arlington, Massachusetts	Date Finished: 11-20-24	

Contractor: Carr-Dee Corp	Casing Type/Depth (ft): 2.25" I.D. HSA/NW Casing	Groundwater Observations	
Driller/Helper: J. DeSimone/C. Smith	Casing Hammer (lbs)/Drop (in): 300 lbs./24 inches	Date	Depth
Logged By/Reviewed By: T. M. Cormican	Sampler Size/Type: 1-3/8" I.D. Split Spoon	11-20-24	11
Surface Elevation (ft): 7.9	Sampler Hammer (lbs)/Drop (in): 140 lbs./30 inches	Elev.	Notes
		-3.1	

Depth (ft)	Elev. (ft)	Symbol	Depth/Elev. to Strata Change (ft)	Stratum	Sample					Sample Description and Boring Notes	
					N-Value	No.	Pen./Rec. (in)	Depth (ft)	Blows Per 6"		
1	7		0.4 / 7.5	TOPSOIL	4	S-1	24/16	0.0-2.0	3 2 2 3	Very loose to loose, mottled gray-brown SILT and SAND, trace gravel. (FILL)	
2	6			FILL							
3	5										
4	4										
5	3										
6	2		5.5 / 2.4	ORGANIC DEPOSIT	4	S-2	6/6	5.0-5.5	2	Very loose, mottled orange-brown and black SILT and SAND, with wood, ash and cinders. (FILL)	
7	1					4	S-2a	18/18	5.5-7.0	2 2 2	Soft to firm, brown FIBROUS PEAT. (ORGANIC DEPOSIT)
8	0		8.0 / -0.1								
9	-1			ALLUVIUM DEPOSIT							
10	-2										
11	-3					17	S-3	24/14	10.0-12.0	9 8 9 9	Compact, gray-brown stratified silty SAND to SAND, trace silt. (ALLUVIUM DEPOSIT)
12	-4										
13	-5										
14	-6										
15	-7										
16	-8					18	S-4	24/16	15.0-17.0	8 8 10 9	Compact, stratified gray silty SAND to SAND, trace silt. (ALLUVIUM DEPOSIT)
17	-9										
18	-10										
19	-11										
20	-12		20.0 / -12.1	MARINE CLAY							
21	-13		21.0 / -13.1			5	S-5	12/12	20.0-21.0	3 2	Very soft to soft, gray silty CLAY with silt and sand seams. (MARINE CLAY)
22	-14			MARINE SAND							
					22	S-5a	12/12	21.0-22.0	8 14	Compact, gray stratified silty SAND to SAND, trace silt. (MARINE SAND)	

GRANULAR SOILS	
BLOWS/FT.	DENSITY
0-4	V.LOOSE
4-10	LOOSE
10-30	COMPACT
30-50	DENSE
>50	V.DENSE

SOIL COMPONENT	
DESCRIPTIVE TERM	PROPORTION OF TOTAL
"TRACE"	0-10%
"SOME"	10-20%
"ADJECTIVE" (eg SANDY, SILTY)	20-35%
"AND"	35-50%

SOIL CONTAINING THREE COMPONENTS EACH OF WHICH COMPRISE AT LEAST 25% OF THE TOTAL ARE CLASSIFIED AS "A WELL-GRADED MIXTURE OF"

COHESIVE SOILS	
BLOWS/FT.	CONSISTENCY
<2	V.SOFT
2-4	SOFT
4-8	FIRM
8-15	STIFF
15-30	V.STIFF
>30	HARD

Notes:
 1. Used Automatic Hammer for SPT.
 2. Drillers switched to casing after obtaining sample from 10-12'.

 Weather: Variable



McPHAIL ASSOCIATES, LLC
 42 3rd AVENUE
 Burlington, MA 01803
 TEL: 617-868-1420
 FAX: 617-868-1423

Page 1 of 2
 462 of 504

Project: Thorndike Place	Job #: 7679.2.01	Boring No.
Location: See Plan	Date Started: 11-20-24	MA-2
City/State: Arlington, Massachusetts	Date Finished: 11-20-24	

Contractor: Carr-Dee Corp	Casing Type/Depth (ft): 2.25" I.D. HSA/NW Casing	Groundwater Observations	
Driller/Helper: J. DeSimone/C. Smith	Casing Hammer (lbs)/Drop (in): 300 lbs./24 inches	Date	Depth
Logged By/Reviewed By: T. M. Cormican	Sampler Size/Type: 1-3/8" I.D. Split Spoon	11-20-24	11
Surface Elevation (ft): 7.9	Sampler Hammer (lbs)/Drop (in): 140 lbs./30 inches	Elev.	Notes
		-3.1	

Depth (ft)	Elev. (ft)	Symbol	Depth/Elev. to Strata Change (ft)	Stratum	Sample					Sample Description and Boring Notes	
					N-Value	No.	Pen./Rec. (in)	Depth (ft)	Blows Per 6"		
24	-16		23.5 / -15.6	MARINE SAND							
25	-17										
26	-18					2	S-6	24/24	25.0-27.0	1/12' 1 1	Very soft, gray silty CLAY with frequent sand partings in bottom ~ 10 inches of sample. (MARINE CLAY)
27	-19										
28	-20										
29	-21										
30	-22										
31	-23					1	S-7	24/24	30.0-32.0	WOH WOH 1 1	Very soft, gray silty CLAY with frequent sand partings. (MARINE CLAY)
32	-24										
33	-25				MARINE CLAY						
34	-26										
35	-27										
36	-28				1	S-8	24/24	35.0-37.0	WOH WOH 1 1	Very soft, gray silty CLAY, with occasional sand partings. (MARINE CLAY)	
37	-29										
38	-30										
39	-31										
40	-32										
41	-33				1	S-9	24/24	40.0-42.0	WOH WOH 1 WOH	Very soft, gray silty CLAY, with occasional sand partings. (MARINE CLAY)	
42	-34		42.0 / -34.1								
43	-35			Bottom of Borehole at 42.0 feet below existing grade.							
44	-36										
45	-37										

GRANULAR SOILS	
BLOWS/FT.	DENSITY
0-4	V.LOOSE
4-10	LOOSE
10-30	COMPACT
30-50	DENSE
>50	V.DENSE

SOIL COMPONENT	
DESCRIPTIVE TERM	PROPORTION OF TOTAL
"TRACE"	0-10%
"SOME"	10-20%
"ADJECTIVE" (eg SANDY, SILTY)	20-35%
"AND"	35-50%

SOIL CONTAINING THREE COMPONENTS EACH OF WHICH COMPRISE AT LEAST 25% OF THE TOTAL ARE CLASSIFIED AS "A WELL-GRADED MIXTURE OF"

COHESIVE SOILS	
BLOWS/FT.	CONSISTENCY
<2	V.SOFT
2-4	SOFT
4-8	FIRM
8-15	STIFF
15-30	V.STIFF
>30	HARD

Notes:
 1. Used Automatic Hammer for SPT.
 2. Drillers switched to casing after obtaining sample from 10-12'.

 Weather: Variable




McPHAIL ASSOCIATES, LLC
 42 3rd AVENUE
 Burlington, MA 01803
 TEL: 617-868-1420
 FAX: 617-868-1423

Page 2 of 2
 463 of 504


THORNDIKE PLACE NOTICE OF INTENT DOROTHY ROAD ARLINGTON, MASSACHUSETTS

SEPTEMBER 6, 2023

REVISED: DECEMBER 10, 2024



LOCUS MAP



PREPARED FOR:

ARLINGTON LAND REALTY, LLC
84 SHERMAN STREET, 2ND FLOOR
CAMBRIDGE, MA 02140

PREPARED BY:

BSC GROUP
803 Summer Street
Boston, Massachusetts
02127
617 896 4300

ISSUED FOR PERMITTING
NOT FOR CONSTRUCTION

INDEX OF DRAWINGS

- G-100 TITLE SHEET
- G-101 GENERAL NOTES & LEGEND
- V-100 EXISTING CONDITIONS
- C-100 EXISTING ENVIRONMENTAL RESOURCE PLAN
- C-101 SITE PREPARATION PLAN
- C-102 OVERALL SITE PLAN
- C-103 LAYOUT & MATERIALS PLAN
- C-104 GRADING & DRAINAGE PLAN
- C-105 UTILITY PLAN
- L-100 PLANTING PLAN
- C-200-203 CIVIL & LANDSCAPE DETAILS
- C-300 TEST PIT PLAN
- C-301 2020 TEST PIT LOGS
- C-302 & 303 2023 TEST PIT LOGS

- GENERAL NOTES
- EXISTING CONDITIONS SURVEY INFORMATION WAS PREPARED BY BSC GROUP, INC. SURVEY IS BASED ON AN ON-THE-GROUND SURVEY CONDUCTED BY BSC GROUP IN DECEMBER 2019-FEBRUARY 2020.
 - REVIEW ALL EXISTING CONDITIONS IN THE FIELD AND REPORT ANY DISCREPANCIES BETWEEN PLANS AND ACTUAL CONDITIONS TO THE OWNER'S REPRESENTATIVE IN WRITING PRIOR TO STARTING WORK.
 - THE LOCATIONS OF UNDERGROUND UTILITIES SHOWN ON THIS PLAN ARE BASED ON THE SURVEY REFERENCED ABOVE. THE CONTRACTOR SHALL CONTACT DIGSAFE (888-344-7233 OR 811) AND THE PROPER LOCAL AUTHORITIES OR RESPECTIVE UTILITY COMPANIES TO CONFIRM THE LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. ANY DAMAGE DUE TO FAILURE OF THE CONTRACTOR TO CONTACT THE PROPER AUTHORITIES SHALL BE BORNE BY THE CONTRACTOR.
 - ANY DISCREPANCIES BETWEEN DRAWINGS, SPECIFICATIONS, AND SITE CONDITIONS SHALL BE REPORTED IMMEDIATELY TO THE ENGINEER IN WRITING FOR CLARIFICATION AND RESOLUTION PRIOR TO BIDDING OR CONSTRUCTION.

- SITE PREPARATION NOTES
- ONLY AREAS DESIGNATED FOR CLEARING SHALL BE CLEARED.
 - THE SUBCONTRACTOR(S) IS/ARE RESPONSIBLE FOR ANY DAMAGE TO EXISTING CONDITIONS TO REMAIN THAT ARE DUE TO SUBCONTRACTOR(S) OPERATIONS.
 - ITEMS TO BE REMOVED THAT ARE NOT STOCKPILED FOR LATER REUSE ON THE PROJECT OR DELIVERED TO THE OWNER SHALL BE LEGALLY DISPOSED OF OFF SITE BY THE SUBCONTRACTOR(S).
 - THE SUBCONTRACTOR(S) SHALL BE RESPONSIBLE FOR COORDINATING THEIR EFFORTS WITH ALL TRADES.
 - THE CONTRACTOR SHALL COORDINATE ALL ADJUSTMENT OR ABANDONMENT OF UTILITIES WITH THE RESPECTIVE UTILITY COMPANY.
 - THE SUBCONTRACTOR(S) SHALL MAINTAIN OR ADJUST TO NEW FINISH GRADE AS NECESSARY ALL UTILITY AND SITE STRUCTURES SUCH AS LIGHT POLES, SIGN POLES, MAN HOLES, CATCH BASINS, HAND HOLES, WATER AND GAS GATES, HYDRANTS, ETC., FROM MAINTAINED UTILITY AND SITE SYSTEMS UNLESS OTHERWISE NOTED OR DIRECTED BY THE CONTRACTOR/ENGINEER.
 - TEMPORARY CONSTRUCTION HAUL ROADS (IF REQUIRED) SHALL BE EXCAVATED AND THE SUB-BASE COMPACTED TO 95% SPMD. THE USE OF SEPARATION FABRICS MAY BE USED TO FACILITATE FUTURE REMOVAL AND RECOVERY OF GRANULAR MATERIALS. HAUL ROAD SHALL HAVE AT LEAST 9" OF 6-INCH MINUS STONE AND SHALL BE MAINTAINED DURING CONSTRUCTION.

- EROSION AND SEDIMENT CONTROL MEASURES
- EROSION CONTROL SHALL BE PROVIDED IN ACCORDANCE WITH THE SEQUENCE OF STAGED CONSTRUCTION. THE CONTRACTOR SHALL SUBMIT A DETAILED EROSION CONTROL PLAN INCLUDING SCHEDULE FOR APPROVAL BY THE TOWN OF ARLINGTON. A COPY OF THE APPROVED NPDES - EROSION AND SEDIMENT CONTROL PLAN SHALL BE MAINTAINED ON THE SITE.
 - ALL EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE INSTALLED PRIOR TO ANY SITE EXCAVATION OR DISTURBANCE AND SHALL BE MAINTAINED THROUGHOUT THE CONSTRUCTION PROCESS. THE SMALLEST PRACTICAL AREA OF LAND SHALL BE EXPOSED AT ANY ONE TIME.
 - SEDIMENT TRAPS SHALL BE INSTALLED AT DRAINAGE STRUCTURES IN PUBLIC STREET IN THE PROJECT AREA. STRAW BALE BARRIERS AND SILTATION FENCES ARE TO BE MAINTAINED AND CLEANED UNTIL ALL SLOPES HAVE BEEN STABILIZED.
 - SEDIMENT BARRIERS SHALL BE INSPECTED AND APPROVED BY THE TOWN OF ARLINGTON BEFORE CONSTRUCTION CAN START.
 - STRAW BALES AND MULCH SHALL BE MOWINGS OF ACCEPTABLE HERBACEOUS GROWTH, FREE OF NOXIOUS WEEDS OR WOODY STEMS, AND SHALL BE DRY WHEN INSTALLED.
 - THE UNDERSIDE OF STRAW BALES SHOULD BE KEPT IN CLOSE CONTACT (TRENCHED IN 3-INCHES MINIMUM) WITH THE EARTH AND RESET AS NECESSARY.
 - DISTURBED AREAS SHALL BE BLANKETED OR SEEDED AND MULCHED AS SOON AS PRACTICAL AFTER CONSTRUCTION ACTIVITIES IN THAT AREA HAVE CONCLUDED. ALL ERODABLE/BARE AREAS SHALL BE BLANKETED OR SEEDED AND MULCHED WITHIN 7 DAYS WITH TEMPORARY EROSION CONTROL SEEDING.
 - STABILIZE SLOPES GREATER THAN 3:1 (HORIZONTAL:VERTICAL) WITH SEED, SECURED GEOTEXTILE FABRIC, SPRAYED COMPOST BLANKET, OR RIP-RAP AS REQUIRED TO PREVENT EROSION DURING CONSTRUCTION.
 - SEDIMENT BARRIERS SHALL BE CONSTRUCTED AROUND ALL SOIL STOCKPILE AREAS.
 - CLEAN OUT DRAINAGE FEATURES AND STRUCTURES AFTER COMPLETION OF CONSTRUCTION.
 - SEDIMENT COLLECTED DURING CONSTRUCTION BY THE VARIOUS TEMPORARY EROSION CONTROL SYSTEMS SHALL BE DISPOSED OF OFF SITE ON A REGULAR BASIS. SEDIMENT SHALL BE REMOVED FROM EROSION CONTROL SYSTEMS WHEN THE HEIGHT OF THE SEDIMENT EXCEEDS ONE-HALF OF THE HEIGHT OF THE SEDIMENT CONTROL MEASURE.
 - AFTER ALL DISTURBED AREAS HAVE BEEN STABILIZED, THE SUBCONTRACTOR(S) SHALL REMOVE ALL TEMPORARY EROSION CONTROL MEASURES AT THE CONTRACTOR/ENGINEER DIRECTION.
 - AFTER THE REMOVAL OF TEMPORARY EROSION CONTROL MEASURES, THE SUBCONTRACTOR(S) SHALL GRADE AND SEED AREA OF TEMPORARY EROSION CONTROL MEASURE.
 - DAMAGED OR DETERIORATED ITEMS WILL BE REPAIRED IMMEDIATELY AFTER IDENTIFICATION OR AS DIRECTED BY THE CONTRACTOR/ENGINEER.
 - THE CONTRACTOR'S SITE SUPERINTENDENT WILL BE RESPONSIBLE FOR DAILY INSPECTIONS, MAINTENANCE, AND REPAIR ACTIVITIES. THE CONTRACTOR SHALL INSPECT EROSION CONTROL MEASURES EVERY SEVEN (7) CALENDAR DAYS. DAMAGED AND INEFFECTIVE EROSION CONTROL MEASURES SHALL BE REPAIRED OR REPLACED WITHIN 48 HOURS.
 - PIPE OUTLETS (IF ANY) SHALL BE STABILIZED WITH STONE.
 - TEMPORARY SEEDING SHALL BE AT A RATE OF 45 LBS PER ACRE. ERODABLE AREAS OUTSIDE AND DOWN SLOPE FROM THE CONSTRUCTION LIMITS SHALL BE SIMILARLY SEEDED.
 - WATER PUMPED OR OTHERWISE DISCHARGED FROM THE SITE DURING CONSTRUCTION DEWATERING SHALL BE FILTERED. DEWATERING PLAN SHALL BE SUBMITTED FOR APPROVAL BY THE ENGINEER.
 - WHEN TEMPORARY DRAINAGE IS ESTABLISHED, EROSION/SEDIMENTATION CONTROL MEASURES MAY BE REQUIRED BY CONTRACTOR/ENGINEER.
 - GRAVEL CONSTRUCTION ROADS AND CONSTRUCTION PARKING AREAS OF SUFFICIENT WIDTH AND LENGTH, AND VEHICLE WASH DOWN FACILITIES, SHALL BE PROVIDED TO PREVENT SOIL FROM BEING TRACKED ONTO PUBLIC OR PRIVATE ROADWAYS. ANY SOIL REACHING A PUBLIC OR PRIVATE ROADWAY SHALL BE REMOVED BEFORE THE END OF EACH WORKDAY AND AS NEEDED.
 - NECESSARY MEASURES SHALL BE TAKEN TO CONTAIN ANY FUEL OR POLLUTION RUNOFF. LEAKING EQUIPMENT OR SUPPLIES SHALL BE IMMEDIATELY REPAIRED OR REMOVED FROM THE SITE.
 - THE COST OF REPAIRING OR REMOVING SEDIMENT FROM EROSION CONTROL SYSTEMS SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR THE APPLICABLE EROSION CONTROL ITEM.
 - ALL EROSION CONTROL MEASURES SHALL BE KEPT OPERATIONAL AND MAINTAINED CONTINUOUSLY THROUGHOUT THE PERIOD OF LAND DISTURBANCE UNTIL PERMANENT SEDIMENT AND EROSION CONTROL MEASURES ARE OPERATIONAL. CONTRACTOR SHALL PROVIDE TO THE CONSERVATION COMMISSION MEASURES (EROSION AND SEDIMENTATION CONTROL) FOR WORK DURING WINTER CONDITIONS.
 - CONTRACTOR SHALL SPRAY WATER FROM A WATER TRUCK ON DRY AND WINDY DAYS TO PREVENT DUST FROM FORMING.
 - EROSION CONTROL MEASURES AS SHOWN ON THESE DRAWINGS ARE INTENDED TO CONVEY MINIMUM REQUIREMENTS. THE CONTRACTOR SHALL IMPLEMENT ADDITIONAL MEASURES AS NECESSARY TO PREVENT SOIL EROSION AND TO COMPLY WITH THE PROJECT'S STORMWATER POLLUTION PREVENTION PLAN.
 - SOILS ON SLOPES THAT ARE 3:1 OR STEEPER SHOULD BE ROUGHENED PER THE EPA'S NPDES SOIL ROUGHENING FACT SHEET IF THEY ARE TO BE SEEDED WITHIN 2 WEEKS OF DISTURBANCE. IF NOT, EROSION CONTROL BLANKETS SHOULD BE INSTALLED ON THESE SLOPES.

- LAYOUT AND MATERIAL NOTES
- THE FOLLOWING LAYOUT CRITERIA SHALL CONTROL UNLESS OTHERWISE NOTED ON THE PLAN:
 - ALL TIES TO PROPERTY LINES ARE PERPENDICULAR TO THE PROPERTY LINE UNLESS OTHERWISE NOTED.
 - DISTANCES AND DIMENSIONS ARE IN DECIMAL FEET.
 - SCREENED IMAGES SHOW EXISTING CONDITIONS. WHERE EXISTING CONDITIONS LIE UNDER OR ARE IMPINGED UPON BY PROPOSED BUILDINGS AND/OR SITE ELEMENTS, THE EXISTING CONDITION SHALL BE REMOVED, ABANDONED AND/OR CAPPED OR DEMOLISHED AS REQUIRED. AMBIGUITIES IN THE PLANS SHALL BE CLARIFIED BY THE ENGINEER OR SITE SUPERINTENDENT UPON WRITTEN REQUEST FOR CLARIFICATION BY THE SUBCONTRACTOR.
- GRADING AND UTILITY NOTES
- THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY AND HAVE NOT BEEN INDEPENDENTLY VERIFIED BY THE APPLICANT. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK, AND AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MAY BE OCCASIONED BY THE CONTRACTOR'S FAILURE TO EXACTLY LOCATE AND PRESERVE ALL UNDERGROUND UTILITIES.
 - THE PROJECT APPLICANT SHALL OBTAIN ALL NECESSARY STREET-OPENING PERMITS, WATER AND SEWER CONNECTION PERMITS AND PAY REQUIRED FEES PRIOR TO COMMENCING WORK ON THESE UTILITIES.
 - WHERE AN EXISTING UTILITY IS FOUND TO CONFLICT WITH THE PROPOSED WORK, THE LOCATION, ELEVATION, AND SIZE OF THE UTILITY SHALL BE ACCURATELY DETERMINED WITHOUT DELAY BY COORDINATION WITH THE TOWN OF ARLINGTON.
 - ALL ARRANGEMENTS FOR THE ALTERATION AND ADJUSTMENT OF ALL GAS, ELECTRIC, TELEPHONE, AND ANY OTHER PRIVATE UTILITIES BY THE UTILITY COMPANIES SHALL BE MADE BY THE PROJECT APPLICANT.
 - AREAS OUTSIDE THE LIMITS OF PROPOSED WORK DISTURBED BY THE CONSTRUCTION SHALL BE RESTORED TO THEIR ORIGINAL CONDITION.
 - WHERE PROPOSED GRADES MEET EXISTING GRADES, SUBCONTRACTOR(S) SHALL BLEND GRADES TO PROVIDE A SMOOTH TRANSITION BETWEEN EXISTING AND NEW WORK. PONDING AT TRANSITION AREAS WILL NOT BE ALLOWED.
 - POSITIVE DRAINAGE SHALL BE MAINTAINED AWAY FROM ALL STRUCTURES.
 - SUBCONTRACTOR(S) SHALL VERIFY EXISTING GRADES AND NOTIFY THE ENGINEER IN WRITING OF ANY DISCREPANCIES.
 - PRIOR TO ANY WORK OVER EXISTING TOWN-OWNED UTILITIES, CONTRACTOR TO EVALUATE CONDITION OF SUBSURFACE UTILITIES PRIOR TO CONSTRUCTION. A POST-CONSTRUCTION EVALUATION SHALL ALSO BE PERFORMED TO IDENTIFY ANY DAMAGE CAUSED DURING CONSTRUCTION.
 - ANY INSTALLATION OF UTILITY POLES OR UNDERGROUND CONDUIT WITHIN THE PUBLIC RIGHT-OF-WAY WILL REQUIRE A GRANT OF LOCATION FROM THE BOARD OF SELECTMEN.

- PLANTING NOTES
- MAINTENANCE SHALL BEGIN IMMEDIATELY AFTER PLANTING AND SHALL CONTINUE UNTIL FINAL WRITTEN ACCEPTANCE OF PLANT MATERIAL.
 - MAINTAIN POSITIVE DRAINAGE AWAY FROM ALL BUILDING FOUNDATIONS AND STRUCTURES.
 - MAXIMUM SLOPE WITHIN DISTURBED AREAS SHALL NOT EXCEED 3:1, UNLESS OTHERWISE NOTED.
 - THE LANDSCAPE CONTRACTOR SHALL SUPPLY ALL PLANT MATERIALS IN QUANTITIES SUFFICIENT TO COMPLETE PLANTINGS SHOWN ON THE DRAWINGS.
 - MATERIALS SHALL CONFORM TO THE GUIDELINES ESTABLISHED BY THE AMERICAN NURSERY AND LANDSCAPE ASSOCIATION.
 - PLANTS SHALL BEAR THE SAME RELATIONSHIP TO FINISH GRADE AS TO ORIGINAL GRADES BEFORE DIGGING.
 - PLANTS SHALL BE BALLED IN BURLAP OR CONTAINERIZED.
 - AREAS PLANTED WITH EVERGREEN TREES SHALL BE COVERED WITH A MINIMUM 3" OF MULCH. MULCH FOR PLANTED AREAS TO BE AGED PINE BARK; PARTIALLY DECOMPOSED, DARK BROWN IN COLOR AND FREE OF WOOD CHIPS THICKER THAN 1/4 INCH.
 - THE LANDSCAPE CONTRACTOR SHALL GUARANTEE ALL PLANT MATERIALS FOR ONE (1) FULL YEAR FROM DATE OF ACCEPTANCE.
 - PLANT MATERIALS ARE SUBJECT TO THE APPROVAL OF THE LANDSCAPE ARCHITECT, AT THE NURSERY, AND AT THE SITE.
 - PLANT SPECIES AS INDICATED IN THE PLANT LIST ARE SUGGESTIONS ONLY. FINAL SELECTION OF SPECIES SHALL OCCUR AT THE TIME OF PLANT PURCHASE, DEPENDING ON AVAILABILITY. PLANT SIZE AND QUANTITY SHALL NOT CHANGE WITHOUT APPROVAL OF LANDSCAPE ARCHITECT. ANY CHANGES TO PLANT SPECIES SHALL BE REVIEWED AND APPROVED BY A REPRESENTATIVE OF THE ARLINGTON CONSERVATION COMMISSION PRIOR TO PURCHASE.

- COMPREHENSIVE PERMIT NOTES
- CONTRACTOR REQUIRED TO ABIDE BY THE "DECISION ON APPLICATION FOR COMPREHENSIVE PERMIT" ISSUED ON NOVEMBER 22, 2021 WITH SPECIFIC ATTENTION BROUGHT TO THE FOLLOWING CONDITIONS.
- BURNING OR BURIAL OF CONSTRUCTION OR DEMOLITION DEBRIS ON THE SITE IS STRICTLY PROHIBITED. ALL SUCH MATERIALS ARE TO BE REMOVED FROM THE SITE IN ACCORDANCE WITH APPLICABLE LAW. DURING CONSTRUCTION, THE SITE SHALL BE SECURED AGAINST UNAUTHORIZED ENTRY OR VANDALISM BY FENCING, OR OTHER APPROPRIATE MEANS, AND ALL CONSTRUCTION MATERIALS SHALL BE STORED OR STOCKPILED ON SITE IN A SAFE MANNER. ANY FLOODLIGHTS USED DURING THE CONSTRUCTION PERIOD SHALL BE LOCATED AND DIRECTED SO AS TO PREVENT SPILLOVER OR ILLUMINATION ONTO ADJACENT PROPERTIES. ALL CONSTRUCTION ACTIVITIES ARE TO BE CONDUCTED IN A WORKMANLIKE MANNER.
 - NO BUILDING AREAS SHALL BE LEFT IN AN OPEN, UNSTABILIZED CONDITION LONGER THAN SIXTY (60) DAYS. TEMPORARY STABILIZATION SHALL BE ACCOMPANIED BY HAY BALES, HAY COVERINGS OR MATTING. FINAL STABILIZATION SHALL BE ACCOMPLISHED BY LOAMING AND SEEDING EXPOSED AREAS.
 - ALL DUMPSTERS SERVING THE PROJECT SHALL BE ENCLOSED AND COVERED (WITH THE EXCEPTION OF CONSTRUCTION DUMPSTERS USED DURING CONSTRUCTION). THE BOARD SHALL REVIEW THE DUMPSTER LOCATION AS PART OF THE APPROVAL OF THE FINAL PLANS IF DIFFERENT FROM WHAT HAS BEEN SHOWN ON THE APPROVED PLANS.
 - ALL WATER AND SEWER INFRASTRUCTURE SHALL BE INSTALLED IN CONFORMANCE WITH THE ARLINGTON WATER AND SEWER DIVISION'S TECHNICAL REQUIREMENTS. THE APPLICANT SHALL PROVIDE THE ARLINGTON WATER AND SEWER DIVISION WITH CALCULATIONS TO ENSURE THE DISTRIBUTION SYSTEM FOR THE AREA HAS THE NECESSARY CAPACITY TO MEET SYSTEM DEMAND REQUIRED PRIOR TO THE COMMENCEMENT OF CONSTRUCTION.
 - PRIOR TO COMMENCEMENT OF SITE CLEARING, PREPARATION, AND CONSTRUCTION, EROSION CONTROL MEASURE SHALL BE INSTALLED CONSISTENT WITH THE APPROVED PLANS.
 - NO UNCOVERED STOCKPIILING OF EARTHEN AND/OR CONSTRUCTION-RELATED MATERIALS SHALL BE PERMITTED WITHIN THE ONE HUNDRED FOOT (100') WETLAND BUFFER ZONE (ALSO REFERENCED LOCALLY AS ADJACENT UPLAND RESOURCES AREA ("AURA")) OR OTHER RESOURCE AREAS.
 - NO HEAVY EQUIPMENT MAY BE STORED OVERNIGHT WITHIN THE FIFTY FEET (50') OF BORDERING OR ISOLATED VEGETATED WETLAND RESOURCE AREAS, AND NO REFUELING OR MAINTENANCE OF MACHINERY OR VEHICLES SHALL BE ALLOWED WITHIN THE ONE HUNDRED FOOT (100') BUFFER ZONE, AURA, OR WITHIN ANY BORDERING OR ISOLATED VEGETATED WETLAND RESOURCE AREA OR BORDERING LAND SUBJECT TO FLOODING (BLSF).
 - THERE SHALL BE NO DUMPING OF WOODY VEGETATION, LEAVES, GRASS CLIPPINGS, BRUSH, OR OTHER DEBRIS INTO A WETLAND RESOURCE AREA OR ASSOCIATED BUFFER ZONES. DUMPING OF SNOW INTO A WETLAND RESOURCE AREA IS ALSO PROHIBITED AND SHALL COMPLY WITH THE CURRENT MASS DEP BUREAU OF WATER RESOURCES SNOW REMOVAL GUIDANCE. THE FOREGOING DOES NOT APPLY TO THE CLEAN SNOW REMOVED FROM THE EMERGENCY ACCESS ROAD AS LONG AS NO SAND OR NON-APPROVED DE-ICING MATERIALS ARE USED, AND THE SNOW IS CLEAR OF ALL FOREIGN DEBRIS. AN ALTERNATIVE DE-ICING PRODUCT SUCH AS MAGNESIUM CHLORIDE (MgCl) MAY BE USED AS RECOMMENDED IN THE WINTER PARKING LOT AND SIDEWALK MAINTENANCE MANUAL PUBLISHED BY THE MINNESOTA POLLUTION CONTROL AGENCY. <http://www.pca.state.mn.us/sites/default/files/d-trl-16.pdf>.

- THE APPLICANT SHALL HIRE A QUALIFIED ENVIRONMENTAL MONITOR WHO WILL REPORT TO THE BOARD AND WILL BE ON-SITE AS PROJECT CONSTRUCTION ADVANCES. THE ENVIRONMENTAL MONITOR SHALL SUBMIT AN ELECTRONIC REPORT TO THE BOARD WEEKLY DURING SITE PREPARATION WORK WITHIN THE ONE HUNDRED FOOT (100') BUFFER ZONE TO VEGETATED WETLANDS, INCLUDING AN UPDATE ON THE FUNCTIONALITY AND CONDITION OF THE EROSION CONTROL MEASURES, UNTIL SUCH TIME THAT THE SITE IS STABILIZED. THE APPLICANT SHALL PROVIDE THE BOARD WITH THE NAME(S), ADDRESS(ES) AND TELEPHONE NUMBER(S) OF THE ENVIRONMENTAL MONITOR PRIOR TO THE START OF WORK.
- WHILE ACTIVE CONSTRUCTION WORK IS UNDERWAY WITHIN THE ONE HUNDRED FOOT (100') BUFFER ZONE, AND DURING THE CREATION OF THE FLOODPLAIN COMPENSATION AREA INCLUDING REMOVAL OF VEGETATION INCLUDING INVASIVE SPECIES, FINAL GRADE ESTABLISHMENT, CREATION OF SOIL PROFILE TO SUPPORT PROPOSED PLANT SPECIES, AND RESTORATION OF A DIVERSIFIED PLANT COMMUNITY, THE ENVIRONMENTAL MONITOR SHALL PROVIDE MONTHLY STATUS REPORTS TO THE BOARD TO CONFIRM THAT ALL ACTIVITIES ARE SUBSTANTIALLY IN COMPLIANCE WITH THE COMPREHENSIVE PERMIT AND ORDER OF CONDITIONS ISSUED BY THE ARLINGTON CONSERVATION COMMISSION. THE ZBA MAY REDUCE THE FREQUENCY OF INSPECTIONS OR REPORTS AS DEEMED APPROPRIATE. THE QUALIFIED ENVIRONMENTAL MONITOR SHALL ALSO SUBMIT AN ELECTRONIC REPORT WITHIN SEVEN DAYS AFTER EVERY RAIN EVENT EXCEEDING 0.5 INCHES OF RAIN IN A 24-HOUR PERIOD TO THE BOARD REGARDING THE CONDITION OF THE PROPERTY DURING AND AFTER THE RAIN EVENT. SUCH REPORT SHALL ALSO INCLUDE THE STATUS OF EROSION CONTROL MEASURES AND ANY ADDITIONAL MEASURES TO ADDRESS STORMWATER MANAGEMENT CAUSED BY SAID RAIN EVENT. THE QUALIFIED ENVIRONMENTAL MONITOR WILL ALSO REVIEW THE APPLICANT'S SWPPP INSPECTION REPORT, AS APPROPRIATE AND NECESSARY.
- ALL WORK SHALL BE CONDUCTED IN ACCORDANCE WITH THE APPROVED EROSION AND SEDIMENTATION CONTROL PLAN. WITHIN ONE WEEK OF FINAL GRADING, WEATHER PERMITTING, ALL DISTURBED AREAS LOCATED WITHIN THE WETLAND RESOURCE AREAS AND BUFFER ZONES SHALL BE STABILIZED AGAINST EROSION. THIS SHALL BE DONE EITHER BY SODDING OR BY LOAMING, SEEDING AND MULCHING ACCORDING TO SOIL CONSERVATION SERVICE STANDARDS AND THE APPROVED PLANS. STABILIZATION WILL BE COMPLETED WHEN THE SURFACE SHOWS COMPLETE VEGETATIVE COVER. TEMPORARY STABILIZATION MEASURES APPROVED BY THE BOARD'S INSPECTIONAL ENGINEER WILL BE REQUIRED SHOULD WORK BE INTERRUPTED FOR MORE THAN TEN (10) DAYS.
- THE APPLICANT, SUCCESSOR OR ASSIGNS SHALL ENSURE THE CLEANLINESS OF ALL CATCH BASINS AND ROADWAY AFFECTED BY THE PROJECT RELATED ACTIVITY. ALL CATCH BASINS WILL BE PROTECTED BY A "SILT BAG INLET PROTECTION" DEVICE OR EQUAL DURING THE PROJECT WORK PERIOD. THE APPLICANT SHALL INSPECT AND CLEAN AS NECESSARY. ALL CATCH BASINS AND SWEEP THE ROADWAY AT LEAST WEEKLY DURING CONSTRUCTION. IT MAY BE REQUIRED MORE FREQUENTLY DURING AND AFTER RAIN EVENTS. IF IT IS DEEMED NECESSARY TO REMOVE THE SILT BAG INLET PROTECTION TO PREVENT LOCALIZED FLOODING AND PUBLIC SAFETY CONCERNS, THE APPLICANT SHALL NOTIFY THE BOARD AND ARLINGTON DPW AND ALSO THE QUALIFIED ENVIRONMENTAL MONITOR.
- THE BOARD OR ITS DULY APPOINTED AGENT (WHICH MAY BE THE TOWN CONSERVATION AGENT ACTING ON BEHALF OF THE BOARD) SHALL HAVE THE RIGHT TO ENTER THE PROPERTY FOR INSPECTIONS AND EVALUATE COMPLIANCE WITH THE WETLANDS CONDITIONS CONTAINED HEREIN UPON REASONABLE NOTICE OF NOT LESS THAN TWENTY-FOUR (24) HOURS. ACCESS SHALL BE ALLOWED WITHOUT THE NEED FOR ADVANCED NOTICE IN EMERGENCY SITUATIONS WHEN NECESSARY TO PREVENT IMMINENT HARM TO WETLANDS RESOURCE AREAS.
- PRIOR TO ANY WORK COMMENCING ON-SITE, THE APPLICANT SHALL SUBMIT TO THE BOARD PROOF THAT A NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) CONSTRUCTION GENERAL PERMIT IS ACTIVE FOR THE PROJECT.
- COPIES OF ALL INFORMATION AND ALL REQUIRED REPORTS REGARDING A US EPA NPDES PERMIT AND STORMWATER POLLUTION PREVENTION PLAN (SWPPP) SHALL BE FORWARDED TO THE BOARD VIA ELECTRONIC COPY.
- THE APPLICANT SHALL RETAIN A QUALIFIED PROFESSIONAL ENGINEER TO OVERSEE THE INSTALLATION OF THE STORMWATER SYSTEM. A STORMWATER MITIGATION REPORT SHALL BE SUBMITTED TO THE BOARD WITHIN TEN (10) DAYS OF THE COMPLETION OF THE INSTALLATION OF THE STORMWATER MANAGEMENT SYSTEM. SUCH STORMWATER MITIGATION REPORT SHALL INCLUDE AS-BUILT PLANS, PHOTOGRAPHS FROM INSTALLATION, AND A WRITTEN SUMMARY OF THE INSTALLATION OF THE STORMWATER MANAGEMENT SYSTEMS, AS WELL AS STORMWATER BEST MANAGEMENT PRACTICES (POROUS PAVEMENT, RAIN GARDENS, AND SIMILAR ELEMENTS THROUGHOUT THE PROPERTY).
- THE APPLICANT SHALL TREAT PLANTED AREAS WITHIN RESOURCE AREAS AND BUFFER ZONES ONLY WITH SLOW RELEASE NITROGEN FERTILIZER ONCE DURING THE INITIAL PLANTING YEAR. APPLICATION OF THIS FERTILIZER IS NOT PERMITTED WITHIN TWO DAYS BEFORE AND AFTER STORM EVENTS. LAWN FERTILIZER MAY ONLY BE APPLIED TWICE PER YEAR, ONCE IN THE SPRING AND ONCE IN THE FALL, WITH THE EXCEPTION OF THE INITIAL PLANNING YEAR. THIS SHALL BE A CONTINUING CONDITION IN PERPETUITY THAT SURVIVES THE EXPIRATION OF THIS PERMIT.
- THE APPLICATION OF PLANT NUTRIENTS SHALL COMPLY WITH 330 CMR 31.00. NO OTHER HERBICIDES OR TREATMENT METHODS MAY BE UTILIZED ON THE PROPERTY UNLESS APPROVED AS PART OF THE APPROVED INVASIVE SPECIES MANAGEMENT PLAN. NO PESTICIDES OR RODENTICIDES SHALL BE USED TO TREAT PEST MANAGEMENT ISSUES WITHIN RESOURCE AREAS. THIS SHALL BE A CONTINUING CONDITION IN PERPETUITY THAT SURVIVES THE EXPIRATION OF THIS PERMIT.
- EXCEPT AS SPECIFICALLY NOTED IN CONDITION 1.5, THE APPLICATION OF SAND AND/OR SALT WITHIN THE ONE HUNDRED FEET (100') OF RESOURCE AREA IS PROHIBITED.
- THE APPLICANT SHALL CONDUCT A THOROUGH CATCH BASIN SUMP CLEANING AT ALL PROTECTED CATCH BASINS AT THE END OF CONSTRUCTION OF THE PROJECT.
- ALL PLANT SPECIES PLANTED AND INVASIVE SPECIES REMOVED THROUGH THE PROJECT SHALL BE MONITORED FOR THREE YEARS. A SURVIVAL RATE OF EIGHTY PERCENT (80%) MUST BE MAINTAINED FOR THE APPROVED PLANTING AT THE END OF THE THIRD YEAR OF MONITORING. IF THE SURVIVAL RATE IS LESS THAN EIGHTY PERCENT (80%) AFTER THE END OF THE THIRD YEAR, THE APPLICANT MUST SUBMIT PROPOSED RECOMMENDATIONS FOR REPLACEMENT TO THE BOARD FOR ITS REVIEW AND ADMINISTRATIVE APPROVAL. A MONITORING REPORT SHALL BE SUBMITTED ANNUALLY IN JUNE FOR EACH OF THE YEARS IN THE THREE-YEAR MONITORING PERIOD, REPORTING ON THE HEALTH OF THE NEW PLANTINGS AND THE SUCCESS OF THE INVASIVE PLANT MANAGEMENT. THE APPLICANT SHALL SUBMIT THE CONTACT INFORMATION OF THE PARTY RESPONSIBLE FOR MONITORING AND MAINTAINING THE PLANTED VEGETATION TO THE ZBA. SHOULD ANY CHANGES BY MADE TO THIS PARTY, THE ZBA SHALL BE NOTIFIED. THIS SHALL BE A CONTINUING CONDITION IN PERPETUITY THAT SURVIVES THE EXPIRATION OF THIS PERMIT.
- NO WORK SHALL BE ALLOWED IN OR WITHIN TWENTY-FIVE FEET (25') OF ANY RESOURCES AREA EXCEPT AS SHOWN ON THE APPROVED PLANS.
- NO DISTURBANCES SHALL BE ALLOWED IN OR WITHIN FIFTY FEET (50') OF ANY RESOURCE AREA, EXCEPT AS SHOWN ON THE APPROVED PLANS.
- ANY BUILDING OR SITE DEWATERING OPERATIONS SHALL CONFORM TO THE FOLLOWING:
 - THE APPLICANT SHALL NOTIFY THE CONSERVATION COMMISSION AND DPW THAT DEWATERING IS REQUIRED PRIOR TO COMMENCING ANY DEWATERING OPERATIONS.
 - ANY CATCH BASINS, DRAINS, AND OUTFALLS TO BE USED IN DEWATERING OPERATIONS SHALL BE CLEANED OUT BEFORE OPERATIONS BEGIN.
 - ANY WATER DISCHARGING AS PART OF ANY DEWATERING OPERATION SHALL BE PASSED THROUGH FILTERS, ON-SITE SETTLING BASINS, SETTLING TANK TRUCKS, OR OTHER DEVICES TO ENSURE THAT NO OBSERVABLE SEDIMENTS OR POLLUTANTS ARE CARRIED INTO ANY RESOURCE AREA, STREET, DRAIN, OR ADJACENT PROPERTY. FILTERING IS ESSENTIAL TO REMOVE ANY AUTOMOTIVE POLLUTANTS FROM THE WATER PRIOR TO DISCHARGE.
 - MEASURES SHALL BE TAKEN TO ENSURE NO EROSION OR SCOURING SHALL OCCUR ON PUBLIC OR PRIVATE PROPERTY, OR ON THE BANKS OR BOTTOMS OF WATER BODIES, AS A RESULT OF DEWATERING OPERATIONS. DISCHARGES ARE TO BE SET BACK AT LEAST FIFTY FEET (50') FROM BWV AND IWV.
 - DEWATERING SHALL NOT TAKE PLACE IN ANY MANNER THAT LEADS TO WATER BEING DISCHARGED OR ALLOWED TO FLOW ONTO PROPERTY NOT UNDER THE CONTROL OF THE APPLICANT WITHOUT THE EXPRESS WRITTEN CONSENT OF THAT PROPERTY OWNER.

ABBREVIATIONS

- BC BOTTOM OF CURB
- BIT CONC BITUMINIOUS CONCRETE
- BWV BORDERING VEGETATED WETLANDS
- CB CATCH BASIN
- CB/DH CONC. BOUND/DRILL HOLE
- CLF CHAIN LINK FENCE
- DIP DUCTILE IRON PIPE
- DMH DRAIN MANHOLE
- ECB EROSION CONTROL BARRIER
- FES FLARED END SECTION
- FH FIRE HYDRANT
- FOC FACE OF CURB
- FD FOUND
- GG GAS GATE
- HW HEADWALL
- ILSF ISOLATED LAND SUBJECT TO FLOODING
- IP IRON PIPE
- ISW ISOLATED WETLANDS
- LA LANDSCAPED AREA
- LOW LIMIT OF WORK
- N/F NOW OR FORMERLY
- NTS NOT TO SCALE
- OCS OUTLET CONTROL STRUCTURE
- PCC PRECAST CONCRETE CURB
- RW RETAINING WALL
- RCP REINFORCED CONCRETE PIPE
- SLC STREET LIGHT CIRCUIT
- SMH SEWER MANHOLE
- TC TOP OF CURB
- TEL TELEPHONE CABLE
- VGC VERTICAL GRANITE CURB
- WG WATER GATE

LEGEND

- STONE BOUND W/DRILL HOLE
- STONE BOUND W/ESCUTCHEON PIN
- CONCRETE BOUND
- SEWER MANHOLE
- DRAIN MANHOLE
- WATER MANHOLE
- ELECTRIC MANHOLE
- TELEPHONE MANHOLE
- CABLE MANHOLE
- MANHOLE
- CATCH BASIN
- HYDRANT
- WATER GATE
- GAS GATE
- UTILITY POLE
- UTILITY POLE W/LIGHT
- UTILITY POLE W/TRANSFORMER
- LIGHT POLE
- ELECTRIC HANDHOLE
- HANDHOLE
- SIGN
- WETLANDS FLAG
- BIT BITUMINIOUS CONCRETE
- CONCRETE
- EDGE OF PAVEMENT
- GRANITE CURB
- WOOD CURB
- INVERT
- RECORD INFORMATION
- SEWER LINE
- DRAIN LINE
- WATER LINE
- GAS LINE
- OVERHEAD WIRE
- CHAIN LINK FENCE
- STOCKADE FENCE
- STEEL GUARDRAIL
- TREELINE
- BRUSHLINE
- SURVEYED BUILDING LOCATION
- GIS BUILDING LOCATION
- WATER VALVE
- CATCH BASIN
- FIRE HYDRANT
- TREE FILTER
- # OF PARKING SPACES
- SEWER MANHOLE
- FENCE LINE
- PROPERTY LINE
- WETLAND LINE/FLAG
- (E) MAJOR CONTOUR
- (E) MINOR CONTOUR
- PROPOSED MAJOR CONTOUR
- PROPOSED MINOR CONTOUR
- 100' WETLAND BUFFER ZONE
- 25' NO DISTURB ZONE
- WATER QUALITY UNIT/INLET
- WATER QUALITY UNIT



ISSUED FOR PERMITTING
NOT FOR CONSTRUCTION

PROFESSIONAL ENGINEER

THORNDIKE PLACE
NOTICE OF INTENT

DOROTHY ROAD
IN
ARLINGTON
MASSACHUSETTS
(MIDDLESEX COUNTY)

GENERAL NOTES
AND LEGEND

SEPTEMBER 6, 2023

REVISIONS:

NO.	DATE	DESC.
1	02/02/24	REVIEW FOR PERMITTING
2	12/10/24	PEER REVIEW REVISIONS

PREPARED FOR:
ARLINGTON LAND REALTY, LLC
84 SHERMAN STREET, 2ND FLOOR
CAMBRIDGE, MA

BSC GROUP
803 Summer Street
Boston, Massachusetts
02127
617 896 4300

© 2023 BSC Group, Inc.

SCALE: NONE

FILE: 2340702\C\D\2340702-LN

DWG.: SHEET C-101

JOB. NO: 23407.02

PLAN REFERENCES


1. PLAN ENTITLED "PLAN AND PROFILE OF LITTLEJOHN STREET" BY FRANK AND DANIEL WYMAN, DATED DECEMBER 1926, AND RECEIVED FROM THE TOWN OF ARLINGTON.
2. PLAN ENTITLED "SUBDIVISION OF LAND IN ARLINGTON" BY BREMER W. POND, DATED APRIL 28, 1927, AND FILED AS LAND COURT PLAN 4351C.
3. PLAN ENTITLED "SUBDIVISION OF LAND SHOWN ON PLAN 4351A" BY J.M. KEANE, DATED OCTOBER 20, 1930, AND FILED AS LAND COURT PLAN 4351G.
4. PLAN ENTITLED "SUBDIVISION OF LAND SHOWN ON PLAN 4351A" BY J.M. KEANE, DATED APRIL 14, 1931, AND FILED AS LAND COURT PLAN 4351H.
5. STATE HIGHWAY LAYOUT NO. 2981, DATED JANUARY 17, 1933, RECEIVED FROM MASSACHUSETTS DEPARTMENT OF TRANSPORTATION.
6. STATE HIGHWAY LAYOUT NO. 2983, DATED JANUARY 17, 1933, RECEIVED FROM MASSACHUSETTS DEPARTMENT OF TRANSPORTATION.
7. PLAN ENTITLED "PLAN OF LAND IN ARLINGTON, MASS" BY C. H. GANNETT CO. CIVIL ENGINEERS, DATED APRIL 30, 1941, AND FILED AS LAND COURT PLAN 18030A.
8. PLAN ENTITLED "SUBDIVISION OF LAND IN ARLINGTON MASS" BY G.E. NORTHRUP, DATED DECEMBER 1948, AND RECORDED AS PLAN 1784 OF 1948.
9. PLAN ENTITLED "SUBDIVISION OF LAND IN ARLINGTON" BY G.E. NORTHRUP, DATED DECEMBER 1950, AND FILED AS LAND COURT PLAN 4351I. PLAN ENTITLED "SUBDIVISION OF LAND IN ARLINGTON" BY G.E. NORTHRUP, DATED DECEMBER 1950, AND FILED AS LAND COURT PLAN 4351J.
10. PLAN ENTITLED "PLAN OF LAND IN ARLINGTON MASS TAKEN FOR STORM DRAIN PURPOSES" BY JAMES M. KEANE, DATED JULY 1951, AND RECORDED AS PLAN 1268 OF 1951.
11. PLAN ENTITLED "PLAN OF LAND IN ARLINGTON MASS TAKEN FOR SEWER PURPOSES" BY W.H. ROBY, DATED FEBRUARY 1965, AND RECORDED AS PLAN 662 OF 1958.
12. STATE HIGHWAY LAYOUT NO. 5211, DATED MARCH 20, 1962, RECEIVED FROM MASSACHUSETTS DEPARTMENT OF TRANSPORTATION.
13. PLAN ENTITLED "PLAN OF LAND IN ARLINGTON MASS TAKEN FOR SEWER PURPOSES" BY W.H. ROBY, DATED FEBRUARY 1965, AND RECORDED AS PLAN 664 OF 1965.
14. STATE HIGHWAY LAYOUT NO. 5584, DATED MAY 17, 1966, RECEIVED FROM MASSACHUSETTS DEPARTMENT OF TRANSPORTATION.

GENERAL NOTES

1. THIS PLAN IS BASED UPON AN ON-THE-GROUND SURVEY PERFORMED BY BSC GROUP, INC. IN DECEMBER, 2019 AND JANUARY, 2020.
2. HORIZONTAL DATUM IS BASED UPON NAD '83 (12B) AS DERIVED VIA GPS OBSERVATIONS PERFORMED BY BSC GROUP, INC. IN DECEMBER 2019.
3. VERTICAL DATUM IS BASED UPON NAVD '88 AS DERIVED VIA GPS OBSERVATIONS PERFORMED BY BSC GROUP, INC. IN DECEMBER, 2019.
TBM 18-1 ELEV=9.13'
DESC: BACK LEFT BOLT ON HYDRANT ON OSBORNE
TBM 18-2 ELEV=11.61'
DESC: FRONT BOLT ON HYDRANT ACROSS FROM UTILITY POLE # 8
TBM 18-3 ELEV=11.71'
DESC: BACK LEFT BOLT ON HYDRANT BETWEEN UNITS
4. LOCUS IS LOCATED WITHIN ZONES ZONES AE, AE FLOODWAY, X AND X SHADED AS GRAPHICALLY DEPICTED ON FLOOD INSURANCE RATE MAP NUMBER 25017C0419E, EFFECTIVE DATE JUNE 4, 2010.
5. WETLAND RESOURCE AREAS SHOWN HEREON WERE DELINEATED BY BSC GROUP, INC. IN JANUARY AND OCTOBER 2020.
6. UTILITY RECORDS HEREON DENOTED WITH "M" ARE FROM EXISTING CONDITIONS SURVEY PREPARED BY PRECISION LAND SURVEYING OF SOUTHBOROUGH, MA IN 2009.
7. CONTOURS SHOWN WITHIN WOODED AREAS ARE BASED UPON AERIAL LIDAR COLLECTED UNDER USGS CONTRACT DURING 2013-2014. DATA MEETS OR EXCEEDS Q12 USGS SPECIFICATIONS. BSC GROUP FOUND A MEAN ERROR OF 0.20'(OBSCURED) & 0.16'(UNOBSCURED) ACROSS 15 LOCATIONS SAMPLED DURING THE ON-THE-GROUND SURVEY IN DECEMBER 2019.
8. TOWN LINE LOCATIONS ESTABLISHED FROM MASSACHUSETTS STATE HIGHWAY LAYOUTS 2981, 2982, 2983, 5211 AND 5579.
9. ABUTTING BOUNDARY LINES ARE APPROXIMATE.
10. RECORD UTILITY INFORMATION WAS NOT RECEIVED FROM VERIZON, TENNESSEE GAS AND ICI.

UTILITY NOTE

EXISTING UTILITIES, WHERE SHOWN HEREON, ARE APPROXIMATE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROPERLY LOCATING AND COORDINATING ANY ON-SITE ACTIVITY WITH DIG-SAFE AND THE APPROPRIATE UTILITY COMPANY AND MAINTAINING EXISTING UTILITY SYSTEM SERVICE. DIG-SAFE SHALL BE NOTIFIED PER THE COMMONWEALTH OF MASSACHUSETTS STATUTE CHAPTER 82, SECTION 40, AT 1-888-344-7233. NO GUARANTEE IS IMPLIED OR INTENDED AS TO THE ACCURACY, LOCATION OR THAT ALL UTILITIES AND/OR SUBSURFACE STRUCTURES ARE SHOWN. THE CONTRACTOR SHALL VERIFY SIZE, LOCATION AND INVERTS OR UTILITIES AND STRUCTURES AS REQUIRED PRIOR TO THE START OF CONSTRUCTION.



**THORNDIKE PLACE
NOTICE OF INTENT**

DOROTHY ROAD
IN
ARLINGTON
MASSACHUSETTS
(MIDDLESEX COUNTY)

EXISTING
CONDITIONS

SEPTEMBER 6, 2023

REVISIONS:


NO.	DATE	DESC.

PREPARED FOR:
ARLINGTON LAND REALTY, LLC
84 SHERMAN STREET, 2ND FLOOR
CAMBRIDGE, MA


BSC GROUP
803 Summer Street
Boston, Massachusetts
02127
617 896 4300

© 2023 BSC Group, Inc.
SCALE: 1" = 80'
0 40 80 160 FEET
FILE: 2340702\C\DW\2340702-EC
DWG.:
JOB. NO: 23407.02 SHEET V-100

**ISSUED FOR PERMITTING
NOT FOR CONSTRUCTION**



SEAN EWALD
PROFESSIONAL LAND SURVEYOR
FOR BSC GROUP, INC.
DATE: 9/5/23



- LEGEND**
- BSC GROUP OCTOBER 2020 WETLAND DELINEATION
 - 25' NO DISTURB ZONE
 - 50' BUFFER
 - 100' BUFFER
 - FLOODPLAIN - ZONE AE (EL. 6.8)

**ISSUED FOR PERMITTING
NOT FOR CONSTRUCTION**



PROFESSIONAL ENGINEER

**THORNDIKE PLACE
NOTICE OF INTENT**

DOROTHY ROAD
IN
ARLINGTON
MASSACHUSETTS
(MIDDLESEX COUNTY)

**EXISTING
ENVIRONMENTAL
RESOURCE PLAN**

SEPTEMBER 6, 2023



REVISIONS:

NO.	DATE	DESC.

PREPARED FOR:
ARLINGTON LAND REALTY, LLC
84 SHERMAN STREET, 2ND FLOOR
CAMBRIDGE, MA

BSC GROUP
803 Summer Street
Boston, Massachusetts
02127
617 896 4300

© 2023 BSC Group, Inc.
SCALE: 1" = 50'
0 25 50 100 FEET
FILE: 2340702\C\2340702-CONSTRAINTS
DWG.:
JOB. NO: 23407.02 SHEET C-100



EROSION AND SEDIMENT CONTROL NOTES

1. THE PROJECT WORK SHALL COMPLY WITH THE 2022 NPDES CONSTRUCTION GENERAL PERMIT FOR MASSACHUSETTS (CGP). A STORMWATER POLLUTION PREVENTION PLAN (SWPPP) SHALL BE PREPARED AND THE CONTRACTOR SHALL COMPLY WITH ALL REQUIREMENTS OF THE SWPPP. THE CONTRACTOR SHALL PROVIDE EVIDENCE THAT A NOTICE OF INTENT (NOI) HAS BEEN FILED FOR COVERAGE UNDER THE CGP AT LEAST 14 DAYS PRIOR TO THE START OF ANY EARTH DISTURBING ACTIVITIES. NO EARTH DISTURBING ACTIVITIES SHALL OCCUR UNTIL THE CONTRACTOR HAS OBTAINED COVERAGE UNDER THE CGP.
2. APPROPRIATE EROSION AND SEDIMENT CONTROL MEASURES SHALL BE INSTALLED PRIOR TO SOIL DISTURBANCE. MEASURES SHALL BE TAKEN TO CONTROL EROSION WITHIN THE PROJECT AREA. SEDIMENT IN RUNOFF WATER SHALL BE TRAPPED AND RETAINED WITHIN THE PROJECT AREA.
3. MINIMIZE TOTAL AREA OF DISTURBANCE AND PROTECT NATURAL FEATURES AND SOIL.
4. THE CONTRACTOR SHALL SEQUENCE ALL ACTIVITIES TO MINIMIZE SIMULTANEOUS AREAS OF DISTURBANCE. MASS CLEARING AND GRADING OF THE ENTIRE SITE SHALL BE AVOIDED.
5. MINIMIZE SOIL EROSION AND CONTROL SEDIMENTATION DURING CONSTRUCTION.
6. DIVERT UNCONTAMINATED WATER AROUND DISTURBED AREAS.
7. INSTALL AND MAINTAIN ALL EROSION AND SEDIMENT CONTROL MEASURES IN ACCORDANCE WITH THE MANUFACTURER'S SPECIFICATIONS AND GOOD ENGINEERING PRACTICES AND IN ACCORDANCE WITH THE 2022 EPA CONSTRUCTION GENERAL PERMIT FOR MASSACHUSETTS.
8. PROTECT AND MANAGE ON AND OFF-SITE MATERIAL STORAGE AREAS (OVERBURDEN AND STOCKPILES OF DIRT, BORROW AREAS, OR OTHER AREAS USED SOLELY BY THE PERMITTED PROJECT SHALL BE CONSIDERED A PART OF THE PROJECT).
9. COMPLY WITH APPLICABLE FEDERAL STATE AND LOCAL LAWS AND REGULATIONS INCLUDING WASTE DISPOSAL, SANITARY OR SEWER REGULATIONS, AND AIR QUALITY REQUIREMENTS, INCLUDING DUST CONTROL.
10. SEDIMENT SHALL BE REMOVED ONCE THE VOLUME REACHES HALF THE HEIGHT OF THE EROSION CONTROL DEVICE. SEDIMENT SHALL BE REMOVED PRIOR TO REACHING THE LOAD-BEARING CAPACITY OF THE SILT FENCE WHICH MAY BE LOWER THAN HALF THE HEIGHT.

EROSION AND SEDIMENT CONTROL NOTES (CONT.)

11. BMPs TO BE USED FOR INFILTRATION AFTER CONSTRUCTION SHALL NOT BE USED AS BMPs DURING CONSTRUCTION UNLESS OTHERWISE APPROVED BY THE ENGINEER. MANY INFILTRATION TECHNOLOGIES ARE NOT DESIGNED TO HANDLE THE HIGH CONCENTRATIONS OF SEDIMENTS TYPICALLY FOUND IN CONSTRUCTION RUNOFF, AND THUS SHALL BE PROTECTED FROM CONSTRUCTION RELATED SEDIMENT LOADINGS.
12. SOIL STOCKPILE SIDE SLOPES SHALL NOT BE GREATER THAN 2H:1V. ALL STOCKPILES SHALL BE SURROUNDED BY SEDIMENT CONTROLS.
13. A TRACKING PAD OR OTHER APPROVED STABILIZATION METHOD SHALL BE CONSTRUCTED AT ALL CONSTRUCTION ENTRANCE/EXIT POINTS OF THE SITE TO REDUCE THE AMOUNT OF SOIL CARRIED ONTO ROADWAYS AND OFF THE SITE.
14. PERMANENT SEEDING SHALL BE UNDERTAKEN IN THE SPRING FROM MARCH THROUGH MAY, AND IN LATE SUMMER AND EARLY FALL FROM AUGUST TO OCTOBER 15. DURING THE PEAK SUMMER MONTHS AND IN THE FALL AFTER OCTOBER 15, WHEN SEEDING IS FOUND TO BE IMPRACTICAL, APPROPRIATE TEMPORARY STABILIZATION SHALL BE APPLIED. PERMANENT SEEDING MAY BE UNDERTAKEN DURING THE SUMMER IF PLANS PROVIDE FOR ADEQUATE MULCHING AND WATERING.
15. TEMPORARY SEDIMENT TRAPPING DEVICES SHALL NOT BE REMOVED UNTIL PERMANENT STABILIZATION IS ESTABLISHED IN ALL CONTRIBUTORY DRAINAGE AREAS.
16. ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES SHALL BE REMOVED AFTER FINAL SITE STABILIZATION. DISTURBED SOIL AREAS RESULTING FROM THE REMOVAL OF TEMPORARY MEASURES SHALL BE PERMANENTLY STABILIZED WITHIN 30 DAYS OF REMOVAL.
17. DUST SHALL BE CONTROLLED AT THE SITE.
18. ALL PREVIOUSLY DISTURBED LAND SHALL BE STABILIZED BY APPROVED METHODS AFTER 14 DAYS IF LEFT UNDISTURBED. THIS INCLUDES STOCKPILES, CONSTRUCTION ENTRANCES, GRADED AREAS AND OTHER CONSTRUCTION ACTIVITY RELATED CLEARING.
19. IF WORK IS HALTED OVER WINTER MONTHS THE CONTRACTOR SHALL BE RESPONSIBLE FOR STABILIZING THE AREA THROUGH GROUND COVER PRACTICES.

GENERAL NOTES:

1. ALL EXISTING UTILITY STRUCTURES, CONDUITS, AND APPURTENANCES OF ANY KIND SHALL BE COMPLETELY REMOVED WITHIN THE LIMITS OF EXCAVATION FOR NEW BUILDINGS. UNLESS NOTED OTHERWISE ON THE DRAWINGS, OUTSIDE THE LIMITS OF EXCAVATION FOR NEW BUILDINGS, ALL ABANDONED AND TO-BE-ABANDONED UTILITIES GREATER THAN 8 INCHES IN DIAMETER SHALL BE SEALED BY FILLING WITH HIGH SLUMP CONCRETE (FLOWABLE FILL) AT THE LIMIT OF EXCAVATION. ALL UTILITY STRUCTURES TO BE REMOVED SHALL HAVE THE ASSOCIATED PIPES REMOVED TO A DISTANCE OF 15 FEET FROM THE STRUCTURE AND SEALED.
2. CONSTRUCTION SETUP IS SHOWN FOR REFERENCE ONLY. EROSION AND SEDIMENTATION CONTROLS TO BE APPROPRIATELY SIZED AND LOCATED/RELOCATED BY THE CONTRACTOR DURING EARTHWORK OPERATIONS.
3. CONTRACTOR SHALL WORK WITH LANDSCAPE ARCHITECT TO DETERMINE SCOPE OF TREE WORK.
4. ALL CONSTRUCTION FENCING AND WARNING SIGNS SHALL BE INSTALLED PRIOR TO ANY CONSTRUCTION. INSTALL CONSTRUCTION FENCING AT THE LIMIT OF WORK.
5. PRIOR TO THE TERMINATION, ABANDONMENT, OR REMOVAL OF ANY UTILITY, VERIFY THAT APPLICABLE NOTIFICATIONS HAVE BEEN MADE TO THE UTILITY OWNER/OPERATOR AND THAT THE UTILITY HAS BEEN PROPERLY TERMINATED, CAPPED, OR PLUGGED AS REQUIRED.
6. PROTECT ALL IMPROVEMENTS NOT INCLUDED IN THE SCOPE OF SITE DEMOLITION. ANY IMPROVEMENT WHICH IS DAMAGED SHALL BE REPAIRED OR REPLACED IN-KIND TO THE OWNER'S SATISFACTION AT NO ADDITIONAL COST.
7. UNLESS OTHERWISE INDICATED, ALL DISTURBED AREAS SHALL BE RESTORED WITH SIX (6) INCHES OF LOAM, SEEDED, FERTILIZED, AND MULCHED. PROVIDE ADDITIONAL EROSION CONTROLS AS REQUIRED.

**ISSUED FOR PERMITTING
NOT FOR CONSTRUCTION**

PROFESSIONAL ENGINEER

**THORNDIKE PLACE
NOTICE OF INTENT**

DOROTHY ROAD
IN
ARLINGTON
MASSACHUSETTS
(MIDDLESEX COUNTY)

SITE PREPARATION PLAN

SEPTEMBER 6, 2023

REVISIONS:

NO.	DATE	DESC.
1	9/12/24	INFILTRATION SYSTEM
2	12/10/24	PEER REVIEW REVISIONS


PREPARED FOR:
ARLINGTON LAND REALTY, LLC
84 SHERMAN STREET, 2ND FLOOR
CAMBRIDGE, MA

BSC GROUP
803 Summer Street
Boston, Massachusetts
02127
617 896 4300

© 2023 BSC Group, Inc.
SCALE: 1" = 30'




FILE: 2340702\C\2340702-PREP
DWG.:
JOB. NO: 23407.02 SHEET C-101



- LEGEND**
- BSC GROUP OCTOBER 2020 WETLAND DELINEATION
 - 25' NO DISTURB ZONE
 - 50' BUFFER
 - 100' BUFFER
 - FLOODPLAIN - ZONE AE (EL. 6.8)

**ISSUED FOR PERMITTING
NOT FOR CONSTRUCTION**



PROFESSIONAL ENGINEER

**THORNDIKE PLACE
NOTICE OF INTENT**

DOROTHY ROAD
IN
ARLINGTON
MASSACHUSETTS
(MIDDLESEX COUNTY)

OVERALL SITE PLAN

SEPTEMBER 6, 2023


REVISIONS:

NO.	DATE	DESC.

PREPARED FOR:
ARLINGTON LAND REALTY, LLC
84 SHERMAN STREET, 2ND FLOOR
CAMBRIDGE, MA

BSC GROUP
803 Summer Street
Boston, Massachusetts
02127
617 896 4300

© 2023 BSC Group, Inc.
SCALE: 1" = 50'
0 25 50 100 FEET
FILE: 2340702\CAD\2340702-SP2
DWG.:
JOB. NO: 23407.02 SHEET C-102



PROFESSIONAL ENGINEER

THORNDIKE PLACE NOTICE OF INTENT

DOROTHY ROAD
IN
ARLINGTON
MASSACHUSETTS
(MIDDLESEX COUNTY)

LAYOUT & MATERIALS PLAN

SEPTEMBER 6, 2023

REVISIONS:

NO.	DATE	DESC.
1	9/12/24	INFILTRATION SYSTEM
2	12/10/24	PEER REVIEW REVISIONS

PREPARED FOR:
ARLINGTON LAND REALTY, LLC
84 SHERMAN STREET, 2ND FLOOR
CAMBRIDGE, MA

BSC GROUP
803 Summer Street
Boston, Massachusetts
02127
617 896 4300

© 2023 BSC Group, Inc.
SCALE: 1" = 30'
0 15 30 60 FEET
FILE: 2340702\C\2340702-LM
JOB. NO: 23407.02 SHEET C-103


ZONING DISTRICT	PUD - PLANNED UNIT DEVELOPMENT	
ZONING CRITERIA	REQUIRED	PROVIDED
MIN LOT AREA	200,000 SF	769,359 SF
MIN FRONT YARD	25*	20.0'
MIN SIDE YARD	25*	30.0'
MIN REAR YARD	25*	20.8' GARAGE / 18.5' UPPER FLOORS
MAX BLDG HEIGHT	85', 5 STORIES	4 STORIES + GARAGE
MAX FAR	0.80	0.22 / 0.69***
LANDSCAPED OPEN SPACE	10%	>10%
USABLE OPEN SPACE	10%	±4%

UNIT COUNTS	REQUIRED	PROVIDED
124 UNITS (ASSISTED LIVING)	50 (0.4 SPACE/UNIT)	118 (SEE BELOW)
12 DUPLEX	24 (2 SPACES/UNIT)	
TOTAL	74	

	PROVIDED	HCP.-ACCESSIBLE REQUIRED
GARAGE	86 (82 STANDARD; 4 HCP. SPACES; ALL OF WHICH ARE VAN-ACCESSIBLE)	MIN. 4 HCP. SPACES - AT LEAST 1 OF WHICH IS VAN-ACCESSIBLE (REFER TO ARCHITECTURAL PLANS)
SURFACE	11 (9 STANDARD; 2 HCP. SPACES, BOTH ARE VAN-ACCESSIBLE)	NONE
DUPLEXES	22 (10 GARAGE/CARPORY; 10 DRIVEWAY; 2 REAR DRIVEWAY)	NONE
TOTAL	119 (113 STANDARD; 6 HCP. SPACES; ALL OF WHICH ARE VAN-ACCESSIBLE)	MIN. 4 HCP. SPACES - AT LEAST 1 OF WHICH IS VAN-ACCESSIBLE

*YARD SETBACKS IN PUD ARE EQUAL TO 1/4 OF THE HEIGHT OF THE AVERAGE OF THE PRINCIPAL BUILDINGS ALONG THE LOT LINE, NO LESS THAN 25'
**AREAS BASED ON LIMITS OF PROJECT DISTURBANCE
***FAR OF 0.22 BASED ON FULL ±17.7 ACRE PARCEL. FAR OF 0.69 BASED ON ±5.66 ACRE PARCEL SHOWN ON PROPOSED CONSERVATION RESTRICTION PLAN.

**ISSUED FOR PERMITTING
NOT FOR CONSTRUCTION**



PROFESSIONAL ENGINEER

THORNDIKE PLACE NOTICE OF INTENT

DOROTHY ROAD
IN
ARLINGTON
MASSACHUSETTS
(MIDDLESEX COUNTY)

GRADING & DRAINAGE PLAN

SEPTEMBER 6, 2023

REVISIONS:


NO.	DATE	DESC.
1	9/12/24	INFILTRATION SYSTEM
2	12/10/24	PEER REVIEW REVISIONS

PREPARED FOR:
ARLINGTON LAND REALTY, LLC
84 SHERMAN STREET, 2ND FLOOR
CAMBRIDGE, MA

BSC GROUP
803 Summer Street
Boston, Massachusetts
02127
617 896 4300

© 2023 BSC Group, Inc.
SCALE: 1" = 30'
0 15 30 60 FEET
FILE: 2340702\C\2340702-GR
DWG.:
JOB. NO: 23407.02 SHEET C-104

ISSUED FOR PERMITTING
NOT FOR CONSTRUCTION



NOTE: FINAL SITE LIGHTING PLANS TO MEET TOWN OF ARLINGTON REGULATION OF OUTDOOR LIGHTING AND SHALL NOT SHINE BRIGHTLY OR CREATE GLARE ON ADJACENT PROPERTIES/STREETS.

PROFESSIONAL ENGINEER

**THORNDIKE PLACE
NOTICE OF INTENT**

DOROTHY ROAD
IN
ARLINGTON
MASSACHUSETTS
(MIDDLESEX COUNTY)

UTILITY PLAN

SEPTEMBER 6, 2023

REVISIONS:


NO.	DATE	DESC.
1	9/12/24	INFILTRATION SYSTEM
2	12/10/24	PEER REVIEW REVISIONS

PREPARED FOR:
ARLINGTON LAND REALTY, LLC
84 SHERMAN STREET, 2ND FLOOR
CAMBRIDGE, MA

BSC GROUP
803 Summer Street
Boston, Massachusetts
02127
617 896 4300

© 2023 BSC Group, Inc.
SCALE: 1" = 30'
0 15 30 60 FEET
FILE: 2340702\C\2340702-UT
DWG.:
JOB. NO: 23407.02 SHEET C-105

**ISSUED FOR PERMITTING
NOT FOR CONSTRUCTION**



- WOODLAND RESTORATION AREA FROM SOUTH EDGE OF EMERGENCY ACCESS DRIVE TO 25' NO DISTURB BUFFER OR CONSERVATION RESTRICTION LINE (SEE PROPOSED CONSERVATION RESTRICTION PLAN)
- REMOVE ALL INVASIVE SPECIES ACCORDING TO ISMP; CUT AND REMOVE (DO NOT STUMP) ALL DEAD TREES THAT POSE A SAFETY HAZARD TO PEOPLE OR PROPERTY AS DETERMINED BY LANDSCAPE ARCHITECT (LA) & WILDLIFE ECOLOGIST (WE) WITH ADMINISTRATIVE APPROVAL OF CONSERVATION COMMISSION; RESTORE AREA WITH NATIVE TREE, SHRUB, AND GRASS PLANTINGS AS DIRECTED BY LA. UTILIZE CUT PLANT MATERIALS TO CONSTRUCT SNAGS AND WILDLIFE HABITATS AS DIRECTED BY LA & WE. ALL PLANTS FOR REMOVAL SHALL BE FLAGGED IN FIELD FOR REVIEW AND APPROVAL BY LA & WE PRIOR TO THE START OF WORK. CONTRACTOR SHALL SUBMIT INVASIVE SPECIES REMOVAL PLAN FOR REVIEW AND APPROVAL BY LA PRIOR TO THE START OF WORK.
- ALL PLANTS FOR REMOVAL SHALL BE FLAGGED IN FIELD FOR REVIEW AND APPROVAL BY LA & WE PRIOR TO THE START OF WORK. CONTRACTOR SHALL SUBMIT INVASIVE SPECIES REMOVAL PLAN FOR REVIEW AND APPROVAL BY LA PRIOR TO THE START OF WORK.

- WOODLAND RESTORATION AREA FROM SOUTH EDGE OF EMERGENCY ACCESS DRIVE TO 25' NO DISTURB BUFFER OR CONSERVATION RESTRICTION LINE (SEE PROPOSED CONSERVATION RESTRICTION PLAN)
- REMOVE ALL INVASIVE SPECIES ACCORDING TO ISMP; CUT AND REMOVE (DO NOT STUMP) ALL DEAD TREES THAT POSE A SAFETY HAZARD TO PEOPLE OR PROPERTY AS DETERMINED BY LANDSCAPE ARCHITECT (LA) & WILDLIFE ECOLOGIST (WE) WITH ADMINISTRATIVE APPROVAL OF CONSERVATION COMMISSION; RESTORE AREA WITH NATIVE TREE, SHRUB, AND GRASS PLANTINGS AS DIRECTED BY LA. UTILIZE CUT PLANT MATERIALS TO CONSTRUCT SNAGS AND WILDLIFE HABITATS AS DIRECTED BY LA & WE. ALL PLANTS FOR REMOVAL SHALL BE FLAGGED IN FIELD FOR REVIEW AND APPROVAL BY LA & WE PRIOR TO THE START OF WORK. CONTRACTOR SHALL SUBMIT INVASIVE SPECIES REMOVAL PLAN FOR REVIEW AND APPROVAL BY LA PRIOR TO THE START OF WORK.
- ALL PLANTS FOR REMOVAL SHALL BE FLAGGED IN FIELD FOR REVIEW AND APPROVAL BY LA & WE PRIOR TO THE START OF WORK. CONTRACTOR SHALL SUBMIT INVASIVE SPECIES REMOVAL PLAN FOR REVIEW AND APPROVAL BY LA PRIOR TO THE START OF WORK.

SEED MIX FOR WOODLAND & FLOODPLAIN RESTORATION AREAS

Botanical Name	Common Name
<i>Asclepias syriaca</i>	Common Milkweed
<i>Asclepias incarnata</i>	Swamp Butterfly Weed
<i>Symphoricarpos racemosa</i>	New England Aster
<i>Chamaecrista fasciculata</i>	Partridge Pea
<i>Elymus canadensis</i>	Canada Wild Rye
<i>Elymus virginicus</i>	Virginia Wild Rye
<i>Festuca rubra</i>	Red Fescue
<i>Rudbeckia laciniata</i>	Green-headed Coneflower
<i>Schizanthus scaberrimus</i>	Little Bluestem
<i>Solidago juncea</i>	Early Goldenrod
<i>Sorghastrum nutans</i>	Indiangrass
<i>Symphoricarpos racemosa</i>	New York Aster
<i>Baptisia tinctoria</i>	Horseshoeweed
<i>Desmodium canadense</i>	Showy Tick Trefail
<i>Euthamia graminifolia</i>	Flat-top Goldenrod
<i>Pycnanthemum virginicum</i>	Virginia Mountain Mint

SEED MIX FOR LAWN AREA


Botanical Name	Common Name
<i>Festuca rubra</i>	Red Fescue
<i>Schizanthus scaberrimus</i>	Little Bluestem
<i>Panicum virgatum</i>	Switch Grass
<i>Elymus virginicus</i>	Virginia Wild Rye
<i>Andropogon gerardii</i>	Big Bluestem
<i>Sorghastrum nutans</i>	Indian Grass
<i>Chamaecrista fasciculata</i>	Partridge Pea
<i>Alopecurus pratensis</i>	Upland Berggrass
<i>Juncus tenuis</i>	Path Rush
<i>Juncus effusus</i>	Soft Rush

HABITATS LEGEND

- COBBLE PILE/BANK/PUDDLE STONE
- BRUSHY THICKET - BRUSH PILE

PLANT SCHEDULE

CODE	QTY	BOTANICAL / COMMON NAME	CONT	CAL	HT	REMARKS
TREES						
AB	14	ABIES BALSAMEA BALSAM FIR	B & B	2-2.5' CAL.		
AS	9	ACER SACCHARINUM SILVER MAPLE	B & B	2.5-3' CAL.		
BL	17	BETULA LENTA SWEET BIRCH	B & B		8-10'	
CC	8	CARPINUS CAROLINIANA AMERICAN HORNBEAM	B & B	2-2.5' CAL.		
CO	4	CELTIS OCCIDENTALIS COMMON HACKBERRY	B & B	2-2.5' CAL.		
NS	16	NYSSA SYLVATICA 'BLACK TUPELO' SOLEL GUM	B & B	2.5-3' CAL.		
PS	4	PINUS STROBUS WHITE PINE	B & B		8-10'	
PW	4	PRUNUS SEROTINA BLACK CHERRY	B & B	2-2.5' CAL.		
QP	4	QUERCUS PALUSTRIS PIN OAK	B & B	2.5-3' CAL.		
SB	4	SALIX NIGRA BLACK WILLOW	B & B	2-2.5' CAL.		
ORNAMENTAL TREES						
AM	4	AMELANCHIER CANADENSIS CANADIAN SERVICEBERRY MULT-TRUNK	B & B	10'-12' CLUMP		
AC	8	AMELANCHIER CANADENSIS CANADIAN SERVICEBERRY	B & B	2.5-3' CAL.		SINGLE STEM
SHRUBS						
IV	13	ILEX GLABRA INKBERRY	2 GAL			
SHRUBS & GROUNDCOVERS						
261		CLETHRA ALNIFOLIA CLETHRA	3 GAL		36" o.c.	
424		GAULTHERIA PROCUMBENS WINTERSGREEN	FLAT		12" o.c.	
74		PIRUS AROMATICA 'GRO-LOW' GRO-LOW FRAGRANT SUMAC	3 GAL		72" o.c.	
320		SPIRAEA TOMENTOSA STEER FISH	2 GAL		36" o.c.	
835		VACCINIUM ANGUSTIFOLIUM LOWBUSH BLUEBERRY	3 GAL		24" o.c.	
200		VERONICASTRUM VIRGINICUM CULVERS FOOT	2 GAL		36" o.c.	



REGISTERED LANDSCAPE ARCHITECT

THORNDIKE PLACE NOTICE OF INTENT

DOROTHY ROAD
IN
ARLINGTON
MASSACHUSETTS
(MIDDLESEX COUNTY)

PLANTING PLAN

SEPTEMBER 6, 2023

REVISIONS:

NO.	DATE	DESC.
1	02/02/24	REVISED FOR SITE AREA
2	02/02/24	REVISED FOR SITE AREA












PREPARED FOR:
ARLINGTON LAND REALTY, LLC
84 SHERMAN STREET, 2ND FLOOR
CAMBRIDGE, MA

BSC GROUP
803 Summer Street
Boston, Massachusetts
02127
617 896 4300

SCALE: 1" = 30'
0 15 30 60 FEET

FILE: \Civil\Drawings\2340700-LM
JOB. NO: 23407.02 SHEET L-100

**ISSUED FOR PERMITTING
NOT FOR CONSTRUCTION**



PROFESSIONAL ENGINEER

THORNDIKE PLACE NOTICE OF INTENT

DOROTHY ROAD
IN
ARLINGTON MASSACHUSETTS (MIDDLESEX COUNTY)

CIVIL & LANDSCAPE DETAILS

SEPTEMBER 6, 2023


NO.	DATE	DESC.
1	9/12/24	INFILTRATION SYSTEM
2	12/10/24	PEER REVIEW REVISIONS

PREPARED FOR:
ARLINGTON LAND REALTY, LLC
84 SHERMAN STREET, 2ND FLOOR
CAMBRIDGE, MA

BSC GROUP
803 Summer Street
Boston, Massachusetts
02127
617 896 4300

© 2023 BSC Group, Inc.
SCALE: AS NOTED


FILE: 2340702\C\2340702-DET
DWG.:
JOB. NO: 23407.02 SHEET C-200




ACCESSIBLE CURB RAMP TYPE 'B' - SINGLE DIRECTION WITH LEVEL ENTRANCE
SCALE: NONE

CURB TRANSITION LENGTH FOR WHEELCHAIR RAMPS	
ROADWAY PROFILE GRADE (%)	TRANSITION LENGTH ROUNDED TO THE NEAREST 4"
0 OR LOW SIDE	6'-6"
>0 - 1	7'-8"
>1 - 2	9'-0"
>2 - 3	11'-0"
>3 - 4	14'-0"
>4	15'-0" (MAX)


- NOTES:**
1. SLOPE TOLERANCE FOR RAMP AND SIDEWALK CONSTRUCTION = ± 0.50%
 2. THE MAX. ALLOWABLE SLOPE OF ACCESSIBLE ROUTE EXCLUDING CURB RAMPS SHALL BE 5%.
 3. THE MAX. ALLOWABLE SLOPE OF ACCESSIBLE ROUTE CURB RAMPS SHALL BE 7.5%.
 4. A MINIMUM OF 3 FEET CLEAR SHALL BE MAINTAINED AT ANY PERMANENT OBSTACLE IN ACCESSIBLE ROUTE (I.E. HYDRANTS, UTILITY POLES, TREE WELLS, SIGNS, ETC.).
 5. BASE OF RAMP SHALL BE GRADED TO PREVENT PONDING.



PEDESTRIAN CROSSWALK MARKINGS
SCALE: NONE




HOT MIX ASPHALT WALKWAY
SCALE: NONE




ACCESSIBLE CURB RAMP TYPE 'E' - PARALLEL PERPENDICULAR WITH LANDSCAPING STRIP
SCALE: NONE

CURB TRANSITION LENGTH FOR WHEELCHAIR RAMPS	
ROADWAY PROFILE GRADE (%)	HIGH SIDE TRANSITION LENGTH ROUNDED TO THE NEAREST 4"
0 OR LOW SIDE	6'-6"
>0 - 1	7'-8"
>1 - 2	9'-0"
>2 - 3	11'-0"
>3 - 4	14'-0"
>4	15'-0" (MAX)


- NOTES:**
1. SLOPE TOLERANCE FOR RAMP AND SIDEWALK CONSTRUCTION = ± 0.50%
 2. THE MAX. ALLOWABLE SLOPE OF ACCESSIBLE ROUTE EXCLUDING CURB RAMPS SHALL BE 5%.
 3. THE MAX. ALLOWABLE SLOPE OF ACCESSIBLE ROUTE CURB RAMPS SHALL BE 7.5%.
 4. A MINIMUM OF 3 FEET CLEAR SHALL BE MAINTAINED AT ANY PERMANENT OBSTACLE IN ACCESSIBLE ROUTE (I.E. HYDRANTS, UTILITY POLES, TREE WELLS, SIGNS, ETC.).
 5. BASE OF RAMP SHALL BE GRADED TO PREVENT PONDING.




FIRE HYDRANT & VALVE
SCALE: NONE




GATE VALVE
SCALE: NONE



HOT MIX ASPHALT PAVEMENT SECTION
SCALE: NONE



CONCRETE STAIRS
SCALE: NONE



CONCRETE THRUST BLOCK FOR PRESSURE PIPE
SCALE: NONE

SIZE OF BRANCH	J	K	L	M	N	O
4" THRU 8"	10"	10"	1'-0"	2'-0"	1'-6"	10"
10" THRU 16"	1'-0"	1'-6"	1'-8"	3'-10"	2'-10"	1'-8"
24"	1'-4"	2'-0"	2'-6"	5'-0"	3'-6"	1'-8"

TEES AND PLUGS

	90 & 45 BENDS	22 1/2 & 11 1/4
D	4"10"8"10"10"16"	24"4" TO 8"10"10"16" 24"
X	1'-8" 3'-4" 3'-6" 1'-4" 2'-0" 3'-6"	
Y	1'-2" 1'-8" 2'-4" 1'-0" 1'-2" 2'-4"	

BENDS

- NOTES:**
1. PROVIDE 3000 PSI CONCRETE THRUST BLOCKS AT ALL BENDS, DEAD ENDS, & TEES UNLESS OTHERWISE DIRECTED. CONCRETE FOR ALL THRUST BLOCKS TO BE PLACED AGAINST FIRM, UNDISTURBED SOIL. PROVIDE APPROVED ANCHOR HARNESS RODS & SOCKET CLAMPS AS SPECIFIED & IN ACCORDANCE WITH PIPE MANUFACTURERS RECOMMENDATIONS WHERE SOIL HAS BEEN DISTURBED OR THRUST BLOCKS CANNOT BE USED, AS DIRECTED BY THE ENGINEER.
 2. ALL SOCKET CLAMP METAL SHALL BE COATED WITH BLACK ASPHALTUM OR OTHER WATER DEPARTMENT APPROVED COATINGS.
 3. CONCRETE THRUST BLOCKS POURED BEHIND 3-WAY TEE & HYDRANT SHOE TO BE USED WITH SOCKET CLAMPS.
 4. NO CONCRETE SHALL COVER PIPE JOINTS, FITTING JOINTS, BOLTS OR HYDRANT DRAINS.

**ISSUED FOR PERMITTING
NOT FOR CONSTRUCTION**

PROFESSIONAL ENGINEER

**THORNDIKE PLACE
NOTICE OF INTENT**

DOROTHY ROAD
IN
ARLINGTON
MASSACHUSETTS
(MIDDLESEX COUNTY)

CIVIL & LANDSCAPE
DETAILS

SEPTEMBER 6, 2023

REVISIONS:





NO.	DATE	DESC.
1	9/12/24	INFILTRATION SYSTEM
2	12/10/24	PEER REVIEW REVISIONS

PREPARED FOR:
ARLINGTON LAND REALTY, LLC
84 SHERMAN STREET, 2ND FLOOR
CAMBRIDGE, MA

BSC GROUP
803 Summer Street
Boston, Massachusetts
02127
617 896 4300

© 2023 BSC Group, Inc.
SCALE: AS NOTED

FILE: 2340702\C\D\2340702-DET
JOB. NO: 23407.02 SHEET C-201







PRECAST CONCRETE DRAIN MANHOLE
SCALE: NONE

PRECAST CONCRETE CATCH BASIN
SCALE: NONE

OUTLET CONTROL STRUCTURE (OCS)
SCALE: NONE

CAST IN PLACE CONCRETE TRENCH DRAIN
SCALE: NONE







WATER QUALITY UNIT (STORMCEPTOR OR APPROVED EQUAL)
SCALE: NONE

WATER QUALITY CATCH BASIN (STORMCEPTOR 450i OR APPROVED EQUAL)
SCALE: NONE

SUMP MANHOLE FROM TRENCH DRAINS
SCALE: NONE

AREA DRAIN
SCALE: NONE



FLARED END SECTION W/ STONE PROTECTION (DISSIPATION BOWL)
SCALE: NONE

FLARED END SECTION W/ STONE PROTECTION (DISSIPATION BOWL)
SCALE: NONE

FLARED END SECTION W/ STONE PROTECTION (DISSIPATION BOWL)
SCALE: NONE

FLARED END SECTION W/ STONE PROTECTION (DISSIPATION BOWL)
SCALE: NONE

PROFESSIONAL ENGINEER

THORNDIKE PLACE NOTICE OF INTENT

DOROTHY ROAD
IN
ARLINGTON MASSACHUSETTS (MIDDLESEX COUNTY)

CIVIL & LANDSCAPE DETAILS

SEPTEMBER 6, 2023

REVISIONS:

NO.	DATE	DESC.
1	9/12/24	INFILTRATION SYSTEM
2	12/10/24	PEER REVIEW REVISIONS

PREPARED FOR:
ARLINGTON LAND REALTY, LLC
84 SHERMAN STREET, 2ND FLOOR
CAMBRIDGE, MA

BSC GROUP
803 Summer Street
Boston, Massachusetts
02127
617 896 4300

© 2023 BSC Group, Inc.
SCALE: AS NOTED


FILE: 2340702\C\2340702-DET
DWG: SHEET C-202

ISSUED FOR PERMITTING
NOT FOR CONSTRUCTION

STORMTRAP INSTALLATION SPECIFICATION

- STORMTRAP MODULES SHALL BE MANUFACTURED ACCORDING TO SHOP DRAWINGS APPROVED BY THE INSTALLING CONTRACTOR AND ENGINEER. THE SHOP DRAWINGS SHALL INDICATE SIZE AND LOCATION OF ROOF OPENINGS AND INLET/OUTLET PIPE OPENINGS.
- STORMTRAP SHALL BE INSTALLED IN ACCORDANCE WITH ASTM C894-09 STANDARD PRACTICE FOR INSTALLATION OF ADJOINING PRECAST CONCRETE UTILITY STRUCTURES. THE FOLLOWING ADDITIONAL REQUIREMENTS SHALL APPLY:
 - SPECIFICATIONS ON THE ENGINEER'S DRAWINGS SHALL TAKE PRECEDENCE.
 - STORMTRAP MODULES SHALL BE PLACED ON LEVEL FOUNDATION (SEE SHEET 3.1) WITH A 1" OVERHANG ON ALL SIDES THAT SHALL BE FOUND IN PLACE BY INSTALLING CONTRACTOR.
 - THE STORMTRAP MODULES SHALL BE PLACED SUCH THAT THE MAXIMUM SPACE BETWEEN ADJACENT MODULES DOES NOT EXCEED 3/4". IF THE SPACES EXCEED 3/4", THE MODULES SHALL BE RESET WITH APPROPRIATE ADJUSTMENT MADE TO LINE AND GRADE TO BRING THE SPACE INTO SPECIFICATION.
 - THE PERIMETER HORIZONTAL JOINT OF THE STORMTRAP MODULES SHALL BE SEALED TO THE FOUNDATION WITH PERFORMED MASTIC JOINT SEALER ACCORDING TO ASTM C818-18 AND 10. SEE DETAIL "A".
 - ALL EXTERIOR JOINTS BETWEEN ADJACENT STORMTRAP MODULES SHALL BE SEALED WITH PERFORMED, GOLD-APPLIED, SELF-ADHESIVE ELASTOMERIC RESIN BONDED TO A WOVEN HIGHLY PUNCTURE RESISTANT POLYMER WRAP CONFORMING TO ASTM C894-09 AND SHALL BE 2" EXTENDED PAST THE JOINT. THE JOINT WRAP SHALL BE ADHESIVE EXTERIOR JOINT WRAP SHALL BE INSTALLED ACCORDING TO THE FOLLOWING INSTALLATION INSTRUCTIONS:
 - USE A BRUSH OR WET CLOTH TO THOROUGHLY CLEAN THE OUTSIDE SURFACE AT THE JOINT (WHERE THE JOINT WRAP IS TO BE APPLIED).
 - A RELEASE PAPER PROTECTS THE ADHESIVE SIDE OF THE JOINT WRAP. PLACE THE ADHESIVE TAPE (BUTYL SIDE DOWN) AROUND THE STRUCTURE. REMOVING THE RELEASE PAPER AS YOU GO. PRESS THE JOINT WRAP FIRMLY AGAINST THE STORMTRAP MODULE SURFACE WHEN APPLYING.

- THE FILL PLACED AROUND THE STORMTRAP UNITS MUST BE DEPOSITED ON BOTH SIDES AT THE SAME TIME AND TO APPROXIMATELY THE SAME ELEVATION. AT NO TIME SHALL THE FILL BEHIND ONE SIDE BE MORE THAN 2" HIGHER THAN THE FILL ON THE OPPOSITE SIDE. BACKFILL SHALL BE COMPACTED TO 95% STANDARD PROCTOR DENSITY OR OTHERWISE SPECIFIED BY ENGINEER. CARE SHALL BE TAKEN TO PREVENT ANY WEIRDING ACTION AGAINST THE STRUCTURE AND ALL SLOPES BEHIND OR WITHIN THE AREA TO BE BACKFILLED MUST BE TYPED OR BEHIND TO PREVENT WEDGE ACTION. REFERENCE ARTICLE 202.10 D.O.T. 5.5 B.B.C. CARE SHALL ALSO BE TAKEN AS NOT TO DISRUPT THE JOINT WRAP FROM THE JOINT DURING THE BACKFILL PROCESS. BACKFILL MATERIAL SHALL BE CLEAN, CRUSHED, ANGULAR No. 5 (ASHTO M4) AGGREGATE.



RECOMMENDED PIPE OPENING SPECIFICATION

- PIPE OPENINGS SHALL MAINTAIN A MINIMUM 1'-0" OF CLEARANCE FROM A VERTICAL EDGE OF THE STORMTRAP UNIT.
- MAXIMUM OPENING SIZE TO BE DETERMINED BY UNIT HEIGHT. PREFERRED OPENING SIZE 3/8" OR LESS. ANY OPENING NEEDED THAT DOES NOT FIT THIS CRITERIA SHALL BE BROUGHT TO THE ATTENTION OF STORMTRAP FOR REVIEW.
- CONNECTING PIPES SHALL BE INSTALLED WITH A 1'-0" CONCRETE COLLAR AND A AGGREGATE COLLAR FOR AT LEAST ONE PIPING BETWEEN A STRUCTURAL GRADE CONCRETE OR GROUT WITH A MINIMUM 28 DAY COMPRESSIVE STRENGTH OF 3000 PSI SHALL BE USED.
- THE ANNUAL SPACE BETWEEN THE PIPE AND THE HOLE SHALL BE FILLED WITH NON-SHRINK GROUT.

RECOMMENDED PIPE INSTALLATION INSTRUCTIONS

- CLEAN AND LIGHTLY LUBRICATE ALL OF PIPE TO BE INSERTED INTO STORMTRAP.
- IF PIPE IS CUT, CARE SHOULD BE TAKEN TO ALLOW NO SHARP EDGES. BEVEL AND LUBRICATE LEAD END OF PIPE.
- ALIGN CENTER OF PIPE TO CORRECT ELEVATION AND INSERT INTO OPENING.

NOTES:


- POROUS ASPHALT AND CHOKER COURSES SHALL MEET THE FOLLOWING REQUIREMENTS:

4" POROUS ASPHALT - SHALL BE POST-BLENDED PG 64-28 SBR WITH 5 POUNDS OF FIBER PER TON OF ASPHALT MIX

- 3/4" = 100%
- 1/2" = 85-100%
- 3/8" = 55-75%
- #4 = 10-25%
- #5 = 5-10%
- #200 = 2-4%
- AIR VOID CONTENT = 16-22%


4" CHOKER COURSE SHALL MEET THE FOLLOWING GRADUATION REQUIREMENTS:

- 1-1/2" = 100%
- 1" = 95-100%
- 1/2" = 25-60%
- #4 = 0-10%
- #6 = 0-5%
- 95% COMPACTION





EMERGENCY ACCESS ROAD

SCALE: NONE



GRASSPAVE (OR APPROVED EQUAL)

SCALE: NONE




RECOMMENDED ACCESS OPENING SPECIFICATION

- TYPICAL ACCESS OPENINGS FOR THE STORMTRAP SYSTEM ARE 3'-0" IN DIAMETER. ACCESS OPENINGS LARGER THAN 2'-0" IN DIAMETER NEED TO BE APPROVED BY STORMTRAP. ALL OPENINGS MUST REMAIN AT LEAST 1'-0" OF CLEARANCE IN ALL DIRECTIONS FROM THE EDGE OF THE STORMTRAP UNITS.
- PLASTIC COATED STEEL STEPS PRODUCED BY MA INDUSTRIES PAK #PSP-PC (SEE DETAIL TO THE RIGHT) ARE PROVIDED. THESE ARE NOT WIPED DEEMED NECESSARY. THE SURFACE OF THE STEP IS TO BE PLACED A MINIMUM 2" FROM THE RISE EDGE OF THE STORMTRAP UNITS. ALL ENDS OF STEPS SHALL BE PLACED WITH A MAXIMUM DISTANCE OF 1/4" BETWEEN STEPS. STEPS MAY BE MOVED OR ALTERED TO AVOID OPENINGS OR OTHER IRREGULARITIES IN THE UNIT.
- STORMTRAP LIFTING INSERTS MAY BE RELOCATED TO COINCIDE WITH THE ACCESS OPENING OR THE CENTER OF GRAVITY OF THE UNIT AND NECESSARY.
- STORMTRAP ACCESS OPENINGS MAY BE RELOCATED TO AVOID INTERFERENCE WITH INLET AND/OR OUTLET PIPE OPENINGS SO PLACEMENT OF STEPS IS ATTAINABLE.
- ACCESS OPENINGS SHOULD BE LOCATED IN ORDER MEET THE APPROPRIATE MUNICIPAL REQUIREMENTS. STORMTRAP RECOMMENDS AT LEAST ONE ACCESS OPENING PER SYSTEM FOR ACCESS AND INSPECTION.
- USE PRECAST ADJUSTING RINGS AS NEEDED TO MEET GRADE. STORMTRAP RECOMMENDS FOR COVER OVER 2" TO USE PRECAST BARREL OR CONE SECTIONS (BY OTHERS).

STORMTRAP SINGLE TRAP (SECTION VIEW)

NOTE: ONE ACCESS TO BE PROVIDED ON EACH DUPLEX INFILTRATION SYSTEM. TOTAL ACCESS RISERS TO BE PROVIDED ON MAIN INFILTRATION SYSTEM - ONE ON EACH UNIT WITH AN INLET OR OUTLET PIPE.




R-TANKXD PANEL

SCALE: NONE

UNDERGROUND INFILTRATION (STORMTRAP SINGLE TRAP OR APPROVED EQUAL)

SCALE: NONE



- TOTAL COVER: 6" MINIMUM AND 200" MAXIMUM. INITIAL COVER UP TO 12" MUST BE FREE DRAINING BACKFILL (SPEC SECTION 2.03B): STONE <1.5" OR SOIL (USCS CLASS GW, GP, SW OR SP). ADDITIONAL FILL MAY BE STRUCTURAL FILL (SPEC SECTION 2.03C): STONE OR SOIL (USCS CLASS SM, SP, SW, GM, GP OR GW) WITH MAX CLAY CONTENT <10%, MAX 25% PASSING NO. 200 SIEVE, AND MAX PLASTICITY INDEX OF 4. CONTACT FERGLUSON WATERWORKS IF MORE THAN 200" OR LESS THAN 6" OF TOP BACKFILL IS REQUIRED (FROM TOP OF TANK TO TOP OF PAVEMENT).
- NOTES:
- FOR COMPLETE MODULE DATA, SEE APPROPRIATE R-TANKXD MODULE SHEET.
 - INSTALLATIONS PER THIS DETAIL MEET GUIDELINES OF HL-93 LOADING PER THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS, CUSTOMARY U.S. UNITS, 7TH EDITION, 2014 WITH 2015 AND 2016 INTERIM REVISIONS.
 - PRE-TREATMENT STRUCTURES NOT SHOWN.
 - FOR INFILTRATION APPLICATIONS, GEOTEXTILE ENVELOPING R-TANK SHALL BE ACF #200 (PER SPEC SECTION 2.02A) AND BASE SHALL BE 4" MIN. UNCOMPACTED FREE DRAINING BACKFILL (SPEC SECTION 2.03A) TO PROVIDE A LEVEL BASE. SURFACE MUST BE SMOOTH, FREE OF LUMPS OR DEBRIS, AND EXTEND 2' BEYOND R-TANKXD FOOTPRINT.

- UTILITY MARKERS AT CORNERS (TYP.)
- PAVED SURFACE
- COVER FROM FINISH GRADE TO TOP OF TANK: 6" (0.15 m) MIN TO 200" (5.08 m) MAX
- INLET PIPE
- R-TANKXD UNITS WRAPPED WITH 8 OZ. NON-WOVEN GEOTEXTILE (OR EQUAL) LOADING RATING: 240.2 PSI (MODULE ONLY)
- SUBGRADE / EXCAVATION LINE: COMPACT PER SPEC SECTION 3.02 D. A BEARING CAPACITY OF 2,000 PSF MUST BE ACHIEVED PRIOR TO INSTALLING R-TANKXD (GEOTEXTILE OR IMPERMEABLE LINER OPTIONAL)
- BASE: 3" MIN. FREE DRAINING BACKFILL (SPEC SECTION 2.03B) COMPACTED TO 95% STANDARD PROCTOR DENSITY IS REQUIRED TO PROVIDE A LEVEL BASE SURFACE. MUST BE SMOOTH, FREE OF LUMPS OR DEBRIS, AND EXTEND 2' BEYOND R-TANKXD FOOTPRINT. NATIVE SOILS MAY BE ACCEPTABLE IF DETERMINED TO BE STABLE BY OWNER'S ENGINEER.
- SIDE BACKFILL: 24" MIN. OF FREE DRAINING BACKFILL (SPEC SECTION 2.03B): STONE <1.5" OR SOIL (USCS CLASS GW, GP, SW OR SP). MUST BE FREE FROM LUMPS, DEBRIS AND OTHER SHARP OBJECTS. SPREAD EVENLY TO PREVENT R-TANKXD MOVEMENT. COMPACT SIDE BACKFILL WITH POWERED MECHANICAL COMPACTOR IN 12" LIFTS.

R-TANKXD HS20-25 LOADS - SECTION VIEW

SCALE: NONE

PROFESSIONAL ENGINEER

THORNDIKE PLACE NOTICE OF INTENT

DOROTHY ROAD
IN
ARLINGTON
MASSACHUSETTS
(MIDDLESEX COUNTY)

CIVIL & LANDSCAPE DETAILS

SEPTEMBER 6, 2023

REVISIONS:

NO.	DATE	DESC.
1	9/12/24	INFILTRATION SYSTEM
2	12/10/24	PEER REVIEW REVISIONS

PREPARED FOR:
ARLINGTON LAND REALTY, LLC
84 SHERMAN STREET, 2ND FLOOR
CAMBRIDGE, MA

BSC GROUP
803 Summer Street
Boston, Massachusetts
02127
617 896 4300

© 2023 BSC Group, Inc.
SCALE: AS NOTED

FILE: 2340702\C\2340702-DET
JOB. NO: 23407.02 SHEET C-203

ISSUED FOR PERMITTING
NOT FOR CONSTRUCTION

JANUARY 2, 2025

Town of Arlington Conservation Commission
c/o Mr. David Morgan, Environmental Planner + Conservation Agent
Robbins Memorial Town Hall
730 Massachusetts Avenue
Arlington, Massachusetts 02476

**RE: Restoration Plan and Invasive Species Management Plan
Thorndike Place Residential Development**

Dear Members of the Arlington Conservation Commission,

At the previous public hearing on the Project, a Commission member did not recall concluding discussions on the Restoration Plan and Invasive Species Management Plan (ISMP) for the above referenced project. As such, we are providing the following, attached information:

1. A letter to the Commission from Mr. P. Chase Bernier, CWB, PWS, CERP, of SWCA Environmental Consultants (SWCA), dated March 27, 2024, *Re: Notice of Intent Restoration Plan Peer Review – Review of Response to Comments, Thorndike Place, Arlington, Massachusetts*. In this letter, SWCA, as peer review consultant for the Commission, confirms adequate response to all except one of their previous review comments. This letter was submitted by SWCA to the Commission in March 2024.
2. A letter to the Commission from Mr. Matt Burne, PWS, Senior Ecologist at BSC Group (BSC), dated April 4, 2024, *RE: Notice of Intent, SWCA Notice of Intent Restoration Plan Peer Review, Thorndike Place Residential Community, Dorothy Road, Arlington, MA*. In this letter, previously submitted to the Commission, BSC details our response to the lone outstanding comment from SWCA's March 27, 2024, letter.
3. The meeting minutes from the Conservation Commission's April 4, 2024, public meeting on the Project Thorndike Place minutes begin on page 9). We have highlighted two portions of this discussion for reference. On page 11, there is a notation of Chase Bernier of SWCA concurring that Japanese knotweed requires herbicide to treat effectively. On page 12, there is a notation that "The Commission has completed the portion of the hearing dealing with the habitat and invasive management portion of the application, and going forward, will focus on the stormwater portion."

We believe that these documents clearly demonstrate that the peer review on the restoration and ISMP portion of the project is complete and that the Commission has completed discussion on this matter.

Sincerely,
BSC GROUP, INC.



Dominic Rinaldi, PE
Senior Associate

Attachments: March 27, 2024, SWCA Review Letter
April 4, 2024, BSC Response to Review
April 4, 2024, Conservation Commission Meeting Minutes



ENVIRONMENTAL CONSULTANTS

Sound Science. Creative Solutions.®

1900 West Park Drive, Suite 280
Westborough, Massachusetts 01581
Tel 413.256.0202
www.swca.com

March 27, 2024

Ryan Clapp
Arlington Conservation Commission
730 Massachusetts Avenue Annex
Arlington, MA 02476

**Re: Notice of Intent Restoration Plan Peer Review – Review of Response to Comments
Thorndike Place, Arlington, Massachusetts**

Dear Mr. Clapp and Members of the Commission:

SWCA Environmental Consultants (SWCA) submitted a peer review letter report dated January 23, 2024 for a proposed restoration plan as part of the proposed Thorndike Place Residential Community Notice of Intent (NOI). In response to that report, BSC Group, Inc. (BSC), submitted a response to comments letter dated February 7, 2024, including revised plan materials. SWCA completed a review of those responses revised NOI documents on March 6, 2024. BSC submitted additional revised materials for review on March 7, 2024 (Invasive Species Management Plan [ISMP]) and March 12, 2024 (Response to Comments response and revised restoration plans). This correspondence represents SWCA’s review of those revised materials.

PROJECT NARRATIVE

Project Activities & Associated Impacts

SWCA Comment 1: Section 3.1.1, second paragraph. The narrative states that dead trees (i.e., snags) that do not provide wildlife habitat will be cut and stumped. Snags provide a wide variety of valuable wildlife habitat functions including shelter and forage opportunities. It is doubtful there are any snags that do not provide any wildlife habitat functions. Additionally, removal of snags does not appear to provide any ecological benefit and stumping of snags within the restoration area would likely result in unnecessary additional impacts (e.g., soil disturbance).

SWCA recommends that this language be revised to indicate that only snags that pose a hazard (e.g., leaning towards the proposed buildings and likely to result in property damage or injury) be removed and that no stumping will occur. SWCA recommends the Commission also consider a condition in the Order of Conditions (OOC), if issued, stating that any snags to be removed shall be approved by the Commission.

BSC Response 1: BSC concurs with the recommended revision and suggests a Special Condition allowing removal of snags from the proposed restoration area that pose a hazard (e.g., leaning toward buildings and/or likely to result in property damage or personal injury) and that no stumping of removed snags shall be permitted. We additionally recommend that the Special Condition allow for a

representative of the Commission be authorized to coordinate, review, and approve any snag removal on behalf of the Commission to avoid construction delays.

SWCA Response 1: SWCA agrees with this response and approach. No further response required.

SWCA Comment 2: Section 3.1.1, second paragraph. The narrative states that an Invasive Species Management Plan (ISMP) for work within resource areas and their buffer zones shall be developed as required by the Comprehensive Permit. During the site walk on January 5, representatives from BSC indicated that invasive species control would be included as part of the proposed restoration efforts. It is unclear how invasive species would be controlled (e.g., mechanical removal, chemical control, etc.) or what the target species would be.

SWCA recommends the Applicant develop a detailed ISMP to be included as part of the NOI that details what the target invasive species will be, proposed specific control methodologies, a monitoring plan to measure invasive vegetation control success, and performance goals. SWCA recommends the ISMP be reviewed by an expert in invasive species removal as some species (e.g., Japanese knotweed [*Reynoutria japonica*]) can be extremely challenging to effectively control.

BSC Response 2: Several invasive plant species occur on the site, most notably Japanese knotweed, oriental bittersweet (*Celastrus orbiculatus*), and garlic mustard (*Alliaria petiolata*). These occur within jurisdictional resource areas and buffer zones, as well as within non-jurisdictional areas of the site.

BSC and the Applicant will prepare an Invasive Species Management Plan (ISMP) to treat invasive plants currently within the proposed wetland restoration area and to control their spread within the restoration area. BSC recommends that approval of such ISMP by the Commission's representative prior to the start of work be made a Special Condition of an OOC for the project.

SWCA Response 2-1: SWCA recommends that the ISMP be submitted to the Commission and reviewed by an expert in the control of invasive species prior to the issuance of an OOC. Effective control of invasive plants is critical to the success of any ISMP and may require complex management methodologies given the extent and diversity of invasive species on the site. Review of the ISMP prior to OOC issuance ensures the ISMP will be effective and that the Commission has the ability to guarantee that the plan is adequate prior to permit issuance.

BSC Response 2-1: BSC submitted a proposed ISMP for peer review on March 7, 2024.

SWCA Response 2-2: *In SWCA's experience, the most effective way to manage sites similar to the proposed project is to utilize an adaptive management approach. The mechanical, manual, and chemical options appear to be presented as if only one can be chosen for each species. For example, common reed (*Phragmites australis*) and Japanese knotweed, benefit from a combined approach (e.g., cutting first at the appropriate time and then treating with herbicide at the appropriate time. There also appears to be consistent issue throughout the ISMP of misrepresenting the proposed concentrations of herbicide and not mentioning that the chose herbicide label must be followed.*

SWCA recommends the ISMP be adaptive and that sticking to a strict pre-set and unchangeable schedule from year to year is not in the best interest of achieving effective invasive management. However, the first year's schedule should be specifically laid out. Depending on when construction is expected to commence (e.g., clearing, grading, etc.) the method of moving forward with treating invasive vegetation may need to be revised. If the exact start date of construction is unknown, the ISMP should be reframed that stresses the qualified invasive applicator/specialist can decide what treatment method and

timing should be utilized based on site conditions. SWCA also recommends the Applicant either check the label and edit the percentages of herbicide or revise the ISMP to specify that the label rates will be followed.

SWCA Comment 3: Section 3.1.1. The narrative includes multiple references to refuse that has been dumped on the site over the years. During the site walk on January 5, it was noted that as part of the proposed restoration work, the refuse would be removed as much as practicable.

SWCA recommends the Commission include a condition in the OOC, if issued, that requires all surficial refuse, including discarded clothing, metal, concrete rubble, lumber, plastic, and other similar garbage, to be removed from within the resource areas and their associated buffer zones within the limit of work. SWCA also recommends the Commission indicate that any refuse at the surface and partially buried be removed to a depth of up to 12 inches below ground (e.g., a shopping cart that has become partially buried in the soil).

BSC Response 3: BSC concurs with SWCA Comment 3 and agrees such a Condition be included as part of the OOC.

SWCA Response 3: No further response required.

SWCA Comment 4: Section 3.1.1. The narrative provides a brief discussion of the proposed restoration activities, specifically restoration plantings. However, successful habitat restorations consider a wide variety of considerations, beyond vegetation. More specifically, the wildlife habitat and vegetation evaluation provided in Attachment G of the NOI identifies numerous wildlife habitat features including large woody debris, snags, hard mast and berry producing forage, rocks and rock piles, and others.

SWCA recommends the restoration plan consider how to improve important wildlife habitat functions within the restoration area and include methods to provide important wildlife habitat features that may be lost due to proposed impacts elsewhere on site.

BSC Response 4: The Restoration Plan has been updated to include proposed placement of coarse woody debris and stones and a few stone piles using natural materials originating from within the limit of work on the project site. The Restoration Plan maximizes the use of native berry and mast producing vegetation to benefit wildlife habitat values of the restoration area. See Appendix for details of wildlife habitat features.

SWCA Response 4: SWCA concurs with these revisions. No further response required.

SWCA Comment 5: Section 3.1.1. The narrative and the wildlife habitat and vegetation evaluation identify numerous native and non-native trees and shrubs within the project limit of work, including the restoration area. However, out of the 17 proposed trees and shrubs to be planted, only two (red maple [*Acer rubrum*] and American hornbeam [*Carpinus carolineana*]) are included on the plant schedule.

SWCA recommends the restoration plan be revised to include species within the restoration area that occur on-site to better represent the diversity and community structure of adjacent habitats. There are numerous trees and shrubs documented in the NOI application materials that would be suitable for the restoration area including American elm (*Ulmus americana*), black cherry (*Prunus serotina*), yellow birch (*Betula allegheniensis*), sweet birch (*Betula lenta*), box elder (*Acer negundo*), silver maple (*Acer saccharinum*), white pine (*Pinus strobus*), sycamore (*Platanus occidentalis*), black willow (*Salix nigra*), and others that are also typically readily available as nursery stock.

BSC Response 5: BSC concurs with SWCA Comment 5 and has updated the proposed planting plan and shown approximate locations of wildlife habitats.

SWCA Response 5-1: The proposed planting plan still includes multiple species that are not representative of the of the diversity and community structure of the adjacent habitats (e.g., Atlantic white cypress [*Chamaecyparis thyoides*] and others). SWCA recommends the planting plan be revised to includes species that better represent the adjacent communities within the restoration area.

BSC Response 5-1: Please refer to Sheet L-100. No tree is proposed within the restoration area or compensatory flood storage area that is not specifically listed in SWCA Comment 5. BSC is providing a color-markup of the restoration planting sheet to clarify proposed species placements.

It should be noted that the planting plan is for the entire project site, including areas outside of the Commission’s jurisdiction.

The proposed woodland and floodplain restoration seed mixes are as follows:

Botanical Name	Common Name
<i>Asclepias syriaca</i>	Common milkweed
<i>Asclepias incarnata</i>	Swamp butterfly weed
<i>Symphotrichum novae-angliae</i>	New England aster
<i>Chamaecrista fasciculata</i>	Partridge pea
<i>Elymus canadensis</i>	Canada wild rye
<i>Elymus virginicus</i>	Virginia wild rye
<i>Festuca rubra</i>	Red fescue
<i>Redbeckia laciniata</i>	Green-headed coneflower
<i>Schizachyrium scoparium</i>	Little bluestem
<i>Solidago juncea</i>	Early goldenrod
<i>Sorghastrum nutans</i>	Indian grass
<i>Symphotrichum novi-belgii</i>	New York aster
<i>Baptisia tinctoria</i>	Horseflyweed
<i>Desmodium canadense</i>	Show tick-trefoil
<i>Euthamia graminifolia</i>	Flat-top goldenrod
<i>Pycnanthemum virginianum</i>	Virginia mountain mint

SWCA Response 5-2: *SWCA concurs with these revisions. No further response required.*

SITE PLANS

SWCA Comment 6: Sheet G-101, Planting Notes, Note 11. The site plans indicate that the plant species indicated on the plant list are recommendations only and that final selection of the species shall occur at the time of plant purchase, depending on availability and that the size and quantity shall not change without approval of the Applicant’s landscape architect.

SWCA recommends this note be revised to indicate that the proposed planting species, sizes, and quantities may be subject to change based on availability. However, these changes should be approved by the Conservation Commission and should be approved prior to purchase.

BSC Response 6: BSC has made the recommended revision to the Sheet G-101 Planting Notes, Note 11. We recommend that the OCC allow administrative approval of such availability-based changes by the Conservation Commission or its authorized representative to prevent undue construction delays in making such substitutions if necessary.

SWCA Response 6: SWCA agrees with these revisions. No further response required.

SWCA Comment 7: Sheet G-101, Comprehensive Permit Notes, Comment I.5. This comment notes that dumping of woody vegetation, brush, and other debris in a resource area or its associated buffer zone is prohibited.

SWCA notes that an exception to this requirement might be considered for the restoration area as large woody debris, brush piles, and other similar wildlife habitat features provide quality habitat functions and are likely to increase the ecological value of the restored habitats.

BSC Response 7: Sheet G-101, Comprehensive Permit Notes, Comment 1.5 is a Condition of the Comprehensive Permit, and the wording is copied directly from that Condition. The intent of the Condition is to prohibit the dumping of materials removed during construction in the wetlands or buffer zone. In accordance with BSC Response 4 above, the Restoration Plan will be updated with detailed natural coarse woody debris and stone wildlife habitat features using materials originating from the site, but material removed from the site during construction will not be disposed of within resource areas or associated buffer zones in accordance with the Comprehensive Permit condition.

SWCA Response 7: SWCA agrees with this approach. No further response required.

SWCA Comment 8: Sheet G-101, Comprehensive Permit Notes, Comment I.25. The site plans note that the survival rate of planted species shall be 80% at the end of the third year and that a corrective action plan must be submitted if the survival rate is less than 80% at the end of the third year.

SWCA recommends the Commission consider requiring a corrective action plan to be developed by the Applicant if the 80% success rate is not met after any year of monitoring. Waiting until the third year of monitoring to develop and implement any corrective actions may unnecessarily prolong reaching the project's performance goals and may result in unnecessary disturbance to the area to rectify any adverse conditions since the restoration area will have had three years to establish.

BSC Response 8: Sheet G-101, Comprehensive Permit Notes, Comment I.25 is a condition of the Comprehensive Permit, and the wording is copied directly from that Condition. The Comprehensive Permit Condition was prepared upon the recommended conditions submitted to the Zoning Board by the Conservation Commission by letter dated October 14, 2021.

SWCA Response 8: No further response required.

SWCA Comment 9: Sheet L-100, Plant Schedule. The plant schedule includes a number of proposed cultivars within the 100-foot Buffer Zone (e.g., *Clethra alnifolia* 'ruby spice', *Hydrangea quercifolia* 'ruby slippers', and *Hydrangea arborescens* 'annabelle'). In accordance with condition I.24 of the Comprehensive Permit, all mitigation plantings and plantings within all resource areas shall be native, non-cultivar species. Additionally, other cultivars are proposed in other areas of the site along side non cultivars of native species (e.g., pin oak [*Quercus palustris*] and green pillar pin oak [*Q. palustris* 'pringreen']).

SWCA recommends the planting plan be revised to not include any cultivars.

BSC Response 9: BSC concurs with SWCA Comment 9 and has revised the planting plan to not include cultivars within the 100-foot buffer.

SWCA Response 9-1: The revised planting plan continues to propose a number of cultivars within the 100-foot Buffer Zone. Other cultivars are still proposed in other areas of the site.

SWCA recommends the planting plan be revised to not include any cultivars. SWCA also encourages the Applicant to utilize non-cultivars of native species throughout the site.

BSC Response 9-1: BSC has revised the proposed restoration planting plan to remove cultivars and has revised the proposed seed mixes for the restoration and compensatory flood storage areas to contain only native plants. The lawn seed mix has also been revised to contain only native species.

It should be noted that the planting plan is for the entire project site, including areas outside of the Commission's jurisdiction. There is one plant proposed that is a non-native landscaping plant, but it is proposed to be located along the walking path between the buildings, outside of the Commission's jurisdiction.

SWCA Response 9-2: SWCA concurs with these revisions. No further response required.

SWCA Comment 10: Sheet L-100. A note on the plans indicates that all dead trees (i.e., snags) that do not provide wildlife habitat per the landscape architect and wildlife ecologist should be removed. Snags provide a wide variety of valuable habitat functions for wildlife including forage for insects, perches to hunt from, shelter if there are cavities or cracks, and other functions.

SWCA recommends this note be revised to indicate that only snags that pose a hazard (e.g., may fall and land on the buildings) may be removed and that removal of any snags must be approved by the Commission.

BSC Response 10: BSC concurs with SWCA Comment 10 and has revised Sheet L-100 according to SWCA's Comments 1 and 10.

SWCA Response 10-1: This note does not appear to indicate that removal of any snags must be approved by the Commission.

SWCA recommends revising this note as to indicate that Commission approval is required for snag removal.

BSC Response 10-1: The note on Sheets L-100 has been updated to state, "2. Remove all invasive species according to ISMP; cut and remove (do not stump) all dead trees that pose a safety hazard to people or property as determined by Landscape Architect (LA) & Wildlife Ecologist (WE) with administrative approval of Conservation Commission; restore areas with native tree, shrub, and grass plantings as directed by LA. Utilize cut plant materials to construct snags and wildlife habitats as directed by LA & WE.

SWCA Response 10-2: SWCA concurs with these revisions. No further response required.

If you have any questions or comments, please do not hesitate to contact me at either (508) 232-6668 or chase.bernier@swca.com.

Sincerely,



P. Chase Bernier, CWB, PWS, CERP
Senior Natural Resources Team Lead

APRIL 4, 2024

www.bscgroup.com

Arlington Conservation Commission
730 Mass Ave Annex
Arlington, MA 02476

**RE: Notice of Intent
SWCA Notice of Intent Restoration Plan Peer Review
Thorndike Place Residential Community
Dorothy Road, Arlington, MA**

Dear Members of the Arlington Conservation Commission:

On behalf of Arlington Land Realty, LLC (the Applicant), BSC Group, Inc. respectfully presents the following response to SWCA's peer review report dated March 27, 2024. The March 27 letter provides closure on nine (9) out of the ten original comments, finding that there is "no further response required" to Comments 1 and 3 – 10. SWCA Comment 2 pertains to the ISMP required under the Comprehensive Permit for this project which was submitted to the Commission and to SWCA for review on March 7, 2024.

From the March 27, 2024 SWCA Peer Review letter:

*SWCA Response 2-2: In SWCA's experience, the most effective way to manage sites similar to the proposed project is to utilize an adaptive management approach. The mechanical, manual, and chemical options appear to be presented as if only one can be chosen for each species. For example, common reed (*Phragmites australis*) and Japanese knotweed, benefit from a combined approach (e.g., cutting first at the appropriate time and then treating with herbicide at the appropriate time. There also appears to be consistent issue throughout the ISMP of misrepresenting the proposed concentrations of herbicide and not mentioning that the chose herbicide label must be followed.*

SWCA recommends the ISMP be adaptative and that sticking to a strict pre-set and unchangeable schedule from year to year is not in the best interest of achieving effective invasive management. However, the first year's schedule should be specifically laid out. Depending on when construction is expected to commence (e.g., clearing, grading, etc.) the method of moving forward with treating invasive vegetation may need to be revised. If the exact start date of construction is unknown, the ISMP should be reframed that stresses the qualified invasive applicator/specialist can decide what treatment method and timing should be utilized based on site conditions. SWCA also recommends the Applicant either check the label and edit the percentages of herbicide or revise the ISMP to specify that the label rates will be followed.

BSC Response 2-2-1:

BSC is recommending an Invasive Species Management Plan that relies on the best management practices (BMP) and professional judgment of a Senior Botanist with many years of successful invasive plant management experience. An adaptive strategy that combines both mechanical and chemical approaches to maximize control of invasives while minimizing unintended impacts is presented (ISMP, page 9). It is our intent to utilize mechanical control methods to the extent practical and minimize the duration and intensity of any chemical controls employed.

The management techniques chosen for this project are specific to this location based on the species found there, proposed future activities, and specific site conditions. The proposed invasive plant species management techniques are the BMPs for this location. For example, while common reed isn't presently within the treatment area, it was included as a potential future species due to its current presence in proximity to the treatment area. Including this species as a potential future invasive species was intended as a dimension of our adaptive management approach.

BSC disagrees with the reviewer's suggestion that pre-cutting Japanese knotweed and/or Phragmites is the best approach based on the potential timing of this project and the specific reproductive biology of this plant. It is well established that both Japanese knotweed and Phragmites spread via cuttings of the stems and rhizomes. Severing plants before chemical treatment will counterproductively spur additional growth and reduce the effectiveness of chemical treatments. In our Senior Botanist's experience, plants that have been chemically treated after being cut in the same season have a decreased probability of successful eradication and instead require increased subsequent chemical use for successful treatment – which we seek to avoid.

The Invasive Species Management Plan developed for Thorndike Place is intended to be an adaptive management plan. The timetables reflect an ability to initiate the ISMP at any time of year depending on a construction schedule that will be determined in the future. We prescribe specific treatment times depending on the specific requirements of the species on the site, i.e. knotweed must be treated after flowering during September and cut-stump treatments should only be performed between July 1 and December. The purpose of the proposed treatment timetable is to allow initiation of treatment at any point in the year, with proper treatment recommendations that fall sequentially into place after the ISMP initiation.

In all cases, the intent of our adaptive approach is to use both mechanical and chemical approaches as appropriate with the overall goal of maximizing successful eradication of invasives utilizing chemical controls in the lowest concentration consistent with best management practices.

It should go without saying that any herbicide applicator will be fully licensed and trained and required to follow the law (i.e.: the label) when applying herbicide. The submitted ISMP does not recommend any deviation from product labels for any specific herbicide and is consistent with standard best management practice for their use.

We look forward to an opportunity to discuss these revisions with the Commission and its Peer Review consultant at the upcoming hearing. Mr. Groves will again be available to discuss the ISMP and is also available to answer questions that may come up during the hearing.

If you have any questions regarding the enclosed information, please contact me at (617) 896-4594 or mburne@bscgroup.com. Thank you for your consideration in this matter.

Thank you,
BSC Group, Inc.



Matt Burne, PWS
Senior Ecologist

cc: Stephanie Kiefer



Arlington Conservation Commission

Date: April 4, 2024

Time: 7:00 PM

Pursuant to State Legislation suspending certain provisions of the Open Meeting Law, G. L. c. 30A, § 20 the meeting was held virtually using Zoom.

Attendance [0:06:45]

Commissioners:	Susan Chapnick (Chair)	Brian McBride
	Chuck Tirone (Vice Chair)	Nathaniel Stevens
	Mike Gildesgame	David White
	David Kaplan	

Conservation Agent: David Morgan

Associate Commissioners: Eileen Coleman Sara Alfaro-Franco

Agenda

I. Administrative

1. Review Meeting Minutes.

- N. Stevens made a motion to approve the minutes of 3/7/2024 as amended. M. Gildesgame seconded the motion. A roll call vote was taken:

C. Tirone – yes	S. Chapnick – yes	M. Gildesgame – yes
D. Kaplan – yes	B. McBride – yes	N. Stevens – yes
D. White – yes		

 Motion passed.

2. Correspondence Received.

- The Chair noted that all correspondence received is available for the public to review by contacting D. Morgan.

II. Discussion [0:14:56]

1. Water Bodies Working Group.

- D. White said that the Working Group requested \$120,000 for FY2025. The Finance Committee approved \$85,000.
- N. Stevens made a motion to appoint E. Coleman to the Water Bodies Working Group. B. McBride seconded the motion. A roll call vote was taken:

C. Tirone – yes	S. Chapnick – yes	M. Gildesgame – yes
D. Kaplan – yes	B. McBride – yes	N. Stevens – yes
D. White – yes		

 Motion passed.



- The next meeting of the Working Group is next Thursday at 6:00 pm. D. White will send out an agenda.
 - D. White noted that a new aerator for Hill's Pond will be purchased.
2. Tree Committee Update.
- S. Alfaro-Franco said that the Tree Committee plans to plant 150 trees this spring season. They are a month and a half ahead of schedule because of the weather.
3. Artificial Turf Study Committee Update.
- The next meeting, which will probably be the final meeting, will be Tuesday, April 9, 2024. The Study Committee is concluding its work. They have issued a draft report and posted it on their web page. That report will soon be finalized.
4. Arlington High School Permit Extension (DEP #091-0323). [0:19:58]
- The team members introduced themselves:
 - Jeff Thielman, Arlington High School (AHS) Building Committee Chair
 - Kirsi Allison-Ampe, School Committee Chair, AHS Building Committee Member
 - Jim Feeney, Town Manager
 - Liz Homan, School Superintendent
 - John Amato, JJA Sports, Sports Field Designer
 - Steve Garvin, Civil Engineer, Samiotes Consultants
 - Laurie Coles, HMFH Architects
 - Arthur Duffy, HMFH Architects
 - Jim Burrows, Skanska, OPM
 - Matthew Janger, AHS Principal
 - J. Thielman said that the AHS Building Committee is requesting an extension of the Order of Conditions granted by the Commission in 2020 for the synthetic turf fields for the new Arlington High School. During early community discussions and the 2019 voter approval of the project, synthetic turf fields have always been proposed. To remain on schedule and on budget, the infill for the synthetic fields must be ordered by June 30, 2024, less than 90 days from this meeting.
 - In the summer of 2020, the Conservation Commission reviewed plans for the turf fields and concluded that the fields as designed did not have a significant or cumulative effect on the wetland values protected by the bylaw, and the Commission granted an Order of Conditions. In 2021, the Town signed seven contracts for work to be performed on the fields; by 2023, some of the systems supporting the fields were built. In July 2023, the AHS Building Committee applied for an extension of the 2020 Order of Conditions. During the meeting, the Commission was told about new information pertaining to 6PPD and 6PPD-quinone. When this information was given to the Building Committee in August 2023, the Committee agreed to evaluate the costs, risks, and benefits of crumb rubber and alternative infills and study the applicability of the research to the specific conditions at AHS. The Commission granted a one-year extension to the 2020 Order of Conditions.



- L. Homan noted that any changes made to the design at this late stage in the project are likely to significantly impact the budget and schedule. The Building Committee initially chose turf fields because they provide a better performance environment and have manageable maintenance, and the environmental impact can be mitigated through the design. Alternatives to crumb rubber create additional costs and have significant drawbacks, including negative impacts to safety and athletic performance. There is also less data on the alternatives. Crumb rubber infill is the best option currently; it has proven data, and many installations have successfully mitigated the environmental impact. It has superior athletic performance, longevity, and safety conditions, as well as lower cost.
- K. Allison-Ampe said that in August 2023, the Commission raised concerns about toxicity of 6PPD-quinone for fish in Mill Brook. The Building Committee and its consultants have reviewed multiple studies and concluded that the conditions needed to create 6PPD-quinone are not present in the AHS field design. 6PPD is used in rubber tires. The combination of smog and volatile organic compounds plus UV light from sunlight acts on 6PPD to form 6PPD-quinone, which occurs in tiny particles called tire abrade which can be washed off roadways and into ecosystems where they are toxic to fish. Biofilters composed of leaf mold sand and crushed stone have been found to protect fish. Tire abrade particles range from 1 to 1,000 microns; rubber infill particles range from 1,000 to 2360 microns. The compositions of tire abrade and rubber infill are also quite different; rubber infill includes no metals and meets Standard Consumer Safety Specification for Toy Safety. The AHS field drainage plan includes extensive filtration, including the possible inclusion of additional baskets, so that only clean water will drain into Mill Brook.
- J. Feeney said that the AHS Building project is funded by 2019 debt exclusion vote, combining funding from Arlington taxpayers and the state. At the beginning of the project, the Town entered into a project funding agreement with the Massachusetts School Building Authority (MSBA), and the Town is required to stay within that budget. If the Town wishes to add more funds, the MSBA has sole discretion to determine if additional funding is eligible. If the funding is ineligible, it would proportionally decrease the Town's maximum total facilities grant portion, so the Town could lose project reimbursement funds. To date, the total committed costs of the turf fields is just over \$1,200,000. Any material changes in the plans for the fields will cause the locked-in subcontract values to increase. If a contract were to be cancelled, a subcontractor to bring a claim against the Town for lost revenue. In August 2023, the Commission asked if the Building Committee could use contingency funds for an alternative infill. The Committee did consider that, but they do not believe that there are enough contingency funds. Contingency funds have been used for several unforeseen costs already, and the project is entering a phase of construction with significantly higher risks. Even if sufficient contingency funds were available, the Committee, the school district's leadership, and the project design team did not believe that it was in the best interest of the students and the community to purchase an alternative infill.
- J. Thielman said that the Building Committee has reviewed all the available information and recently voted unanimously to reaffirm their decision to use crumb rubber infill. They request an extension of the Order of Conditions.
- C. Tirone clarified that this is not a hearing and will not result in a vote. The hearing will be held at the Commission's next meeting.



- N. Stevens said that he would like to know more about how the proposed basket filtration works and how it would be maintained, as well as whether contingency funds could be used to pay for it. J. Thielman said that it would be an additional cost of \$15,000 to \$18,000. A. Duffy said that there are 18 trench drain basins, which have sump pumps. The manufacturer also offers the option of screen baskets that can capture larger particulars of crumb rubber, leaves, pine needles, etc. The maintenance plan would be to open up the hatches and empty the baskets a few times a year. N. Stevens said that he would like to see a cut screen of the basket. He also said that an extension would not allow for any changes, so including the baskets might require an amendment to the Order of Conditions.
- B. McBride asked how confident the Building Committee is that 6PPD-quinone will not develop under the conditions of the turf fields, and if they would be willing to accept a monitoring condition to determine whether it does develop. K. Allison-Ampe said that an approved test for 6PPD-quinone in water does not currently exist. When such a test becomes available, they would be willing to consider it.
- M. Gildesgame said that in his experience of the turf field at Arlington Catholic, the crumb rubber is everywhere, both above and below the grass, so he is not confident that it would be shaded by the grass and therefore not exposed to the environment. Such exposure would make it more likely that 6PPD-quinone would develop. K. Allison-Ampe said that she does not know the exact conditions of the Arlington Catholic field, but that their plans include a large enough layer of fiber that the crumb rubber would be protected. A. Duffy said that they cannot guarantee that the crumb rubber will not be exposed to any sunlight, but that it will be significantly more shaded than tire abrade on a highway, as the fiber layer will form a constant shadow. Different types of field carpet exist; the product that the Building Committee intends to use has a tall fiber height, as well as shorter fibers that grip the crumb rubber, reducing the likelihood that the rubber will migrate.
- N. Stevens asked about the plans for clearing the field of snow. M. Janger said that in his eleven years as principal, they have only once had to clear the fields of snow, and it was done by the turf company. J. Thielman said that they would follow the instructions of the turf company to do so safely.
- C. Tirone said that his understanding is that the field would be filled up as much as possible with crumb rubber, which would then be shifted around by weather conditions. He asked how often maintenance and grooming of the field would happen, and whether the Building Committee owns the equipment necessary to do the maintenance. Without regular maintenance, crumb rubber will end up outside of the field area. J. Thielman said that a maintenance plan is attached to the memo shared with the Commission. Some of the maintenance will be done by school staff, and some will be done by a contractor.
- C. Tirone asked if the treatment train is an isolated system or if it accepts infiltration from other sources. K. Allison-Ampe said that it is an isolated system and will not accept water from any other source.
- N. Stevens said that the Commission needs to check the existing Order of Conditions to see if the maintenance plan is included in it. D. Morgan said that the maintenance plan is not in the Order of Conditions; J. Thielman said that they would include that as an amendment.



- Discussion of the procedural issues involved in extending and/or amending an Order of Conditions followed.
- S. Chapnick noted that, although issues such as playing time and player safety are not in the purview of the Commission, the Artificial Turf Study Committee has clearly stated in its draft report that alternatives to crumb rubber infill should be used because of its negative impacts to human health, safety, and the environment.
- S. Chapnick stated that the Commission's review of the permit extension request is concerned with environmental issues, particularly as they affect Mill Brook. In 2020, the Commission placed specific conditions on testing the field materials, including the crumb rubber. Those tests must meet the regulatory requirements put forth by the Commission. The Commission did not require testing for 6PPD-quinone, because it was not discovered as a potential aquatic toxin until 2021, so it is important that the Commission consider that issue now. She noted that tire crumb rubber contains some amount of 6PPD-quinone. K. Allison-Ampe agreed, but said that it would remain within the field and, because of the filtration system in place, not run off into Mill Brook. S. Chapnick said that bio-retention basins have been shown to reduce the amount of 6PPD-quinone from getting into the environment, but the field filtration system does not include bio-retention basins. K. Allison-Ampe said that the filtration system contains some components of bio-retention basins.
- S. Chapnick noted that when a Commission considers a request for a permit extension, the Commission may deny the request in cases "where new information, not available at the time the permit was issued, has become available and indicates that the permit is not adequate to protect the resource area values protected by the Bylaw." Since the original permit, it has been established that tire crumb rubber can contain 6PPD-quinone, and that 6PPD-quinone is toxic to fish at extremely low concentrations. She noted that the filtration system may prevent crumb rubber from ending up in Mill Brook, but that does not prevent the chemicals coming off it from ending up in the brook. S. Chapnick concludes that used-tire-derived material may already contain 6PPD-quinone and may have the opportunity for 6PPD to convert to 6PPD-quinone. An EPA draft method for evaluating 6PPD-quinone just came out in January 2024, and will likely be finalized this year. Many labs are already using this test.
- K. Allison-Ampe noted that most of the crumb rubber material lost from turf fields is not lost through surface water. A recent literature review suggests that only 125 kg of the material is lost through surface water and ends up in drains. Another review suggests that Arlington residents generate between 135 and 250 metric tons of tireware particles per year, a vastly larger amount than results from crumb rubber materials in surface water. She also noted that Peirce field, AHS's current artificial turf field, is not packed to overflowing with crumb rubber, and future fields would not be over-filled either.
- N. Stevens said that he would like the Building Committee to apply to amend the Order of Conditions to include the maintenance plan and the use of the filtration baskets. Those amendments and the extension request could both be considered at the same hearing. C. Tirone noted that the application to amend the Order of Conditions could not be considered at the Commission's next meeting due to the application deadline. The hearing would have to be scheduled for May 2, at which the Order of Conditions would first be amended and then extended.



- S. Chapnick noted that there is precedent from DEP for a superseding Order of Conditions to allow the field to proceed with conditions, including monitoring of the stormwater coming out of the field before it goes into the resource area. She would like the Building Committee to consider a monitoring well that would monitor for 6PPD-quinone. B. McBride agreed.
- C. Tirone noted that the Commission cannot require the Building Committee to apply for an amendment to the Order of Conditions.
- C. Tirone summarized the items that the Commission have asked the Building Committee to provide before the hearing: a cut sheet for the filter basket, the study on sand filters, the study on tire road particulates. The Commission would also like the Building Committee to apply for an amendment to the Order of Conditions, including maintenance specs and a monitoring well and program.
- S. Garvin noted that they have already applied for a permit extension, the hearing for which is scheduled for April 18. If they choose to file an application for an amendment to the Order of Conditions, that hearing would be scheduled on May 2. They may choose to postpone the hearing for the permit extension until May 2, but the hearing is currently scheduled for April 18.
- M. Gildesgame asked what the testing standard would be if a monitoring well is installed. S. Chapnick said that she would propose the number that caused fish kills in a peer-reviewed paper. She proposed using the testing frequency that the DEP approved for a test well in Wilmington, which N. Stevens can provide information about.

5. Eagle Scout Proposal for Arlington Great Meadows. [1:49:00]

- Ben Gregory, from Troop 313 based in Arlington, has proposed an Eagle Scout project at Arlington Great Meadows. He has been working with D. White on planning an Eagle Scout Project.
- The proposed project is to build a sign that reads “Arlington’s Great Meadows” at the Emerson Gardens entrance and a new kiosk at the Sheila Road entrance. The new kiosk will be modeled on the current kiosk at the Waldorf School entrance. It will be constructed of pressure-treated lumber, with 6x6 posts. If permitted, he would like to use concrete to secure the posts of both the kiosk and the sign.
- The estimated cost is approximately \$550, which will be raised by the Troop. He hopes to have the project completed by mid- to late-April. His grandfather, who has construction experience, will help with the carpentry.
- D. White said that using concrete should be fine because it is not near a resource area.
- The Commission members appreciated the proposal and thanked B. Gregory for taking on the project.
- D. White made a motion to approve the project. N. Stevens seconded the motion. A roll call vote was taken:

C. Tirone – yes	S. Chapnick – yes	M. Gildesgame – yes
D. Kaplan – yes	B. McBride – yes	N. Stevens – yes
D. White – yes		

Motion passed.



6. 47 Spy Pond Lane Certificate of Compliance. [2:01:12]
- R. Clapp said that the Commission issued an Order of Conditions in 2020 for construction of a single-family house at 47 Spy Pond Lane. A previous site visit confirmed compliance with the Order of Conditions, except that the owner had constructed a chain link fence that blocked the passage of wildlife next to the resource area. The property owner has since cut three gaps in the fence, each of which are about four to six inches from the ground and about three feet long, to allow for the movement of wildlife.
 - Overall, the project is in compliance with the Order of Conditions, and R. Clapp recommends that the Commission issue a Certificate of Compliance.
 - N. Stevens made a motion to issue a Certificate of Compliance for 47 Spy Pond Lane. D. Kaplan seconded the motion. A roll call vote was taken:
 - C. Tirone – yes
 - D. Kaplan – yes
 - D. White – yes
 - S. Chapnick – yes
 - B. McBride – yes
 - M. Gildesgame – yes
 - N. Stevens – yes
- Motion passed.

7. 19 Sheraton Park Certificate of Compliance. [2:05:54]
- D. Morgan said that the Commission issued an Order of Conditions in 2011. The only item not completed by the time the permit was expired was the installation of dry wells. The owners asked for a Certificate of Compliance in 2022, but the Commission noted that the work was not complete. The Commission issued an RDA for the completion of the work required by the original Order. R. Clapp conducted a site visit and found it to be in compliance.
 - D. Kaplan made a motion to issue a Certificate of Compliance for 19 Sheraton Park, and N. Stevens seconded the motion. A roll call vote was taken:
 - C. Tirone – yes
 - D. Kaplan – yes
 - D. White – yes
 - S. Chapnick – yes
 - B. McBride – yes
 - M. Gildesgame – yes
 - N. Stevens – yes
- Motion passed.

III. Hearings

1. **Request for Determination of Applicability: 36 Peabody Road (Continued from 3/21/2024).** [2:09:34]
- This public hearing will consider a Request for Determination of Applicability for an addition to the existing structure at 36 Peabody Road in Arlington along with landscaping and hardscaping activities within the 100-foot Buffer Zone and Adjacent Upland Resource Area to Spy Pond.
 - S. Chapnick reported that the project is to repair walls that are failing due to improper installation and the steepness of the grade. The project also includes an addition to the house with a minor intrusion into the 100-foot buffer zone and the Adjacent Upland Resource Area (AURA) to Spy Pond.



- S. Chapnick, N. Stevens, M. Gildesgame, B. McBride, and C. Tirone conducted a site visit, with the owners present. They saw an example of the type of wall the owners plan to install. They also saw the terracing of the steep hill, which includes extensive native plantings. The Commission previously expressed concern with the placement of the walls; at the site visit, the Commissioners agreed that the proposed placement of the walls is necessary due to the erosion. The owners also plan to move one tree and remove two trees, one of which is hazardous, as well as plant several new trees.
- S. Chapnick expressed uncertainty about whether this work should be an RDA or an NOI, given that it is stonework. All the work will be done by hand, and it will include erosion controls.
- Eliza Hatch, the homeowner, said that they plan to move the wall and repair the staircase, all by hand. They plan to place erosion control at the bottom of the hill, where the slope gets less steep.
- C. Tirone said that the owners have taken great care of the property and the resource area. Given all the care that they've taken, he has no problem with approving this work as an RDA.
- M. Gildesgame agreed that the owners have done a good job stabilizing a very steep slope.
- S. Chapnick opened the hearing to public comment. Seeing no one who wished to speak, she closed public comment.
- N. Stevens made a motion to close the hearing. M. Gildesgame seconded the motion. A roll call vote was taken:

C. Tirone – yes	S. Chapnick – yes	M. Gildesgame – yes
D. Kaplan – yes	B. McBride – yes	N. Stevens – yes
D. White – yes		

Motion passed.

- C. Tirone made a motion to issue a positive negative determination to the RDA, with the condition of a 20-foot section of erosion control at the bottom of the hill, to be reviewed by the Conservation Agent prior to work. N. Stevens seconded the motion. A roll call vote was taken:

C. Tirone – yes	S. Chapnick – yes	M. Gildesgame – yes
D. Kaplan – yes	B. McBride – yes	N. Stevens – yes
D. White – yes		

Motion passed.

2. DEP #091-0278: Amendment to Order of Conditions: 88 Coolidge Road (Continued from 3/21/2024). [2:22:15]

- This public hearing will consider the peer review report for an amendment to an Order of Conditions for construction of a new house at 88 Coolidge Road in the Buffer Zone to a Bordering Vegetated Wetland. The applicant requested that the hearing be continued to April 18, 2024.



- N. Stevens made a motion to continue the hearing to April 18, 2024. B. McBride seconded the motion. A roll call vote was taken:
 - C. Tirone – yes
 - S. Chapnick – yes
 - M. Gildesgame – yes
 - D. Kaplan – yes
 - B. McBride – yes
 - N. Stevens – yes
 - D. White – yes

Motion passed.

3. DEP #091-0356: Notice of Intent: Thorndike Place (Continuation from 3/21/2024). [2:23:09]

- The Conservation Commission will hold a public hearing under the Wetlands Protection Act to consider a Notice of Intent for the construction of Thorndike Place, a multifamily development on Dorothy Road in Arlington. Continued Planting Plan/Habitat discussion including Invasive Species Management Plan, and, if time allows, continued stormwater discussion.
- D. White recused himself from the hearing and left the meeting.
- The applicant was represented by Matt Burne, BSC Group Senior Ecologist, Tom Groves, BSC Group Senior Botanist, Dominic Rinaldi, BSC Group Civil Engineer, Stephanie Kiefer, Project Attorney, John Hessian, Consulting Engineer, and Scott Oran and Mark Duffon, Dinosaur Capital Partners.
- M. Burne noted that peer reviewer SWCA issued a letter in February with 10 comments relating to the planting plan and invasive species management. SWCA issued a follow-up letter on March 27, which said that all but one of their comments had been adequately addressed. The only remaining comment was 2-1, which recommended that the Invasive Species Management Plan (ISMP) be submitted for review, which was done. The SWCA response 2-2 expressed their experience in effective ways to manage sites similar to the proposed project, using an adaptive management approach. It also said that there are consistent issues throughout the ISMP of misrepresenting the proposed concentrations of herbicide, and not mentioning the choice of herbicide label must be followed. M. Burne said that the whole purpose of the ISMP is to be an adaptive management plan, using a combined approach that ultimately reduces the need for chemical controls.
- T. Groves said that the ISMP includes two main approaches – the first is a primarily chemical approach but includes a mulching option; the second is a chemical, mechanical, and chemical approach, dependent on species. Japanese knot weed does not respond well to a mechanical approach first, so it is best to use a chemical approach first, followed by mechanical cutting, and then another chemical application. The timetable included in the ISMP allows for some variability of start times, since the construction timetable is unknown. The construction should not be an impediment to treatment.
- S. Chapnick said that the Commission is concerned about the use of glyphosate. She quoted an NIH study saying that exposure to glyphosate-based herbicides cause neurotoxic effects in humans, rodents, fish, and invertebrates. T. Groves replied that much of the information relating to glyphosate is based on industrial farming, which generally applies glyphosate throughout the growing season to unhealthy soil, which results in a lot of runoff. Many agencies use glyphosate,



because it has been used for a long time and has been well-studied, and it is the safest herbicide to use in these situations. The herbicide proposal in the ISMP is a wetland herbicide with a non-ionic surfactant. In an ecosystem application, it is applied once a season in small amounts, directly to the surface area, so it stays within the root system, with little runoff. At this location, the wetland is not close to where the treatment would take place. The invasive plants being treated are also destructive to the environment, more so than glyphosate would be. He estimated that less than a quart of herbicide would be used to get the invasive species under control, which is minimal compared to the amount of effort and money it would take to use a mechanical method, which would also ultimately not solve the problem.

- S. Chapnick asked if there are safer alternatives to glyphosate. She noted that many countries have banned glyphosate. T. Groves replied that glyphosate is the safest herbicide for these situations, and banning glyphosate will lead to the use of more dangerous chemicals.
- S. Chapnick also asked if they can avoid using air spray. T. Groves replied that he has proposed a low-volume, low-pressure backpack sprayer. In his experience, using stem-injection or cut-stump techniques on Japanese knotweed results in putting the herbicide into water within the plant, diluting it. The concentration required for that type of treatment is higher than what is allowable per acre. Using a low-pressure spray treatment is very targeted and more effective than stem injection. Even if the spray gets on nearby native plants, it will not kill those plants as long as the whole plant is not treated.
- S. Chapnick also asked if using the herbicide will harm newly planted plants that are part of the landscaping plan. T. Groves replied that for glyphosate to kill a plant, it must be applied to the leaf surface or an open wound on the plant; it does not work in the soil, so will not harm other nearby plantings. The return interval is four hours, so it would be safe to re-enter an area four hours after treatment.
- S. Chapnick asked if the applicant could do a treatment plan with no spraying at all. T. Groves said that using a spray is the only way to effectively treat Japanese knotweed. The ISMP does include mechanical treatment of other species.
- M. Gildesgame asked how long it would take to control the Japanese knotweed. T. Groves replied that with the methods laid out in the ISMP, he could achieve 95% control within a year. The ISMP does include a follow-up, because seedlings will reappear, but the follow-up may not be needed in the first year after a treatment. Monitoring the site is important.
- D. Kaplan asked if wiping herbicide on the plant would result in sufficient coverage to be effective, rather than spraying. He also asked if there should be no-spray buffer zones near the wetlands. T. Groves replied that the backpack sprayers result in very little drift; they can be closely targeted, and the droplets are large enough not to drift. He also said that wiping requires a heavier substance, so that it doesn't drip, and it doesn't work well on knotweed. Wiping works better with fragmites. Japanese knotweed is primarily a monoculture, so it's unlikely that a spray would hit native plants.
- D. Kaplan expressed concern that using mulch to smother invasives would prevent other groundcover to grow. T. Groves said that the site includes a large amount of garlic mustard, which is very tenacious and changes the soil chemistry. The mulch



would both kill the garlic mustard and help to rebuild the soil, which would enable other groundcover to grow in the future. He proposed three inches of mulch in the areas with garlic mustard.

- C. Tirone asked if the ISMP includes recommendations of nozzle and droplet size. T. Groves said that backpack sprayers generally come with either wands or guns, which come with nozzle sizes already within particular parameters. Low-pressure backpack sprayers won't aerosolize the droplets. He also noted that there are laws about the conditions under which treatments can take place. The label outlines the requirements regarding conditions and application gear. S. Chapnick noted that the Commission has in the past placed conditions on spraying that are stricter than the requirements on the label.
- M. Burne noted that SWCA's response 2.2 says that the ISMP should be adaptive and not stick to an unchangeable schedule from year to year. He said that the ISMP is intended to be adaptive to when the project starts and what windows of opportunity will be available.
- SWCA also recommended that the ISMP be revised to indicate that label rates of herbicides will be followed. M. Burne noted that the label is the law, so a licensed applicator should follow it, and they did not think it necessary to include that in the ISMP. They can revise the ISMP to say that the label must be followed if necessary, but for professionals, that goes without saying.
- Chase Bernier from SWCA said that he agreed with a lot of what T. Groves and M. Burne said. This is a challenging site, with a lot of different species, and the ISMP approaches it well. Japanese knotweed is extremely difficult to control, and it requires herbicide to treat effectively.
- C. Tirone opened the floor to public comment:
 - Lisa Fredman, 63 Mott St – She found the discussion on glyphosate concerning. She is trained as an epidemiologist. Although epidemiology deals with large populations, most studies start with case studies and examples. Her friend's brother recently died of ALS. He was the first of a growing number of cases of relatively young people in Vermont dying of ALS who are presumed to have had exposure to algae growth and ponds where herbicides were used. The Mugar property is right next to the wetland. Every time she walks by Thorndike Field, there has been standing water. Use of herbicides on the property will move toward that standing water, which will affect the people who use and live near Thorndike Field. She thinks that epidemiologists should be included in this discussion.
 - S. Chapnick responded to say that while the Commission cares about human health, it's not in their purview; they need to focus on the environmental impact. She encouraged L. Fredman to share her comments with the Arlington Board of Health, because if there are issues involved that affect human health, they need to be involved.
 - T. Groves recommended that L. Fredman look at lawn-care companies. Herbicide and pesticide applicators are required to report to the state what herbicides and pesticides they use and in what quantities. That information is available to the public, so it's possible to see what has been used in any given neighborhood. Lawn care companies generally use far more of such



chemicals than the ecological industry, which uses them in very low quantities. Once a habitat is restored, you don't need to continue to use herbicides, but they are used year after year in lawn care, particularly in the golf industry.

- C. Tirone said that between the last two meetings, the Commission has received 11 emails from abutters and residents throughout Arlington, all of which are available on the Thorndike page of the Commission's website. Most of those had to do with groundwater testing.
- **The Commission has completed the portion of the hearing dealing with the habitat and invasive management portion of the application, and going forward, will focus on the stormwater portion.**
- D. Rinaldi said that the applicant has authorized the BSC Group to do more stormwater test pits and install a second well in the area of the large infiltration system, and to monitor those through April and into May. The installation will likely take place the week of April 15, so they would like to continue the hearing until May 2. C. Tirone said that the Commission would like someone representing the Town to witness the installation of the wells. D. Rinaldi said that he would communicate the installation date to D. Morgan.
- C. Tirone re-opened the floor to public comment:
 - Scott Horsley, water engineer representing the Arlington Land Trust – He would recommend that the applicant use continuous recording pressure transducers. Water levels vary frequently, and it's easy to miss high points without continuous recording.
 - D. Rinaldi replied that the current well on the site does not have continuous monitoring, and the new one is not intended to either. S. Chapnick asked BSC to consider using continuous monitoring, which could be easier to use than wells that require some to go to the site to collect the data. D. Rinaldi said that continuous monitoring is not required under the Wetlands Protection Act. C. Tirone asked how many times BSC expects to go to the site to collect data. D. Rinaldi said that they hope to do it at least weekly through the end of April and into May. C. Tirone asked if a representative of the Town could be present each time the well is checked, and D. Rinaldi replied that he would have to talk to the applicant about that.
- With the approval of the applicant, N. Stevens made a motion to continue the hearing to May 2, 2024. M. Gildesgame seconded the motion. A roll call vote was taken:

C. Tirone – yes	S. Chapnick – yes	M. Gildesgame – yes
D. Kaplan – yes	B. McBride – yes	N. Stevens – yes

Motion passed.

D. Kaplan made a motion to adjourn. The meeting adjourned at 10:20 PM.

JANUARY 3, 2025

Town of Arlington Conservation Commission
c/o Mr. David Morgan, Environmental Planner + Conservation Agent
Robbins Memorial Town Hall
730 Massachusetts Avenue
Arlington, Massachusetts 02476

**RE: Revisions to Stormwater Management/Response to Peer Review
Thorndike Place Residential Development**

Dear Members of the Arlington Conservation Commission,

On behalf of the Applicant, Arlington Land Realty, LLC, BSC Group, Inc. (BSC) is pleased to submit this supplemental response to peer review comments provided by GZA GeoEnvironmental, Inc. (GZA) relative to the Thorndike Place residential development (the Project) to be located off of Dorothy Road in the Town of Arlington. On August 1, 2024, GZA submitted written peer review comments (referenced as “Peer Review of Stormwater Mound Evaluation and Design Groundwater Elevation Proposed Thorndike Place Residential Development.”) On October 4, 2024, BSC provided its initial response to the GZA peer review comments. Thereafter, at the October 24, 2024 public hearing on the Project, GZA requested that the groundwater mounding analysis for the primary underground infiltration system be performed based on the total volume of water infiltrated during the 100-year, 24-hour storm event. While BSC stands by our previous statement that the stormwater management system as previously submitted meets the requirements of the DEP’s Stormwater Standards (the “Standards”) as detailed within the Massachusetts Wetlands Protection Act (WPA) regulations, at 310 CMR 10.00, we have made the revisions detailed below to the infiltration system design to address GZA’s request while maintaining compliance with the Standards. The revisions to infiltration systems detailed below have been made to accomplish the following while addressing comments made pertaining to groundwater mounding and drawdown in these systems:

1. The use of multiple infiltration systems more closely mimics existing groundwater recharge by providing infiltration throughout the Project site.
2. The systems were designed to reduce the overall volume of infiltration during a 100-year storm event to limit the potential impacts of groundwater mounding during this extreme storm.
3. Each infiltration system is designed to maximize the separation to Estimated Seasonal High Groundwater (“ESHGW”).
4. The use of multiple infiltration systems throughout the site allowed the Project to eliminate the previously proposed rooftop detention system.

A complete set of revised Site Plans and revised Stormwater Report are attached to this letter. Additionally, to help simplify review, we are attaching a summary of just the revised calculations and a revised Grading & Drainage Plan (C-104) with the revised stormwater management system notated in red. The following specific revisions have been made to the stormwater management system design to respond to GZA’s request while maintaining compliance with the Standards.

1. A revised version of the smaller underground infiltration systems in the townhouse driveways has been incorporated into the design. These systems had been removed in the last iteration of design as shown in BSC’s filings of October 4, 2024. Each of the townhouse driveway systems (shown on the attached

Sheet C-104 as Infiltration Systems 2-6) consists of varying numbers of R-Tank XD units with the same footprint and a bottom of stone elevation of 7.0 (i.e., 3-feet above estimated seasonal high groundwater), and designed so they maintain a minimum of 10-feet separation from any building foundation. In larger storm events, these systems will overflow to a larger underground infiltration system (Infiltration System 1). A groundwater mounding analysis of these systems has been performed utilizing the total volume infiltrated during the 100-year, 24-hour storm event resulting in an expected groundwater mound of less than 1-foot. A drawdown analysis utilizing the full volume below the lowest outlet and the Rawls Rate for silt loam per GZA's request (0.27 in/hr) has been performed demonstrating that these systems will drain in less than the required 72-hours. The mounding analysis and drawdown calculations are included in Section 6 of the attached Stormwater Report and Summary of Revised Calculations.

2. With respect to the larger, primary infiltration system, the StormTrap underground chamber system has been modified into two (2) separate underground infiltration systems (shown on the attached plans as Infiltration System 1 and Infiltration System 7) that collect and infiltrate runoff from different areas of the site, as described below.
 - a. Infiltration System 1 consists of 77 3.0-foot StormTrap chambers with a bottom elevation of 8.0. Overflow from the R-Tank infiltration systems in the townhouse driveways, area drains behind the townhouses, and the roof of the multi-unit building are routed through this system. This system maintains a separation from ESHGW of 4.0-feet, and therefore a groundwater mounding analysis is not required per DEP's Massachusetts Stormwater Handbook. A drawdown analysis using the full volume below the lowest system outlet and the Rawls rate for silt loam demonstrates that the system will drain in less than the required 72-hours (see Section 6 of the attached Stormwater Report and Summary of Revised Calculations).
 - b. A separate underground infiltration system, Infiltration System 7 (see attached Sheet C-104), has been located to the west of Infiltration System 1 and consists of 25 1.75-foot StormTrap chambers with a bottom elevation of 7.15 (which corresponds to 3.15-feet above ESHGW). This system collects runoff from driveway and paved areas associated with the multi-unit building. A groundwater mounding analysis of this system has been performed utilizing the total volume infiltrated during the 100-year, 24-hour storm event resulting in an expected groundwater mound of less than 3 feet. A drawdown analysis utilizing the full volume below the lowest outlet and the Rawls Rate for silt loam has been performed demonstrating that this system will drain in less than the required 72-hours (see Section 6 of the attached Stormwater Report and Summary of Revised Calculations). As part of this design, an additional trench drain has been added to the driveway entrance to the multi-unit building to collect runoff and route it into Infiltration System 7 after passing through a water quality unit.
 - c. During larger storm events, both Infiltration Systems 1 and 7 overflow to a flared end section (FES-1) to the south of the multi-family building via outlet control structures that connect to a new drain manhole. This is the same discharge point as in the previous designs (see attached Sheet C-104). Please note that the two systems are not connected to each other, but overflow to the same point.
3. The original trench drain in the entrance to the multi-unit building is no longer routed to an underground infiltration system. Stormwater collected in this trench drain, after passing through a water quality unit, will be routed to the same overflow point as Infiltration Systems 1 and 7 (see attached Sheet C-104). Required recharge and TSS removal calculations have been updated to reflect this revision and continue to demonstrate compliance with Stormwater Standards 3 and 4, respectively.
4. The rooftop detention system, or "blue roof," that was previously shown on a portion of the multi-unit building roof has been eliminated from the design. Additionally, the outlet that previously discharged the remaining portion of roof runoff to a flared end section within the open space area of the building

has been eliminated as well, and all roof runoff from this building is routed via roof drains to Infiltration System 1 (see attached Sheet C-104).

5. On November 20, 2024, McPhail Associates, LLC (McPhail) performed two (2) soil borings on the Project site in the areas of proposed Infiltration Systems 1 and 7. These soil borings were performed to better understand the depth to a restrictive layer to more accurately determine the initial saturated thickness to be used in groundwater mounding analyses for the Project. All previous groundwater mounding analyses were performed using an initial saturated thickness of 5-feet, which represented the maximum depth of test pits performed below ESHGW. These borings, included in the attached McPhail memorandum (included as Appendix G of the attached Stormwater Report and Summary of Revised Calculations), showed a marine clay layer with a highest elevation between -12.1 and -17.4. Based on this additional data, all groundwater mounding analyses have been performed using an initial saturated thickness of 16-feet representing the depth between ESHGW (4.0) and the marine clay layer (-12.1).

As previously stated, the plan and stormwater management system revisions described above have been incorporated into the Site Plan Set and Stormwater Report, which are both attached in addition to the Summary of Revised Calculations. As previously stated during the Commission's public hearings on the Project, BSC believes that this design continues to demonstrate full compliance with all the Stormwater Standards of the Wetlands Protection Act and fully responds to all comments and questions received from GZA as the peer reviewer. We look forward to discussing this matter further as the public hearing process moves forward. Please feel free to contact me at (617) 896-4386 or drinaldi@bscgroup.com should you have any questions on the information attached.

Sincerely,
BSC GROUP, INC.



Dominic Rinaldi, PE
Senior Associate

Attachments: Revised Thorndike Place Notice of Intent Site Plan Set (December 10, 2024)
Revised Stormwater Report (December 2024)
Revisions to Stormwater Management Design (December 2024)