
THORNDIKE PLACE NOTICE OF INTENT

DOROTHY ROAD ARLINGTON, MASSACHUSETTS

SEPTEMBER 6, 2023


REVISED: DECEMBER 10, 2024



PREPARED FOR:

ARLINGTON LAND REALTY, LLC 84 SHERMAN STREET, 2ND FLOOR CAMBRIDGE, MA 02140

LOCUS MAP



INDEX OF DRAWINGS

G-100 TITLE SHEET

G-101 GENERAL NOTES & LEGEND

V-100 EXISTING CONDITIONS

C-100 EXISTING ENVIRONMENTAL

RESOURCE PLAN

C-101 SITE PREPARATION PLAN

C-102 OVERALL SITE PLAN

C-103 LAYOUT & MATERIALS PLAN

C-104 GRADING & DRAINAGE PLAN

C-105 UTILITY PLAN

L-100 PLANTING PLAN

C-200-203 CIVIL & LANDSCAPE DETAILS

C-300 TEST PIT PLAN

C-301 2020 TEST PIT LOGS

C-302 & 303 2023 TEST PIT LOGS

PREPARED BY:



ISSUED FOR PERMITTING NOT FOR CONSTRUCTION

GENERAL NOTES

- I. EXISTING CONDITIONS SURVEY INFORMATION WAS PREPARED BY BSC GROUP, INC. SURVEY IS BASED ON AN ON-THE-GROUND SURVEY CONDUCTED BY BSC GROUP IN DECEMBER 2019-FEBRUARY 2020.
- 2. REVIEW ALL EXISTING CONDITIONS IN THE FIELD AND REPORT ANY DISCREPANCIES BETWEEN PLANS AND ACTUAL CONDITIONS TO THE OWNER'S REPRESENTATIVE IN WRITING PRIOR TO STARTING WORK.
- 3. THE LOCATIONS OF UNDERGROUND UTILITIES SHOWN ON THIS PLAN ARE BASED ON THE SURVEY REFERENCED ABOVE. THE CONTRACTOR SHALL CONTACT DIGSAFE (888–344–7233 OR 811) AND THE PROPER LOCAL AUTHORITIES OR RESPECTIVE UTILITY COMPANIES TO CONFIRM THE LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. ANY DAMAGE DUE TO FAILURE OF THE CONTRACTOR TO CONTACT THE PROPER AUTHORITIES SHALL BE BORNE BY THE CONTRACTOR.
- 4. ANY DISCREPANCIES BETWEEN DRAWINGS, SPECIFICATIONS, AND SITE CONDITIONS SHALL BE REPORTED IMMEDIATELY TO THE ENGINEER IN WRITING FOR CLARIFICATION AND RESOLUTION PRIOR TO BIDDING OR CONSTRUCTION.

SITE PREPARATION NOTES

- 1. ONLY AREAS DESIGNATED FOR CLEARING SHALL BE CLEARED.
- 2. THE SUBCONTRACTOR(S) IS/ARE RESPONSIBLE FOR ANY DAMAGE TO EXISTING CONDITIONS TO REMAIN THAT ARE DUE TO SUBCONTRACTOR(S) OPERATIONS.
- 3. ITEMS TO BE REMOVED THAT ARE NOT STOCKPILED FOR LATER REUSE ON THE PROJECT OR DELIVERED TO THE OWNER SHALL BE LEGALLY DISPOSED OF OFF SITE BY THE SUBCONTRACTOR(S).
- 4. THE SUBCONTRACTOR(S) SHALL BE RESPONSIBLE FOR COORDINATING THEIR EFFORTS WITH ALL TRADES.

 5. THE CONTRACTOR SHALL COORDINATE ALL ADJUSTMENT OR ARANDONMENT OF LITHIUTIES WITH THE RESPECTIVE.
- 5. THE CONTRACTOR SHALL COORDINATE ALL ADJUSTMENT OR ABANDONMENT OF UTILITIES WITH THE RESPECTIVE UTILITY COMPANY.
- 6. THE SUBCONTRACTOR(S) SHALL MAINTAIN OR ADJUST TO NEW FINISH GRADE AS NECESSARY ALL UTILITY AND SITE STRUCTURES SUCH AS LIGHT POLES, SIGN POLES, MAN HOLES, CATCH BASINS, HAND HOLES, WATER AND GAS GATES, HYDRANTS, ETC., FROM MAINTAINED UTILITY AND SITE SYSTEMS UNLESS OTHERWISE NOTED OR DIRECTED BY THE CONTRACTOR/ENGINEER.
- 7. TEMPORARY CONSTRUCTION HAUL ROADS (IF REQUIRED) SHALL BE EXCAVATED AND THE SUB-BASE COMPACTED TO 95% SPMDD. THE USE OF SEPARATION FABRICS MAY BE USED TO FACILITATE FUTURE REMOVAL AND RECOVERY OF GRANULAR MATERIALS. HAUL ROAD SHALL HAVE AT LEAST 9" OF 6-INCH MINUS STONE AND SHALL BE MAINTAINED DURING CONSTRUCTION.

EROSION AND SEDIMENT CONTROL MEASURES

- 1. EROSION CONTROL SHALL BE PROVIDED IN ACCORDANCE WITH THE SEQUENCE OF STAGED CONSTRUCTION. THE CONTRACTOR SHALL SUBMIT A DETAILED EROSION CONTROL PLAN INCLUDING SCHEDULE FOR APPROVAL BY THE TOWN OF ARLINGTON. A COPY OF THE APPROVED NPDES EROSION AND SEDIMENT CONTROL PLAN SHALL BE MAINTAINED ON THE SITE.
- ALL EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE INSTALLED PRIOR TO ANY SITE EXCAVATION OR DISTURBANCE AND SHALL BE MAINTAINED THROUGHOUT THE CONSTRUCTION PROCESS. THE SMALLEST PRACTICAL AREA OF LAND SHALL BE EXPOSED AT ANY ONE TIME.
- 3. SEDIMENT TRAPS SHALL BE INSTALLED AT DRAINAGE STRUCTURES IN PUBLIC STREET IN THE PROJECT AREA. STRAW BALE BARRIERS AND SILTATION FENCES ARE TO BE MAINTAINED AND CLEANED UNTIL ALL SLOPES HAVE BEEN STABILIZED.
- 4. SEDIMENT BARRIERS SHALL BE INSPECTED AND APPROVED BY THE TOWN OF ARLINGTON BEFORE CONSTRUCTION CAN START.
- 5. STRAW BALES AND MULCH SHALL BE MOWINGS OF ACCEPTABLE HERBACEOUS GROWTH, FREE OF NOXIOUS WEEDS OR WOODY STEMS, AND SHALL BE DRY WHEN INSTALLED.
- 6. THE UNDERSIDE OF STRAW BALES SHOULD BE KEPT IN CLOSE CONTACT (TRENCHED IN 3-INCHES MINIMUM)
- WITH THE EARTH AND RESET AS NECESSARY.

 7. DISTURBED AREAS SHALL BE BLANKETED OR SEEDED AND MULCHED AS SOON AS PRACTICAL AFTER

CONSTRUCTION ACTIVITIES IN THAT AREA HAVE CONCLUDED. ALL ERODABLE/BARE AREAS SHALL BE BLANKETED

- OR SEEDED AND MULCHED WITHIN 7 DAYS WITH TEMPORARY EROSION CONTROL SEEDING.

 8. STABILIZE SLOPES GREATER THAN 3:1 (HORIZONTAL:VERTICAL) WITH SEED, SECURED GEOTEXTILE FABRIC,
- SPRAYED COMPOST BLANKET, OR RIP-RAP AS REQUIRED TO PREVENT EROSION DURING CONSTRUCTION.
- SEDIMENT BARRIERS SHALL BE CONSTRUCTED AROUND ALL SOIL STOCKPILE AREAS.
 CLEAN OUT DRAINAGE FEATURES AND STRUCTURES AFTER COMPLETION OF CONSTRUCTION.
- 11. SEDIMENT COLLECTED DURING CONSTRUCTION BY THE VARIOUS TEMPORARY EROSION CONTROL SYSTEMS SHALL BE DISPOSED OF OFF SITE ON A REGULAR BASIS. SEDIMENT SHALL BE REMOVED FROM EROSION CONTROL SYSTEMS WHEN THE HEIGHT OF THE SEDIMENT EXCEEDS ONE—HALF OF THE HEIGHT OF THE SEDIMENT CONTROL MEASURE.
- 12. AFTER ALL DISTURBED AREAS HAVE BEEN STABILIZED, THE SUBCONTRACTOR(S) SHALL REMOVE ALL TEMPORARY EROSION CONTROL MEASURES AT THE CONTRACTOR/ENGINEER DIRECTION.
- 13. AFTER THE REMOVAL OF TEMPORARY EROSION CONTROL MEASURES, THE SUBCONTRACTOR(S) SHALL GRADE AND SEED AREA OF TEMPORARY EROSION CONTROL MEASURE.
- 14. DAMAGED OR DETERIORATED ITEMS WILL BE REPAIRED IMMEDIATELY AFTER IDENTIFICATION OR AS DIRECTED BY THE CONTRACTOR/ENGINEER.
- 15. THE CONTRACTOR'S SITE SUPERINTENDENT WILL BE RESPONSIBLE FOR DAILY INSPECTIONS, MAINTENANCE, AND REPAIR ACTIVITIES. THE CONTRACTOR SHALL INSPECT EROSION CONTROL MEASURES EVERY SEVEN (7) CALENDAR DAYS. DAMAGED AND INEFFECTIVE EROSION CONTROL MEASURES SHALL BE REPAIRED OR REPLACED WITHIN 48 HOURS.
- 16. PIPE OUTLETS (IF ANY) SHALL BE STABILIZED WITH STONE.
- 17. TEMPORARY SEEDING SHALL BE AT A RATE OF 45 LBS PER ACRE. ERODABLE AREAS OUTSIDE AND DOWN SLOPE FROM THE CONSTRUCTION LIMITS SHALL BE SIMILARLY SEEDED.
- 18. WATER PUMPED OR OTHERWISE DISCHARGED FROM THE SITE DURING CONSTRUCTION DEWATERING SHALL BE FILTERED. DEWATERING PLAN SHALL BE SUBMITTED FOR APPROVAL BY THE ENGINEER.
- 19. WHEN TEMPORARY DRAINAGE IS ESTABLISHED, EROSION/SEDIMENTATION CONTROL MEASURES MAY BE REQUIRED BY CONTRACTOR/ENGINEER.
- 20. GRAVEL CONSTRUCTION ROADS AND CONSTRUCTION PARKING AREAS OF SUFFICIENT WIDTH AND LENGTH, AND VEHICLE WASH DOWN FACILITIES, SHALL BE PROVIDED TO PREVENT SOIL FROM BEING TRACKED ONTO PUBLIC OR PRIVATE ROADWAYS. ANY SOIL REACHING A PUBLIC OR PRIVATE ROADWAY SHALL BE REMOVED BEFORE THE END OF EACH WORKDAY AND AS NEEDED.
- 21. NECESSARY MEASURES SHALL BE TAKEN TO CONTAIN ANY FUEL OR POLLUTION RUNOFF. LEAKING EQUIPMENT OR SUPPLIES SHALL BE IMMEDIATELY REPAIRED OR REMOVED FROM THE SITE.
- 22. THE COST OF REPAIRING OR REMOVING SEDIMENT FROM EROSION CONTROL SYSTEMS SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR THE APPLICABLE EROSION CONTROL ITEM.
- 23. ALL EROSION CONTROL MEASURES SHALL BE KEPT OPERATIONAL AND MAINTAINED CONTINUOUSLY THROUGHOUT THE PERIOD OF LAND DISTURBANCE UNTIL PERMANENT SEDIMENT AND EROSION CONTROL MEASURES ARE OPERATIONAL. CONTRACTOR SHALL PROVIDE TO THE CONSERVATION COMMISSION MEASURES (EROSION AND SEDIMENTAITON CONTROL) FOR WORK DURING WINTER CONDITIONS.
- 24. CONTRACTOR SHALL SPRAY WATER FROM A WATER TRUCK ON DRY AND WINDY DAYS TO PREVENT DUST FROM FORMING.
- 25. EROSION CONTROL MEASURES AS SHOWN ON THESE DRAWINGS ARE INTENDED TO CONVEY MINIMUM REQUIREMENTS. THE CONTRACTOR SHALL IMPLEMENT ADDITIONAL MEASURES AS NECESSARY TO PREVENT SOIL EROSION AND TO COMPLY WITH THE PROJECT'S STORMWATER POLLUTION PREVENTION PLAN.
- 26. SOILS ON SLOPES THAT ARE 3:1 OR STEEPER SHOULD BE ROUGHENED PER THE EPA'S NPDES SOIL ROUGHENING FACT SHEET IF THEY ARE TO BE SEEDED WITHIN 2 WEEKS OF DISTURBANCE. IF NOT, EROSION CONTROL BLANKETS SHOULD BE INSTALLED ON THESE SLOPES.

LAYOUT AND MATERIAL NOTES

OTHERWISE NOTED.

- THE FOLLOWING LAYOUT CRITERIA SHALL CONTROL UNLESS OTHERWISE NOTED ON THE PLAN:

 a. ALL TIES TO PROPERTY LINES ARE PERPENDICULAR TO THE PROPERTY LINE UNLESS
- b. DISTANCES AND DIMENSIONS ARE IN DECIMAL FEET.
- 2. SCREENED IMAGES SHOW EXISTING CONDITIONS. WHERE EXISTING CONDITIONS LIE UNDER OR ARE IMPINGED UPON BY PROPOSED BUILDINGS AND/OR SITE ELEMENTS, THE EXISTING CONDITION SHALL BE REMOVED, ABANDONED AND/OR CAPPED OR DEMOLISHED AS REQUIRED. AMBIGUITIES IN THE PLANS SHALL BE CLARIFIED BY THE ENGINEER OR SITE SUPERINTENDENT UPON WRITTEN REQUEST FOR CLARIFICATION BY THE SUBCONTRACTOR.

GRADING AND UTILITY NOTES

- 1. THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY AND HAVE NOT BEEN INDEPENDENTLY VERIFIED BY THE APPLICANT. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK, AND AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MAY BE OCCASIONED BY THE CONTRACTOR'S FAILURE TO EXACTLY LOCATE AND PRESERVE ALL UNDERGROUND UTILITIES.
- THE PROJECT APPLICANT SHALL OBTAIN ALL NECESSARY STREET—OPENING PERMITS, WATER AND SEWER CONNECTION PERMITS AND PAY REQUIRED FEES PRIOR TO COMMENCING WORK ON THESE UTILITIES.
- 3. WHERE AN EXISTING UTILITY IS FOUND TO CONFLICT WITH THE PROPOSED WORK, THE LOCATION, ELEVATION, AND SIZE OF THE UTILITY SHALL BE ACCURATELY DETERMINED WITHOUT DELAY BY COORDINATION WITH THE TOWN OF ARLINGTON.
- 4. ALL ARRANGEMENTS FOR THE ALTERATION AND ADJUSTMENT OF ALL GAS, ELECTRIC, TELEPHONE, AND ANY OTHER PRIVATE UTILITIES BY THE UTILITY COMPANIES SHALL BE MADE BY THE PROJECT APPLICANT.
- 5. AREAS OUTSIDE THE LIMITS OF PROPOSED WORK DISTURBED BY THE CONSTRUCTION SHALL BE RESTORED TO THEIR ORIGINAL CONDITION.
- 6. WHERE PROPOSED GRADES MEET EXISTING GRADES, SUBCONTRACTOR(S) SHALL BLEND GRADES TO PROVIDE A SMOOTH TRANSITION BETWEEN EXISTING AND NEW WORK. PONDING AT TRANSITION AREAS WILL NOT BE ALLOWED.
- 7. POSITIVE DRAINAGE SHALL BE MAINTAINED AWAY FROM ALL STRUCTURES.
- B. SUBCONTRACTOR(S) SHALL VERIFY EXISTING GRADES AND NOTIFY THE ENGINEER IN WRITING OF ANY DISCREPANCIES.
- 9. PRIOR TO ANY WORK OVER EXISTING TOWN-OWNED UTILITIES, CONTRACTOR TO EVALUATE CONDITION OF SUBSURFACE UTILITIES PRIOR TO CONSTRUCTION. A POST-CONSTRUCTION EVALUATION SHALL ALSO BE PERFORMED TO IDENTIFY ANY DAMAGE CAUSED DURING CONSTRUCTION.
- 10. ANY INSTALLATION OF UTILITY POLES OR UNDERGROUND CONDUIT WITHIN THE PUBLIC RIGHT-OF-WAY WILL REQUIRE A GRANT OF LOCATION FROM THE BOARD OF SELECTMEN.

PLANTING NOTES

DIGGING.

- MAINTENANCE SHALL BEGIN IMMEDIATELY AFTER PLANTING AND SHALL CONTINUE UNTIL FINAL WRITTEN ACCEPTANCE OF PLANT MATERIAL.
- 2. MAINTAIN POSITIVE DRAINAGE AWAY FROM ALL BUILDING FOUNDATIONS AND STRUCTURES.
- 3. MAXIMUM SLOPE WITHIN DISTURBED AREAS SHALL NOT EXCEED 3:1, UNLESS OTHERWISE NOTED.
- 4. THE LANDSCAPE CONTRACTOR SHALL SUPPLY ALL PLANT MATERIALS IN QUANTITIES SUFFICIENT TO COMPLETE PLANTINGS SHOWN ON THE DRAWINGS.
- 5. MATERIALS SHALL CONFORM TO THE GUIDELINES ESTABLISHED BY THE AMERICAN NURSERY AND
- LANDSCAPE ASSOCIATION.

 6. PLANTS SHALL BEAR THE SAME RELATIONSHIP TO FINISH GRADE AS TO ORIGINAL GRADES BEFORE
- Z. PLANTS SHALL BE BALLED IN BURLAP OR CONTAINERIZED.
- 8. AREAS PLANTED WITH EVERGREEN TREES SHALL BE COVERED WITH A MINIMUM 3" OF MULCH. MULCH FOR PLANTED AREAS TO BE AGED PINE BARK: PARTIALLY DECOMPOSED, DARK BROWN IN COLOR AND FREE OF WOOD CHIPS THICKER THAN 1/4 INCH.
- 9. THE LANDSCAPE CONTRACTOR SHALL GUARANTEE ALL PLANT MATERIALS FOR ONE (1) FULL YEAR FROM DATE OF ACCEPTANCE.
- 10. PLANT MATERIALS ARE SUBJECT TO THE APPROVAL OF THE LANDSCAPE ARCHITECT, AT THE NURSERY, AND AT THE SITE.
- 11. PLANT SPECIES AS INDICATED IN THE PLANT LIST ARE SUGGESTIONS ONLY. FINAL SELECTION OF SPECIES SHALL OCCUR AT THE TIME OF PLANT PURCHASE, DEPENDING ON AVAILABILITY. PLANT SIZE AND QUANTITY SHALL NOT CHANGE WITHOUT APPROVAL OF LANDSCAPE ARCHITECT. ANY CHANGES TO PLANT SPECIES SHALL BE REVIEWED AND APPROVED BY A REPRESENTATIVE OF THE ARLINGTON CONSERVATION COMMISSION PRIOR TO PURCHASE.

COMPREHENSIVE PERMIT NOTES

CONTRACTOR REQUIRED TO ABIDE BY THE 'DECISION ON APPLICATION FOR COMPREHENSIVE PERMIT' ISSUED ON NOVEMBER 22, 2021 WITH SPECIFIC ATTENTION BROUGHT TO THE FOLLOWING CONDITIONS.

- D.15 BURNING OR BURIAL OF CONSTRUCTION OR DEMOLITION DEBRIS ON THE SITE IS STRICTLY PROHIBITED. ALL SUCH MATERIALS ARE TO BE REMOVED FROM THE SITE IN ACCORDANCE WITH APPLICABLE LAW. DURING CONSTRUCTION, THE SITE SHALL BE SECURED AGAINST UNAUTHORIZED ENTRY OR VANDALISM BY FENCING, OR OTHER APPROPRIATE MEANS, AND ALL CONSTRUCTION MATERIALS SHALL BE STORED OR STOCKPILED ON SITE IN A SAFE MANNER. ANY FLOODLIGHTS USED DURING THE CONSTRUCTION PERIOD SHALL BE LOCATED AND DIRECTED SO AS TO PREVENT SPILLOVER OR ILLUMINATION ONTO ADJACENT PROPERTIES. ALL CONSTRUCTION ACTIVITIES ARE TO BE CONDUCTED IN A WORKMANLIKE MANNER.
- D.16 NO BUILDING AREAS SHALL BE LEFT IN AN OPEN, UNSTABILIZED CONDITION LONGER THAN SIXTY (60) DAYS. TEMPORARY STABILIZATION SHALL BE ACCOMPANIED BY HAY BALES, HAY COVERINGS OR MATTING. FINAL STABILIZATION SHALL BE ACCOMPLISHED BY LOAMING AND SEEDING EXPOSED AREAS
- D.17 ALL DUMPSTERS SERVING THE PROJECT SHALL BE ENCLOSED AND COVERED (WITH THE EXCEPTION OF CONSTRUCTION DUMPSTERS USED DURING CONSTRUCTION). THE BOARD SHALL REVIEW THE DUMPSTER LOCATION AS PART OF THE APPROVAL OF THE FINAL PLANS IF DIFFERENT FROM WHAT HAS BEEN SHOWN ON THE APPROVED PLANS.
- H.2 ALL WATER AND SEWER INFRASTRUCTURE SHALL BE INSTALLED IN CONFORMANCE WITH THE ARLINGTON WATER AND SEWER DIVISION'S TECHNICAL REQUIREMENTS. THE APPLICANT SHALL PROVIDE THE ARLINGTON WATER AND SEWER DIVISION WITH CALCULATIONS TO ENSURE THE DISTRIBUTION SYSTEM FOR THE AREA HAS THE NECESSARY CAPACITY TO MEET SYSTEM DEMAND REQUIRED PRIOR TO THE COMMENCEMENT OF CONSTRUCTION.
- I.1 PRIOR TO COMMENCEMENT OF SITE CLEARING, PREPARATION, AND CONSTRUCTION, EROSION CONTROL MEASURE SHALL BE INSTALLED CONSISTENT WITH THE APPROVED PLANS.
- I.3 NO UNCOVERED STOCKPILING OF EARTHEN AND/OR CONSTRUCTION—RELATED MATERIALS SHALL BE PERMITTED WITHIN THE ONE HUNDRED FOOT (100') WETLAND BUFFER ZONE (ALSO REFERENCED LOCALLY AS ADJACENT UPLAND RESOURCES AREA ("AURA")) OR OTHER RESOURCE AREAS.
- 1.4 NO HEAVY EQUIPMENT MAY BE STORED OVERNIGHT WITHIN THE FIFTY FEET (50') OF BORDERING OR ISOLATED VEGETATED WETLAND RESOURCE AREAS, AND NO REFUELING OR MAINTENANCE OF MACHINERY OR VEHICLES SHALL BE ALLOWED WITHIN THE ONE HUNDRED FOOT (100') BUFFER ZONE, AURA, OR WITHIN ANY BORDERING OR ISOLATED VEGETATED WETLAND RESOURCE AREA OR
- BORDERING LAND SUBJECT TO FLOODING (BLSF).

 THERE SHALL BE NO DUMPING OF WOODY VEGETATION, LEAVES, GRASS CLIPPINGS, BRUSH, OR OTHER DEBRIS INTO A WETLAND RESOURCE AREA OR ASSOCIATED BUFFER ZONES.

 DUMPING OF SNOW INTO A WETLAND RESOURCE AREA IS ALSO PROHIBITED AND SHALL COMPLY WITH THE CURRENT MASS DEP BUREAU OF WATER RESOURCES SNOW REMOVAL GUIDANCE. THE FOREGOING DOES NOT APPLY TO THE CLEAN SNOW REMOVED FROM THE EMERGENCY ACCESS ROAD AS LONG AS NO SAND OR NON-APPROVED DE-ICING MATERIALS ARE USED, AND THE SNOW IS CLEAR OF ALL FOREIGN DEBRIS. AN ALTERNATIVE DE-ICING PRODUCT SUCH AS MAGNESIUM CHLORIDE (MgCI) MAY BE USED AS RECOMMENDED IN THE WINTER PARKING LOT AND SIDEWALK MAINTENANCE MANUEL PUBLISHED BY THE MINNESOTA POLLUTION CONTROL AGENCY,

- THE APPLICANT SHALL HIRE A QUALIFIED ENVIRONMENTAL MONITOR WHO WILL REPORT TO THE BOARD AND WILL BE ON—SITE AS PROJECT CONSTRUCTION ADVANCES. THE ENVIRONMENTAL MONITOR SHALL SUBMIT AN ELECTRONIC REPORT TO THE BOARD WEEKLY DURING SITE PREPARATION WORK WITHIN THE ONE HUNDRED FOOT (100') BUFFER ZONE TO VEGETATED WETLANDS, INCLUDING AN UPDATE ON THE FUNCTIONALITY AND CONDITION OF THE EROSION CONTROL MEASURES, UNTIL SUCH TIME THAT THE SITE IS STABILIZED. THE APPLICANT SHALL PROVIDE THE BOARD WITH THE NAME(S), ADDRESS(ES) AND TELEPHONE NUMBER(S) OF THE ENVIRONMENTAL MONITOR PRIOR TO THE START OF WORK.
- WHILE ACTIVE CONSTRUCTION WORK IN UNDERWAY WITHIN THE ONE HUNDRED FOOT (100') BUFFER ZONE, AND DURING THE CREATION OF THE FLOODPLAIN COMPENSATION AREA INCLUDING REMOVAL OF VEGETATION INCLUDING INVASIVE SPECIES, FINAL GRADE ESTABLISHMENT, CREATION OF SOIL PROFILE TO SUPPORT PROPOSED PLANT SPECIES, AND RESTORATION OF A DIVERSIFIED PLANT COMMUNITY, THE ENVIRONMENTAL MONITOR SHALL PROVIDE MONTHLY STATUS REPORTS TO THE BOARD TO CONFIRM THAT ALL ACTIVITIES ARE SUBSTANTIALLY IN COMPLIANCE WITH THE COMPREHENSIVE PERMIT AND ORDER OF CONDITIONS ISSUED BY THE ARLINGTON CONSERVATION COMMISSION. THE ZBA MAY REDUCE THE FREQUENCY OF INSPECTIONS OR REPORTS AS DEEMED APPROPRIATE. THE QUALIFIED ENVIRONMENTAL MONITOR SHALL ALSO SUBMIT AN ELECTRONIC REPORT WITHIN SEVEN DAYS AFTER EVERY RAIN EVENT EXCEEDING 0.5 INCHES OF RAIN IN A 24-HOUR PERIOD TO THE BOARD REGARDING THE CONDITION OF THE PROPERTY DURING AND AFTER THE RAIN EVENT. SUCH REPORT SHALL ALSO INCLUDE THE STATUS OF EROSION CONTROL MEASURES AND ANY ADDITIONAL MEASURES TO ADDRESS STORMWATER MANAGEMENT CAUSED BY SAID RAIN EVENT. THE QUALIFIED ENVIRONMENTAL MONITOR WILL ALSO REVIEW THE APPLICANT'S SWPPP INSPECTION REPORT, AS APPROPRIATE AND NECESSARY.
- ALL WORK SHALL BE CONDUCTED IN ACCORDANCE WITH THE APPROVED EROSION AND SEDIMENTATION CONTROL PLAN. WITHIN ONE WEEK OF FINAL GRADING, WEATHER PERMITTING, ALL DISTURBED AREAS LOCATED WITHIN THE WETLAND RESOURCE AREAS AND BUFFER ZONES SHALL BE STABILIZED AGAINST EROSION. THIS SHALL BE DONE EITHER BY SODDING OR BY LOAMING, SEEDING AND MULCHING ACCORDING TO SOIL CONSERVATION SERVICE STANDARDS AND THE APPROVED PLANS. STABILIZATION WILL BE COMPLETED WHEN THE SURFACE SHOWS COMPLETE VEGETATIVE COVER. TEMPORARY STABILIZATION MEASURES APPROVED BY THE BOARD'S INSPECTIONAL ENGINEER WILL BE REQUIRED SHOULD WORK BE INTERRUPTED FOR MORE THAN TEN (10) DAYS.
- I.9 THE APPLICANT, SUCCESSOR OR ASSIGNS SHALL ENSURE THE CLEANLINESS OF ALL CATCH BASINS AND ROADWAY AFFECTED BY THE PROJECT RELATED ACTIVITY. ALL CATCH BASINS WILL BE PROTECTED BY A "SILT BAG INLET PROTECTION" DEVICE OR EQUAL DURING THE PROJECT WORK PERIOD. THE APPLICANT SHALL INSPECT AND CLEAN AS NECESSARY, ALL CATCH BASINS AND SWEEP THE ROADWAY AT LEAST WEEKLY DURING CONSTRUCTION. IT MAY BE REQUIRED MORE FREQUENTLY DURING AND AFTER RAIN EVENTS. IF IT IS DEEMED NECESSARY TO REMOVE THE SILT BAG INLET PROTECTION TO PREVENT LOCALIZED FLOODING AND PUBLIC SAFETY CONCERNS, THE APPLICANT SHALL NOTIFY THE BOARD AND ARLINGTON DPW AND ALSO THE QUALIFIED ENVIRONMENTAL MONITOR.
- I.11 THE BOARD OR ITS DULY APPOINTED AGENT (WHICH MAY BY THE TOWN CONSERVATION AGENT ACTING ON BEHALF OF THE BOARD) SHALL HAVE THE RIGHT TO ENTER THE PROPERTY FOR INSPECTIONS AND EVALUATE COMPLIANCE WITH THE WETLANDS CONDITIONS CONTAINED HEREIN UPON REASONABLE NOTICE OF NOT LESS THAN TWENTY—FOUR (24) HOURS. ACCESS SHALL BE ALLOWED WITHOUT THE NEED FOR ADVANCED NOTICE IN EMERGENCY SITUATIONS WHEN NECESSARY TO PREVENT IMMINENT HARM TO WETLANDS RESOURCE AREAS.
- I.14 PRIOR TO ANY WORK COMMENCING ON—SITE, THE APPLICANT SHALL SUBMIT TO THE BOARD PROOF THAT A NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) CONSTRUCTION GENERAL PERMIT IS ACTIVE FOR THE PROJECT.
- I.15 COPIES OF ALL INFORMATION AND ALL REQUIRED REPORTS REGARDING A US EPA NPDES PERMIT AND STORMWATER POLLUTION PREVENTION PLAN (SWPPP) SHALL BE FORWARDED TO THE BOARD VIA ELECTRONIC COPY.
- I.19 THE APPLICANT SHALL RETAIN A QUALIFIED PROFESSIONAL ENGINEER TO OVERSEE THE INSTALLATION IF THE STORMWATER SYSTEM. A STORMWATER MITIGATION REPORT SHALL BE SUBMITTED TO THE BOARD WITHIN TEN (10) DAYS OF THE COMPLETION OF THE INSTALLATION OF THE STORMWATER MANAGEMENT SYSTEM. SUCH STORMWATER MITIGATION REPORT SHALL INCLUDE AS—BUILT PLANS, PHOTOGRAPHS FROM INSTALLATION, AND A WRITTEN SUMMARY OF THE INSTALLATION OF THE STORMWATER MANAGEMENT SYSTEMS, AS WELL AS STORMWATER BEST MANAGEMENT PRACTICES (POROUS PAVEMENT, RAIN GARDENS, AND SIMILAR ELEMENTS THROUGHOUT THE PROPERTY).
- I.20 THE APPLICANT SHELL TREAT PLANTED AREAS WITHIN RESOURCE AREAS AND BUFFER ZONES ONLY WITH SLOW RELEASE NITROGEN FERTILIZER ONCE DURING THE INITIAL PLANTING YEAR. APPLICATION OF THIS FERTILIZER IS NOT PERMITTED WITHIN TWO DAYS BEFORE AND AFTER STORM EVENTS. LAWN FERTILIZER MAY ONLY BE APPLIED TWICE PER YEAR, ONCE IN THE SPRING AND ONCE IN THE FALL, WITH THE EXCEPTION OF THE INITIAL PLANNING YEAR. THIS SHALL BE A CONTINUING CONDITION IN PERPETUITY THAT SURVIVES THE EXPIRATION OF THIS PERMIT.
- I.21 THE APPLICATION OF PLANT NUTRIENTS SHALL COMPLY WITH 330 CMR 31.00. NO OTHER HERBICIDES OR TREATMENT METHODS MAY BE UTILIZED ON THE PROPERTY UNLESS APPROVED AS PART OF THE APPROVED INVASIVE SPECIES MANAGEMENT PLAN. NO PESTICIDES OR RODENTICIDES SHALL BE USED TO TREAT PEST MANAGEMENT ISSUES WITHIN RESOURCE AREAS. THIS SHALL BE A CONTINUING CONDITION IN PERPETUITY THAT SURVIVES THE EXPIRATION OF THIS PERMIT.
- I.22 EXCEPT AS SPECIFICALLY NOTED IN CONDITION i.5, THE APPLICATION OF SAND AND/OR SALT WITHIN THE ONE HUNDRED FEET (100') OF RESOURCE AREA IS PROHIBITED.
- CATCH BASINS AT THE END OF CONSTRUCTION OF THE PROJECT.

 I.25

 ALL PLANT SPECIES PLANTED AND INVASIVE SPECIES REMOVED THROUGH THE PROJECT SHALL BE MONITORED FOR THREE YEARS. A SURVIVAL RATE OF EIGHTY PERCENT (80%) MUST BE MAINTAINED FOR THE APPROVED PLANTING AT THE END OF THE THIRD YEAR OF MONITORING. IF THE SURVIVAL RATE IS LESS THAN EIGHTY PERCENT (80%) AFTER THE END OF THE THIRD YEAR, THE APPLICANT


1.23 THE APPLICANT SHALL CONDUCT A THOROUGH CATCH BASIN SUMP CLEANING AT ALL PROTECTED

- RATE IS LESS THAN EIGHTY PERCENT (80%) AFTER THE END OF THE THIRD YEAR, THE APPLICANT MUST SUBMIT PROPOSED RECOMMENDATIONS FOR REPLACEMENT TO THE BOARD FOR ITS REVIEW AND ADMINISTRATIVE APPROVAL. A MONITORING REPORT SHALL BE SUBMITTED ANNUALLY IN JUNE FOR EACH OF THE YEARS IN THE THREE—YEAR MONITORING PERIOD, REPORTING ON THE HEALTH OF THE NEW PLANTINGS AND THE SUCCESS OF THE INVASIVE PLANT MANAGEMENT. THE APPLICANT SHALL SUBMIT THE CONTACT INFORMATION OF THE PARTY RESPONSIBLE FOR MONITORING AND MAINTAINING THE PLANTED VEGETATION TO THE ZBA. SHOULD ANY CHANGES BY MADE TO THIS PARTY, THE ZBA SHALL BE NOTIFIED. THIS SHALL BE A CONTINUING CONDITION IN PERPETUITY THAT SURVIVES THE EXPIRATION OF THIS PERMIT.
- I.26 NO WORK SHALL BE ALLOWED IN OR WITHIN TWENTY—FIVE FEET (25') OF ANY RESOURCES AREA EXCEPT AS SHOWN ON THE APPROVED PLANS.
- 1.27 NO DISTURBANCES SHALL BE ALLOWED IN OR WITHIN FIFTY FEET (50') OF ANY RESOURCE AREA, EXCEPT AS SHOWN ON THE APPROVED PLANS.
- I.30 ANY BUILDING OR SITE DEWATERING OPERATIONS SHALL CONFORM TO THE FOLLOWING:
 1. THE APPLICANT SHALL NOTIFY THE CONSERVATION COMMISSION AND DPW THAT DEWATERING IS REQUIRED PRIOR TO COMMENCING ANY DEWATERING OPERATIONS.
 - 2. ANY CATCH BASINS, DRAINS, AND OUTFALLS TO BE USED IN DEWATERING OPERATIONS SHALL BE CLEANED OUT BEFORE OPERATIONS BEGIN.
 - 3. ANY WATER DISCHARGING AS PART OF ANY DEWATERING OPERATION SHALL BE PASSED THROUGH FILTERS, ON—SITE SETTLING BASINS, SETTLING TANK TRUCKS, OR OTHER DEVICES TO ENSURE THAT NO OBSERVABLE SEDIMENTS OR POLLUTANTS ARE CARRIED INTO ANY RESOURCE AREA, STREET, DRAIN, OR ADJACENT PROPERTY. FILTERING IS ESSENTIAL TO REMOVE ANY AUTOMOTIVE POLLUTANTS FROM THE WATER PRIOR TO DISCHARGE.
 - 4. MEASURES SHALL BETAKEN TO ENSURE NO EROSION OR SCOURING SHALL OCCUR ON PUBLIC OR PRIVATE PROPERTY, OR ON THE BANKS OR BOTTOMS OF WATER BODIES, AS A RESULT OF DEWATERING OPERATIONS. DISCHARGES ARE TO BE SET BACK AT LEAST FIFTY FEET (50') FROM BVW AND IVW.
 - 5. DEWATERING SHALL NOT TAKE PLACE IN ANY MANNER THAT LEADS TO WATER BEING DISCHARGES OR ALLOWED TO FLOW ONTO PROPERTY NOT UNDER THE CONTROL OF THE APPLICANT WITHOUT THE EXPRESS WRITTEN CONSENT OF THAT PROPERTY OWNER.

ABBREVIATIONS

, F. F. S.	CB CB/DH CLF DIP DMH ECB FH FOC FD GG HW ILSF IP ISW LOW N/F NTS OCC RW RCP SLC	BOTTOM OF CURB BITUMINIOUS CONCRETE BORDERING VEGETATED WETLANDS CATCH BASIN CONC. BOUND/DRILL HOLE CHAIN LINK FENCE DUCTILE IRON PIPE DRAIN MANHOLE EROSION CONTROL BARRIER FLARED END SECTION FIRE HYDRANT FACE OF CURB FOUND GAS GATE HEADWALL ISOLATED LAND SUBJECT TO FLOODING IRON PIPE ISOLATED WETLANDS LANDSCAPED AREA LIMIT OF WORK NOW OR FORMERLY NOT TO SCALE OUTLET CONTROL STRUCTURE PRECAST CONCRETE CURB RETAINING WALL REINFORCED CONCRETE PIPE STREET LIGHT CIRCUIT SEWER MANHOLE
N	RW	RETAINING WALL
S	SMH TC TEL	SEWER MANHOLE TOP OF CURB TELEPHONE CABLE
Г	VGC WG	VERTICAL GRANITE CURB WATER GATE

LEGEND







DECIDUOUS TREES



ISSUED FOR PERMITTING NOT FOR CONSTRUCTION

THORNDIKE PLACE NOTICE OF INTENT

PROFESSIONAL ENGINEER

DOROTHY ROAD

ARLINGTON MASSACHUSETTS

GENERAL NOTES AND LEGEND

(MIDDLESEX COUNTY)

SEPTEMBER 6, 2023

REVISIONS:

NO. DATE DESC.

11 092/1027/1224 IRENLTRATAIONINGSYSTICENE 11

2 12/10/24 PEER REVIEW REVISIONS

PREPARED FOR:

ARLINGTON LAND REALTY, LLC 84 SHERMAN STREET, 2ND FLOOR CAMBRIDGE, MA

BSC GROU
803 Summer Street

Boston, Massachusetts 02127 617 896 4300


SCALE: NONE


© 2023 BSC Group, Inc.


JOB. NO: 23407.02


FILE: 2340702\C\D\2340702-LN


DWG.:
SHEET G-101


























SEE CONCRETÉ

COMPACTED GRAVEL BORROW BASE, SEE

SECTION A-A

DIRECTION WITH LEVEL ENTRANCE

ACCESSIBLE CUR<u>B RAMP TYPE 'B' — SINGLE</u>

CONCRETE WALKWAY DETAIL

WALKWAY DETAIL

CURB TRANSITION LENGTH FOR WHEELCHAIR RAMPS					
ROADWAY PROFILE GRADE (%)	TRANSITION LENGTH ROUNDED TO THE NEAREST 4"				
0 OR LOW SIDE	6'-6"				
>0 - 1	7'–8"				
>1 - 2	9'-0"				
>2 - 3	11'-0"				
>3 - 4	14'-0"				
>4	15'-0" (MAX)				


1. SLOPE TOLERANCE FOR RAMP AND SIDEWALK CONSTRUCTION = \pm 0.50%

ELEVATION

DETECTABLE WARNING


2. THE MAX. ALLOWABLE SLOPE OF ACCESSIBLE ROUTE EXCLUDING CURB RAMPS SHALL BE 5%. 3. THE MAX. ALLOWABLE SLOPE OF ACCESSIBLE ROUTE CURB RAMPS SHALL BE 7.5%. 4. A MINIMUM OF 3 FEET CLEAR SHALL BE MAINTAINED AT ANY PERMANENT OBSTACLE IN ACCESSIBLE ROUTE (I.E. HYDRANTS, UTILITY POLES, TREE WELLS, SIGNS, ETC.).

5. BASE OF RAMP SHALL BE GRADED TO PREVENT PONDING.




- 1. ALL TWELVE INCH (12") LINES SHALL BE APPLIED IN ONE APPLICATION, NO COMBINATION OF LINES (TWO - 6 INCH LINES) WILL BE ACCEPTED.
- 2. ALL PAVEMENT MARKING MATERIALS WHETHER THERMOPLASTIC OR WATERBORNE PAINT TO BE REFLECTORIZED WITH GLASS
- 3. LONGITUDINAL CROSSWALK LINES TO BE PARALLEL TO CURBLINE.
- 4. ALL LONGITUDINAL CROSSWALK LINES TO BE THE SAME
- LENGTH AND PROPERLY DRESSED. 5. STRIPES TO BE SOLID WHITE.

PEDESTRIAN CROSSWALK MARKINGS SCALE: NONE



*CONSTRUCTION TOLERANCE = 0.5%

HOT MIX ASPHALT WALKWAY




CURB TRANSITION LENGTH FOR WHEELCHAIR RAMPS					
ROADWAY PROFILE GRADE (%)	HIGH SIDE TRANSITION LENGTH ROUNDED TO THE NEAREST 4"				
0 OR LOW SIDE	6'-6"				
>0 - 1	7'-8"				
>1 - 2	9'-0"				
>2 - 3	11'-0"				
>3 - 4	14'-0"				
>4	15'-0" (MAX)				

1. SLOPE TOLERANCE FOR RAMP AND SIDEWALK CONSTRUCTION = \pm 0.50%

2. THE MAX. ALLOWABLE SLOPE OF ACCESSIBLE ROUTE EXCLUDING CURB RAMPS SHALL BE 5%. 3. THE MAX. ALLOWABLE SLOPE OF ACCESSIBLE ROUTE CURB RAMPS SHALL BE 7.5%.

4. A MINIMUM OF 3 FEET CLEAR SHALL BE MAINTAINED AT ANY PERMANENT OBSTACLE IN ACCESSIBLE ROUTE (I.E. HYDRANTS, UTILITY POLES, TREE WELLS, SIGNS, ETC.).

5. BASE OF RAMP SHALL BE GRADED TO PREVENT PONDING.



-ADJUSTABLE VALVE BOX PER LOCAL WATER DEPT. STANDARDS FINISH GRADE √6" GATE VALVE M.J. FITTINGS (TYP.) WATER LINE (SEE TYP TRENCH DETAIL)

GA7	Έ	VALVE
SCALE:	NONE	


-1-1/2" HOT MIX ASPHALT WEARING COURSE -2" HOT MIX ASPHALT BINDER COURSE 12" COMPACTED GRAVEL BORROW BASE (M 1.03.0 C) COMPACTED SUBGRADE


PERPENDICULAR WITH LANDSCAPING STRIP


STANDARD DUTY FLEXIBLE PAVEMENT

PAVEMENT SECTIONS ARE SUBJECT TO CHANGE AND WILL BE BASED ON THE RESULTS OF GEOTECHNICAL INVESTIGATIONS

HOT MIX ASPHALT PAVEMENT SECTION







CONCRETE THRUST BLOCK FOR PRESSURE PIPE SCALE: NONE

`	SB	SIZE OF RANCH	J	K	L	М	N	0
>	4"	THRU 8"	10"	10"	1'-0"	2'-0"	1'-6"	10"
	10"	THRU 16"	1'-0"	1'-6"	1'-8"	3'-10"	2'-10"	1'-6"
		24"	1'-4"	2'-0"	2'-6"	5'-0"	3'-6"	1'-8"
			TE	ES AND	PLUG	5		

	90 8	& 45 BEN	NDS	22 1/2 & 11 1/4			
D	4"TO8"	10"TO16"	24"	4"TO 8"	10"TO16"	24"	
Х	1'-8"	3'-4"	3'-6"	1'-4"	2'-0"	3'-6"	
Y	1'-2"	1'-8"	2'-4"	1'-0"	1'-2"	2'-4"	
BENDS							

BY THE ENGINEER.

- 1. PROVIDE 3000 PSI CONCRETE THRUST BLOCKS AT ALL BENDS, DEAD ENDS, & TEES UNLESS OTHERWISE DIRECTED. CONCRETE FOR ALL THRUST BLOCKS TO BE PLACED AGAINST FIRM, UNDISTURBED SOIL. PROVIDE APPROVED ANCHOR HARNESS RODS & SOCKET CLAMPS AS SPECIFIED & IN ACCORDANCE WITH PIPE MANUFACTURERS RECOMMENDATIONS WHERE SOIL HAS BEEN DISTURBED OR THRUST BLOCKS CANNOT BE USED, AS DIRECTED
- 2. ALL SOCKET CLAMP METAL SHALL BE COATED WITH BLACK ASPHALTUM OR OTHER WATER DEPARTMENT APPROVED COATINGS.
- 3. CONCRETE THRUST BLOCKS POURED BEHIND 3-WAY TEE & HYDRANT SHOE TO BE USED WITH SOCKET CLAMPS. 4. NO CONCRETE SHALL COVER PIPE JOINTS, FITTING JOINTS, BOLTS OR HYDRANT DRAINS.

ISSUED FOR PERMITTING NOT FOR CONSTRUCTION

THORNDIKE PLACE
NOTICE OF INTENT

PROFESSIONAL ENGINEER

DOROTHY ROAD

ARLINGTON **MASSACHUSETTS**

(MIDDLESEX COUNTY)

CIVIL & LANDSCAPE DETAILS

SEPTEMBER 6, 2023

NO. DATE DESC. 1 | 9/12/24 | INFILTRATION SYSTEM 2 12/10/24 PEER REVIEW REVISIONS

PREPARED FOR:

ARLINGTON LAND REALTY, LLC 84 SHERMAN STREET, 2ND FLOOR CAMBRIDGE, MA



803 Summer Street Boston, Massachusetts

617 896 4300

© 2023 BSC Group, Inc. SCALE: AS NOTED

FILE: 2340702\C\D\2340702-DET

DWG.: SHEET C-201JOB. NO: 23407.02

